

Approved:



MEMO

To: Kristopher Byrd, Well Construction Manager
From: Tommy Laird, Well Construction Program Coordinator
Subject: Review of Water Right Application G-19477
Date: June 3, 2025

The attached application was forwarded to the Well Construction Section by the Groundwater Section. Gabriela Ferreira reviewed the application. Please see Gabriela's Groundwater Review and the Well Report.

Applicant's Well #1 (MULT 32): Based on a review of the Well Report, Well #1 does not appear to comply with current minimum well construction standards (See OAR 690 Division 210). The problem is that according to the Well Report, the liner does not extend a minimum of 8 feet into the upper permanent well casing. In order to meet minimum construction standards, the liner must be extended, or it may also be removed.

My recommendation is that the Department not issue a permit for Well #1 unless it is brought into compliance with current minimum well construction standards or information is provided showing that it is constructed to meet current minimum well construction standards.

The repair of Well #1 may not satisfy hydraulic connection issues.

