Oregon Water Resources Department Water Rights Division

Application for Extension of Time

In the Matter of the Application)	
for an Extension of Time for)	
Permit #G-11376, Water Right)	PROPOSED FINAL ORDER
Application #G-12579)	
(Crooked River Ranch Water Company))	

Permit Information

Application File #G-12579 / Permit #G-11376

Basin: #5 - Deschutes Basin / Watermaster District: #11
Date of Priority: June 18, 1991

Authorized Use of Water

Source of Water: Two Wells (Wells #2 and #3) in the Deschutes River

Basin, amended on October 30, 1997, by Special Order

Volume 51, Pages 1235 through 1237 to add an

additional point of appropriation (Well #4)

Purpose or Use: Quasi-Municipal Use

Maximum Rate: 5.0 cubic foot per second (cfs)

This Extension of Time request is being processed in accordance with Oregon Administrative Rule Chapter 690, Division 315.

Please read this Proposed Final Order in its entirety.

This Proposed Final Order applies only to Permit #G-11376, water right Application #G-12579. A copy of Permit #G-11376 is enclosed as Attachment 1.

Summary of Proposed Final Order for Extension of Time

The Department proposes to:

- grant the extension for complete construction of the water system from October 1, 1998, to October 1, 2008; and
- grant the extension for complete application of water from October 1, 1998, to October 1, 2008.

AUTHORITY

ORS 537.230 and ORS 537.630(1) provide in pertinent part that the Water Resources Department shall, for good cause shown, order an extension of time within which irrigation or other works shall be completed or the right perfected. In determining the extension, the Department shall give due weight to the considerations described under ORS 539.010(5).

ORS 539.010(5) provides in pertinent part that the Water Resources Director, for good cause shown, may extend the time within which the full amount of the water appropriated shall be applied to a beneficial use. This statute instructs the Director to consider: the cost of the appropriation and application of the water to a beneficial purpose; the good faith of the appropriator; the market for water or power to be supplied; the present demands therefore; and the income or use that may be required to provide fair and reasonable returns upon the investment.

OAR 690-315-0080 provides in pertinent part that the Water Resources
Department shall make findings to determine if an extension of time for municipal
and/or quasi-municipal water use permit holders may be approved to complete
construction and/or apply water to full beneficial use.

FINDINGS OF FACT

Background

- 1. Permit #G-11376 was granted by the Water Resources Department (Department) on November 18, 1991. The permit authorizes the use of up to 5.0 cfs of water from two wells, being Well #2 (now known as CRRWC Well #2) and Well #3 (now known as Crooked River Ranch Association (CRRA) Well #3), in the Deschutes River Basin for quasi-municipal purposes. It specified that construction of the water system was to be completed by October 1, 1993, and complete application of water was to be made on or before October 1, 1994.
- One prior extension has been granted for Permit #G-11376. It resulted in the construction and completion dates being extended to October 1, 1998.
- 3. The CRRWC submitted a permit amendment application (T-7828) to the Department on August 13, 1997, proposing to add an additional point of appropriation, being Well #4 (now known as CRRWC Well #1) under Permit #G-11376. On October 30, 1997, the Department issued an order (Special Order Volume 51, Pages 1235 through 1237) approving the permit amendment request.
- 4. The Crooked River Ranch Water Company (CRRWC) submitted an "Application for Extension of Time" to the Department on April 3, 2000, requesting the time in which to complete construction of the water system and to accomplish beneficial use of water to the full extent under the terms of Permit #G-11376 be extended to October 1, 2006.
- 5. Due to ongoing permit extension rulemaking, the Department placed all pending municipal and quasi-municipal permit extension of time requests on hold and did not require municipal and quasi-municipal water use permit holders to submit an extension application until the new rules were adopted.
- Municipal and quasi-municipal water use permit extension rules were adopted by the Water Resources Commission and became effective on November 1, 2002 (OAR 690-315-0070 through 690-315-0100).
- 7. On April 6, 2004, the CRRWC submitted additional extension information and amended their extension of time request for Permit #G-11376. The CRRWC requested that both the time in which to complete construction of the water system and to complete beneficial use of water to the full extent under the terms of Permit #G-11376 be extended to October 1, 2009.

- Notification of the CRRWC's extension of time request for Permit #G-11376
 was published on the Department's Public Notice dated April 20, 2004. No
 public comment on the extension application was received.
- On May 3, 2004, the CRRWC amended their extension of time application for Permit #G-11376 to request the amount of time to complete construction of the water system and to accomplish full beneficial use of water be extended to October 1, 2008.

Review Criteria for Municipal and Quasi-Municipal Water Use Permits [OAR 690-315-0080(1)] The time limits to complete construction and/or apply water to full beneficial use may be extended if the Department finds that the permit holder has met the requirements set forth under OAR 690-315-0080(1).

Complete Extension of Time Application (OAR 690-315-0080(1)(a)]

10. The Department received a completed extension of time application and the statutory fee specified in ORS 536.050 from the permit holder.

Start of Construction [ORS 537,630[1], OAR 690-315-0080[1][b]]

 Construction of the wells and water system began within the time specified in the permit, being November 18, 1992.

Duration of Extension (ORS 539.010(5), OAR 690-315-0080(1)(c)(d))
Under OAR 690-315-0080(1)(c)(d), the Department shall find that the time requested is reasonable and the applicant can complete the project within the time requested.

- The remaining work to be accomplished under Permit #G-11376 consists of complete construction of the water system and complete application of water to beneficial use.
- As of April 6, 2004, the permit holder has diverted 3.75 cfs of the 5.0 cfs of water allowed under Permit #G-11376 for quasi-municipal purposes.

Proposed Final Order: Permit #G-11376 Page 4 of 13

- 14. In addition to the 5.0 cfs of water from the three wells allowed under Permit #G-11376 for quasi-municipal purposes, the CRRWC holds only one other water right (Certificate #75144) authorizing the use of 0.06 cfs of water from Well #2 for irrigation of 4.4 acres.
- 15. Currently, under Permit #G-11376, the CRRWC utilizes CRRWC Well #1 and CRRWC Well #2 as its primary water sources and maintains CRRA Well #3 as an emergency stand-by source only.
- 16. CRRWC's delivery system is made up of two different service levels, being the upper level system in the northern portion of the Ranch supplied by CRRWC Well #1 and the lower level system in the southern portion of the Ranch supplied by CRRWC Well #2. CRRWC's water system also includes two reservoirs (Standpipe and Cistern) which are connected by a booster pumping station located at the Cistern Reservoir. The Standpipe Reservoir is located in the upper service level and capable of serving the entire system, but is primarily used for daily operations in the upper level system. The Cistern Reservoir is located in the lower service level and primarily serves the lower portion of the Ranch. During times of peak demand, however, CRRWC Well #2 sends water to the Cistern Reservoir which is pumped via the booster pumping station to the upper service level.
- 17. At this time, the CRRWC can pump 800 gpm each from CRRWC Wells #1 and #2 (or 1600 gpm total). Moving water from CRRWC Well #2 in the lower service level to the upper level system, however, is impaired because the pumps at the booster pumping station connecting the two service levels cannot pump more than 500 gpm. This system limitation results in a flow of only 1300 gpm being available to the upper service level. Additionally, the CRRA Well #3 is of little help as it is also located in the lower service level and subject to the same booster pumping station constraints.
- 18. Currently, CRRWC supplies domestic and fire protection flows to approximately 3500 people located within their current service boundary, being the northern portion of Crooked River Ranch. Residents in the southern portion of Crooked River Ranch rely upon private wells to supply their domestic use needs. Because these private wells cannot adequately meet water needs in the event of a house or wild fire, CRRWC also supplies water for fire protection to the southern portion of the Ranch through the Crooked River Ranch Rural Fire Protection District. All water used by the Fire Department on the Ranch, both to fight fires and suppress simulated fire events, is from the CRRWC system. (Section 2.1 of CRRWC's "Water Management and Conservation Plan Sept 2003")

- 19. The fire marshal requires that fire protection flows of 1200 gpm be available for residential sites and 1500 gpm be available at commercial sites. Currently, because of the system limitations at the booster pumping station, CRRWC does not have access to adequate fire protection flows for commercial sites in the upper service level. Additionally, CRRWC's current reservoir storage is not adequate for fire protection in severe situations, such as a grassland wildfire.
- 20. On March 9, 2004, the CRRWC submitted permit amendment application #T-9663 proposing the addition of another well to be constructed in the upper service level of the system. The proposed well (CRRWC Well #3) will allow the CRRWC to provide system redundancy and an adequate level of fire protection, by meeting fire marshal fire flow requirements for commercial sites, currently unavailable in the upper service level. Additionally, the construction of a new well through the permit amendment process (#T-9663) is necessary because the Crooked River Ranch is not located near any potential water suppliers where an interconnection could be accomplished at a reasonable cost.
- 21. Once the additional well is drilled and operational, the CRRWC expects to utilize the full 5.0 cfs of water allowed under Permit #G-11376 within a relatively short time frame as the demand for the water already exists and is expected to increase further in the near future. Full beneficial use of the water is simply limited by the current constraints of the wells and water system.
- 22. Given the amount of development left to occur, the CRRWC's need to provide adequate flow for community fire protection, and considering the CRRWC's current water supply situation, the permittee's request to have until October 1, 2008, to complete construction of the water system and to complete the application of water to beneficial use under the terms of Permit #G-11376 is reasonable.

Good Cause IORS 539.010(5), OAR 690-315-0080(1)(e) and (2)1

The Department's determination of good cause shall consider the requirements set forth under OAR 690-315-0080(2).

Page 6 of 13

Reasonable Diligence and Good Faith of the Appropriator (ORS 537.230, ORS 537.630(1), ORS 539.010(5), OAR 690-315-0080(2)(a)(c) and (3)1

Reasonable diligence and good faith of the appropriator during the permit period constitutes a continuing test of whether and under what conditions to grant an extension. In determining the reasonable diligence and good faith of a municipal or quasi-municipal water use permit holder, the Department shall consider activities associated with the development of the right including, but not limited to, the items set forth under OAR 690-315-0080(3).

- 23. Prior to October 1, 1998, the following had occurred: construction of the CRRWC Well #1 was completed and subsequently repaired; CRRWC Well #2 was repaired; the cistern was repaired; a chlorination system and an emergency use generator were purchased; 1028 meter connections were established; the distribution system as expanded; and a 20-Year Master Plan was completed.
- 24. Since the October 1, 1998, the following has occurred: a Water Management and Conservation Plan consistent with OAR Chapter 690, Division 86 was completed and submitted; an additional 420 meter connections were established; and the distribution system was expanded with the installation of 10.5 miles of pipeline.
- 25. As of April 6, 2004, the permit holder has invested 40 percent of the total projected cost for complete development of this project, being an approximate total of \$2,024,700. An additional \$3,000,000 investment is anticipated for the completion of this project.
- 26. Since the issuance of Permit #G-11376 on November 18, 1991, approximately 3.75 cfs of water has been diverted from the wells for beneficial quasi-municipal purposes under the terms of the permit.

Financial Investment and Cost to Appropriate and Apply Water to a Beneficial Purpose (ORS 539.010(5), OAR 690-315-0080(2)(b))

27. As of April 6, 2004, the permit holder has invested an approximate total of \$2,024,7000 into the project consisting of complete construction of the CRRWC Well #1 and subsequent repairs; repairs made to CRRWC Well #2 and the cistern, the purchase of a chlorination system and an emergency use generator, the establishment of 1448 meter connections, the expansion of the distribution system including installation of 10.5 miles of pipeline; completion of a 20-Year Master Plan, and completion of a Water

Management and Conservation Plan consistent with OAR Chapter 690, Division 86. An additional \$3,000,000 investment is anticipated for the completion of this project.

The Market and Present Demands for Water (ORS 539.010(5), OAR 690-315-0080(2)(d)]

- 28. As described in findings #14 through #21 above, a demand for the water under Permit #G-11376 currently exists, however, full beneficial use of the water has been limited by the constraints of the wells and water system. Additionally, these system limitations have placed the CRRWC in a position where fire marshal fire flow requirements are not being met for commercial sites located in the upper service level.
- 29. Based upon past growth trends, the CRRWC expects development in the community to continue and the demand for water to increase further in the near future.
- 30. The CRRWC must maintain Permit #G-11376 because the Crooked River Ranch is not located near any potential water suppliers where an interconnection could be accomplished at a reasonable cost.
- 31. In order to provide system redundancy and an adequate level of fire protection for the community, the CRRWC is pursuing a permit amendment (#T-9663) to add an additional well (CRRWC Well #3) to Permit #G-11376.
- Given CRRWC's current water supply situation and their existing and expected needs, there is a market and present demand for the water to be supplied under Permit #G-11376.

Fair Return Upon Investment (ORS 539.010(5), OAR 690-315-0080(2)(e)]

33. Use and income from the permitted water development project results in reasonable returns upon the investment made to date. Additionally, future rate fees collected from water service area expansions will provide funds necessary for water system updates and maintenance.

Other Governmental Requirements (ORS 537.230(2), OAR 690-315-0080(2)(f))

 Delay in the development of this project was not caused by any other governmental requirements.

Proposed Final Order: Permit #G-11376 Page 8 of 13

Events which Delayed Development under the Permit 10AR 690-315-0080(2)(g)

35. Delay of development under Permit #G-11376 was due to the scope and nature of the project, which was designed to be phased in over a period of years as the lots were sold and homes built. Additionally, full beneficial use of the water under the permit has been limited by the constraints of the wells and water system.

CONCLUSIONS OF LAW

- The applicant is entitled to apply for an extension of time to complete construction and/or completely apply water to the full beneficial use pursuant to ORS 537.230 and ORS 537.630.
- The applicant has submitted a complete extension application form and the fee specified under ORS 536.050(1)(k), as required by OAR 690-315-0080(1)(a).
- The applicant demonstrated that actual construction on the project began within the time specified in the permit, as required by OAR 690-315-0080(1)(b).
- The time requested to complete construction of the water system and to apply water to full beneficial use is reasonable, as required by OAR 690-315-0080(1)(c).
- 5. Completion of construction and full application of water to beneficial use can be completed by October 1, 2008¹, [OAR 690-315-0080(1)(d)].
- After considering the reasonable diligence and good faith of the appropriator, the financial investment made, the market and present demands for water, the fair return upon the investment, the requirements of other governmental

Pursuant to ORS 537.630(3), upon the completion of beneficial use of water allowed under the permit, the permittee shall hire a certified water rights examiner to survey the appropriation. Within one year after the complete application of water to a beneficial use (or by the date allowed for the complete application of water to a beneficial use), the permittee shall submit a map of the survey and the claim of beneficial use.

agencies and uncontrollable events which delayed development under the permit, the Department has determined that the applicant has shown good cause for an extension to complete construction of the water system and complete the application of water to full beneficial use pursuant to OAR 690-315-0080(1)(e).

Proposed Order

Based upon the foregoing findings of fact and conclusions of law, the Department proposes to issue an order to:

Extend the time for complete construction of the water system under Permit #G-11376 from October 1, 1998, to October 1, 2008; and

Extend the time for complete application of water to beneficial use under Permit #G-11376 from October 1, 1998, to October 1, 2008.

DATED: May 25, 2004

Dwight French

Water Rights Section Manager

If you have any questions, please check the information box on the last page for the appropriate names and phone numbers.

Proposed Final Order Hearing Rights

1. Under the provisions of OAR 690-315-0100(1) and 690-315-0060, the applicant or any other person adversely affected or aggrieved by the proposed final order may request a contested case hearing on the proposed final order. Your request for contested case hearing must be in writing and must be received by the Water Resources Department no later than *Friday*, July 9, 2004, being 45 days from the date of publication of the proposed final order in the Department's weekly public notice.

- 2. A written request for contested case hearing shall include:
 - a. The name, address and telephone number of the petitioner;
 - A description of the petitioner's interest in the final order and if the protestant claims to represent the public interest, a precise statement of the public interest represented;
 - A detailed description of how the action proposed in the final order would adversely affect or aggrieve the petitioner's interest;
 - A detailed description of how the final order is in error or deficient and how to correct the alleged error or deficiency;
 - e. Any citation of legal authority supporting the petitioner, if known;
 - f. Proof of service of the petition upon the water right permit holder, if petitioner is other than the water right permit holder; and
 - g. The protest fee required under ORS 536.050.
- Within 60 days after the close of the period for requesting a contested case hearing, the Director shall:
 - a. Issue a final order on the extension request; or
 - b. Schedule a contested case hearing if a request for contested case hearing has been submitted, and:
 - A. Upon review of the issues, the Director finds there are significant disputes related to the proposed agency action; or
 - B. The applicant submitted a timely request for a contested case hearing.

If you have other questions about the Department, or any of its programs, please contact our Water Rights Information Group at (503)986-0900. Address all other correspondence to:

Water Rights Section
Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem, OR 97301-1271
Fax #: (503)986-0901

This document was prepared by Lisa J. Juul. If you have any questions about any of the statements contained in this document, I am most likely the best person to answer your questions. You may contact me by telephone at (503)986-0808.

If you have questions about how to file a protest or if you have previously filed a protest and want to know the status, please contact Renee Moulun. Her telephone number is (503)986-0824.

If you have other questions about the Department or any of its programs, please contact our Water Rights Information Group at (503)986-0900.

BEFORE THE WATER RESOURCES DEPARTMENT OF THE STATE OF OREGON

In the Matter of Permit Amendment)	
T-9663, Jefferson and Deschutes Counties,)	FINAL ORDER
Oregon)	

ORS 537.211 establishes the process in which a water right permit holder may submit a request to change the point of appropriation and/or place of use authorized under an existing water right permit.

Applicant

Crooked River Ranch Water Company, P.O. Box 879, Crooked River Ranch, Oregon 97760.

Findings of Fact

- Crooked River Ranch Water Company filed an application to amend the point of appropriation of Well 3 under Permit G-11376. The Department assigned the application number T-9663.
- 2. The permit to be amended is as follows:

Permit:

G-11376, in the name of Crooked River Ranch Water Company;

Use:

Quasi-municipal;

Priority Date: June 18, 1991;

Quantity:

5.0 cubic feet per second (cfs), being 2.5 cfs from each well;

Source:

Wells 2, 3, and 4, in the Crooked River Basin.

Date Of Complete

Application of

Water:

October 1, 2008.

RECEIVED

NOV 0 6 2008 WATER RESOURCES DEPT SALEM, OREGON

RECEIVED

SEP 25 2008

WATER RESOURCES DEPT SALEM, OREGON

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order other than a contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-080 and OAR 690-01-005, you may either petition for judicial review or petition the Director for reconsideration of this order.

Authorized Points of Appropriation:

Township		Range		Meridian	Sec	1/4	1/4	Lot	DLC	Location
13	S	12	Е	W.M.	24	NW	NW			Well 2 – 680 feet South and 780 feet East from the NW Corner of Section 24.
13	s	12	Е	W.M.	24	sw	SE			Well 3 – 80 feet North and 480 feet East from the S ¹ / ₄ Corner of Section 24.
13	S	12	Е	W.M.	16	NE	SE			Well 4 – 990 feet South and 680 feet West from the E1/4 Corner of Section 16.

Authorized Place of Use:

Tow	nship	Rai	ige	Meridian	Sec	1/4	V4	Lot	DLC	Acres	
13	S	12	Е	W.M.	4	NW	NW				
13	S	12	Е	W.M.	4	SW	SW				
13	S	12	Е	W.M.	4	SE	SW				
13	S	12	E	W.M.	5	NE	NE				
13	S	12	Е	W.M.	5	SE	NE				
13	S	12	E	W.M.	5	SE	SW				
13	S	12	E	W.M.	5	NE	SE				
13	S	12	E	W.M.	5	NW	SE				
13	S	12	E	W.M.	5	SW	SE				
13	S	12	E	W.M.	5	SE	SE				
13	S	12	E	W.M.	8	NE	NE				
13	S	12	E	W.M.	8	NW	NE				
13	S	12	E	W.M.	8	SW	NE				RECEIVED
13	S	12	E	W.M.	8	SE	NE				THOUSE OF THE PARTY OF THE PART
13	S	12	E	W.M.	8	NE	NW				MUN 0 & 5008
13	S	12	E	W.M.	9	NW	NW				WATEH HESOURCES DEPT
13	S	12	E	W.M.	9	SW	NW				SALEM, OREGON
13	S	12	E	W.M.	9	SE	NW				
13	S	12	E	W.M.	9	NE	SW				
13	S	12	E	W.M.	9	NW	SW				
13	S	12	E	W.M.	9	SW	SW				
13	S	12	E	W.M.	9	SE	SW				RECEIVED
13	S	12	E	W.M.	9	NE	SE				
13	S	12	E	W.M.	9	NW	SE				SEP 2 5 2008
13	S	12	E	W.M.	9	sw	SE				WATER RESOURCES DEPT
13	S	12	E	W.M.	9	SE	SE				SALEM. OREGON

Town	ship	Ran	ge	Meridian	Sec	1/4 1/4	L	ot	DLC	Acre	S	
13	S	12	E	W.M.	10	SW N	WW					
13	S	12	Е	W.M.	10	SE 1	NW					
13	S	12	Е	W.M.	10	NE S	sw					
13	S	12	E	W.M.	10	NW S	sw					
13	S	12	E	W.M.	10	SW S	sw					
13	S	12	Е	W.M.	10	SE S	sw					
13	S	12	Е	W.M.	10	sw	SE					
13	S	12	E	W.M.	10	SE	SE					
13	S	12	E	W.M.	13	SW :	sw					
13	S	12	Е	W.M.	14	sw	NE					
13	S	12	E	W.M.	14	NW I	NW					
13	S	12	E	W.M.	14	SW 1	NW					
13	S	12	Е	W.M.	14	SE 1	NW					
13	S	12	Е	W.M.	14	NE	sw					
13	S	12	E	W.M.	14	NW	SW					
13	S	12	Е	W.M.	14	SW	SW					
13	S	12	E	W.M.	14	SE	SW					
13	S	12	E	W.M.	14	NE	SE					
13	S	12	E	W.M.	14	NW	SE					
13	S	12	Б	W.M.	14	SW	SE					
13	S	12	E	W.M.	14	SE	SE					
13	S	12	E	W.M.	15	NE	NE					
13	S	12	E	W.M.	15	NW	NE					
13	S	12	E	W.M.	15	SW	NE					
13	S	12	E	W.M.	15	SE	NE					RECEIVED
13	S	12	E	W.M.	15	NE	NW					
13	S	12	E	W.M.	15	NW	NW					NOV 0 6 2008
13	S	12	E	W.M.	15	-	NW		-		WATE	R RESOURCES DEPT ALEM, OREGON
13	S	12	E	W.M.	15	SE	NW					ALEW, ONEGON
13	S	12	E	W.M.	15	NE	SW					
13	S	12	E	W.M.	15	NW	SW					
13	S	12	E	W.M.	15	SW	SW					
13	S	12	E	W.M.	15	SE	SW					
13	S	12	E	W.M.	15	NE	SE					RECEIVED
13	S	12	E	W.M.	15	NW	SE					
13	S	12	E	W.M.	15	sw	SE					SEP 2 5 2008
13	S	12	E	W.M.	15	SE	SE				W	ATER RESOURCES DEPT
13	S	12	E	W.M.	16	NE	NE					SALEM. OREGON

Town	ship	Rai	ige	Meridian	Sec	1/4	1/4	Lot	DLC	Acres	
13	S	12	E	W.M.	16	NW	NE				
13	S	12	E	W.M.	16	SW	NE				
13	S	12	Е	W.M.	16	SE	NE				
13	S	12	Е	W.M.	16	NE	NW				
13	S	12	E	W.M.	16	NW	NW				
13	S	12	Е	W.M.	16	SW	NW :				
13	S	12	E	W.M.	16	SE	NW				
13	S	12	E	W.M.	16	NE	SW				
13	S	12	E	W.M.	16	NW	SW				
13	S	12	Е	W.M.	16	SW	SW				
13	S	12	Е	W.M.	16	SE	SW				
13	S	12	Е	W.M.	16	NE	SE				
13	S	12	Е	W.M.	16	NW	SE				
13	S	12	E	W.M.	16	SW	SE				
13	S	12	E	W.M.	16	SE	SE				
13	S	12	Е	W.M.	17	NE	NE				
13	S	12	E	W.M.	17	SE	NE				
13	S	12	E	W.M.	17	NE	SE				
13	S	12	E	W.M.	17	SE	SE				
13	S	12	E	W.M.	21	NE	NE				
13	S	12	E	W.M.	21	NW	NE				
13	S	12	E	W.M.	21	SW	NE				
13	S	12	E	W.M.	21	SE	NE				
13	S	12	E	W.M.	21	NE	NW				
13	S	12	E	W.M.	21	NW	NW				RECEIVED
13	S	12	E	W.M.	21	SW	NW				
13	S	12	E	W.M.	21	SE	NW				NDV 06 2008
13	S	12	E	W.M.	22	NE	NE			WATE	RESOURCES DEPT
13	S	12	E	W.M.	22	NW	NE			- 01	LEW, OHEGON
13	S	12	E	W.M.	22	SW	NE				
13	S	12	E	W.M.	22	SE	NE				
13	S	12	E	W.M.	22	NE	NW				
13	S	12	E	W.M.	22	NW	NW				
13	S	12	E	W.M.	22	SW	NW				RECEIVED
13	S	12	E	W.M.	22	SE	NW				
13	S	12	E	W.M.	22	NW	SW				\$EP 2 5 2008
13	S	12	E	W.M.	22	NE	SE			WA	TER RESOURCES DEF
13	S	12	E	W.M.	22	NW	SE				SALEM. OREGON

	Acres	DLC	Lot	1/4	1/4	Sec	Meridian	ge	Ran	ship	Town
				SE	SE	22	W.M.	E	12	S	13
				NE	NE	23	W.M.	E	12	S	13
				NE	NW	23	W.M.	Е	12	S	13
				NE	SW	23	W.M.	Е	12	S	13
				NE	SE	23	W.M.	Е	12	S	13
				NW	NE	23	W.M.	Е	12	S	13
				NW	SE	23	W.M.	Е	12	S	13
				SW	NE	23	W.M.	Е	12	S	13
				SW	SE	23	W.M.	Е	12	S	13
				SE	NE	23	W.M.	Е	12	S	13
				SE	NW	23	W.M.	Е	12	S	13
				SE	SW	23	W.M.	Е	12	S	13
				SE	SE	23	W.M.	Е	12	S	13
				NW	NE	24	W.M.	Е	12	S	13
				NW	NW	24	W.M.	Е	12	S	13
				NW	SW	24	W.M.	Е	12	S	13
				NW	SE	24	W.M.	Е	12	S	13
				SW	NE	24	W.M.	Е	12	S	13
				SW	NW	24	W.M.	E	12	S	13
				SW	SW	24	W.M.	Е	12	S	13
				SW	SE	24	W.M.	E	12	S	13
				SE	NE	24	W.M.	Е	12	S	13
				SE	NW	24	W.M.	E	12	S	13
				SE	SW	24	W.M.	Е	12	S	13
				SE	SE	24	W.M.	Е	12	S	13
RECEIVED				NE	NE	25	W.M.	E	12	S	13
				NE	NW	25	W.M.	E	12	S	13
NOV 0 a 2008	1000			NE	SW	25	W.M.	E	12	S	13
R RESOURCES DEPT ALEM, OREGON	VVAIL			NE	SE	25	W.M.	Е	12	S	13
ONEGON				NW	NE	25	W.M.	E	12	S	13
				NW	NW	25	W.M.	Е	12	S	13
				NW	SW	25	W.M.	E	12	S	13
				NW	SE	25	W.M.	E	12	S	13
EIVED	RE			SW	NE	25	W.M.	E	12	S	13
2 5 2008	CED			SW	NW	25	W.M.	Е	12	S	13
				SW	SW	25	W.M.	E	12	S	13
SOURCES DEPT				SW	SE	25	W.M.	E	12	S	13
M. OREGON	SALE			SE	NE	25	W.M.	E	12	S	13

Town	ship	Ran	ige	Meridian	Sec	1/4	1/4	Lot	DLC	Acres	
13	S	12	Е	W.M.	25	NW	SE				
13	S	12	Ē	W.M.	25	SW	SE				
13	S	12	E	W.M.	25	SE	SE				
13	S	12	E	W.M.	26	NE	NE				
13	S	12	E	W.M.	26	NW	NE				
13	S	12	Е	W.M.	26	SW	NE				
13	S	12	Е	W.M.	26	SE	NE				
13	S	12	Е	W.M.	26	NE	NW				
13	S	12	E	W.M.	26	NW	NW				
13	S	12	Е	W.M.	26	sw	NW				
13	S	12	E	W.M.	26	SE	NW				
13	S	12	E	W.M.	26	NE	SW				
13	S	12	E	W.M.	26	NW	SW				
13	S	12	Е	W.M.	26	sw	sw				
13	S	12	Е	W.M.	26	SE	SW				
13	S	12	E	W.M.	26	NE	SE				
13	S	12	E	W.M.	26	NW	SE				
13	S	12	E	W.M.	26	SW	SE				
13	S	12	E	W.M.	26	SE	SE				
13	S	12	E	W.M.	27	NE	NE				
13	S	12	E	W.M.	27	NW	NE				
13	S	12	E	W.M.	27	SW	NE				
13	S	12	E	W.M.	27	SE	NE				
13	S	12	E	W.M.	27	NE	NW				
13	S	12	E	W.M.	27	NW	NW				
13	S	12	E	W.M.	27	SE	NW			- Popular	OFFICE
13	S	12	E	W.M.	27	NE	SW			ME	CEIVED
13	S	12	E	W.M.	27	SW	SW			NOV	0 s 2008
13	S	12	E	W.M.	27	SE	SW			WATER RE	OURCEC DEE
13	S	12	E	W.M.	27	NE	SE			SALEN	OURCES DEPT OREGON
13	S	12	E	W.M.	27	NW	SE				
13	S	12	E	W.M.	27	SW	SE				
13	S	12	E	W.M.	27	SE	SE			RE	CEIVED
13	S	12	E	W.M.	34	NE	NE				
13	S	12	E	W.M.	34	NW	NE			SEP	2 5 2008
13	S	12	E	W.M.	34	sw	NE			WATERR	ESOURCES DEPT
13	S	12	E	W.M.	34	NE	NW				M. OREGON
13	S	12	Е	W.M.	34	NW	NW				

	Acres	DLC	Lot	1/4	1/4	Sec	Meridian	ge	Ran	ship	Town
				NW	sw	34	W.M.	E	12	S	13
				NW	SE	34	W.M.	E	12	S	13
				SW	NE	34	W.M.	Е	12	S	13
				SW	SE	34	W.M.	Е	12	S	13
				SE	NE	34	W.M.	Е	12	S	13
				SE	NW	34	W.M.	Е	12	S	13
				SE	SW	34	W.M.	E	12	S	13
				SE	SE	34	W.M.	Е	12	S	13
				NE	NE	35	W.M.	E	12	S	13
				NE	NW	35	W.M.	Е	12	S	13
				NE	sw	35	W.M.	E	12	S	13
				NE	SE	35	W.M.	Е	12	S	13
				NW	NE	35	W.M.	Е	12	S	13
				NW	NW	35	W.M.	Е	12	S	13
				NW	SW	35	W.M.	Е	12	S	13
				NW	SE	35	W.M.	E	12	S	13
				SW	NE	35	W.M.	Е	12	S	13
				SW	NW	35	W.M.	Е	12	S	13
				SW	SW	35	W.M.	E	12	S	13
				SW	SE	35	W.M.	Е	12	S	13
				SE	NE	35	W.M.	Е	12	S	13
				SE	NW	35	W.M.	E	12	S	13
				SE	SW	35	W.M.	Е	12	S	13
				SE	SE	35	W.M.	E	12	S	13
RECEIVED				NE	NE	36	W.M.	E	12	S	13
1120211				NE	NW	36	W.M.	E	12	S	13
NUA 0 ≥ 5008				NE	SW	36	W.M.	E	12	S	13
H HESOURCES DEPT	WATE		-	NW	NE	36	W.M.	E	12	S	13
SALEM, OREGON			1	NW	NW	36	W.M.	E	12	S	13
				NW	SW	36	W.M.	E	12	S	13
				NW	SE	36	W.M.	E	12	S	13
				SW	NE	36	W.M.	E	12	S	13
PARILES				SW	NW	36	W.M.	E	12	S	13
ECEIVED	RI			SW	SW	36	W.M.	E	12	S	13
P 2 5 2008	-00			sw	SE	36	W.M.	E	12	S	13
				SE	NE	36	W.M.	E	12	S	13
RESOURCES DEPT				SE	NW	36	W.M.	E	12	S	13
LEM, OREGON	SF		-	SE	SW	36	W.M.	E	12	S	13

	SE	SE	-	THE RESERVE AND DESCRIPTION OF THE PERSON NAMED IN				-
	OL	SE	36	W.M.	E	12	S	13
	sw	sw	31	W.M.	Е	13	S	13
	SW	SE	31	W.M.	Е	13	S	13
	SE	SW	31	W.M.	Е	13	S	13
	NE	NE	1	W.M.	Е	12	S	14
	NE	NW	1	W.M.	Е	12	S	14
	NE	NE	1	W.M.	Е	12	S	14
	NW	NW	1	W.M.	Е	12	S	14
	NW	SW	1	W.M.	E	12	S	14
	NE	NE	2	W.M.	Е	12	S	14
	NE :	NW	2	W.M.	Е	12	S	14
	NE	SE	2	W.M.	Е	12	S	14
	SW	NW	2	W.M.	E	12	S	14
	SW	SW	2	W.M.	Е	12	S	14
	SW	SE	2	W.M.	E	12	S	14
	NE	NE	3	W.M.	E	12	S	14
	NE	NW	3	W.M.	E	12	S	14
	NE	SW	3	W.M.	E	12	S	14
	NE	SE	3	W.M.	E	12	S	14
	NW	NE	3	W.M.	Е	12	S	14
	NW	NW	3	W.M.	Е	12	S	14
	NW	SW	3	W.M.	E	12	S	14
	NW	SE	3	W.M.	E	12	S	14
	SW	NE	3	W.M.	E	12	S	14
	SW	NW	3	W.M.	E	12	S	14
	SW	SW	3	W.M.	Е	12	S	14
	sw	SE	3	W.M.	Е	12	S	14
	SE	NE	3	W.M.	E	12	S	14
	SE	NW	3	W.M.	E	12	S	14
	SE	SW	3	W.M.	Е	12	S	14
	SE	SE	3	W.M.	E	12	S	14
	NW	NW	11	W.M.	E	12	S	14
	NE	NW	6	W.M.	Е	13	S	14
	NW	NE	6	W.M.	Е	13	S	14
	NW	NW	6	W.M.	Е	13	S	14
		NE NW NW NE NE NE SW SW SW NE NE NE NE NE NE NE NE SW	NE NE NW NW SW NW NE NE NW NE SE NE NW SW SE SW NE NE NW NE SE NE NE NW SW NW SE NW NE SW NW SW SE SW NE SE NW SE NW SE NW SE NW NW NW <	1 NE NE 1 NW NW 1 SW NW 2 NE NE 2 NW NE 2 SE NE 2 SW SW 2 SE SW 3 NE NE 3 NE NE 3 NE NE 3 NE NW 3 NE NW 3 NE SW 3 NE SW 3 NW SW 3 NW SW 3 NE SE 3 NW SE	W.M. 1 NE NE W.M. 1 NW NW W.M. 2 NE NE W.M. 2 NE NE W.M. 2 NW NE W.M. 2 SE NE W.M. 2 SE SW W.M. 3 NE NE W.M. 3 NE NE W.M. 3 NE NE W.M. 3 NE NW W.M. 3 NE NW W.M. 3 NE NW W.M. 3 NE NW W.M. 3 NE SW W.M. 3 NE SW W.M. 3 NW SW W.M. 3 NE SW W.M. 3 NW SE W.M. 3 NW SE W.M. 3	E W.M. 1 NE NE E W.M. 1 NW NW E W.M. 2 NE NE E W.M. 2 NE NE E W.M. 2 NW NE E W.M. 2 SE NE E W.M. 2 SE SW E W.M. 3 NE NE E W.M. 3 SE NE E W.M. 3 SE NE E W.M. 3 SE NW	12 E W.M. 1 NE NE 12 E W.M. 1 NW NW 12 E W.M. 1 SW NW 12 E W.M. 2 NE NE 12 E W.M. 2 NW NE 12 E W.M. 2 SE NE 12 E W.M. 2 SW SW 12 E W.M. 3 NE NE 12 E W.M. 3 NE NE 12 E W.M. 3 NE NE 12 E W.M. 3 SW NE 12 E W.M. 3 NE NW 12 E W.M. 3 NE NW 12 E W.M. 3 NW NW 12 E W.M. 3 <	S 12 E W.M. 1 NE NE S 12 E W.M. 1 NW NW S 12 E W.M. 2 NE NE S 12 E W.M. 2 NW NE S 12 E W.M. 2 NW NE S 12 E W.M. 2 SW SW S 12 E W.M. 2 SW SW S 12 E W.M. 2 SE SW S 12 E W.M. 3 NE NE S 12 E W.M. 3 NW NE S 12 E W.M. 3 NW NE S 12 E W.M. 3 NW NW S 12 E W.M. 3 NW NW S 12 E W.M. 3 NW NW <td< td=""></td<>

WATER RESOURCES DEPT SALEM, OREGON Application T-9663 proposes to change the point of appropriation of Well 3 under the permit to:

Town	nship	Rai	nge	Meridian	Sec	1/4 1/4	Lot	DLC	Location
13	s	12	E	W.M.	16	NW SE			Crater Loop Road Well 3 – 2550 feet North and 2100 feet West from the SE Corner of Section 16.

- Notice of the application for permit amendment was published pursuant to ORS 540.520(5).
 No comments were filed in response to the notice.
- 5. The change would not result in injury to other water rights.
- 6. The change does not enlarge the permit.
- 7. The change does not alter any other terms of the permit.
- Approval of this permit amendment does not grant the permittee permission to trespass on lands not owned by the permittee.

Conclusion of Law

The change in point of appropriation of Well 3 proposed by Permit Amendment Application T-9663 is consistent with the requirements of ORS 537.211.

RECEIVED

NOV 0 6 2008 WATER RESOURCES DEPT SALEM, OREGON

RECEIVED

SFP 25 2008

WATER RESOURCES DEPT SALEM, OREGON

ALLEN, SHERIDAN & McCLANAHAN, LLP ATTORNEYS AT LAW

WM. G. SHERIDAN, JR.

PORTLAND CENTER COMMERCIAL BLDG. TELEP 190 S.W. HARRISON ST. FACS PORTLAND, OREGON 97201 EMAIL.

TELEPHONE (503) 224-4840 FACSIMILE (503) 299-6663 EMAIL WGSESO@AOL.COM

APPLICATION FOR EXTENSION OF TIME

for Quasi-Municipal and Municipal Water Use Permits

TO THE WATER RESOURCES DIRECTOR OF OREGON

I, <u>C</u> r	NAME OF ENTITY RANCH WATER CO. JAMES ROOKS A	Nanager_
P.O.		541-923-1041 HONE
	of record, or duly authorized agent, of Application No. 6-12579, Permit eby request that the time in which to:	No.6-11376,
Q	complete the construction of diversion/appropriation works and/or purchase the equipment necessary to the use of water, which time now expires on Oct be extended to October 1, 2009, 2008 - See E-Mai and/or the time in which to:	ober 1. 1999 .
d	accomplish beneficial use of water to the full extent under the terms of the p now expires on October 1, 1998, be extended to October 1, 2009.	permit, which time
NOTE	Permit extensions for Quasi-Municipal and Municipal permits are eval Chapter 690, Division 315. Except under limited circumstances, upon order approving an extension, you will be required to submit within 3 Management and Conservation Plan (WMCP) under OAR Chapter 69 Diversion of water beyond the maximum rate currently diverted under only be authorized upon approval of your WMCP. The rules may be "www.wrd.state.or.us/law/oar1999.shtml"	issuance of an years a Water 90, Division 86. or the permit shall

Attached are instructions to assist you in completing the information on the permit extension application form. Oregon Water Law and Administrative Rules require this information to be considered by the Water Resources Department when reviewing a Quasi-Municipal or Municipal water use permit extension application. For each permit, a separate extension application must be submitted. All items must be addressed or the application may be returned. Please feel free to provide the Department with any additional information or evidence that will aid us in making our decision. Please use additional sheets of paper as needed to fully respond to the questions.

After reviewing the application form and the instruction sheet, if you have any questions, you may contact the Department at (503) 378-3739, and request assistance from the Water Rights Division, permit extensions personnel. RECEIVED

RECEIVED

Page 1 of 3

APR 06 2004

WATER RESOURCES DEPT SALEM, OREGON

WATER RESOURCES DEPT SALEM, OREGON

APPLICATION FOR EXTENSION OF TIME of Quasi-Municipal and Municipal Water Use Permits

- The appropriate fee, as specified under ORS 536.050.
 A check in the amount of \$100 is attached.
- For water use permits, evidence of the actions taken to begin actual construction on the project, if required under the applicable statute.

The Water Conservation and Management Plan has been completed.

- Evidence of actions taken to develop the right within the permitted time period and/or time period of the previous extension.
 - A) CRRWC has submitted the paperwork to show that we have met the beneficial use and are applying for the certificate.
 - B) The Water Management and Conservation Plan has been completed.
 c) See attached into from 4/3/00 extension app. #3.
- 4. Evidence of compliance with conditions contained in the permit and any previous extension(s). If any of the conditions have not been satisfied, please explain the reason(s) why.

No evidence needed. The Water Management and Conservation Plan has been completed and submitted.

Evidence of the maximum rate of water diverted to date, if any, for Quasi-Municipal or Municipal purposes.

Total water usage from Wells #2, 3, and 4: max.rate 3.75cs 10/95 - 9/96 25,670,595 cubic feet 10/96 - 9/97 26,168,084 cubic feet see attached peak 10/97 - 9/98 27,689,435 cubic feet daily use chart. 10/98 - 9/99 29,201,495 cubic feet 10/99 - 12/99 2,770,800 cubic feet 01/00 - 12/00 18,017,247 cubic feet 20,707,500 cubic feet 01/01 - 12/01

An estimate of the population served under this permit and a description of the methodology(ies) used to make this estimate.

22,680,700 cubic feet

01/02 - 12/02

At this time, CRRWC has approximately 3500 persons which it serves. This number is based on 1448 connections . 2.5 persons per household.

A description of the financial expenditures made toward completion of the water development.

Wages and investigation time and cost total approximately \$24,700, plus Expression Cost of Agr. 2 million. RECEN

APR 0 6 2004

WATER RESOURCES DEPT SALEM, OREGON

8. An estimate of the cost necessary to complete the water WATER RESOURCES DEPT development. Administrative fees (wages, copy charges, etc.) Total approximately OREGON \$15,000. I kn Iliou Sich Ape- 03-0200000

9. A summary of any events that delayed completion of the water development or application of water to full beneficial use, including other governmental requirements, if any, relating to the project that have significantly delayed completion of construction or perfection of the right.

The extent of investigation and research needed to complete the plan, plus the expense of the research and writing of the plan, has delayed the process. Added 10'12 mi of pipeline, waiting for

Lot buildout.

10. An estimated demand projection and a description of the methodology(ies) used for the subject water right permit, considering the other water rights and contracts held by the municipal or quasi-municipal water use permit holder, and a date by which the water development is anticipated to be completed and water put to full beneficial use.

A "Claim of Beneficial Use Site Report" has been submitted to WRD for CRRWC. It has been determined that CRRWC has met beneficial use, perfected the water right, and is applying for a certificate. Growth & projected build out vates indicate growth requirements will exceed water availability. Water needed for service & fire flows

11. A summary of the plan and schedule to complete construction and/or perfect the water right.

Paperwork has been submitted to WRD to show that CRRWC is applying the water to full beneficial use, and requesting a certificate for our water rights. Complete current expansion of system (already expended over #2 million) & drill new well.

to prove up on the 12. Justification for the time requested to complete the project CRRWC is requesting a permit extension of one (5) year in order for Full 5.0cb and/or apply the water to full beneficial use. Air WRD to review and approve our request for certification of our water rights and to approve our Water Conservation and Management plan.

13. Any other information you wish the Department to consider while evaluating the extension of time application.

There are approximately 3500 persons on the water system at this time. Our climate is high plains desert. Without adequate fire protection, it would be impossible to live here. These water rights are invaluable to the residents of Crooked River Ranch and to the members of this water company. We respectfully request that WRD

There are an additional 1500 persons not on the water system but who receive fire protectionprovide this extension as requested. If you require any additional information, please contact James Rooks, General Manager, at 541-923-1041.

RECEIVED

APR 0 6 2004 WATER RESOURCES DEPT SALEM, OREGON In order for the Department to evaluate your extension of time request for a Quasi-Municipal or Municipal water use permit, please provide the following:

RECEIVED

1. The appropriate fee, as specified under ORS 536.050.

APR 0 6 2004
WATER RESOURCES DEPT
SALEM, OREGON

- For Quasi-Municipal water use permits, evidence of the actions taken to begin actual construction on the project, if required under the applicable statute.
- 3. Evidence of actions taken to develop the right within the permitted time period and/or time period of the previous extension.
- 4. Evidence of compliance with conditions contained in the permit and any previous extension(s). If any of the conditions have not been satisfied, please explain the reason(s) why.
- Evidence of the maximum rate of water diverted to date, if any, for Quasi-Municipal or Municipal purposes.
- 6. An estimate of the population served under this permit and a description of the methodology(ies) used to make this estimate.
- 7. A description of the financial expenditures made toward completion of the water development.
- 8. An estimate of the cost necessary to complete the water development.
- 9. A summary of any events that delayed completion of the water development or application of water to full beneficial use, including other governmental requirements, if any, relating to the project that have significantly delayed completion of construction or perfection of the right.
- 10. An estimated demand projection and a description of the methodology(ies) used for the subject water right permit, considering the other water rights and contracts held by the municipal or quasi-municipal water use permit holder, and a date by which the water development is anticipated to be completed and water put to full beneficial use.

Extension requests for greater than 50 years must include documentation that the demand projection is consistent with the amount and types of lands and uses proposed to be served by the permit holder.

- 11. A summary of the plan and schedule to complete construction and/or perfect the water right.
- Justification for the time requested to complete the project and/or apply the water to full beneficial use.
- 13. Any other information you wish the Department to consider while evaluating the extension of time application.

I am the permittee, or have authorization from the permittee, to apply for an extension of time under this permit. I certify that the information I have provided in this application is true and correct to the best of my knowledge.

Signature

Date


MAIL COMPLETED APPLICATION and STATUTORY FEE (under ORS 536.050) TO:

WATER RIGHT PERMIT EXTENSIONS WATER RESOURCES DEPARTMENT 158 - 12th STREET NE SALEM, OREGON 97301-4172

RECEIVED

APR 0 6 2004
WATER RESOURCES DEPT SALEM, OREGON

revised: December 12, 2002



STATE OF OREGON WATER RESOURCES DEPARTMENT

BEEPT # 36665

158 12TH ST. N.E.

INVOICE #_

SALEM, OR 97310-0210 378-8455 / 378-8130 (FAX) 5-105 APPLICATION wer Kanch RECEIVED FROM: PERMIT TRANSFER OTHER: (IDENTIFY) CHECK: # CASH: TOTAL REC'D 910-455 WRD MISC CASH ACCT 0417 S **ADJUDICATIONS** S PUBLICATIONS / MAPS c OTHER: (IDENTIFY) S OTHER: (IDENTIFY) REDUCTION OF EXPENSE CASH ACCT. S VOUCHER # PCA AND OBJECT CLASS SCA# loce11 WRD OPERATING ACCT 0427 MISCELLANEOUS S 0407 **COPY & TAPE FEES** S RESEARCH FEES 0410 S 0408 MISC REVENUE: (IDENTIFY) DEPOSIT LIAB. (IDENTIFY) TC162 (New) RECORD FEE WATER RIGHTS: **EXAM FEE** 0201 SURFACE WATER 0202 S S GROUND WATER 0204 0203 S 0206 0205 TRANSFER WELL CONSTRUCTION LICENSE FEE **EXAM FEE** 0219 0218 WELL DRILL CONSTRUCTOR S \$ LANDOWNER'S PERMIT 0220 S (IDENTIFY) EXTONSION 0240 100.00 OTHER WELL CONST. START FEE 0437 CARD # S WELL CONST START FEE 0211 S CARD # 0210 MONITORING WELLS OTHER (IDENTIFY) 0539 LOTTERY PROCEEDS LOTTERY PROCEEDS S 1302 HYDRO ACTIVITY 0467 LIC NUMBER POWER LICENSE FEE (FW/WRD) 0233 \$ 0231 HYDRO LICENSE FEE (FW/WRD) \$ HRDRO APPLICATION

36665 RECEIPT #

DATED: 4.5.00 BY amanda Ginea

APPLICATION FOR EXTENSION OF TIME

APR 0 3 2000

TO THE WATER RESOURCES DIRECTOR OF OREGON ALEM, OREGON OREGON

1,	CROOKED RIVER	R RANCH WATER	R COMPANY		
	NAME				
	PO BOX 1388	CROOKED	RIVER RANCH,	OR 97760	541-923-1041
	ADDRESS		CITY	STATE ZIP	PHONE

owner of record, or duly authorized agent, of Application No.G-12579, Permit No.G-11376, do hereby request that the time in which to:

(x) complete the construction of diversion/appropriation works and/or purchase and installation of the equipment necessary to the use of water, which time now expires on October 1, 1999, be extended to October 1, 2006,

and/or the time in which to:

accomplish beneficial use of water to the full extent under the terms of the permit, which time now expires on October 1, 1999, be extended to October 1, 2006.


NOTE: The extension of time requested should be long enough to finish the project. Should this request be approved, it will be the Department's expectation that you will complete your project within the new time period allowed. Future extensions may not be granted.

Attached is an instruction sheet to assist you in completing the information on the permit extensions application form. Oregon Water Law and Administrative Rules requires this information to be considered by the Water Resources Department when reviewing a permit extension. All items must be completed or the application will be returned. Please feel free to provide the Department with any additional information that would aid us in making our decision. Please use additional sheets of paper as needed to fully respond to the questions.

After reviewing the application form and the instruction sheet, if you have any questions, please contact the Department at 1-800-624-3199, or locally in the Salem vicinity at (503) 378-3739, and request assistance from the Water Rights Division, permit extensions personnel.

1-Did water system construction/well drilling begin within the time specified in the permit [yes/no]?

2-Has construction of diversion/appropriation works, distribution system, and use of water, if any, been accomplished consistent with the limitations and conditions of this permit [yes/no]? Yes



B) If you have not complied with all applicable conditions, please explain the reasons why and indicate a date certain, in the near future, by which time you will be in compliance with applicable conditions. Three managers in 18 months has disrupted the flow of information regarding projects that needed to be completed. Present management was not aware of this deadline until receipt of a letter from OWRD on 9/17/99. As plans are underway to expand the system, we are asking that this deadline be extended until 10/1/2006.

- 3-I have accomplished the following described works, purchases and installation of equipment necessary to the use of water under said permit:
- A) Within the past year or, if a prior extension was authorized, during the last permit extension period:

 The well #4 project was completed 12/95 at a cost of \$404,000. At that time, we had 1028 meter connections and that number has increased to 1237 meters. The 20 Year Plan was completed at a cost of \$25,500. An additional \$90,360 has been spent for repairs to well #2 and the cistern, the purchase of a chlorination system and an emergency use generator, and emergency repairs to well #4 when the shaft broke.
- B) Prior to the past year or, if a prior extension was authorized, prior to the last extension period:

 Added approximately 100 meters to existing line. Excavated and prepared site for third well (well #4). Had two working (on line) wells completed. Aggresively pursued 800 homesites available to be on (then) current line for hook up.

or acres migatous.	TOTAL Water usage from wells #2, #3 and #4;	
10/95 - 9/96	25,670,595 cubic feet	
10/96 - 9/97	26,168,084 cubic feet	
10/97 - 9/98	27,689,435 cubic feet	
10/98 - 9/99	29,201,495 cubic feet	

Total residential water use 62,874,429 cubic feet Total irrigation water use 45,855,180 cubic feet

- 5-Please list the reasons why the project was not constructed, and/or water not beneficially used within permit time limits under the appropriate categories below. Please provide supporting information for each reason identified.
- A) The project is of a size and scope that the original intent was to phase it in over a period longer than the timeframes allowed in the permit. Although well #4 was completed and went on line to provide adequate water to the existing 1600 lots in our service area, the growth of CRR prompted a plan to increase services to 1932 lots in 2003, and to include all 2630 lots in CRR by the year 2017 (see enclosed charts). In 1997 a high growth, high demand projection of 6% was actually a 6.3% increase in growth and demand.
- B) Financing and/or cash-flow needs to develop the project precluded completion of the project within authorized timeframes. Expansion of our service area will cost an estimated \$3 million, or approximately \$250,000 per year, except for one year when needed improvements will cost approximately \$525,000.
- C) Good faith attempts to comply with permit conditions and/or to acquire permits from other agencies, or otherwise comply with government regulations, delayed completion of the project.

D) Acts of God or other unforeseen events delayed full development of the water system and use of

water. The unforeseen cost increases of repairs and equipment in the last few years was not adequately planned for by this company.

6-Please identify the economic market or markets to which beneficial use of water under the permit is responding. Active water meter connections have increased over 5% per year.

10/95 - 9/96	1020 meters to 1071 meters	
10/95 - 9/97	1079 meters to 1122 meters	

64 meters 237 meters
nit was issued? Added connections has every year, for an average high growth, high demand may continue for several years.
bility of your project? New connection ements since the founding of is built out; these funds will pital improvements without vice area must be expanded.
your community? Yes. There are as outside our service area.
since the permit was issued? _{Yes.} As service area, more private
be able to satisfy the competing demands?
f water that may have been caused by recent

8-Will the income or use from the water development project authorized by this permit provide reasonable returns against the investment in the project? Yes. The fees collected from the expansion of our service area will provide the necessary funds to bring our aging water system up to date. Once the expansion is complete, the additional revenue from water rates will maintain the system.

9-If the extension request is denied, is the current level of water use economically feasible?

We have 396 remaining water sites today. At the present rate of growth, these will be sold within the next 5 to 7 years. We can increase our service area by 272 meters when the first expansion phase is completed. If we are unable to expand, an annual revenue from connection fees of approximately \$84,000 to \$118,000 (at the present fee) will be ended.

I am the permittee, or have authorization from the permittee, to apply for an extension of time under this permit. I understand that false or misleading statements in this extension application are grounds for the Department to suspend processing of the request and/or reason to deny the extension.

Signature

10/12/99

Date

MAIL COMPLETED APPLICATION AND STATUTORY FEE OF \$ 100 TO:

WATER RIGHT PERMIT EXTENSIONS WATER RESOURCES 158 12TH ST NE SALEM, OREGON 97310

Table 6-1 Crooked River Ranch Water Company Capital Improvement Program (CIP)

	Project Title		Estimated Capital Cost during Year of Construction (3)													
CIP Proj ID # ⁽¹⁾		Estimated Capital Cost in 1997 Dollars ⁽²⁾	19	1998		1999		2000		2001		2002	2003	2004 to 2010 ⁽⁴⁾		2011 to 2014 ⁽⁵⁾
SO-1	Source	40.000													,	
SO-2	Convert Well #2 to Production Status	\$34,000	\$ 3	6,040											4 100 100	
30-2	New Well #5 (Scenario C2)	\$1,160,500		7.050		0 407		0.000		0.400			***	\$	2,078,279	400 000
WQ-1	Annual Source Renewal and Replacement Continuous Disinfection Well #4	\$7,500		7,950	\$	8,427	\$	8,933	2	9,469	\$	10,037	\$10,639	\$	80,588	\$71,897
WQ-2	Continuous Disinfection Well #4 Continuous Disinfection Well #2	\$29,000 \$29,000		0,740												
	The state of the s	425,000		0,140												
40	Storage	4.400														
ST-1	Resurface Tower	\$187,000	\$ 19	8,220												
ST-2	Tower Overflow Drainage Improvements	\$20,500			\$	23,034										
ST-3	Tower Security Fencing	\$21,000			\$	23,596										
ST-4	Cistern Repair	\$10,500	\$ 1	1,130												
ST-5	New 1.8 MG Reservoir	\$1,350,000												\$	2,417,644	
	Distribution															
DI-1	Annual Distribution Piping Extensions	\$180,000	\$ 190	0,800	\$	202,248	\$	214,383	\$	227,246	\$	240,881	\$255,333	\$	1,934,116	\$1 70E E00
DI-2	Annual Pipe Renewal and Replacement	\$15,000		No. of the last of	\$	16,854	\$	17,865	\$	18,937	\$	20,073		\$	161,176	\$1,725,522 \$143,793
	The same of the sa											20,010	421,210	*	101,170	\$143,793
	Operation & Management														*	
OM-1	New Meter for Standpipe Customers	\$1,000	\$	1,060												
OM-2	Annual Meter Renewal and Replacement	\$1,000		1,060	\$	1,124	\$	1,191	\$	1,262	\$	1,338	\$1,419	\$	10,745	\$9,586
	TOTAL	3 046,000	\$523	3,640	\$	275,282	-	\$242,372	-	\$256,914	_	272,329	\$288,669		\$6,682,548	\$1,950,798

(1) SO: Source, WQ: Water Quality, ST: Storage, DI: Distribution, OM: Operation and Management

ENR CCI for Seattle for May 1997 = 6,466.29

Costs escalated at estimated

6 percent per year

Costs estimated for 2007 (4)

Costs estimated for 2012


Table 3	-2		
Water Demand	Forecast		
Scenario	1997	2003	2017
High (610% Growth High Demand)	THE STATE OF THE S	は記るる。	経出る地でから
Number of Connections [Meters]"	1,147	1,627	3.679(2)
Average Demand [gpd] (3)	422,096	621,514	1,405,378
[gpm]	293	432	976
Peak Demand [gpd](3)	970,362	1,428,353	3,229,819
[gpm]	674	992	2,243
Medium (48% Growth Typical Demand)	NA CONTRACTOR		
Number of Connections [Meters]"	1,147	1,477	2,662
Average Demand [gpd][3]	422,096	543,536	979,616
[gpm]	293	377	680
Peak Demand [gpd](3)	970,362	1,249,542	2,252,052
[gpm]	674	868	1,564
Eow (2.0% Growth, Low Demand)	世紀 300 300 300 300 300 300 300 300 300 30	SERVICE SERVIC	14、2000000000000000000000000000000000000
Number of Connections [Meters](")	1,147	1,292	1,704
Average Demand [gpd] (3)	422,096	231,268	305,016
[gpm]	293	161	212
Peak Demand [gpd] (3)	970,362	532,304	702,048
[gpm]	674	370	488
Total Number of Lots within Service Area	1,660	1,932	2,630

(1) The number of connections for 1997 was provided by CRRWC. Number of connections for 2003 and 2017 was calculated using the equation N = n(1+%) where N is the future number of connections, n is the current number of connections, percentage is the growth rate, and y is the number of years.

(2) The number of connections in 2017 exceeds the 2,630 total number of lots at the Ranch. This estimate includes the potential for re-zoning at the Ranch thereby creating more lots, or that at 6.0% growth rate the Ranch reaches the 2,630 buildout prior to 2017.

(3) Average demand and peak demand are calculated by multiplying the number of connections by Meter Demands. Meter demands are as follows:

Trend	Meter Demand (gpmd)
High Usage	60、100人或数数数数数数
Average Day	382
Peak Day	878
Typical Usage of the	ENGINEE TENEDONIO AND ENGINE
Average Day	368
Peak Day	846
Low Usage P Service	引用於公路及否認的的性子
Average Day	179
Peak Day	412








Exhibit 3-2 Growth Projections







February 21, 2007

Water Resources Division Water Rights/Adjudications 725 Summer St. NE Suite A Salem, OR 97301

Re: Correction of Address

G12579, G11376, T9663

Dear Sirs:

In reviewing the Water Rights Information Query, I found that the incorrect mailing address is on file for the Crooked River Ranch Water Co-op. Please note the correct address:

Crooked River Ranch Water Cooperative PO Box 2319 Terrebonne, OR 97760

Please update your files and confirm that the address has been corrected.

Sincerely,

Barb Oakley

Administrative Assistant

Barb@crrwc.com

RECEIVED

FEB 26 2007

WATER RESOURCES DEPT SALEM, OREGON



Want Charles Charles

PO BOX 2319 TERREBONNE, OR 97760



Water Resources Division Water Rights/Adjudications 725 Summer St. NE Suite A Salem, OR 97301



Water Resources Department North Mall Office Building 725 Summer Street NE, Suite A Salem, OR 97301-1271 503-986-0900

FAX 503-986-0904

April 14, 2009

REFERENCE: Application for Extension of Time

Dear Extension of Time Applicant:

The Water Rights Section has received your application for an extension of time for **APPLICATION FILE#: G-12579 (PERMIT#: G-11376).** Your application will be reviewed in the near future. Following the review, you will receive a Proposed Final Order either approving or rejecting the extension of time request. A 45-day protest period begins upon issuance of the Proposed Final Order. After the protest period closes, a Final Order is issued.

If you have questions concerning your extension of time application, please contact Scott Kudlemyer at (503) 986-0813. For general information about the Water Resources Department, you may contact the Water Resources' Customer Service Group at (503) 986-0801 or you may access the Department's Internet home page at: "www.wrd.state.or.us".

STATE OF OREGON WATER RESOURCES DEPARTMENT

RECEIPT # 94829

725 Summer St. N.E. Ste. A SALEM, OR 97301-4172

(503) 986-0900 / (503) 986-0904 (fax)

INVOICE # _

RECEIVED FROM: CYDD KED RIVEY RANCH	APPLICATION	9-12579
BY:	PERMIT	
	TRANSFER	
CASH: CHECK# OTHER: (IDENTIFY) 5945	TOTAL REC'D	\$350.00
1083 TREASURY 4170 WRD MISC CASH A	ACCT	
0407 COPIES		\$
OTHER: (IDENTIFY)		\$
0243 I/S Lease 0244 Muni Water Mgmt. Plan 02	45 Cons. Water	
4270 WRD OPERATING	ACCT	
MISCELLANEOUS / / 1 - 111		
0407 COPY & TAPE FEES		\$
0410 RESEARCH FEES		\$
0408 MISC REVENUE: (IDENTIFY)		S
TC162 DEPOSIT LIAB. (IDENTIFY)		\$
0240 EXTENSION OF TIME		\$ 350,00
WATER RIGHTS: EXAM FEE		RECORD FEE
0201 SURFACE WATER S	0202	\$
0203 GROUND WATER \$	0204	\$
0205 TRANSFER \$		
WELL CONSTRUCTION EXAM FEE		LICENSE FEE
0218 WELL DRILL CONSTRUCTOR \$	0219	\$
LANDOWNER'S PERMIT	0220	\$
OTHER (IDENTIFY)		
0536 TREASURY 0437 WELL CONST. STA	RT FEE	
0211 WELL CONST START FEE \$	CARD #	
0210 MONITORING WELLS \$	CARD #	
OTHER (IDENTIFY)		
0607 TREASURY 0467 HYDRO ACTIVITY	LIC NUMBER	
0233 POWER LICENSE FEE (FW/WRD)	LIO HOMBELL	s
0231 HYDRO LICENSE FEE (FW/WRD)		\$
		\$
HYDRO APPLICATION		\$
TREASURY OTHER / RDX		
FUND TITLE		
OBJ. CODE VENDOR #		
DESCRIPTION		\$

RECEIPT: 94829 DATED: 11/6/08 BY: LTG

STATE OF OREGON WATER RESOURCES DEPARTMENT

песеірт# 94829

725 Summer St. N.E. Ste. A SALEM, OR 97301-4172

INVOICE # _

		(203) 300-	09007 (503) 90	U-USU4 (Idx		le lot ac
RECEIVED FRO	M: Crooked	RIVer	Kanch		APPLICATION	9-12719
BY:					PERMIT	
					TRANSFER	
CASH: C	5745	OTHER: (IDE	NTIFY)	[TOTAL REC'D	\$350.00
1083	TREASURY	4170	WRD MISC	CASH A	CCT	
0407	COPIES					S
	OTHER: (IDENTIFY)				\$
0243 I/S L	ease 0244	Muni Water	Mgmt, Plan	024	5 Cons. Water	
			WRD OPER			
-	MISCELLANEOUS	3	111	111		
0407	COPY & TAPE FE		410	111		\$
0410	RESEARCH FEES		1 =			\$
0408	MISC REVENUE:	(IDENTIFY)				\$
TC162	DEPOSIT LIAB. (I	DENTIFY)				\$
0240	EXTENSION OF T	IME				\$350,00
	WATER RIGHTS:			XAM FEE		RECORD FEE
0201	SURFACE WATER	}	S		0202	\$
0203	GROUND WATER		\$		0204	\$
0205	TRANSFER		\$			
	WELL CONSTRU	CTION	1	EXAM FEE		LICENSE FEE
0218	WELL DRILL CON	STRUCTOR	\$		0219	\$
	LANDOWNER'S P	ERMIT			0220	\$
	OTHER	(IDENTIFY	()			
0000	TDE 4 011DV	0.407	WELL CON	OT OTAL	DT FFF	
0536	TREASURY	0437	WELL CON	151. 51AI	RIFEE	
0211	WELL CONST ST	ART FEE	\$		CARD #	
0210	MONITORING WE	LLS	\$		CARD #	
	OTHER	(IDENTIFY	Y)			
0607	TREASURY	0467	HYDRO AC	TIVITY	LIC NUMBER	
0233	POWER LICENSE	FEE (FW/W	(RD)			\$
0231	HYDRO LICENSE	FEE (FW/W	RD)			\$
	HYDRO APPLICA	TION				\$
	TREASURY		OTHER / R	DX		
OBJ. COD)E	_ VENDOR	#			[6
DESCRIP	TION					\$
-				_		

94829

DATED: 11/6/08 BY: 48

05945

Crooked River Ranch Water Co-Op WATER RESOURCES DEPT

> Date Type 9/19/2008 Bill

Reference

Original Amt. 350.00

Balance Due 350.00 Check Amount

Discount

9/19/2008

Payment 350.00 350.00

RECEIVED

SEP 25 2008

WATER RESOURCES DEPT SALEM, OREGON

Applicati	ion # G- 12579 Permit # G- 1/376
	(amended by T-7828 and T-9663)
Put	per Division 315 Rules (Extensions received on July 1, 2001 or after)
♦ WRIG	Money Receipted on: 11/6/08 ension Specialist
Ø	Added to tracking spreadsheet
	is receipted and app is added to spreadsheet, route to nine Skaug Publish on Public Notice (initial 30-day comment): Date of notice
	Update WRIS Database
	In the "PNotice Date" field Enter the date the Extension Application was published on the Public Notice.
	the "Ext Filed" field Enter the date the Extension Application was received.
Yes or No:	Return file to Extension Specialist after PN

STATE OF OREGON

COUNTY OF JEFFERSON AND DESCHUTES

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

CROOKED RIVER RANCH WATER COMPANY P.O. BOX 879 (300)
CROOKED RIVER RANCH, OREGON 97760

503-548-8939

to use the waters of WELLS 2 & 3 in the CROOKED RIVER BASIN for QUASI-MUNICIPAL USE.

This permit is issued approving Application G-12579. The date of priority is JUNE 18, 1991. The use is limited to not more than 5.0 CUBIC FEET PER SECOND (CFS), BEING 2.5 CFS FROM EACH WELL, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

NW 1/4 NW 1/4, SW 1/4 SE 1/4, SECTION 24, T 13 S, R 12 E, W.M.; WELL 2 - 680 FEET SOUTH AND 780 FEET EAST FROM NW CORNER, SECTION 24, WELL 3 - 80 FEET NORTH AND 480 FEET EAST FROM S 1/4 CORNER, SECTION 24.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

NW 1/4 NW 1/4 S 1/2 SW 1/4 SECTION 4 E 1/2 NE 1/4 SE 1/4 SW 1/4 SE 1/4 SECTION 5 NE 1/4 NE 1/4 NW 1/4 SECTION 8 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 9 S 1/2 NW 1/4 SW 1/4 S 1/2 SE 1/4 SECTION 10 SW 1/4 SW 1/4 SECTION 13 SW 1/4 NE 1/4 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 14 ALL SECTION 15 ALL SECTION 16 E 1/2 NE 1/4 E 1/2 SE 1/4 SECTION 17 N 1/2 SECTION 21

PAGE TWO

```
N 1/2
              NW 1/4 SW 1/4
              N 1/2 SE 1/4
              SE 1/4 SE 1/4
               SECTION 22
                 NE 1/4
              E 1/2 NW 1/4
              E 1/2 SW 1/4
                 SE 1/4
               SECTION 23
                 NW 1/4
                 S 1/2
               SECTION 24
               SECTION 25
                  ALL
               SECTION 26
                 E 1/2
              N 1/2 NW 1/4
              SE 1/4 NW 1/4
              NE 1/4 SW 1/4
              S 1/2 SW 1/4
              SECTION 27
              N 1/2 NE 1/4
              SW 1/4 NE 1/4
                 NW 1/4
              E 1/2 SW 1/4
                 SE 1/4
               SECTION 34
                  ALL
               SECTION 35
              N 1/2 NE 1/4
             SW 1/4 NE 1/4
                 W 1/2
                 SE 1/4
               SECTION 36
TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.
              S 1/2 SW 1/4
             SW 1/4 SE 1/4
               SECTION 31
TOWNSHIP 13 SOUTH, RANGE 13 EAST, W.M.
              N 1/2 NE 1/4
              N 1/2 NW 1/4
             SW 1/4 NW 1/4
               SECTION 1
             N 1/2 NE 1/4
             SE 1/4 NE 1/4
             W 1/2 SW 1/4
             SE 1/4 SW 1/4
               SECTION 2
                  ALL
               SECTION 3
             NW 1/4 NW 1/4
              SECTION 11
TOWNSHIP 14 SOUTH, RANGE 12 EAST, W.M.
             NW 1/4 NE 1/4
             N 1/2 NW 1/4
               SECTION 6
TOWNSHIP 14 SOUTH, RANGE 13 EAST, W.M.
```

Within one year from the date the Water Resources Commission adopts rules describing the schedules, standards and procedures for water conservation management plans by water suppliers, Crooked River Ranch Water Company shall submit a plan which is consistent with said rules.

PAGE THREE

Within one year of permit issuance, Crooked River Ranch Water Company shall prepare a plan/timetable for the Water Resources Commission which shall indicate the steps which the Water Company intends to pursue to obtain a long-term water supply.

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the wells at all times. When required by the department, the permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before November 18, 1992, and shall be completed on or before October 1, 1993. Complete application of the water shall be made on or before October 1, 1994.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

Issued this date, NOVEMBER 18, 1991.

/b/ WILLIAM H. YOUNG

Water Resources Department William H. Young Director Final Draft to

Crooked River Ranch Water Company

Water Management and Conservation Plan (WMCP) Final Draft Report

September 2003







MAR 1 5 2004

WATER RESOURCES DEPT SALEM, OREGON



Final Draft to

Crooked River Ranch Water Company

Water Management and Conservation Plan (WMCP) Final Draft Report

September 2003







Table of Content

Exe	ecutive Summary	
E-1	Meeting the WMCP Criteria	ES-1
E-2	Proposed Schedule for Updating Plan	
Sec	ction 1 Overview	
1.1	General System Description	1-1
1.2	Purpose	
1.3	Proposed Progress Report and Update Schedule	1-2
1.4	Summary of Data Sources	1-2
1.5	Input During Plan Development	1-2
1.6	Document Organization	1-2
Sec	ction 2 Municipal Supplier Description	
2.1	Service Area and Population	2-1
2.2	Source of Supply	2-3
2.3	Summary of Existing System	2-5
2.4	Summary of Historic Production	2-9
2.5	Water Customers Served	2-10
2.6	Interconnections	2-12
2.7	System Efficiency	2-13
Sec	ction 3 Conservation Element	
3.1	Water Use and Reporting	3-1
3.2	Previous and Existing Conservation Measures	3-2
3.3	Planned Conservation Measures	3-4
3.4	Summary of 5-Year Benchmarks	3-6
Sec	ction 4 Water Curtailment Element	
4.1	Assessment of CRRWC's Ability to Supply Water Long Term	4-2
4.2	Water Emergency Response	
4.3	The Curtailment Plan	4-3
	ction 5 Municipal Water Supply Element	
5.1	Future Service Area	5-1
5.2	Schedule for Beneficial Use	5-2
53	Demand Forecast	5.2

Tables and Exhibits

-			
	ſa	n	C
-		_	

2-1	Population Estimates from the Association	2-2
2-2	Population Estimates from CRRWC	
2-3	Water Rights Summary	
2-4	Summary of System Pipe Sizes	2-5
2-5	Well Facilities Summary	2-6
2-6	Finished Water Storage Summary	2-7
2-7	Summary of Recent Water Production	2-9
2-8	Accounts Per Customer Class	2-11
2-9	Historic Customer Count and Annual Water Use 1998 through 2002	2-12
2-10	Fireflow Usage	2-12
2-11	Summary of Leakage Calculation	
3-1	5 Year Conservation Benchmark Savings	3-6
3-2	5-Year Conservation Benchmarks	3-7
4-1	Proposed Curtailment Plan	4-4
5-1	Customers of CRRWC by Customer Class	5-1
5-2	Residential Population Estimates	
5-3	Water Demand Factor	
5-4	Metered Customers' Demand Forecast	
5-5	Total System Demand Forecast	
Figu	re	
2-1	Monthly Production: 1998-2002	2-10
Exhi	ibits (at end of each section)	
-1	Location of Crooked River Ranch	
2-1	Crooker River Ranch Water Company Service Area	
2-2	Well Depth and Location	
2-3	Deschutes River Basin Hydrology Schematic	
-4	Well Depth Diagram	
-5	Topographic Map of CRRWC's System	
-1	Example Flyer: "Groundwater Friendly Gardening"	

Executive Summary

The Crooked River Ranch Water Company (CRRWC) presents its 2003 Water Management and Conservation Plan (WMCP) to the Water Resources Department (WRD) and interested parties. CRRWC believes this WMCP outlines a plan to effectively manage its present water rights and provides a means for developing a comprehensive strategy for meeting its quasi-municipal water supply needs over the next 20 years. This WMCP will enhance management techniques of the State of Oregon's water resources, including an increased effort to improve the efficiency of the water system, thereby meeting the intent of the regulations defined under Oregon Administrative Rules 690-086.

CRRWC is submitting this plan in preparation for future system improvements. Specifically, the paperwork proving beneficial use and filing for a certificate of our 5.0 cfs water rights was submitted in August of 2003 to WRD. Approval of this WMCP will initiate the submittal of an application by CRRWC to WRD for a change in point of diversion from the same aquifer.

E.1 Meeting the WMCP Criteria

Approval of this WMCP is contingent upon CRRWC meeting the criteria outlined under OAR 690-086-0130. In accordance, CRRWC has prepared a concise statement addressing each of the review criteria cited in that regulation.

- Inclusion of specific elements under 690-086-125: This WMCP includes specific sections that address each of the elements, including the water system and history, an updated conservation plan, a new curtailment plan, and a 20-year supply strategy.
- Projections of future water need: CRRWC is projecting an increase in average day demand over the next 20 years of about 6.5% to 491,000 gallons per day. Maximum day demand is forecast at almost 1.5 million gallons per day for 2023. To meet these demands and meet fire flow standards set by the local fire marshal, CRRWC will need access to its entire 5.0 cfs water right.
- Water Conservation Measures under OAR 690-086-0150: CRRWC has developed a conservation program targeted at reducing peak and non-peak day demand. The program and associated measures are designed to incorporate each of the appropriate components noted under OAR 690-086-0150 (4). A summary of the measures and related benchmarks for the conservation program are outlined in Table ES-1.

	Table ES-1 ver Ranch Water Co onservation Benchm		
Existing Measures	Implementation Date	Completion Date	Frequency of Program
Annual water audit	On-going	On-going	Annually
Visual inspection of reservoirs	On-going	On-going	Daily
Meter testing & maintenance program	On-going	On-going	Annually
Production meter testing	On-going	On-going	Annually
Public Education Low water use landscaping Bill back messages	On-going	On-going	As Needed
Pressure reducing valves	On-going	On-going	N/A
SCADA system monitoring	On-going	On-going	Daily
Water conserving policies	On-going	On-going	N/A
System metering	On-going	On-going	N/A
Planned Measures			
Rate adjustments	July 2004	July 2011	Annually
Public Education Enhanced frequency of bill back messages Inefficient water fixture brochure Semi-yearly newsletter	??		See text in Section 3.3
GPS mapping of system to indirectly reduce leakage volumes	March 2003	March 2008	N/A

- Identification of Resource Issues: The source of water being drawn by CRRWC is exclusively groundwater and, to CRRWC's knowledge, CRRWC's diversions have not been identified as impacting local surface water bodies. Therefore, the issues defined under OAR 690-086-140 (5) (i) do not apply.
- Curtailment Plan: The curtailment plan element represents a tool available to the CRRWC to meet a water emergency. The curtailment plan includes four stages of alert, triggers for each stage, and curtailment actions that will satisfactorily promote conservation practices.
- Submittal of Plan to affected local governments: 30 days prior to the submittal of this WMCP, CRRWC provided copies of this WMCP to the following affected local governments for review and comment: Deschutes County and Jefferson County. No comments were received from either government regarding the content of this WMCP.

E.2 Proposed Schedule for Updating Plan

CRRWC proposes to submit an updated WMCP within 10 years of the date of approval of this initial WMCP unless significant changes occur at the Ranch before that time which would impact the validity and applicability of this WMCP. In such a case, an updated WMCP will be submitted earlier.

Section 1

Overview

1.1 General System Description

Crooked River Ranch is located on the east side of the Cascade Mountains in Central Oregon and is 12,000 acres in size. The Ranch is approximately nine miles west of Terrebonne (see Exhibit 1-1), and 20 miles northwest of Redmond. Crooked River Ranch is located at the southern end of Jefferson County though a portion sits in Deschutes County. The Ranch is the largest subdivision in the state of Oregon. Crooked River Ranch Club and Maintenance Association (Association) is a home owners association, run by an elected, 9 member Board of Directors. The Crooked River Ranch Water Company (CRRWC) serves approximately 3,500 customers within its quasi-municipal service.

The Crooked River Ranch Water Company and the Association are two separate entities. CRRWC is a member of the Association in that it pays yearly dues, and the Association is a member of the CRRWC in that some of the Association's facilities, like the golf club house, are connected to the water system. Neither organization has any control over the other.

Approximately 97% of CRRWC's connections serve residential customers since this community is comprised of primarily single-family dwellings. Approximately three (3%) percent of the CRRWC accounts are commercial. These residential and commercial users are further described in Section 2.4.

CRRWC has been permitted 5.0 cfs of water rights for its quasi-municipal use under permit #G-11376, with a priority date of June 18, 1991. CRRWC is in the process at this time of having these rights certificated. The water rights are associated with two wells owned by CRRWC and one well owned by the Association, which is used by CRRWC for emergency purposes. This is described in further in Section 2.3.

Both CRRWC and the Association have wells on the Ranch. CRRWC plans to renumber their wells in order to try to prevent confusion regarding ownership of the wells by the two entities. The new numbering system is used throughout this report. The changes will be as follows:

Current	New
Well No. 1	Crooked River Ranch Association Well # 1
Well No. 2	Crooked River Ranch Water Co. Well #2
Well No. 3	Crooked River Ranch Assn. Well #3
Well No. 4	Crooked River Ranch Water Co. Well #1
Well #5 (proposed)	Crooked River Ranch Water Co. Well #3

1.2 Purpose

The CRRWC recently completed research on their water rights, and found that CRRWC's previous permit extension had expired. As a result, a new permit extension was filed which then triggered the need to prepare a Water Management and Conservation Plan (WMCP) per Oregon Administrative Rules (OAR) 690-315 and 690-086.

The CRRWC is in the process of updating their 20 Year Water System Master Plan in conjunction with this WMCP.

1.3 Proposed Progress Report and Update Schedule

Following the administrative rules, the CRRWC proposes to submit a progress report on or before July 2008 (five years) to review noted benchmarking and water use progress. CRRWC does anticipate the need for a new point of diversion, and will be filing for such in the spring of 2004. This will be CRRWC's third production well (CRRWC's Well #3), which is needed as an alternate source in case of a well failure of CRRWC's newly renumbered Well #1 or if it is down for preventative maintenance. As part of the process of developing this third production well, CRRWC has applied to certificate their current water right, and plans to subsequently transfer water rights from the Association's Well #3 to the planned CRRWC Well #3. This is addressed in the WMCP, and as a result CRRWC is not planning to submit an updated WMCP until the required 10 year period in 2013.

1.4 Summary of Data Sources

Throughout this WMCP are references to data, most of which were obtained from CRRWC's files including records of pumping withdrawal, customer billings, operational control, and conservation program implementation. Historical data related to service area, such as connections and demand, was obtained from the CRRWC's billing system, the water demand management software system (SCADA), and the 20 Year Water System Master Plan.

1.5 Input During Plan Development

During the preparation and completion of this plan, CRRWC consulted with Economic and Engineering Services, Inc. (EES), and Bruce Estes, Certified Water Rights Examiner of Estes Surveys, LLC, and had discussions with the Water Resources Department (WRD), and the Department of Human Services Drinking Water Program. In addition, CRRWC staff attended the workshop presented by the League of Oregon Cities, EES and WRD regarding the preparation of a WMCP.

1.6 Document Organization

This WMCP is organized in a manner consistent with the Division 86 rules. Section 2 describes the water supply system, including key demographic information, water consumption, and the

type of infrastructure present in the water system. Section 3 identifies the conservation measures CRRWC has implemented and proposed new measures with associated benchmarks for each new measure. Section 4 describes the three tools available to the company in the event of a water emergency, including a water curtailment plan. Section 5 uses the information presented in Section 2 and Section 3 to forecast future demand, compares that demand to present water rights, and assesses the need for additional source water diversions (e.g. "green light water").



Exhibit 1-1
Location of Crooked River Ranch

Section 2

Municipal Supplier Description

Section 2 describes characteristics of CRRWC's service area, customers, supply, and production, as well as other key elements of the system.

2.1 Service Area and Population

The majority of the 12,000 acres called Crooked River Ranch is situated in the southern portion of Jefferson County and a small portion of Deschutes County. The area is bounded on the north by National grass lands and the Crooked River, on the west by the Deschutes River and Bureau of Land Management lands, on the east by the Crooked River, and on the south by Bureau of Land Management and privately owned land. The Ranch is approximately ten miles in length. The south end of the Ranch is approximately four miles wide, and the north end approximately one mile wide. Crooked River Ranch is approximately 18 miles NW of Redmond and 26 miles SW of Madras. It sits approximately 5 miles off Hwy. 97. Exhibit 1-1 shows the location of Crooked River Ranch.

Service Area

CRRWC's service area boundaries are the same as the Crooked River Ranch boundaries, however the types of services offered residents differ for those customers in the northern versus southern portions of the Ranch. A map of the CRRWC's service area is shown in Exhibit 2-1.

The northern section of the ranch, which holds the majority of the population, is served by CRRWC with domestic water and fire flow service. In this portion of the Ranch, there are approximately 1,450 customers (read: accounts) of CRRWC. Note that there are approximately 40 residences in this northern portion which rely on private wells for domestic use, but these customers also rely on CRRWC for fire protection.

In the southern portion of the Ranch, CRRWC does not provide domestic water to residents, but does provide fire flow via hydrants and standpipes near the border between the northern and southern portion of the Ranch. The Ranch is provided fire protection services by the Crooked River Ranch Rural Fire Protection District, which covers the entire Ranch. Since the private wells which all southern Ranch residents rely upon cannot adequately supply water in the event of a house or wild fire, the Fire Department will fill their tanker trucks at a hydrant or standpipe and haul the water to the fire scene. It's important to note that the Fire Department is totally volunteer, and they only have tanker trucks – no ladder or pump trucks. Again, all water used by the Fire Department on the Ranch, both to fight fires and suppress simulated fire events, is from the CRRWC system. The construction of CRRWC Well #3 as described in Section 1 will

decrease the amount of time it takes for the fire department to fill its water tankers and provide more adequate fire flow for the community.

Population Estimates

The Association provided population estimates summarized in Table 2-1. These estimates represent a population for the entire Ranch since CRRWC serves all Ranch residents with at least fire flow service. Note that since the Association only maintains records of the total number of properties that have been sold on the Ranch and not population, the Association estimates population by assuming 2.5 persons per household.

Table 2-1 Crooked River Ranch Water Company Population Estimates from the Association		
Year	Total Population	Households
1998	3,015	1,206
1999	3,327	1,331
2000	3,640	1,456
2001	N/A	*N/A
2002	3,795	1,518

^{*}Crooked River Ranch Administration did not have numbers available for 2001.

In 2002, there were 3,795 developed lots in the Ranch, which represents about a 9 percent increase since 1998. Using data from CRRWC's billing system, CRRWC estimates that in 2002 a little more than a third of these developed lots, or 1,404 residential lots, were served domestic water by CRRWC. Applying a persons per household count of 2.5 reveals 3,510 people were served by CRRWC at that time. Table 2-2 shows the estimated population of CRRWC from 1998 to 2002.

Table 2-2 Crooked River Ranch Water Company Population Estimates from CRRWC		
Year	Total Population	Households
1998	2,763	1,105
1999	3,215	1,286
2000	3,283	1,313
2001	3,368	1,374
2002	3,510	1,404

Regarding the 2.5 person per household figure, the Ranch is inhabited by retired persons and families in an approximate ratio of 1 to 1. In light of the fact that the Census 2000 counted 2.8 persons per household for Jefferson County¹, CRRWC agrees with the Association's estimate of 2.5 persons per household given the higher percentage of retired residents inhabiting the Ranch than the County as a whole.

CRRWC used Association estimates of developed properties as a basis for population estimates because population estimates from the county or Census 2000 were not available for Crooked River Ranch. The Ranch is considered a subdivision and unincorporated and therefore all Ranch statistics are wrapped up within total county population estimates. Also, when the 2000 Census was referenced, population for the Ranch was not available without attempting the task of apportioning population within Ranch boundaries based on census track data. This arduous task would have revealed probably no more accurate population estimates than the ones provided by the Association.

2.2 Source of Supply

CRRWC relies strictly on groundwater to provide its source of supply. This section includes of a summary of CRRWC's water rights and the adequacy and reliability of their source of supply.

Water Rights Summary

The CRRWC has a water right permit allowing for access to 5 cfs or 3.23 mgd at three wells. Table 2-3 describes this right, including permit number, priority date, and other pertinent information.

Table 2-3 Crooked River Ranch Water Company Water Rights Summary						
Groundwater Source	Permit #	Priority Date	Amount	Completion Date	Type of Use	Well No.
Crooked River Basin	G-2280	Jan. 24, 1963	(1)	(1)	IR	2
Crooked River Basin	G-11376	June 18, 1991	5 cfs (3.23 MGD)	Oct. 1, 1994	Quasi- municipal	1, 2, and Assn. 3
Crooked River Basin	Cert. 75144 T-6604	Jan. 24, 1963	0.06 cfs		IR	2

⁽¹⁾ Permit G-2280 is superceded by G-111376.

CRRWC believes it is important to provide a history of their water rights issues as a point of reference for the current water right permit being considered in this WMCP. Permit #G-2280 was originally in the name of Thomas Bell, who owned the ZZ Cattle Company, now known as Crooked River Ranch. On April 10, 1979, Mr. Bell assigned all his water rights to the Crooked River Ranch Water Company, and on August 23, 1979, the Water Resources Department issued a Certificate of Water Right to the CRRWC for irrigation of 91.1 acres using Well #2. This was limited to 1.14 cfs. WRD determined that the CRRWC was not the "owner" of these water

¹ Though CRRWC falls within Jefferson and Deschutes County, most of the Ranch is within Jefferson County.



Municipal Supplier Description
Crooked River Ranch Water Company

rights since CRRWC did not provide irrigation. In November, 1991, the WRD issued Permit #G-11376 to CRRWC establishing 5.0 cfs for quasi-municipal use from Wells #2 and 3. On October 30, 1997, WRD approved Permit Amendment #T-7828 for an additional point of appropriation for CRRWC to add Well #1. This modified Permit G-11376. It still limits CRRWC to 5.0 cfs, but now lists CRRWC Wells #1 and 2, and the Association Well #3 as authorized points of diversions.

On March 27, 2003, WRD issued a letter outlining the water rights for the CRRWC and the Association. They stated that there are 4.4 acres of irrigation rights remaining from Well #2, as described in Certificate #75144. Since Well #2 is owned by CRRWC, 0.06 cfs to irrigate these 4.4 acres was determined to be part of CRRWC's water rights.

Adequacy and Reliability

According to the Watermaster's Office in Bend, the wells used by CRRWC are utilizing the same aquifer since the wells are all basically near the same depth. This aquifer feeds the Crooked River and the Deschutes River. Exhibit 2-2 shows the relative elevations of the wells and well screens.

Estimates of groundwater age can be used to assess the relative vulnerability of an aquifer to contamination from land surface, by evaluating the tritium concentrations in the ground water. Alternatively, the age of groundwater provides an indication of whether production from the aquifer is capturing more recently recharged groundwater and causing more direct depletion of recharge. Kyle Gorman, Regional Watermaster, states that the USGS did a survey of the Deschutes Aquifer, and at Opal Springs, and found no Tritium in the water. Mr. Gorman states that this means the water was recharged before nuclear testing began, and that would have been about 50+ years ago². This provides evidence that the aquifer current production from the aquifer has not depleted the older water in the reservoir.

The Water Resources Department has also determined that the Deschutes River Basin is *not* a "critical ground water area". However, the Deschutes River Basin has received much attention due to the low summer flows in the middle Deschutes River area attributed to historical diversions. Exhibit 2-3 is a graphical model of the various flows within the Deschutes Basin.

In Exhibit 2-3, the locations of the zones of groundwater aquifer recharge and discharge are identified. Recall that Exhibit 1-1 showed CRRWC located a few miles upstream from the confluence of the Crooked River and Deschutes River. Using the Crooked River as reference point in Exhibit 2-3, CRRWC is shown to be located in the Deschutes groundwater discharge zone, and thefore does not contribute to the historic low summer flows of the middle Deschutes basin.

CRRWC considers the aquifer from which it draws drinking water both adequate and reliable and therefore CRRWC does not anticipate future restrictions on this supply. CRRWC has not experienced any declining water levels in the aquifer nor had a lack of supply even during peak

² Higher levels of tritium were introduced into the atmosphere as a result of nuclear testing.



production. Also, the 1997 20 Year Master Plan discusses the depth and abundance of the aquifer, suggesting a low probability of quantity problems in the near future.

2.3 Summary of Existing System

The existing water system at CRRWC consists of two wells and one shared well with the Association, two storage reservoirs and about 35 miles of distribution piping and related components. A description of the existing facilities follows. See Exhibit 2-1 for the location of these facilities.

Source and Treatment

All wells are currently in compliance with state drinking water standards outlined under OAR 333-065. No water treatment is being done at this time at either Well # 1 or 2 as neither are plumbed correctly to accommodate a chlorination station. However, CRRWC has not experienced any problems with water samples, and has won taste test contests with the quality of the water.

Transmission and Distribution

Crooked River Ranch Water Company has a system network of pipe sizes ranging from 2-inch to 12-inch pipes. These are shown in Exhibit 2-1. The total linear feet of each nominal pipe size 2-inch and above is shown in Table 2-4.

	Table 2-4 ked River Ranch Water Compa summary of System Pipe Sizes	
Nominal Pipe Size	Total Length (ft)	% of Total
2"	800	0.004%
4"	35,810	17%
6"	88,360	43%
8"	79,020	39%
12"	750	0.004%

Pressure Zones

CRRWC has two service levels: the upper level and the lower level. The upper level is approximately 200 feet higher in elevation than the lower level. Within these levels, there are eight pressure zones, controlled by 4 pressure reducing valves. There is a different pressure zone on each side of the pressure reducing valve.

Wells

The two wells owned by CRRWC are Well #1, located in the upper service level, and #2, located in the lower level. Well #1 and #2 are both production wells. The Association Well #3, located

in the lower level, is owned (and operated) by the Association for irrigation only, but CRRWC has quasi-municipal water rights affiliated with this well per Permit #G-11376. This permit allows CRRWC to draw a total of 5.0 cfs from Wells #1 and #2, and the Association Well #3. CRRWC has used this well as an emergency stand-by source only and did so only once in the past 5 years when Wells #1 and 2 were both out of commission. Table 2-5 describes the location, depth, and other information about the wells used by CRRWC. Well depth and elevation of CRRWC's water system is displayed in Exhibit 2-2.

Croo			
Description	CRRWC Well No. 1	CRRWC Well No.	Association Well No.
Location	Lower Ridge Road	Commercial Loop	Golf/Maintenance Area
Well House	Yes	Yes	Yes
Wellhead Elevation	2,760 ft	2,540 ft	2,590 ft
Well Depth	951 ft	483 ft	379 ft
Depth to Static Water Level	502 ft	280 ft	319 ft
Static Water Level Elevation`	2,258 ft	2,260 ft	2,304 ft
Pump Capacity	800 gpm	800 gpm	500 gpm
Pump Horsepower	200 hp	150 ph	100 hp
TDH Added	720 ft	550 ft	400 ft
Purpose	Production	Production	Emergency

Finished Water Storage

CRRWC's water system includes two reservoirs: The Standpipe (Tower), which is capable of serving the entire system, but primarily serves the upper service level during day-to-day system operation, and, 2) the Cistern, which serves primarily the lower level, but may serve the upper level during peak demand times. The Standpipe is located in the upper level near Well #1. The Cistern is located in the lower level, about one mile from Well #2. When the Standpipe or Cistern reaches certain minimum levels, the pumps are activated to replenish the storage reservoirs. When the demand for water is great, such as during peak hours of use, Well #2 sends water to the cistern which is pumped via the cistern booster pump to the upper level of the system. The data associated with CRRWC's Standpipe (Tower) and Cistern are presented on Table 2-6 below.

Table 2-6 Crooked River Ranch Water Company Finished Water Storage Summary						
Description	Standpipe	Cistern				
Location	Tower Road	Chinook Drive				
Capacity	700,000 gallons	100,000 gallons				
Usable Capacity	600,000 gallons	80,000 gallons				
Base Elevation	2,855 feet	2,780 feet				
Height	70 feet	10 feet				
Overflow Elevation	2,925 feet	2,790 feet				
Incremental Volume	10,000 gallons/foot	10,000 gallons/foot				
Maximum Customer Elevation for minimum 30 psi pressure when reservoir is full	2,856 feet	2,720 feet				
Material	Steel	Concrete				

Note that both the standpipe and the cistern have a usable storage volume less than their total capacity due to operational constraints of these reservoirs: CRRWC estimates only 600,000 gallons is available for use in the standpipe, and 80,000 is available in the cistern.

It is important to note that the CRRWC reservoir storage is not adequate at this time for fire protection in severe situations, such as a grassland wildfire. The best storage available to CRRWC is the water in the ground. This is discussed further in the section below entitled "Facilties Deficiencies and Upgrades."

Pump Stations

Each well has a pump house that pumps finished water out to the distribution network. There is a booster pumping station, located at the cistern which pumps the water from the cistern to the system, which covers both levels. However, the pumps associated with this booster station have the capacity to pump only 500 gallons per minute (gpm) to the upper service level despite the fact that wells supplying the cistern can pump at a rate of 800 gpm.

At this time, CRRWC can pump 800 gpm from Wells #1 and 2 each or 1,600 gallons total—theoretically 100 gpm more than the 1,500 gpm flow rate sought by the fire marshall. However, moving water from Well #2 (in the lower system) to the upper system is impaired because the booster pump station connecting the upper and lower level can only pump out 500 gallons per minute. This means the upper level has a maximum of 1,300 gpm at this time. The Association Well #3 would also be of little use in fighting a fire in the upper level since it is situated in the lower level and also constrained by the 500 gpm pumphouse.

Facilities Deficiencies and Upgrades

The fire marshall requires 1,200 gallons per minute (gpm) for fire flow for residential sites and 1,500 gpm at commercial sites. Given that usable storage capacity in the standpipe (tower) totals

600,000 gallons, CRRWC calculates that the reservoirs would be drained within about 4 hours in the event of a commercial site fire during peak day use. This number is noted for the upper level. For the lower level, approximately 80,000 gallons of water is kept in the cistern. There is an 8" line that drops 200' from the cistern to the lower level. At this time, CRRWC can only provide about 50% of the required fire flow, and the cistern would provide approximately 30 minutes of fire protection at the maximum.

Futhermore, the CRRWC system has antiquated pumping facilities. Over the past 30 years the development and upgrades of the system have not kept pace with the increase demand and associated fire flow requirements of the customer base. This system, being on two different levels in which there is a 200 foot difference in elevation, having one well on the lower level and one on the upper level, with one very inadequate pumping station in-between, falls short of adequate fire protection as required by the local fire chief. An illustration of the elevation differences between CRRWC's Well #1 and #2 are shown in Exhibits 2-4 and 2-5.

CRRWC has little system redundancy to rely upon during periods of high demand and low operational capacity. For example, CRRWC would not be able to provide enough water for fire suppression in the upper system if the standpipe became unusable or the booster pumphouse was not operational, even during the times of low demand. Given CRRWC's current predicament, staff intend to apply for a permit to obtain a new point of diversion to provide system redundancy, as described in the next section.

New Point of Diversion Planned

As previously described, CRRWC's infrastructure is such that CRRWC cannot adequately provide fire flow to the upper level, the area in which most of CRRWC's customers reside. To solve this problem, CRRWC will be sumbitting an application to drill a new well and apply for a water right transfer in the spring of 2004. The new well will be constructed in the upper level of the system; the transfer will request a point of diversion transfer from the Association Well #3 to CRRWC's proposed well location. Exhibits 2-1 and 2-2 show the location of this proposed well.

The new well, with a planned pumping capacity of 800 gpm, will be owned and operated by CRRWC and the source will be the same aquifer used by the other wells. No additional water rights will be requested for this new well beyond CRRWC's currently permitted 5 cfs. Following the completion of this new well, total pumping capacity for all three wells will be 2,400 gpm and 1,600 gpm in the upper service level.

This new well will provide system redundancy and an adequate level of fire protection currently unavailable in the upper service level. Specifically, the existing infrastructure and infrastructure configuration, coupled with the capacities of the wells and pumps, allow for only 1,300 gpm from the wells for fire flow. If the standpipe was full, it could provide an additional 200 gpm over a long period, but should the standpipe become unavailable, fire protection would be

Peak hour use for 2002 was used for this calculation.



Note that a major brush fire would require significant amounts of water over potentially several days.

inadequate.⁵ An additional well with a production rate of 800 gpm would ensure adequate fire protection.

2.4 Summary of Historic Production

The following subsection described annual average production and seasonal production characteristics. Data for these sections was obtained from CRRWC production well logs and billing records.

Average Annual Production

Table 2-7 summarizes the production from each of the two wells over the past five years in terms of total annual production, average day production, peak season and peak day production.

			Table 2-7			
				iter Company		
		Summary of	Recent Wate	er Production	1	
Well	Permit No.	1998	1999	2000	2001	2002
1	G-11376	122.7	92.4	113.8	106.7	128.8
2	G-11376	6.2	40.2	38.2	46.3	40.7
Totals (MG)		124.9	134.1	167.0	154.9	169.6
Average Day	y (MGD)	0.34	0.37	0.46	0.42	0.46
Peak Season (MG)	May -Sept.	83.1	91.0	109.5	105.6	116.3
Peak Day (M	(IGD)	N/A	N/A	1.43	1.09	1.61
Peaking Fact	tor	N/A	N/A	3.13	2.57	3.47

N/A - For these years, peak data records were not considered as reliable as those for subsequent years.

The numbers shown in Table 2-7 are not consistent with the CRRWC's annual water use reporting as required under OAR 690-085. While completing the Water Conservation and Management Plan, files were audited for the years 2000 thru 2002, and errors were found in the reporting and record keeping. CRRWC is submitting amended reports for those years.

Seasonal Usage and Peaking

A review of usage between 1998-2002 indicates a peak month demand of 30,724,848 gallons which occured in June, 2002. In general, peak usage occurs each year between May or June and early September. Figure 2-1 provides a graphical summary of this phenomenon.

CRRWC's peaking factor was obtained by dividing average day demand by the average demand of the peak month (peak day) for each of the years with data as shown in Table 2-7. Peaking factors for the years 2000, 2001, and 2002 were averaged to obtain 3.06. CRRWC does not believe this factor is abnormally high given the climate of the region and the fact that many


Note that this scenario does not consider customer demand. If a fire would occur during a peak day, an additional 1,111 gpm would be needed.



residents are summer time residents only, calling Crooked River Ranch home six months or less per year, and the two RV parks which reach and maintain capacity during the summer. Regardless of the components associated with peaking, CRRWC's conservation program help reduce the summer peaking phenomenon as described in Section 3.

Figure 2-1

Monthly Production: 1998-2002



2.5 Water Customers Served

Customer Count

CCRWC has historically tracked its water uses under the following classifications:

- Residential
- Commercial
- "Fireflow"

As of 2002, CRRWC had a total of 1,448 customer accounts. A summary of account history from 1998 to 2002 is shown in Table 2-8.

Table 2-8 Crooked River Ranch Water District Accounts Per Customer Class (1)							
	1998	1999	2000	2001	2002		
Residential	1,105	1,286	1,313	1,374	1,404		
Commercial	10	15	15	44	44		
Total	1,115	1,301	1,328	1,418	1,448		

^{(1) &}quot;Fireflow" class is not included.

Customers identified as "residential" represent one dwelling unit. This includes single family houses and mobile homes. Since the Ranch was developed primarily for single-family dwellings, it stands to reason that 97% of CRRWC's customers fall within the residential class. CRRWC does not have apartment complexes, condominiums, or other multi-family housing.

All residential meters are 5/8-inch, except for the newer five acre parcels of which there are approximately 55. Most of these five acre parcel owners have animals that require large amounts of water, and the distance of the piping from the meter to the residence requires a larger meter and pipe in order to provide adequate flow. These meters are 1-inch.

The "commercial" class includes all commercial customers within the CRRWC service area and represents 3% of CRRWC's customers. The largest users of water from the commercial businesses are the market, which includes a deli and post office, two RV parks, a restaurant/bar, beauty salon, motel, and the Crooked River Ranch Club and Maintenance Association. The other businesses are primarily small and service oriented, such as an excavation company, garbage service, diesel repair, roofing company, etc.

Metered Demand

Though the billing system tracks customers by customer class, CRRWC was not able to obtain a report summarizing historic metered demand by customer class: only total metered demand was available for the residential and commercial class combined. As it turns out, a detailed review of the billing records for select individual commercial class customers reveals that metered demand for these customers is very similar to the average demand of the residential class. CRRWC assumes this holds true for most, if not all, the commercial customers.

Table 2-9 shows water usage for the commercial and residential customer class combined between the period 1998 to 2002.

Table 2-9 Crooked River Ranch Water Company Historic Customer Count and Annual Water Use 1998 through 2002						
Year	# of Customers	Metered Demand (gal)				
1998	1,115	108,692,628				
1999	1,301	119,011,136				
2000	1,328	130,064,955				
2001	1,418	142,207,018				
2002	1,448	162,305,641				

Unlike the metered residential and commercial customer classes, the "fireflow" class is unmetered, but represents an authorized use. Fireflow is estimated on a monthly basis by the Crooked River Ranch Fire Department, primarily a volunteer organization which practices weekly. The volunteer firemen and fire chief keep a log of all water drawn to fill their trucks and portable tanks. They estimate the amount of water drawn based upon the size of the trucks and tanks. These logs are given to the fire department secretary at the end of each month, and she in turn adds the number of gallons used and phones the report in to the CRRWC. In Table 2-10 is a recording of these volumes.

Table 2-10 Crooked River Ranch Water Company Fireflow Usage				
Year	Water Usage (Cf)			
2002	32,986			
2001	1,332,834			
2000	590,513			
1999	17,687			
1998	17,000			

During 2001, there were two major fires in the area in which our local fire department was called upon to assist. Because of these fires, our volunteer department had increased practice and were considerably more vigilant in monitoring for local fires and putting them out quickly. This is the reason for the high usage during that year.

2.6 Interconnections

CRRWC does not have any interconnections with other suppliers of drinking water primarily because Crooked River Ranch is not located near any potential supplier where an interconnection could be accomplished at a reasonable cost. (See Exhibit 1-1 for CRRWC's proximity to other potential water suppliers.) Therein lies the reason and necessity for drilling CRRWC Well #3 and the necessity to maintain a 350 kw portable generator that can be connected to all three wells in case of electrical supply interruption.

2.7 System Efficiency

Since 2001, CRRWC has been tracking and recording unmetered, authorized uses. Leakage was computed by taking the difference of metered withdrawals at the wells and metered and unmetered-authorized demands. Annual consumption for unmetered-authorized uses for the last two years are identified in Table 2-11. For years previous to 2001, authorized use records were deemed highly inaccurate. CRRWC calculated a non-revenue rate of 1% of production for 2002 and 5% for 2001. Based on an average leakage rate of 3.3% over the last two years, CRRWC manages its water resource very efficiently.

Increased maintenance over the last 5 years also has greatly reduced the water leakage. The system consists of all PVC piping, Bell & Spicket construction which is less prone to leakage. A flushing and maintenance schedule of all fire standpipes and fire hydrants has netted the repair of any leaky valves in this area. Another large factor involved in low leakage is that no contractors are allowed to do any additions or repairs to the water system. All work is done in-house by highly trained staff. In addition, no customer, plumber, or contractor is allowed in the meter boxes. As a result of these and other preventative measures, the annual water audit shows leakage well below 10% in the past two years.

Table 2-11 Crooked River Ranch Water Company Summary of Leakage Calculation									
Year	Fireflow	Road Maintenance	Water Haulers	Sale To Contractors	Water Pump Lubricating	Line Flushing (1)	Total Usage	Production from Wells	Percent Leakage
2001	228,342	588,953	1,302,919	2,102	2,325,083	0	4,747,399	154,892,100	5.1%
2002	246,735	1,590,405	1,256,640	25,432	4,901,875	1,544,321	9,565,408	174,353,130	1.4%

Note: Units are in gallons

- Fire: Water used by the fire department for fire fighting and practice.
- Road Maintenance: The Crooked River Ranch Road Department uses water for dust abatement and to maintain the roads on the Ranch.
- Water Haulers: Approximately 40 homes within CRRWC's service area are not metered customers of CRRWC nor have a private well, but rely on water to be trucked in and pumped into on-site cisterns. This group pays private water haulers to haul the water to their properties.
- Sales to Contractors: Occasionally a contractor will purchase water when working on developing a property for a customer of CRRWC or when paving a customer's driveway.
- Water Pump Lubricating: This is metered water and is used to pre-lubricate the pump bearings before the pump starts. All pumps in the system are lubricated in this manner.
- Line Flushing: Flushing of lines is done on a quarterly basis at dead ends to maintain high water quality in the system.

There are no numbers available for line flushing in the year 2001 as they apparently were not tracked

Demand for water pump lubricating and line flushing increased dramatically from 2001 to 2002 as shown in Table 2-11. This is because CRRWC rebuilt the head on Well #1 and installed a second lubrication line which runs 24 hours per day, seven (7) days per week. Well #1 now has two lube lines, one that runs full time, and the other that comes on and runs ten (10) minutes before the well begins pumping. Water used for lubrication re-injected into the aquifer.

3.2 Previous and Existing Conservation Measures

CRRWC has undertaken the following conservation efforts:

- Encourage newcomers to use low water use landscaping when developing their lots. A flyer, published by the Extension Service, is available in the CRRWC office giving hints and tips on "Groundwater Friendly Gardening". See Exhibit 3-1.
- Reservoir and tank leak detection program: CRRWC continues to visually inspect reservoirs and tanks for leakage.
- Meter testing program: Meters are tested when specifically requested by a customer. When the water billing staff recognizes an unusual meter reading, or when the meter reader reports a potential problem, CRRWC checks and tests the meter. AWWA's accuracy standards are applied during any testing and repairing or maintenance of meters.
- Meter replacement inventory: In March of 1999, an extensive meter survey was taken. All original meters were located, documented, checked for condition and leaks, and entered into the replacement program. Service orders were written up at that time and any suspected leaks in meter boxes were investigated and serviced. The condition of resetters was checked and CRRWC purchased three different sizes to fill the needs. Insulation was also checked and operations personnel experimented with various types to protect the meters from freezing. A combination of quilted foam and closed cell foam pieces has been chosen for adequate protection during our winter weather. The condition of the meter box was also noted and some defective ones have already been replaced.
- Meter replacement program: The entire 12,000 acres of the Crooked River Ranch is divided into 16 phases. CRRWC has mainline piping to thirteen of these phases, and has established a meter testing program based upon the date the phase became connected. Starting with the oldest, CRRWC has developed a 10 year rotation, replacing meters rather than testing them. This program began four years ago on phase 2. It is important to note that not all phases are of the same size or have the same quantity of meters. In addition to this program, CRRWC has a policy of replacing meters whenever a house is sold, repossessed, or if there has been a problem identified during the billing process or leakage is discovered. CRRWC replaces 100 200 meters per year. Except for one meter, located at the CRR Administration office, all meters are 5/8-inch or 1-inch.
- The meters on the production wells are tested and calibrated yearly.
- CRRWC currently lists water conservation messages on the back of the monthly water bills. During the summer season, when there is a higher use of water, CRRWC includes a conservation message on each monthly bill. During the other times of the year, messages are included quarterly at a minimum. The bills are printed on post cards and space is allotted for CRRWC news and updates to the customers. Examples of messages used in the past are:





- "One gallon of water is made up of about 15,000 drops. That's a lot of drops which add up quickly. If
 your bill seems unusually high, check all your indoor & outdoor faucets for drips. Also, check around
 your property for areas that appear greener than others or for icy spots. These could be indications of
 leaks. This only wastes water and is costly to you, our valued customer."
- "If you wash your vehicles in the driveway, you might want to consider doing so on your lawn. While
 washing your vehicle on your lawn you will be saving water too."
- "When waiting for hot water from the faucet, save the cool water for other uses. Example watering
 plants. Keep a jug of water in the refrigerator for drinking so you don't need to let the faucet run while
 waiting for the water to get colder."
- Annual Water Audit: This information has been used as an ongoing report and is done at the time of our annual audit of our financial records. A daily report of water used is compiled from our daily log totals. These figures are also kept on a monthly basis and combined to result in a yearly total that coincides with our fiscal year from January to December. CRRWC takes the total water pumped, subtracts the total water sold and factors in unmetered-authorized. The resulting volume is considered leakage.
- Pressure Reducing Valves: CRRWC's system has 5 pressure reducing valve stations installed. These valves limit line breaks due to high pressure mainlines. If a break occurs, the valves will close, which insures that the CRRWC will know there's a problem. In addition, the entire system is piped with PVC, which does not rot away.
- SCADA System: The SCADA computer program is used to monitor the water system. Inline flow meters are connected to SCADA and will sound an alarm when an excessive amount of flow is detected. SCADA is also programmed to read daily usage. When it becomes excessive, an alarm sounds and staff are dispatched to determine the cause.
- Water Conserving Policies: One of the biggest conservation measures implemented by CRRWC was not allowing anyone besides CRRWC staff to work on the water system or get into the meter box. This has saved the CRRWC many thousands of gallons of water in that contractors and individuals are not digging up and breaking lines or meters. Also, CRRWC will continue with the policy of not turning on water unless there is someone in the home, and require that shut-off valves be installed on all properties.

In sum, CRRWC has designed and manages the water system to reduce waste as evident by the numerous conservation efforts performed over the last few years.

3.3 Planned Conservation Measures

The conservation program described within the following subsection was developed based on analyses of the characteristics of historical demand patterns and customer demographics. The measures are described below.

Water Audit and Leakage As described in the water audit description above, CRRWC has maintained a leakage rate of less than 5%, so is not required to implement a "leak repair" program per Division 86. However, CRRWC will continue to monitor meters, fire hydrants, fire standpipes, and the mainlines for any leaks.

System Metering All CRRWC's customers are metered.

Meter Testing and Maintenance See previous discussion. CRRWC continues with the same process and plans to continue doing so.

Rate Adjustments The rate structure that CRRWC uses to charge its customers encourages water conservation. All CRRWC customers pay a minimum base amount each month, whether they use the water or not. (CRRWC's Board of Directors recently approved a base rate increase to \$27.50 per month effective July 1, 2003.) In addition to this base amount, usage above 700 cubic feet is charged a commodity rate per 100 cubic feet. Amounts exceeding the 700 cubic foot minimum are billed at \$.72 per 100 cf (the commodity rate).

All customers are metered and all are billed monthly. The bills include the meter reading, amount of water used, and the cost of the water used for that month and an occasional conservation message.

Over the next five years, CRRWC will reduce the quantity of water, which is included in the minimum rate from 700 cubic feet to 0. This will occur over a seven year period by 100 cubic feet per year. At the end of seven years, there will be zero minimum cubic feet provided in the base rate.

Public Education

Public education is an important component of CRRWC's overall conservation program. The following public education measures are planned:

- Bill Back Messages: Continue to provide conservation messages on the bill backs, especially during the peak usage months however CRRWC will significantly increase the frequency of these messages. These would be included monthly during the peak usage season, and every three to four months outside the peak season. (See Section 3.2 for examples.)
- Inefficient Water Fixture Replacement Brochure: Provide information to local residents about replacement of inefficient fixtures. This will be in the form of brochures or marketing materials provided by businesses or manufacturers and distributed by direct mailings and/or

placed in the office lobby for customers to pick up. An example would be working with a local dealer to provide a discount on low water use toilets to customers that replace old fixtures and contract with a plumber to install at a reduced rate. Work with a dealer to notify customers of in-store workshops that are available describing new fixtures that conserve water use.

 Semi-Yearly Newsletter: Produce a semi-yearly newsletter, which will include conservation information.

Additional Conservation Measures

As described in Section 2.1, CRRWC draws water from an aquifer in the Deschutes River Basin, an area in dispute due to limited water availability for sensitive, threatened or endangered aquatic species. However, because CRRWC is in the ground water discharge zone and has small production volumes relative to the size of the aquifer, CRRWC believes its use of the aquifer does not translate into an impediment to aquatic species in the Deschutes River or other surface water bodies. Therefore, CRRWC has not identified "additional water conservation measures" as described in OAR 690-086-150 (5) and (6).

Even though CRRWC does not believe there are any resource issues associated with the execution of its water rights, CRRWC draws attention to one of its programs which may indirectly reduce leakage in the system. CRRWC plans to map its entire system using GPS technology. This will allow CRRWC to be able to access information immediately via a computer "CAD" program that will identify mainlines, valves, meters, etc., in case of line breaks or leaks. This technology will enable the CRRWC to respond immediately to the problem area and begin needed repairs quickly.

Conservation Savings

CRRWC anticipates that the savings gained from the planned and additional conservation measures identified above will reduce demand in years 10 and 20 by 13.5%. Table 3-1 identifies the approximate additional percentage savings for each measure as estimated by Crooked River Ranch Water Staff.

Table 3-1 Crooked River Ranch Water Company 5 Year Conservation Benchmark Savings					
	Primarily Impacts ADD	Primarily Impacts MDD	Additional Water Savings		
Existing Measures					
Annual water audit	X		0%		
Visual inspection of reservoirs	X		0%		
Meter testing & maintenance program	X		0%		
Production meter testing	X		0%		
Public Education		X	0%		
Low water use landscapingBill back messages					
Pressure reducing valves	X				
SCADA system monitoring	X				
Water conserving policies	X				
System metering	X		0%		
Planned Measures					
Rate adjustments	X		10%		
Public Education		X	0.5%		
 Enhanced frequency of bill back messages Inefficient water fixture brochure Semi-yearly newsletter 					
GPS mapping of system to reduce leakage volumes	Х		3%		

CRRWC anticipates that the greatest conservation savings will come from the rate adjustments. As rates come closer to having customers pay for what they actually use, natural conservation will occur. The rate adjustments and meter testing/maintenance program will result in annual savings whereas the GPS mapping will reduce leakage volumes.

3.4 Summary of 5-Year Benchmarks

A summary of the relevant benchmarks for the CRRWC's on-going and planned conservation activities is outlined in the Table 3-2. All previous measures listed as "existing", except the meter replacement inventory performed in 1999, will continue at the same level of implementation for five years.

	Table 3-2		The state of			
Crooked River Ranch Water Company 5-Year Conservation Benchmarks						
Existing Measures	Implementation Date	Completion Date	Frequency of Program			
Annual water audit	On-going	On-going	Annually			
Visual inspection of reservoirs	On-going	On-going	Daily			
Meter testing & maintenance program	On-going	On-going	Annually			
Production meter testing	On-going	On-going	Annually			
Public Education	On-going	On-going	As Needed			
Low water use landscapingBill back messages						
Pressure reducing valves	On-going	On-going	N/A			
SCADA system monitoring	On-going	On-going	Daily			
Water conserving policies	On-going	On-going	N/A			
System metering	On-going	On-going	N/A			
Planned Measures						
Rate adjustments Public Education	July 2004	July 2011	Annually			
□ Enhanced frequency of bill back messages □ Inefficient water fixture brochure □ Semi-yearly newsletter	??		See text in Section 3.3			
GPS mapping of system to indirectly reduce leakage volumes	March 2003	March 2008	N/A			

Section 4

Water Curtailment Element


CRRWC's water supply is ground water obtained from a deep aquifer in the Deschutes Basin. Given past history, CRRWC does not anticipate water supply shortages, however CRRWC recognizes that unforeseen problems may occur which may require the use of a curtailment plan. This section describes CRRWC's water shortage history, assesses CRRWC's ability to maintain adequate water supply during an emergency, and presents a curtailment plan for use in the event of an emergency.


According to CRRWC's 20 Year Master Plan the depth and abundance of the aquifer makes vulnerability of the system to quantity problems a remote possibility. Similarly, the deep aquifer also provides significant protection against vulnerability to water quality problems. Also, drought has not had an effect on the CRRWC's wells in the past, and is not expected to do so in the future.

However, unforeseen emergency situations may impact CRRWC's ability to fully utilize permitted water rights. For example, a multiplicity of small events may warrant the need to enact water curtailment measures, as described below. In the past 10 years, CRRWC has experienced one event in which the water supply was deficient and counter measures were implemented. In 2000, Well #1 was taken off line because the tower (standpipe) was being resurfaced inside. Because of the configuration of the plumbing in Well #1, it could not be operated without the standpipe. Well #2 had been prepared to handle the water load during this down time. Unfortunately, an Association employee turned off a valve on a mainline by mistake, causing 40' of line to blow out of the ground and making Well #2 pump dry.

During this emergency, CRRWC brought the Association Well #3 on line in order to provide water to CRRWC's customers and maintain a source for fire protection. In addition, Public Service Announcements were made on local radio stations advising Ranch residents that there was a water emergency in place and that conservation was needed. There were also articles placed in the local newspapers. In addition, a reader board was obtained from ODOT and placed at a major intersection advising residents of the emergency and the need to conserve.

Well #2 was repaired as quickly as possible, but the Association Well #3 was kept on-line to supplement Well #2 until the standpipe and Well #1 could be brought back on line as a production well.





THE DESCHUTES RIVER BASIN - SEEING THINGS WHOLE

A"WHALE" OF A VIEW


If you use your imagination, part of the map below looks a bit six a whale swimming off the page. So when Bob Main, former Central Oregon Watermaster created the map, it was aptly named "The Blue Whale", it is a graphic model of the various flows throughout the Deschutes Basin, with the width of the river corresponding to actual river flow in cubic feet per second (cfs) at the limes noted.


REACH BY REACH -IT'S THE GROUNDWATER


The Deschutes is talked about in three distinct parts, called reaches. The "Upper Deschutes" is considered from the headwaters to the north diversion dam in Bend. The "Middle" reach is from the north diversion to Lake Billy Chinook, and the "Lower" reach is from there to it's terminus at the Columbia. Each reach has its own story to tell and opportunity for enhancement. About half of the surface water flows in the lower reach come from groundwater discharge near Lake Billy Chinook. Most of this groundwater enters the aquifer in the high Cascades.

A CHOICE OF FLOWS - "ALTERED" OR "MORE NATURAL"

As you can see, the summer flows are very altered from the natural flows (shown as cross-hatching). Historical diversions have created the opportunity for restoration of flows in the middle section of the river and various tributaries by doing conservation projects applied to the current system of open, leaky canals and antiquated delivery systems. This presents a great opportunity for conservation and possible reallocation of some of the water while still providing for productive agriculture and restoration of flows in our basin for fish, widificand scenic qualities so important to the Deschutes Basin.







Section 3

Conservation Element

CRRWC has historically promoted water conservation to its members. The Crooked River Ranch is located in high desert country, has a short growing season, and a large deer population, which limits gardening efforts. However, because of the natural landscaping (sagebrush, junipers, etc.), great emphasis is placed on making homes fire safe. This means either replacing all growing matter with rock, or keeping lawns and shrubs green, resulting in increased water use.

CRRWC is committed to targeting a comprehensive conservation plan consistent with the requirements for Water Management and Conservation Plans which will encourage residential customers to conserve during peak and non-peak demand times. However, limited resources of the CRRWC hamper the ability of CRRWC to offer a full-scale conservation program as is available in larger cities.

3.1 Water Use and Reporting

CRRWC's water-use reporting is done in compliance with OAR 690-085. The report is submitted annually by December 31st on the form provided by the Water Resources Department using the "Flow Meter Method" approved by the Department in OAR 690-085-0015 (5).

Water that is pumped by each well is logged every day on the Daily Log Form. An Operations Technician visits each of the well houses and also goes into the cistern building on a daily basis. The main well, No. 1, uses a Sensus W-3500 meter, which is tested and calibrated on a yearly basis. Well No. 2, the second well, utilizes a Hersey Model MHR model meter and this one is also calibrated and tested on a yearly basis. CRRWC counts monthly water usage by their fiscal year, which goes from January to December. A yearly total of all water used by CRRWC is sent to the Oregon Department of Revenue. CRRWC calibrates and tests the meters annually, and accuracy of the meters is within 15% of true usage.

¹ Note in Section 2, discrepancies in the water use reports were discovered and will be rectified by sending WRD revised reports for those years in which discrepancies were found.

4.1 Assessment of CRRWC's Ability to Supply Water Long Term

In case of a long term shortage, such as an extensive power outage, or a well or pump going out of commission, CRRWC would have to enact the "severe" or "critical" stage since the water storage and system capacity that is currently available would likely not be able to meet both residents demands and provide for adequate fire protection coverage. System capacity is limited due to infrastructure limitations as described in Section 2.

In general, CRRWC's ability to meet its customer's needs during a long term emergency is not up to CRRWC's current standards. CRRWC has plans to drill another well on the upper level in 2004, also described in Section 2, which would help alleviate these storage and capacity issues. In addition, storage capacity does need to be increased from its current 800,000-gallon capacity to a minimum of 1,700,000 gallons over the next 10 years. This would provide improved water storage as well as fire protection.

4.2 Water Emergency Response

CRRWC's two production wells produce an adequate supply of water *combined to meet ADD* and MDD and provide for fire protection. ² Therefore, CRRWC defines an emergency as a point in time when at least one of the two production wells would be lost for a period of two hours or more.

It must be noted that no plan can anticipate the countless number of emergency scenarios. Factors such as weather, availability of mechanical parts, and customers' response to the curtailment plan, among other factors, will dictate the degree and speed to which the Company responds to an actual event. Therefore, CRRWC anticipates that any emergency plan will have to remain flexible and be adjusted according to various factors at hand.

The four stages of alert range from mild to critical and are triggered by changes in capacity. Capacity is defined as the total rate of water accessible at any given time through CRRWC's wells. A brief description of each stage as well as potential events that could trigger the stage follows:

Mild: Examples of a "mild" situation might be a line break that will require sections of the system to be down for several hours, or a pump that is out of commission for repairs. It would result in the water capacity being reduced by twenty (20%) percent. Public Service Announcements would announce this stage and other methods, requesting that water use be

² As discussed in Section 2, Water Supplier Description, CRRWC has another well with water rights, called Association Well #3, but this well is only used for emergency purposes. CRRWC shares this well with the Association which also has rights appropriated to this well.

reduced, i.e., limit lawn sprinkling, car washing, etc. This would be a voluntary watering reduction schedule, probably enacting an odd/even watering schedule.

Moderate: An example of a "moderate" stage would be a pump that is down for an extended period of time, reducing water capacity by 40%. In this situation, all lawn sprinkling would be terminated, as well as car washing, road watering, and line flushing (except in case of potential health risk). This would be a mandatory schedule. In addition, CRRWC would activate Assn. Well #3 to support the one working CRRWC well. This action will no longer be needed once CRRWC drills its Well #3 and has it on line.

<u>Severe:</u> In this stage, water capacity would be reduced by 60%. An example of an event that may cause this would be a major line break along with a pump down. In this case, the "moderate" measures would continue, and in addition, there would be no outside use of water (except for fire).

Critical: This would be the worst stage that could occur. In this scenario, potential disasters may include an earthquake that destroys the aquifer or caves in the wells; an act of terrorism that may destroy the storage tanks or wells; a regional power outage that lasts for a week or more; a substantial grassland fire that requires major amounts of water in order to save property and/or lives. In this stage, it is important to note that CRRWC does have a 350 K.W.- Genset generator and that both well houses have been wired to accommodate the generator. Should a power outage occur, the company could provide water with the generator, but it would be on an extremely limited basis. In this stage, CRRWC would allow water usage for one hour each day per household, and would be controlled by the company by way of shutting down streets in order to provide for specific areas at any one time. The water would be limited to human and domestic animal consumption only. As much water as possible would be conserved for fire protection.

Since Crooked River Ranch is not incorporated, the predominant governing body for CRRWC is the Board of Directors. However, since the CRRWC Board of Directors are not involved in the daily management of CRRWC, the Critical stage would require the manager of the company to manually control the water usage by regulating the flow to areas of the subdivision. Ultimately, CRRWC's Board of Directors would declare an emergency and CRRWC would drastically limit availability. Having the CRRWC Board of Directors declare the critical stage and implementation measures would be politically correct and provide coverage for the CRRWC manager.

4.3 The Curtailment Plan

Table 4.1 describes the Company's proposed curtailment plan. Included within the plan are four stages of alert, the trigger for each stage, the goals for the implemented measures per stage and the curtailment measures.

		Table 4-1						
	Cro	oked River Ranch W Proposed Curtailn						
Stage Trigger Goal Implementation Measures								
Mild	Capacity is reduced by 20%	Awareness and 20% reduction in consumption	 Activate curtailment plan Broadcast via radio and television station Public Service Announcements Coordinate outreach to customers through direct means (phone call, personal visit and indirect means (media) Voluntary watering reduction schedule (odd/even) in early morning/late evening. Flushing lines for essential needs only No read watering 					
Moderate	Capacity is * reduced by 40%	40% reduction in consumption	 Continue with "mild" stage measures Watering schedule mandatory Eliminate road watering and line flushing (except for health risk) Activate Association Well No. 3 					
Severe	Capacity is reduced by 60%	60% reduction in consumption	 Continue with "moderate" stage measures No use of company supplied water to fill swimming pools, hot tubs, etc. Outdoor irrigation banned No use of company water to wash vehicles. 					
Critical	Terrorism Earthquake Regional power outage Substantial grassland fire	75% reduction in consumption	 Continue with "severe" stage Households limited to one (1) hour per day per street Water limited for human consumption and domestic animals only. Exceptions for health and safety issues. 					

^{*}Capacity is defined as the total rate of water accessible at any given time through the CRRWC wells.

Staff Responsibility

The Manager of CRRWC is the ultimate person responsible in the event the water curtailment plan is enacted. Specific duties will be assigned to CRRWC staff, with the assistance from CRRWC's Board of Directors to ensure that all activities are commensurate with the curtailment plan.

The CRRWC Board of Directors will be approving the process for declaring a state of emergency. The plan is that the General Manager will advise the Board of Directors of the emergency, and identify the stage and implementation measures. The Board of Directors will then sign the emergency declaration, and the curtailment actions will then be implemented.

Section 5

Municipal Water Supply Element

CRRWC projects a steady, but slow rate of growth in the number of new customers from 2003 to 2023 which translates into an increased water demand over this time period. As described below, however, CRRWC will not need any additional water beyond its currently permitted 5 cfs. In this section CRRWC discusses changes to its future service area, describes plans to fully utilize its water rights, presents estimates of future demand, and comments on the reliability of the existing sources.

5.1 Future Service Area

In 2002, CRRWC had 1,448 connections and estimates there are approximately 316 buildable lots remaining in CRRWC's northern service area which are likely to be connected to the water system over the next 20 years. This would bring the total connections to 1,764. See Table 5-1 for the detail. Estimates in Table 5-1 are based on the Association's future development data.

	Table 5-1 ed River Ranch Water (ers of CRRWC by Custo		
	2002	2013	2023
Residential Accounts	1,404	1,574	1,660
Commercial Accounts	44	84	104
Total Accounts	1,448	1,658	1,764

From 2002 to 2013, a 12% increase in residential accounts is projected and between 2013 and 2023, a 5% increase is forecasted. The increasing residential accounts should spawn commercial development in CRRWC's service area. Commercial accounts will increase 91% from 2002 to 2013 and 23% the following ten years. (Commercial growth will outpace residential growth because the Ranch is believed to be currently underserved given the size of the residential class.)

The south end of the Ranch has additional buildable lots; however, these are not included in the forecast for two reasons. First, existing residents and businesses are served by private wells and it would be economically infeasible to supply only new buildable lots strewn throughout the area with CRRWC water as they are developed. CRRWC once considered serving domestic water to the entire southern portion or major parts thereof as described in CRRWC's 20 Year Water Master Plan (1997), however, CRRWC is not planning on pursuing this option at this time.

Second, the buildable lots in the southern portion of the Ranch were not included in CRRWC's forecast because CRRWC does not serve domestic water to current residents and businesses in

the southern portion of the Ranch—only fire flow protection. Note that CRRWC does not have fire flow infrastructure in this area and only provides fire flow volumes through hydrants and standpipes near the border between the northern and southern portion of the Ranch. Therefore, fire flow volumes are limited by the number and capacities of the fire trucks and associated water hauling vehicles. At present, the volumes supplied are anticipated to meet these vehicle capacities for the next 20 years.

Within the Ranch Jefferson County enforces a 10-acre minimum lot size, however, there are many 1-acre parcels that were "grandfathered" in under the old County codes. According to the County's Planning Department staff, they do not anticipate the 10 acre minimum lot size as set forth in the County code reverting to one acre parcels in the near future.

As was mentioned in Section 2, Crooked River Ranch is bound by rivers and BLM lands. Therefore, the service area is not anticipated to expand beyond the existing boundaries within the next 20 years.

Future Population

Section 2 noted that Jefferson County does not have population estimates for the Crooked River Ranch or CRRWC's service area. Therefore, population estimates were calculated using a projected residential customer count based on buildable lots and a person per household estimate of 2.5.

Projected customer counts in 2013 and 2023 are constrained by the number of available, undeveloped lots (316) and growth rates from 2002 to 2023 were projected based on the amount of water line extension work planned by CRRWC. As such, it is anticipated that the majority of the new customers will be added within the first 10 years—form 2003 to 2013—and the balance of the estimated customers will develop lots during the remaining 10 years.

To make an estimate of population, CRRWC assumes a person per household count of 2.5 and applied this factor to the number of residential accounts shown in Table 5-1. Population estimates for 2013 and 2023 are found in Table 5-2.

	Table 5- oked River Ranch \ esidential Populati	Water Company		
,	2002	2013	2023	
Estimated Population 3,510 3,935 4,150				

5.2 Schedule for Beneficial Use

After reviewing CRRWC's water rights with the Water Resources Department over the past few months, the company is in the process of certificating its rights at this time. A "Claim of

Beneficial Use Site Report" was submitted to WRD on August 6, 2003, showing that CRRWC has proved up on its claim and met the beneficial use prior to Oct. 1, 1998.

5.3 Demand Forecast

The four components required to forecast CRRWC's total system demand includes average day demand (ADD) and maximum day demand (MDD) of metered customers, unmetered authorized demand, leakage, and fire flow protection. These are described in detail below.

ADD and MDD of Metered Demand

To calculate future ADD, a water demand factor was applied to the total number of customers forecasted for the years 2013 and 2023. The water demand factor was calculated by dividing historic total metered customers' ADD by the total number of associated accounts. This calculation was performed for 2000 through 2002. 1998 and 1999 were not used because demand characteristics for CRRWC's customers during these years were thought to less accurately reflect future demand characteristics than the demand for 2000 through 2002. Table 5-3 shows how the water demand factor was calculated.

Table 5-3 Crooked River Ranch Water Company Water Demand Factor						
	Consumption (gal)	Residential and Commercial Accounts (1)		Gallons per Account per Day		
2000	130,064,955	1,328	97,940	268		
2001	142,207,018	1,418	100,287	275		
2002	162,305,641	1,448	112,090	307		
			Average	283		

⁽¹⁾ Data for individual demand for the residential and commercial classes were not disaggregated due to the limited capabilities of CRRWC's automated billing system.

Two assumptions were made regarding the calculation of the water demand factor. First, it was assumed that consumption for the commercial class is similar to demand by the residential class on an account by account basis, as stated in Section 2. Second, it was assumed that the character of the residential and commercial class will remain the same; in other words, average consumption volumes per account will not change in the next 20 years.

Future demand was calculated by applying the demand factor of 283 gallons per day per account to the future number of accounts as presented in Table 5-1. Table 5-4 shows the forecasted average day demand for CRRWC for 2013 and 2023.

Table 5-4 Crooked River Ranch Water Company Metered Customers' Demand Forecast								
	Demand Factor	Accounts	ADD (gal)	ADD with conservation (gal)	MDD (gal) (1)	MDD with conservation (gal) (2)		
2002 (actual)	307	1,448	444,673	N/A	1,543,015 (3)	N/A		
2013	283	1,658	469,997	421,522	1,289,858	1,283,441		
2023	283	1,764	499,908	448,348	1,371,945	1,365,119		

- 3.06 peaking factor multiplied by "ADD with conservation"
- (2) 3.04 peaking factor multiplied by "ADD with conservation"
- (3) Estimated from existing records

As identified in Section 3, CRRWC's conservation measures are anticipated to reduce average day demand by 13.5%. Table 5-4 shows the difference in average day demand when conservation savings are applied.

Maximum day demand was also calculated and shown in Table 5-4. Recall that Section 2 noted an average peaking factor of 3.06 over 2000 to 2002. Section 3, however, suggested that due to the conservation messages on the back of customers bills during peak season, maximum day demand is anticipated to decrease by 0.5% which translates to a peaking factor of 3.04. This peaking factor was multiplied by "ADD with Conservation" to get "MDD with Conservation." Table 5-4 shows the maximum day demand with and without conservation. For these MDD forecasts, CRRWC assumed the peaking factor would stay the same over the 20 year planning horizon.

Unmetered Authorized Demand

Section 2 identified the demand of six unmetered, but authorized uses of water. (Recall that "Water Pump Lubricating", a metered use, is also categorized as unmetered and authorized and included in this category.) Since consumption estimates for this category was most reliable for the year 2002, it was assumed that the 2002 unmetered authorized demand of 9,565,408 gallons will also be the standard annual demand volume for future years.

Leakage

Leakage is an important element used to determine total future system demand. In Section 2 a average historic leakage amount of 3.3% of total system production was calculated. To determine future leakage, this same percentage may be applied to total system production, but since leakage is a component of total system production, future production volumes are not known. Therefore the historic leakage estimate of 3.3% was manipulated algebraically to obtain 3.6% of metered demand. When this percentage is applied to forecasted metered demand, a forecasted leakage volume is obtained.

Fire Protection Flow

Section 2 discussion about fire protection flow noted a need to maintain an instantaneous fire protection flow capacity of 1,500 gpm for commercial sites and 1,200 gpm for residential sites. Since commercial sites may be found on both the upper and lower levels in the next 20 years, CRRWC's demand forecast assumes a maximum fire protection flow for the entire system of 1,500 gpm.

Though CRRWC usage of this volume of water for fire protection flow will be very infrequent, CRRWC still needs to plan for such use. For this reason, this flow rate of 1,500 gpm has been translated to 2.16 mgd and was added to the demand forecast.

Total System Demand

The demands previously described—that is metered demand, unmetered authorized demand, leakage, and fire protection flow—were summed to forecast total system demand in 2013 and 2023. These values are shown in Table 5-5. Note conservation has been factored into the "Metered Average Day Demand with Conservation" figures for 2013 and 2023.

Table 5-5						
Crooked River Ranch Water Company						
Total System Demand Forecas	it .					
Total System Demand (gallons per day)	2013	2023				
Metered Average Day Demand with Conservation	421,522	448,348				
Unmetered Authorized (1)	26,207	26,207				
Leakage (3.6% of metered demand)	15,175	16,141				
ADD Subtotal	462,904	490,695				
MDD Subtotal (2)	1,409,438	1,494,057				
Instantaneous Demand for Fireflow						
1,500 GPM translated to GPD	2,160,000	2,160,000				
Total System Demand with Fireflow (gallons per day)						
ADD Total	2,622,904	2,650,695				
MDD Total	3,569,438	3,654,057				

^{1.} Included is the metered use "Water Pump Lubricating".

^{2.} Maximum day demand calculated by applying a reduced peaking factor of 3.04 (due to conservation) to the categories "Leakage", "Metered Average Day Demand", and "Unmetered Authorized".

For 2013, CRRWC projects an average day demand of 462,904 gallons with an instantaneous demand of 1,500 gpm or 2.16 mgd for a total ADD of 2.6 mgd (4.06 cfs). The ADD for 2023 increases to almost 2.7 mgd (4.10 cfs). MDD is forecasted to be about 3.6 mgd (5.52 cfs) and reach about 3.7 mgd (5.65 cfs) by 2023. In light of CRRWC's water right of 5 cfs, or 3.2 mgd, CRRWC's forecasted demands exceed this rate when factoring in fire protection flow demands. Exhibit 5-1 and 5-2 shows CRRWC's total ADD and MDD system demands from 1998 to 2023 without and with fireflow requirements, respectively, relative to CRRWC's water right of 5.0 cfs.

Based on the projected instantaneous demands that include fire protection flow, the demands exceed the current 5.0 cfs of CRRWC's water rights. However, since CRRWC has reservoirs that can provide a portion of the fire protection flow demand over a short-term, green light water of 5.0 cfs is an appropriate rate to maintain. Therefore, CRRWC requests full quasi-municipal use of the instantaneous rate 5.0 cfs on the aquifer in the event of a short term fire.

Source Reliability

As discussed earlier in Section 2.2, the aquifer from which CRRWC draws water is considered a reliable source of water for the next 20 years. Current constraints to use full water right volumes are due to capacity limitations and not aquifer producing capabilities. In other words, the aquifer will be able to supply CRRWC's customers with the volumes and rates forecasted until 2023.





Exhibit 5-1 Crooked River Ranch Water Company Groundwater-Friendly Gardening

- Apply fertilizer according to the plant's needs. Fertilizer in excess of plant uptake can pollute the groundwater and it is a waste of money. DO NOT fertilize in the winter because plants aren't growing and the heavy rains transport the nitrogen below the rooting zone before spring growth begins.
- Use a mulching lawn mower instead of removing clippings.
- Install backflow devices to prevent the siphoning of irrigation water back down the well or into your drinking water supply.
- DO NOT use spray devices that attach to the end of the hose for fertilizer or pesticides because of backflow risk.
- ♦ DO NOT store any chemicals in the pump house. Accidental spills can reach the groundwater directly via the well hole.
- Refuel all motorized equipment (mowers, tillers, chain saws, etc.) on a hard surface at least 100 feet away from the well. Collect all petroleum products from oil changes and winter drainage of fuel tanks. Check with your local garbage company on proper disposal methods.
- Take special care when using FRESH MANURE in your garden because it contains fecal coliform bacteria and nitrogen. Time fresh manure applications like fertilizer use when the plants are growing and able take up the nitrogen. If you are storing manure for spring use, cover the piles to prevent leaching by winter rains. You can spread fresh manure in the fall if you are adding uncomposted organic matter, such as shredded leaves or sawdust, because the process of breaking down the organic matter takes up the nitrogen. Prevent manure contaminated surface runoff from reaching your well area.
- Use water conservation practices around your homestead. Install low-flow irrigation and/or drought tolerant plant. Let your lawn go dormant (brown) in the hottest part of the summer; it will green up when the fall rains return.
- Consider the potential impacts on groundwater and surface water runoff when building any structures or initiating new practices on your homestead.

Prepared by Gail Glick, Oregon Home*A*Syst Coordinator and Master Gardener, Revised Dec. 1995. Home*A*Syst is a groundwater protection project to help rural residents assess structures and practices that may be contaminating the groundwater that supplies their drinking water.











Gerry Clark

From: Gerry Clark

Sent: Monday, October 08, 2007 1:33 PM

'DOUGHERTY Michael' Subject: RE: Crocked River

As requested, here is a follow up to our conversation from earlier today. No effect for demonstration of Ben. U.S. When the Department determines the amount of water beneficially used by a municipal or quasi-municipal water user, we look for a demonstration by the water user that they can appropriate/divert to use (not waste) the rate they are claiming in the Claim of Beneficial Use. Water appropriated/diverted during the demonstration period must be beneficially used, but not necessarily during the demonstration period. The water can also be diverted into in-system storage tanks and consumed later.

The second issue we discussed was if fire flows would be considered as part of the demonstration beneficial use. The answer is that they are not used in determining the extent of beneficial use. Again, the Department is looking for a demonstration of the ability of the water user to divert to use/in-system storage a specific rate of water for four hours within a maximum eight hour period. This does not mean that, in the case of a fire related emergency, the water user would not be able to divert a rate greater than the right.

Let me know if you have any additional questions.

Gerry Clark Water Rights Specialist/Certificates 725 Summer St. NE, Ste. A Salem. OR 97303

Phone: 503-986-0811 Fax: 503-986-0901 http://www.wrd.state.or.us/

From: DOUGHERTY Michael [mailto:Michael.Dougherty@state.or.us]

Sent: Friday, September 21, 2007 2:10 PM To: CLARK Gerald E

Subject: RE: Crooked River

Gerry.

I hate to be pain, but on Crooked River's CBU, what is the effect of fire flow?

According to CRRWC's Water Management and Conservation Plan, the Company lists the total system demand for 2013 as:

Metered ADD with Conservation 421,522 Unmetered Authorized 26.207

Leakage (3.6% of metered demand) 15,175

ADD Subtotal 462,904 MDD Subtotal 1,409,438

Instantaneous Demand for Fire flow

1,500 GPM translated to GPD 2,160,000

Total System Demand with Fire flow

ADD Total 2,622,904 MDD Total 3,569,438

The fire flow and MDD gets the Company to the permit 3.23 MGD. ADD for 2006 was approximately 409,853; MDD for 2006 was about 927,182. So would emergency firefighting be an exempt use (I'm not sure what an exempt use is)? According to Bill's e-mail below, "at this time, when assessing demand on new water right applications it is not part of a daily need that should be incorporated into the demand. '

The Company's current T-9663 adds the new well in order to get to the permit MGD based on above calculations. Customer count isn't going to increase dramatically (and average household will not increase either). Maybe a hundred customers in the next 6 years (to 1,658) and probably maxing out at 1,764 in 2023. If average use per customer stays steady then ADD and MDD will increase about 15 percent in the next 16 years. Still way below the permit amount.

Although this is an issue for the current rate case, it mainly has to do with fire flow and the need for a new well. According to the plan, the two current wells, can pump out 1,300 gpm.

I'm going into Evidentiary Hearings in a few weeks and any back-up info would be extremely useful.

Thanks - Mike

Michael Dougherty Program Manager Corporate Analysis & Water Regulation Oregon Public Utility Commission (503) 378-3623 michael.dougherty@state.or.us

From: Bill Fujii [mailto:fujiiwh@wrd.state.or.us] Sent: Friday, September 07, 2007 11:33 AM To: DOUGHERTY Michael Cc: CLARK Gerald E

Subject: RE: Crooked River

Michael - I've not gotten a chance to review the VMCP as yet. The CBU issue is interesting I'll ask my colleague that works on certificates. One aspect of the discussion may be that emergency firefighting is an exempt use, at this time, when assessing demand on new water right applications it is not part of a daily need that should be incorporated into the demand.

We may allow a municipal use to take water to fill their in-line storage at a pretty high rate, typically they do not do this since the transmission and distribution system are not built to handle maximums of all water use permits. All that being said, all systems are different I have not reviewed their capacity as yet. Gerry is the one that assesses their diliegence on the CBU and I would defer to his process. My role is to assess their efficiency, preparation for curtailment and water supply planning for future.

Bill Fujii 503 986 0887

From: DOUGHERTY Michael [mailto:Michael.Dougherty@state.or.us] Sent: Friday, September 07, 2007 10:08 AM

To: Bill Fujii

Subject: RE: Crooked River

I remember you mentioning that you were going to read CRRWC's Water Management and Conservation Plan. I'm not sure if you got through it all (I haven't), but on page 5-3 (starting on 5-2) the Company states,

"A 'Claim of Beneficial Use Site Report' was submitted to WRD on August 6, 2003, showing that CRRWC has proved up on its claim and met the beneficial use prior to Oct. 1, 1998.

It seems (on page 5-5) the beneficial use is dependent on the Instantaneous Demand for Fire flow at 1,500 GPM.

Based on the last e-mail, I understood as the Company Claim of beneficial use is due on October 1, 2008 (T-9663), so the above statement appears not to be accurate.

So being unschooled in this area (but getting smarter by the week), I take it that the Company is building Well #3 (T-9663) in order to be able to provide the additional gpm for instantaneous fire flow. According to the Plan, this fire flow coupled with its maximum daily demand would allow the Company to perfect its permit of 5.0 cfs and 3.23 MGD.

So some questions

- 1. How deeply does OWRD look a fire flow gpm in terms of perfecting water rights? Is the gpm something that OWRD analyzes or accepts on face value? (Since 59% of the MGD is in the fire flow).
- 2. Am I on track with this stuff?

Thanks - Mike

From: Bill Fujii [mailto:fujiiwh@wrd.state.or.us] Sent: Wednesday, September 05, 2007 9:39 AM To: DOUGHERTY Michael Subject: RE: Crooked River

you are welcome, did you get everything you need?

Bill Fujii 503 986 0887

From: DOUGHERTY Michael [mailto:Michael.Dougherty@state.or.us] Sent: Tuesday, September 04, 2007 5:06 PM

To: Bill Fujii

Subject: RE: Crooked River

Bill.

Thanks and very timely,

Mike

From: Bill Fujii [mailto:fujiiwh@wrd.state.or.us] Sent: Tuesday, September 04, 2007 2:54 PM To: DOUGHERTY Michael Cc: Kyle Gorman Subject: FW: Crooked River

Bill Fujii 503 986 0887

Michael - please refer to the email from Kyle Gorman, our Region Manager in that area. We appreciate your checking with us

Bill

From: Kyle Gorman Sent: Tuesday, September 04, 2007 2:43 PM To: Bill Fujii Subject: RE: Crooked River

Bill

The first transfer (actually permit amendment) added well number #4. At present they have the ability to pump up to 5 cfs from wells #2,3, and 4. The second permit amendment moved the well location of well #3. If the well was already drilled this must have been a new well and they renamed it well #3. They currently are using substantially less than allowed by the permit - 1.43 cfs peak vs. their allowed rate of 5 cfs.

The statement about the well being placed in operation by 10/1/08 is not completely accurate. They need to perfect the water right by this date in 2008 or file for an extension of time which I assume they will do.

The last statement is also misleading. The company can perfect their rights at that time but just to a lesser amount. There is nothing wrong with that but I would advise them to file an extensi

Kyle

From: DOUGHERTY Michael [mailto:Michael.Dougherty@state.or.us] Sent: Wednesday, August 29, 2007 5:19 PM To: Bill Fujii Subject: Crooked River

Bill.

If you have the time, can you let me know if the following statements (in red) are accurate concerning Crooked River's water permit. Thanks. I appreciate the help, but apologize for always asking for help! Mike

The Company has water rights of 5 cubic feet per second (cfs), 3.23 million gallons per day (MGD) under permit No. G-11376, with a priority date of June 18, 1991. The water rights are assumed to cover 2,600 potential lots at Crooked River Ranch. Based on data received from the Company, customer usage in 2006 was approximately 20 million cubic feet. This annual usage equates to approximate average of 409,863 gallons per day. Actual peak demand in August 2006 was 927,182 gallons per day (gpd). This usage aligns with the Company's 20-Year Master Plan lists peak demand of 970,362 gpd. As a result, the Company currently has sufficient water rights for current and future operations.

Although the Company has sufficient water rights, CRRWC applied for and received an Order (T-963) from the Oregon Water Resources Department (OWRD) to change the point of appropriation of a new well, Well No. 3. To fulfill the Order, the well must be legally conveyed to CRRWC and placed in operation by October 1, 2008. If CRRWC fails to meet this date, they will need to refile with OWRD. However, it should be noted that the application did not change the permit ofs and MGD, both staying at 5 and 3.23 respectively. As previously demonstrated, the actual peak demand of 927,182 gpd is substantially lower than the permit amount of 3.23 MGD and current wells have sufficient capacity to fulfill current usage.

And

Additionally, the new well without associated increased usage to meet the Company's current water permit would not necessarily result in the Company perfecting its water right.

):	Water Rights Section	
.oM:	Groundwater/Hydrology Section Sauch P	Leyer r's Name
BJECT:	Application G- /2579 Reviewe	r's Name
PER surface	R THE Deshates Basin rules, one or more of the propose ace water source and taps a groundwater source hydraulically of	d POA's is within mile of a connected to the surface water.
	SED UPON OAR 690-09 currently in effect, I have determined will, or \(\) have the potential for substantial interference	that the proposed groundwater use with the nearest surface water
b. <u>×</u>	will not source, namely Croced Cico will, if properly conditioned, adequately protect the surface iThe permit should contain condition #(s); iiThe permit should contain special condition(s) as ind	water from interference: icated in "Remarks" below;
d	iiiThe permit should be conditioned as indicated in item will, with well reconstruction, adequately protect the surface	
a b	will, or \ will not \ likely be available in the amounts requested was an if properly conditioned, avoid injury to existing rights or i. The permit should contain condition #(s) ; ii. The permit should contain special condition(s) as indicated in item.	without injury to prior rights; or or to the groundwater resource; icated in "Remarks" below;
a	THE PERMIT should allow groundwater production from no	deeper thanft. below land
b	surface; The permit should allow groundwater production from no sha surface;	llower than ft. below land
		t. below land surface; of the above conditions. er. The applicant must select one
EMARKS:	Diack letter confined aquiser lo Riven > 14 an	wer than
	> 14 an	rile away

STATE OF OREGON WATER RESOURCES DEPARTMENT

	TO:	FILE G	-12 579		DAT	E: 3/3-91	
	FROM:	SARAH	CMEYER				
	SUBJECT: SURFACE/GROUND WATER CONSIDERATIONS						
	The applicant seeks 5 cfs from two wells for quasimunicipal use in Crooked River BASIN Per Division 9 Tefferson Gunty						
	Per Division 9 Jefferson Gonty						
	FACTS						
	The well locations and aquifer display the following: 2000'						
	1) Well #1 located	is located 23 50'	dfrom	from Cr Crooket R	bored River	and well #2 is	
	2) Well #1	is4/3	deep and	d well #2 is	194 deep . The well	developing water in logs are in the file.	
	3) The static water level for well #1 was on and for well #2 it was & from the log reports.						
	4) The approximate elevations of the wells are 25240' for well #1 and 2606' for well #2.						
	5) The nearby stream reach elevation is 2280 /242 feet.						
	6)		describ	es groundwater co	nditions in the ar	ea of the application.	
	7) A pump test on the well #1 produced gpm with feet drawdown in hours. Well #2 produced gpm w/ / feet d.d in						
	CONCLUSIONS						
	1) The head at well #1 is (2187)' and at well #2, 2314 ', indicating a lower standing with the nearby stream reach.						
A860 307	2) The well develops water from the <u>Deschwies Foremention</u>						
	3) Based on requested rate, heads, distances, general geologic environment and logged materials, I conclude that the alluvial aquifer is 						
	均 353 381 -	406	Joft F	POR OUS Black BLOWN PORCUS	ROCK (U	vatu)	
	#3 307 352 394-478-	-313' -356 401	Soft grey Soft por Soft por	BLOWN PORCUS I ROCK, BROKA OUS GEEY KO COUS BLOCK I	N (WB)	3	

Application # <u>G-12579</u> / Permit # <u>G-11376</u>

Route Slip ... Extension of Time

per Division 315 Rules... (Extensions received on July 1, 2001 or after)


+	WRIG Money Receipted: \$100.00 4-3-00
+	Lisa Juul. Extension Completeness: (If NOT complete, send certified letter requesting add Information.)
If E	extension Appl complete and \$100 fee submitted, route to
*	Jonnine Fuss Initial 30-day Public Notice: 4/20/04
	Update Extension Database: 41004
	Files back to filing cabinets: 4/10/01 but to list
+	the close of the Initial 30-day Comment Period Lisa Juul Pull files for Ext PFO review:
Onc •	e Extension PFO signed by Dwight French Jonnine Fuss Prepare Ext PFO for mailing to applicant:
	Mail to those who commented and paid copy fee:
	Include Ext PFO on weekly Public Notice:
	in 60 days after the close of the 45-day PFO Protest Period Protest Period ends 45 days from PFO sign date) Lisa Juul Issue an Extension FO:

Municipal or Quasi-Municipal EXTENSION REVIEW CHECKLIST for PFO... per Div. 315 Rules

	Application #: G - 12579/ Permit #: G - 1/376
	Permittee's Name: Crooked River Ranch Water Co. Tomes
	Permittee's Mailing Address: PO Box 1388, Crooked River Ranch, OR 97760
	POD Location: Township 3-5 Range 12-E Section 24 1/4 NWW SSUSE
	Stream Basin: County: Tefferson & Deschutes
1.	Has the applicant completely filled out the <i>updated</i> Extension Application form (Ves./ No \$100 paid on 4-3-00, ***If "No" has certified request for the new extension form been sent? Yes / No
1/2.	Shortcomings of Extension Request based upon review of updated extension form Yes / No ***(NOTE: Any missing Extension information that is needed before an Extension PFO can be completed???)
NOT	to add additional point of appropriation.
√3. √4. √5.	Date Permit was issued: (**Sp. Order Vol. 51, 13, 1235 Rapproved an add 1 performed the Permit, being Well#4) Source: Two Wells (#2;#3) In the crooked River Brisin Use: Quasi-Municipal Use
6.	"Q": 5.9 cfs (being 2.5 cfs from each well)
8. With	Conditions of Permit: Original "A" Date: 11-18-92 in one year of permit issuance shall submit a ter Management of Conservation Plan.
9.	Extension request received: \$ amended 4-6-04 Request Number (1st 2nd, 3rd): 2nd
V 10.	Last Authorized "B" Date: 10-1-98 Last Authorized "C" Date: 10-1-98
/	Proposed "B" Date: 10-1-2009 Proposed C Date: 10-1-2009

12. Amount Invested to date: 2,024,700. Estimated Total Cost: \$5,024,700.	2
12. Amount Invested to date: 4,024,700, Estimated Total Cost: 42,000,000	00
212. Amount Invested to date: 2,021, 100 Estimated Total Cost: \$3,000,000 (***Estimated Remaining Cost: \$3,000,000 pulation = Apricx 2,570 (based on 1028 connection s@ 2.5 persons he what 2,570 (based on: 1448 connection s@ 2.5 persons he	2.) —
year 1995 population= 11 2,500 (boolen 1028 connection 50 2.5 persons he	usehold)
Var 2004 population = 3,500 (based on: 1448 connections @ 2.5 persons (he 13. The water project development made to date has been accomplished in accordance with the terms and conditions co	
"A" Date Met (Orig Wells #20#3 were in existence for permit (tG-11376)
o Submitted a WMCP (Div 86) on 3-15-04.	
14. Work on the water development project completed to date includes: 14. Work on the water development project completed to date includes: 15. fs of water, Wellst2, #3 & #4 (T-7828) constr. establish	ed Service
· Used 3.75 cfs of water. • Welletz, #3 & #4 (1-7828) Constr. established Submitted a Div86 WMCP. • Repairs to well #2 & cistern 1448 ho	ons to
· purchased Chlorination system · Construction of 2 storage reservoirs (In 1999, he	ad approx)
purchased Chlorination system · Construction of 2 storage reservoirs (In 1999, he emergency use generator (Isee rg. 2-6 of WMCP-sept 2003) (1237 conr	
construction & full beneficial & . Need to	drill
construction & Use of water, & under per	nit amend
V 16. Progress in perfecting the permit is being held up by:	3).
· Waiting for full buildout of lots & the associa	iteal
increased demand for water.	
· Constraints of wells & water system have limited dev	date
17. Has the applicant pursued perfection of the right in good faith and with reasonable diligence? (Yes) No 1 Complied 1 of take used approx. I have invested to take a	onstructed
with 75% of total approx. 40% approx 75%	16-80%
I Care I at the w	sater
- Yes. Quantity of Water project. Complete delivery	system.
18. Determination of the market and the present demand for water or power to be supplied:	
a sleet to maintain o CRRWC, expects a 10 No other potential	Need to
to Great and Great Cheveroprised Market Scaperes 1	Server and the server of the server
for the northern & future based on, at a reasonable cost.	POP (T-9663)
Crocked River Ranch! Past growth trends. 1- Must maintain Hermit	G-11376.
219. Based on the written record, can the Department make a finding of "Good Cause" to approve the extension request?	
Yes "Good Cause" can be found. Approval of Extension Request	
No "Good Cause" cannot be found. Denial of Extension Request	
20. Conditions to be included on Extension PFO:	3
NO Conditions	
	\rightarrow
Extension "PFO" Dates Checklist Lag Revised: 1731 / 200	3//
Mailing / Issuance Date: 5 - 25 - 0 Reviewer's Name: Reviewer's Name:	W
Protest Deadline Date: 7-9-04 Date: 5-4-04	

Water Rights Information Query Results



Name	Application	Permit	Certificate	Decree	Claim	Transfer	Status	
CROOKED RIVER RANCH WATER CO. PO BOX 1477 CROOKED RIVER RANCH OR 97760 (details)		G2280	A			T6828 (Confirming)	NC	(0
CROOKED RIVER RANCH WATER Co. PO BOX 1477 CROOKED RIVER RANCH OR 97760 (details)		G2280	75144	0.06 for I of 4.4		T6604 T6828	NC	a
CROOKED RIVER RANCH WATER CO. PO BOX 1388 CROOKED RIVER RANCH OR 97760 (details)	G12579 * Subj	G11376	Permit	*		T7828 (Confirming)- T9663 (Terminating)	Sp. Orde NC	186,51 155he
CROOKED RIVER RANCH CO. TERREBONNE OR 97760 (details)	S9258	S7149	64216				NC	

Page:1

Download Place of Use Data, Point of Diversion Data, or Owner Data

Return to the Water Right Information search screen

Paul R. Cleary, Director

Oregon Water Resources Department • 725 Summer ST NE, Suite A • Salem, OR 97301 • Phone: 503-986-0900 • Fax: 503-986-0903

STATE OF OREGON

COUNTY OF JEFFERSON

CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

CROOKED RIVER RANCH P.O. BOX 1477 CROOKED RIVER RANCH, OREGON 97760

confirms the right to use the waters of WELL 2 in the CROOKED RIVER BASIN for IRRIGATION OF 4.4 ACRES.

This right was perfected under Permit G-2280. The date of priority is JANUARY 24, 1963. The amount of water to which this right is entitled is limited to an amount actually beneficially used and shall not exceed 0.06 CUBIC FOOT PER SECOND or its equivalent in case of rotation, measured at the well.

The well is located as follows:

NWW, NWW, SECTION 24, T 13 S, R 12 E, WM; 680 FEET SOUTH AND 780 FEET EAST FROM THE NW CORNER, SECTION 24.

The amount of water used for irrigation, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second, or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 3 acre-feet per acre for each acre irrigated during the irrigation season of each year.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the place of use to which this right is appurtenant is as follows:

NEW SWW 0.3 ACRE SEW SWW 0.7 ACRE NWW SEW 2.8 ACRES SWW SEW 0.6 ACRE SECTION 24

TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.

When required by the Department the water user shall install an inline flow meter or other suitable device for measuring and recording the quantity of water used. The type and plans of the measuring device must be approved by the Department prior to beginning construction and shall be installed under the general supervision of the Department.

The well shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon.

This use may be regulated if analysis of data available discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of this right or as those quantities may be subsequently reduced.

This certificate is issued to confirm a change in PLACE OF USE approved by an order of the Water Resources Director entered november 6, 1991, and together with Transfer 6828, supersedes Certificate 48452, State Record of Water Right Certificates.

Cert # 75144 page 1 The issuance of this superseding certificate does not confirm the status of the water right in regard to the provisions of ORS 540.610 pertaining to forfeiture or abandonment.

The right to the use of the water for the above purpose is restricted to beneficial use on the lands or place of use described.

witness the signature of the Water Resources Director, affixed _______.


MARTHA O. PAGEL


Martha O. Pagel, Director


Recorded in State Record of Water Right Certificates numbered 75144.


T-6828.LHN


Cert # 75144 page 2















To drive to ranch: From Portland take Mt. Hood highway past Government Camp to Madras then 20 miles south on US 97 to turnoff. From Salem and Eugene take Santiam Pass to Redmond, then north on US 97 6 miles to turnoff. At turnoff, just north of Terrebonne, go west, follow signs seven miles to

OCT 1 4 2003



ORIGINAL RANCH COMPLEX

- STABLES & RODEO GROUNDS
- **COMMUNITY RV PARK**
- KIDS FISHING & PICNIC AREA
- (5) CLUBHOUSE, CAFE, POOL, COMMUNITY STORE & POST OFFIC
- 6 GOLF COURSE
- (7). CHURCH!
- (8) FIRE STATION
- (9) GAS STATION, AUTO & RV REPAIR
- (10) LIGHT INDUSTRIAL AREA
- (11) RECREATIONAL VEHICLE STORAGE SEWAGE DUMP STATION
- (12) PLAYFIELD

- Well # 3 140'N\$ 770'E from 5%

1



LAND & WATER RIGHTS Bruce A. Estes, PLS, CWRE

60382 Arnold Mkt. Rd. Bend, OR 97702 (541) 382-7391 FAX 382-7391 PO Box 17519 Salem, OR 97305-7519 (503) 585-7593 FAX 585-7593

RECEIVED

AUG 0 6 2003

WATER RESOURCES DEPT. SALEM, OREGON FIRST MAP

CLAIM OF BENEFICIAL USE SITE REPORT

Application G-12579, Permit G-11376

in the name of Crooked River Ranch Water Co.

INFORMATION: Went over the project with Jim (JR) Rooks, manager.

SOURCE: Three wells in the Crooked River Basin. Wells 2 & 3 were drilled prior to filing the application. Well # 4 was authorized under permit amendment T-7828. It was drilled April 25 to May 26, 1994.

DIVERSION POINTS: Well # 2 - NW 1/4 NW 1/4 Section 24, Well # 3 - SW 1/4 SE 1/4 Section 24; Well # 4 - NE 1/4 SE 1/4 Section 16, all in T 13 S, R 12 E, W.M.; # 2 - 680' South and 780' East from the NW corner of section 24; # 3 - 140' North & 770' East from S 1/4 corner of section 24; # 4 - 1800' North & 770' West from SE corner of section 16.

USE: Quasi - Municipal Use in the unincorporated town site and on 1131 lots prior to October 1, 1998.

CAPACITY: Well # 2 has a 150 HP turbine pump. It has a static level of 280' and a drawdown of only 2'. It should be capable of 7.04x150/280+2+203 = 2.18 cfs (978 GPM) at 80 psi. Well # 3 has a 100 HP turbine pump with a static level of 286' and a drawdown of 2'. It should be capable of 7.04x100/286+2+203 = 1.43 cfs (642 GPM) at 80 psi. Well # 4 has a 200 HP turbine pump with a static level of 502' and a drawdown of 2'. That pump should be capable of 7.04x200/502+2+203 = 1.99 cfs (893 GPM) at 80 psi. The three wells pump into two reservoirs with 800,000 gallons of capacity. Total pump capacity is 2.18 + 1.43 + 1.99 = 5.60 cfs. In use the reservoirs are pulled down so the delivery rate exceeds the well pumping rate.

According to WRD policy the allowable rates for domestic including lawn and garden (domestic expanded) should be 0.03 cfs for 6 to 10 houses. With an evaporation rate exceeding 4' per season this location has one of the highest usage rates for lawns in the state. Therefore this permit should be authorized 0.03 cfs for 6 houses. The 1131 lots alone should have an allowance of $188 \times .03 = 5.65$ cfs (1131/6 = 188.5). The commercial use in the town site was not determined. The claim must be limited to the 5.0 cfs authorized by the permit.

TIE: The map was tied to the tax lot maps.

REMARKS: The B & C dates were extended to 10/1/98. Use was made within the extension. Well # 4 land surface datum is approximately 200' above wells 2 and 3. All 3 wells pump from the same aquifer.

RECEIVED

AUG 0 6 2003

WATER RESOURCES DEPT. SALEM, OREGON

An inspection of the land under the terms of permit G-11376 was made by me February 12, 2003, and the facts contained in this report and accompanying map are correct to the best of my knowledge.

I, J. R. Rooks, agree with Mr. Estes' findings and submit this site report and map as our Claim of Beneficial Use of the water as provided under the terms and conditions of permit G-11376 and hereby request a water right certificate be issued.

J. R. Rooks, General Manager



Water Resources Department

North Mall Office Building 725 Summer Street NE, Suite A Salem, OR 97301-1271 503-986-0900 FAX 503-986-0904

March 19, 2004

James Rooks, General Manager Crooked River Ranch Water Company P.O. Box 1388 Crooked River Ranch, OR 97760

Reference: Application File No. G-12579, Permit No. G-11376, Transfer Application No. T-9663

Dear Mr. Rooks:

Thank you for providing a copy of your Water Management and Conservation Plan Final Draft Report along with the chart of your maximum water use made on or before the completion date of your permit.

According to your chart, your maximum use of water on or before October 1, 1998, is approximately 3.75 cubic feet per second. This amount of water is less than the full quantity of water allowed by your permit.

If you wish to receive a certificate of water right at this time, the amount of water will be limited to the extent you can prove you have used water for a four hour period on or before October 1, 1998. If you wish additional time to fully apply the amount of water allowed by your permit, I recommend you complete a new extension form as requested in our letter of December 18, 2002.

Provided the extension of time request is approved, you may request the construction of an additional well by way of a permit amendment. Permit amendments are processed by our Field Services Division and they will assist you in completion of the requirements.

Please feel free to contact me if you have any questions and I will be happy to address any concerns you may have.

Sincerely,

Steve Brown Certificates

c: Tom Paul, Administrator, Field Services Division Dwight French, Manager, Water Rights Division Bruce Estes, CWRE

Fax



Name: STEVE BROWN

Organization: WRD

Fax: 503-986-0901

From: Barb Oakley, CRRWC

Date: March 12, 2004 **Subject:** RE: G-12579

Pages: 4

Comments: Attached is a letter, daily well logs for the month of August, 1998, and a graph to illustrate the water usage.

We have mailed the originals plus our WCMP this afternoon. If you have any questions or need further information, please give us a call or email. Thanks!

MAR 1 5 2004

WATER RESOURCES DEPT SALEM, OREGON

From the desk of...



March 12, 2004

Steve Brown Certificate Section Water Resources Department 725 Summer Street NE Salem, OR 97301-1271

Re: G-12579

Dear Mr. Brown:

Enclosed is the documentation you requested to show that in August, 1998, we did, in fact, pump 3.75 cfs for a time period of approximately five hours. We realize that this is not the full 5 cfs that we will be requiring once our new Well #3 is on-line. By the year 2007, we will be in a position with three, 850 gallon per minute wells and will show the need for and the use of 5 cfs. We will be glad to supply you with any documentation you need to qualify for the 5 cfs at that time.

Just a reminder, we have renumbered Crooked River Ranch Water Company's wells. Well #4 has been renumbered to Well #1, Well #2 remains the same, and the new well will be CRRWC Well #3.

Thank you very much for your expedient attention to this matter as it's vitally important to this community.

Sincerely,

JAMES ROOKS

James Rooks, General Manager Crooked River Ranch Water Company


RECEIVED

MAR 1 5 2004

WATER RESOURCES DEPT SALEM, OREGON

AUGUST, 1998 DATE DAILY LOG – WELL # 2 DISCHARE LINE STANDING WATER LEVEL OPERATOR LUBE METER READING CU.FT. MOTOR TEMP. Vibration ON/OFF Oil Level ROOM TEMP. METER READING IN CL 1 YES ŏ CU.FT LDPM

MAINTENANCE:	
Chlistid LANKing ON BypASS.	
	RECEIVED
	MAR 1 5 2004
AILY LOG2	WATER RESOURCES DEPT SALEM, OREGON



Fax

Name: STEVE BROWN

Organization: WRD

Fax: 503-986-0901

From: Barb Oakley, CRRWC

Date: March 12, 2004 Subject: RE: G-12579

Pages: 4

Comments: Attached is a letter, daily well logs for the month of August, 1998, and a graph to illustrate the water usage.

We have mailed the originals plus our WCMP this afternoon. If you have any questions or need further information, please give us a call or email. Thanks!



March 12, 2004

Steve Brown Certificate Section Water Resources Department 725 Summer Street NE Salem, OR 97301-1271

Re: G-12579

Dear Mr. Brown:

Enclosed is the documentation you requested to show that in August, 1998, we did, in fact, pump 3.75 cfs for a time period of approximately five hours. We realize that this is not the full 5 cfs that we will be requiring once our new Well #3 is on-line. By the year 2007, we will be in a position with three, 850 gallon per minute wells and will show the need for and the use of 5 cfs. We will be glad to supply you with any documentation you need to qualify for the 5 cfs at that time.

Just a reminder, we have renumbered Crooked River Ranch Water Company's wells. Well #4 has been renumbered to Well #1, Well #2 remains the same, and the new well will be CRRWC Well #3.

Thank you very much for your expedient attention to this matter as it's vitally important to this community.

Sincerely,

James Rooks, General Manager

Crooked River Ranch Water Company

	-	DAIL	Y LO	G – WE	LL#	2	DATE	-	AUG	USI	199	98
DATE 8. TIME	OPERATOR	METER READING IN CU.FT	CL 1 YES NO	LUBE METER READING CU.FT.	DISCHARE	LINE	STANDING WATER LEVEL	MOTOR TEMP.	ROOM TEMP.	Oil Level	Vibration	ON/OFF
LDPM 1	- D											-
2	4	8 20 10 44		- a		115	3,0		00	111		+-
3		12 1 10 7	-	93		11.5	118		04	TU!	-	
4		1998/1		17		1116			7/		-	
5		11/200		96		110	11		90			+
6		22 350		10		1/15	11		19		-	1 -
7		- 1 × 10	-	97		111	11		07			+
8			-			118	"		186	-		
9		11.77		97		115	- 11		41			
10		1.29526		-//		1111	11		91			
11	1 10	000		97		115			91			1
12		The strike				109	11		89		-	
13		14		98		116	11		92			
14		902688				116	11		81			
15		No. 10 Personal Property of the Property of th		98		117	11		90			
16 / "		1000				114	11	- P T W W C C	90			
17		100 1		99		115	11		87			T.
18		172875				116	11		71			
19		5. 1 1 1 1 1 5 E		101		114	.,		71 84 91 93			
20		374861				111	11		91			
21		2' 0 0		100		110	11		93			
22		4-2 0.1				114	.,		62			1
23		Sect Track		105		118	,,		81			
24		5925.39				116	ji		82			
25		and the second		103		116	11		76			
26		277646				112	4		81			
27		7:11 36		104		111	11		90			
28				,		110	11		96			
29		72.69.1				111	11		81			
30 /		Agriculty				116	11		85			
31		112112				117	11		76			

MAINTENANC	E:	
Chlivin	I Lanking ON BULDRES	
+		2
LY LOCA		

	~			(2)	шш	3	9			=	5	
	OPERATOR	METER READING IN CU.FT	CL 1 YES NO	LUBE METER READING CU.FT.	DISCHARE	LINE	STANDING WATER LEVEL	MOTOR TEMP.	ROOM TEMP.	Oil Level	Vibration	SHOW
		-										
116	1/2		NO	9236	75	80	520	NA	80	Tull		
c5 7	1		NO	97.57	1	75	1.	1	1/	11		
C7/		525 830		92.48	72	8/4	,,		92	11		
100		1.15841		92 95	9/	81	,,		81	1.		
100		1/27/8/2		93 05	1	76	,,		178	11		
16		719812		93 20	84	11	1.		91			
10		911.295	1	9331	80	80	11		94	11		
TAG		018 782	-	93 46	91	82	11_		96			
110		114782		93.61	0	75	11		91	1.		
,20		225052		90. 92	76	74	11		11	11		
10		335456		93 88	8/2	81	Li.		89	11		
)		445 869		90.90	7/	181			11	1		
100		548854		93 99	10	80	11		91	11		1
10		1,47506		94,21	0	76	10		96	li		
1:0		759 088		94,42	72	11.	,,		11	j.		
100		859546		9461	78	71	1.		79	il		
10		950060		94.80	0	93	11		18	- PT		1
(0)		1146 04		94,97	0	775	11		91	+		
710		165/86		95,11)	72-	10	11		80	4		+
105		2:6 722	-	95 31	86	81	11		82	1		-
110		346 80	-	95.54	81	10	11		91	1		-
120		457401	-	95.61	175	60	11-		40	2		+
100		557985	-	95.93	7/	1	11	-	KC.	ii		+
100		448254		111,0	1 0	76	11		72	1.		+
116		235 193	-	93,92		- "	11	1	84	1	-	
100		829760	1	96.00	1 11	86	11	-	91	i.		_
100		922345	-	96,21	77	"	11		90			
10		19821		96.56	1//	82	1:		14	f:		_ -
100		119116		96.41	75	20	11		92	-1-	-	-
15		350885		91.82	0	1/3	11		90	-4 -	-	

MAINTENANCE	: ,	,		-		
1818	ill /u	b_MKTI	EE.			 1660
			/			
MEGY	CLKDU	ing	CX-1			
	-					 -
						 -
					-	
						 _

NOTE:

Include a copy of the "Important Notice" document along with the original copy of the Final Order being sent to the permit holder.

Mailing List for Extension FO Copies

Application #G-12579 Permit #G-11376

.....

FO Date: July 14, 2004

Original mailed to:

Crooked River Ranch Water Co. Attn: James Rooks PO Box 1388 Crooked River Ranch, OR 97760 By: (SUPPORT STAFF)
on: (DATE)

For Extension FO's - Copies sent to:

- WRD Appl. File #G-12579 / Permit #G-11376
- 2. WRD Watermaster District: #11 Jeremy Giffin, Bend
- 3. WRD Municipal Liaison Bill Fujii, Salem
- WRD Permit Amendments Kelly Starnes, Salem.
- 5. ODFW Biologist District: #7 Steve Marx, Bend
- 6. DEQ Regional Office: Eastern Dick Nichols, Bend
- 7. WRD Support Staff, Salem...Permit record update

Other interested parties:

- 8. Allen, Sheridan & McClanahan, LLP
 Attn: William G. Sheridan, Jr.
 190 SW Harrison Street
 Portland, OR 97201
- Bruce Estes, CWRE #001
 Estes Surveys, LLC
 PO Box 17519
 Salem, OR 97305-7519

CASEWORKER: LJJ

S:\groups\wr\extensions\F O\Done\2004 final orders\g12579.wpd

Mailing List for Extension PFO Copies

Application #G-12579 PFO Date: May 25, 2004 Permit #G-11376

Original mailed to:

Applicant: Crooked River Ranch Water Company

Attn: James Rooks

PO Box 1388 Crooked River Ranch, OR 97760

For Extension PFO's - Copies sent to:

- 1. WRD Appl. File #G-12579/ Permit #G-11376
- 2. WRD Watermaster District: #11 Jeremy Giffin, Bend
- 3. WRD Doug Parrow, Salem
- 4. WRD Kelly Starnes Permit Amendments, Salem
- 5. DEQ Eastern Region: Dick Nichols, Bend
- 6. ODFW District #7: Steve Marx, Bend

Other interested parties:

- Allen, Sheridan & McClanahan, LLP Attn: William G. Sheridan, Jr. 190 SW Harrison Street Portland, OR 97201
- 8. Bruce Estes, CWRE #001 Estes Surveys, LLC PO Box 17519 Salem, OR 97305-7519

CASEWORKER: LJJ

S:\groups\wr\extensions\P F O\Work_315 rules\g12579.wpd

By: SUPPORT STAFF)

Proposed Final Order: Permit #G-11376

BEFORE THE WATER RESOURCES DEPARTMENT OF THE STATE OF OREGON

In the Matter of Permit Amendment)	
T-9663, Jefferson and Deschutes Counties,)	FINAL ORDER
Oregon)	

ORS 537.211 establishes the process in which a water right permit holder may submit a request to change the point of appropriation and/or place of use authorized under an existing water right permit.

Applicant

Crooked River Ranch Water Company, P.O. Box 879; 2 319
Crooked River Ranch, Oregon 97760.

Findings of Fact

- Crooked River Ranch Water Company filed an application to amend the point of appropriation of Well 3 under Permit G-11376. The Department assigned the application number T-9663.
- 2. The permit to be amended is as follows:

Permit: G-11376, in the name of Crooked River Ranch Water Company;

Use: Quasi-municipal; Priority Date: June 18, 1991;

Quantity: 5.0 cubic feet per second (cfs), being 2.5 cfs from each well;

Source: Wells 2, 3, and 4, in the Crooked River Basin.

Date Of Complete Application of

Water: October 1, 2008.

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order other than a contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-080 and OAR 690-01-005, you may either petition for judicial review or petition the Director for reconsideration of this order.

Authorized Points of Appropriation:

Town	nship	Range		Meridian	Sec	1/4	1/4	Lot	DLC	Location
13	S	12	Е	W.M.	24	NW	NW			Well 2 – 680 feet South and 780 feet East from the NW Corner of Section 24.
13	S	12	Е	W.M.	24	sw	SE			Well 3 – 80 feet North and 480 feet East from the S¼ Corner of Section 24.
13	S	12	Е	W.M.	16	NE	SE			Well 4 – 990 feet South and 680 feet West from the E ¹ / ₄ Corner of Section 16.

Authorized Place of Use:

Tow	nship	Ra	inge	Meridian	Sec	1/4	1/4	Lot	DLC	Acres
13	S	12	E	W.M.	4	NW	NW			116
13	S	12	Е	W.M.	4	SW	SW			
13	S	12	E	W.M.	4	SE	SW			
13	S	12	Е	W.M.	5	NE	NE			
13	S	12	Е	W.M.	5	SE	NE			
13	S	12	E	W.M.	5	SE	SW			
13	S	12	Е	W.M.	5	NE	SE			
13	S	12	E	W.M.	5	NW	SE			
13	S	12	E	W.M.	5	SW	SE			
13	S	12	Е	W.M.	5	SE	SE			
13	S	12	Е	W.M.	8	NE	NE			
13	S	12	Е	W.M.	8	NW	NE			
13	S	12	E	W.M.	8	SW	NE			
13	S	12	Е	W.M.	8	SE	NE			
13	S	12	Е	W.M.	8	NE	NW			
13	S	12	E	W.M.	9	NW	NW			
13	S	12	Е	W.M.	9	SW	NW			
13	S	12	E	W.M.	9	SE	NW			
13	S	12	Е	W.M.	9	NE	SW			
13	S	12	Е	W.M.	9	NW	SW			
13	S	12	Е	W.M.	9	SW	SW			
13	S	12	Е	W.M.	9	SE	SW			
13	S	12	Е	W.M.	9	NE	SE			
13	S	12	Е	W.M.	9	NW	SE			
13	S	12	Е	W.M.	9	SW	SE			
13	S	12	Е	W.M.	9	SE	SE			

Tow	nship	Rai	nge	Meridian	Sec	1/4	1/4	Lot	DLC	Acres
13	S	12	Е	W.M.	10	SW	NW			
13	S	12	Е	W.M.	10	SE	NW			
13	S	12	Е	W.M.	10	NE	SW			
13	S	12	Е	W.M.	10	NW	SW			
13	S	12	Е	W.M.	10	SW	SW			
13	S	12	Е	W.M.	10	SE	SW			
13	S	12	Е	W.M.	10	SW	SE			
13	S	12	Е	W.M.	10	SE	SE			
13	S	12	Е	W.M.	13	SW	SW			
13	S	12	Е	W.M.	14	SW	NE			
13	S	12	Е	W.M.	14	NW	NW			
13	S	12	Е	W.M.	14	SW	NW			
13	S	12	Е	W.M.	14	SE	NW			
13	S	12	Е	W.M.	14	NE	SW			
13	S	12	Е	W.M.	14	NW	SW			
13	S	12	Е	W.M.	14	SW	SW			
13	S	12	Е	W.M.	14	SE	SW			
13	S	12	Е	W.M.	14	NE	SE			
13	S	12	Е	W.M.	14	NW	SE			
13	S	12	Е	W.M.	14	SW	SE			
13	S	12	Е	W.M.	14	SE	SE			
13	S	12	Е	W.M.	15	NE	NE			
13	S	12	Е	W.M.	15	NW	NE			
13	S	12	E	W.M.	15	SW	NE			
13	S	12	Е	W.M.	15	SE	NE			
13	S	12	E	W.M.	15	NE	NW			
13	S	12	Е	W.M.	15	NW	NW	(I		
13	S	12	E	W.M.	15	SW	NW			
13	S	12	Е	W.M.	15	SE	NW			
13	S	12	Е	W.M.	15	NE	SW			
13	S	12	E	W.M.	15	NW	SW			
13	S	12	Е	W.M.	15	SW	SW			
13	S	12	Е	W.M.	15	SE	SW			
13	S	12	Е	W.M.	15	NE	SE			
13	S	12	Е	W.M.	15	NW	SE			
13	S	12	Е	W.M.	15	SW	SE			
13	S	12	Е	W.M.	15	SE	SE			
13	S	12	Е	W.M.	16	NE	NE			

Town	ship	Rar	nge	Meridian	Sec	Sec 1/4 1/4		Lot	DLC	Acres
13	S	12	Е	W.M.	16	NW	NE			
13	S	12	E	W.M.	16	SW	NE			
13	S	12	Е	W.M.	16	SE	NE			
13	S	12	Е	W.M.	16	NE	NW			
13	S	12	Е	W.M.	16	NW	NW			
13	S	12	Е	W.M.	16	SW	NW			
13	S	12	Е	W.M.	16	SE	NW			
13	S	12	Е	W.M.	16	NE	SW			
13	S	12	Е	W.M.	16	NW	SW			
13	S	12	Е	W.M.	16	SW	SW			
13	S	12	Е	W.M.	16	SE	SW			
13	S	12	Е	W.M.	16	NE	SE			
13	S	12	Е	W.M.	16	NW	SE			
13	S	12	Е	W.M.	16	SW	SE			
13	S	12	Е	W.M.	16	SE	SE			
13	S	12	Е	W.M.	17	NE	NE			
13	S	12	Е	W.M.	17	SE	NE			
13	S	12	Е	W.M.	17	NE	SE			
13	S	12	Е	W.M.	17	SE	SE			
13	S	12	Е	W.M.	21	NE	NE			
13	S	12	Е	W.M.	21	NW	NE			
13	S	12	Е	W.M.	21	SW	NE			
13	S	12	E	W.M.	21	SE	NE			
13	S	12	Е	W.M.	21	NE	NW			
13	S	12	Е	W.M.	21	NW	NW			
13	S	12	Е	W.M.	21	SW	NW			
13	S	12	Е	W.M.	21	SE	NW			
13	S	12	Е	W.M.	22	NE	NE			
13	S	12	Е	W.M.	22	NW	NE			
13	S	12	Е	W.M.	22	SW	NE			
13	S	12	Е	W.M.	22	SE	NE			
13	S	12	Е	W.M.	22	NE	NW			
13	S	12	E	W.M.	22	NW	NW			
13	S	12	Е	W.M.	22	SW	NW			
13	S	12	Е	W.M.	22	SE	NW			
13	S	12	Е	W.M.	22	NW	SW			
13	S	12	Е	W.M.	22	NE	SE			
13	S	12	Е	W.M.	22	NW	SE			

Town	Township		nge	Meridian	Sec	1/4 1/4		Lot	DLC	Acres
13	S	12	Е	W.M.	22	SE	SE			
13	S	12	Е	W.M.	23	NE	NE			
13	S	12	Е	W.M.	23	NW	NE	LU		
13	S	12	Е	W.M.	23	SW	NE			
13	S	12	Е	W.M.	23	SE	NE			
13	S	12	Е	W.M.	23	NE	NW			
13	S	12	E	W.M.	23	SE	NW			
13	S	12	Е	W.M.	23	NE	SW			
13	S	12	E	W.M.	23	SE	SW			
13	S	12	Е	W.M.	23	NE	SE			
13	S	12	Е	W.M.	23	NW	SE			
13	S	12	Е	W.M.	23	SW	SE			
13	S	12	E	W.M.	23	SE	SE			
13	S	12	Е	W.M.	24	NE	NW			
13	S	12	Е	W.M.	24	NW	NW			
13	S	12	Е	W.M.	24	SW	NW			
13	S	12	Е	W.M.	24	SE	NW			
13	S	12	Е	W.M.	24	NE	SW			
13	S	12	Е	W.M.	24	NW	SW			
13	S	12	Е	W.M.	24	SW	SW			
13	S	12	E	W.M.	24	SE	SW			
13	S	12	E	W.M.	24	NE	SE			
13	S	12	Е	W.M.	24	NW	SE			
13	S	12	Е	W.M.	24	SW	SE			
13	S	12	Е	W.M.	24	SE	SE			
13	S	12	Е	W.M.	25	NE	NE			
13	S	12	E	W.M.	25	NW	NE			
13	S	12	Е	W.M.	25	SW	NE			
13	S	12	E	W.M.	25	SE	NE			
13	S	12	E	W.M.	25	NE	NW			
13	S	12	Е	W.M.	25	NW	NW			
13	S	12	Е	W.M.	25	SW	NW			
13	S	12	Е	W.M.	25	SE	NW			
13	S	12	Е	W.M.	25	NE	SW			
13	S	12	Е	W.M.	25	NW	SW			
13	S	12	Е	W.M.	25	SW	SW			
13	S	12	Е	W.M.	25	SE	SW			
13	S	12	Е	W.M.	25	NE	SE			

Tow	Township		nge	Meridian	Sec	1/4 1/4		Lot	DLC	Acres
13	S	12	Е	W.M.	25	NW	SE			C. C. S. C.
13	S	12	Е	W.M.	25	SW	SE			
13	S	12	Е	W.M.	25	SE	SE			
13	S	12	Е	W.M.	26	NE	NE			
13	S	12	E	W.M.	26	NW	NE			
13	S	12	Е	W.M.	26	SW	NE			
13	S	12	Е	W.M.	26	SE	NE			
13	S	12	Е	W.M.	26	NE	NW			
13	S	12	Е	W.M.	26	NW	NW			
13	S	12	Е	W.M.	26	SW	NW			
13	S	12	Е	W.M.	26	SE	NW			
13	S	12	Е	W.M.	26	NE	SW			
13	S	12	E	W.M.	26	NW	SW			
13	S	12	Е	W.M.	26	SW	SW			
13	S	12	Е	W.M.	26	SE	SW			
13	S	12	Е	W.M.	26	NE	SE			
13	S	12	Е	W.M.	26	NW	SE			
13	S	12	Е	W.M.	26	SW	SE			
13	S	12	Е	W.M.	26	SE	SE			
13	S	12	Е	W.M.	27	NE	NE			
13	S	12	Е	W.M.	27	NW	NE			
13	S	12	Е	W.M.	27	SW	NE			
13	S	12	Е	W.M.	27	SE	NE			
13	S	12	E	W.M.	27	NE	NW			
13	S	12	Е	W.M.	27	NW	NW			
13	S	12	Е	W.M.	27	SE	NW			
13	S	12	Е	W.M.	27	NE	SW			
13	S	12	Е	W.M.	27	SW	SW			
13	S	12	Е	W.M.	27	SE	SW			
13	S	12	Е	W.M.	27	NE	SE	L.Y		
13	S	12	Е	W.M.	27	NW	SE			
13	S	12	Е	W.M.	27	SW	SE			
13	S	12	Е	W.M.	27	SE	SE			
13	S	12	Е	W.M.	34	NE	NE			
13	S	12	Е	W.M.	34	NW	NE			
13	S	12	Е	W.M.	34	SW	NE			
13	S	12	Е	W.M.	34	NE	NW			
13	S	12	Е	W.M.	34	NW	NW			-

Tow	nship	Range		Meridian Se		Sec 1/4 1/4			DLC	Acres
13	S	12	Е	W.M.	34	SW	NW			
13	S	12	Е	W.M.	34	SE	NW			
13	S	12	Е	W.M.	34	NE	SW			
13	S	12	Е	W.M.	34	SE	SW			
13	S	12	Е	W.M.	34	NE	SE			
13	S	12	Е	W.M.	34	NW	SE			
13	S	12	Е	W.M.	34	SW	SE			
13	S	12	Е	W.M.	34	SE	SE			
13	S	12	Е	W.M.	35	NE	NE			
13	S	12	Е	W.M.	35	NW	NE			
13	S	12	E	W.M.	35	SW	NE			
13	S	12	Е	W.M.	35	SE	NE	130		
13	S	12	Е	W.M.	35	NE	NW			
13	S	12	Е	W.M.	35	NW	NW			
13	S	12	Е	W.M.	35	SW	NW			
13	S	12	Е	W.M.	35	SE	NW			
13	S	12	Е	W.M.	35	NE	SW			
13	S	12	Е	W.M.	35	NW	SW			
13	S	12	Е	W.M.	35	SW	SW			
13	S	12	Е	W.M.	35	SE	SW			
13	S	12	Е	W.M.	35	NE	SE			
13	S	12	Е	W.M.	35	NW	SE			
13	S	12	Е	W.M.	35	SW	SE			
13	S	12	Е	W.M.	35	SE	SE			
13	S	12	E	W.M.	36	NE	NE			
13	S	12	Е	W.M.	36	NW	NE			
13	S	12	Е	W.M.	36	SW	NE			
13	S	12	E	W.M.	36	NE	NW			
13	S	12	Е	W.M.	36	NW	NW			
13	S	12	Е	W.M.	36	SW	NW			
13	S	12	Е	W.M.	36	SE	NW			
13	S	12	Е	W.M.	36	NE	SW			
13	S	12	Е	W.M.	36	NW	SW			
13	S	12	Е	W.M.	36	SW	SW			
13	S	12	Е	W.M.	36	SE	SW			
13	S	12	Е	W.M.	36	NE	SE			
13	S	12	Е	W.M.	36	NW	SE			111
13	S	12	Е	W.M.	36	SW	SE			

Town	nship	Range		Meridian Sec		1/4 1/4		Lot	DLC	Acres
13	S	12	Е	W.M.	36	SE	SE			
13	S	13	Е	W.M.	31	SW	SW			
13	S	13	Е	W.M.	31	SE	SW			
13	S	13	Е	W.M.	31	SW	SE			
14	S	12	Е	W.M.	1	NE	NE			
14	S	12	Е	W.M.	1	NW	NE			
14	S	12	Е	W.M.	1	NE	NE			
14	S	12	Е	W.M.	1	NW	NW			
14	S	12	Е	W.M.	1	SW	NW			
14	S	12	Е	W.M.	2	NE	NE			
14	S	12	Е	W.M.	2	NW	NE			
14	S	12	Е	W.M.	2	SE	NE			
14	S	12	Е	W.M.	2	NW	SW			
14	S	12	Е	W.M.	2	SW	SW			
14	S	12	Е	W.M.	2	SE	SW			
14	S	12	Е	W.M.	3	NE	NE			
14	S	12	Е	W.M.	3	NW	NE			
14	S	12	Е	W.M.	3	SW	NE			
14	S	12	Е	W.M.	3	SE	NE			
14	S	12	Е	W.M.	3	NE	NW			
14	S	12	E	W.M.	3	NW	NW			
14	S	12	Е	W.M.	3	SW	NW			
14	S	12	Е	W.M.	3	SE	NW			
14	S	12	Е	W.M.	3	NE	SW			
14	S	12	E	W.M.	3	NW	SW			
14	S	12	Е	W.M.	3	SW	SW			
14	S	12	Е	W.M.	3	SE	SW			
14	S	12	E	W.M.	3	NE	SE			
14	S	12	Е	W.M.	3	NW	SE			
14	S	12	Е	W.M.	3	SW	SE			
14	S	12	Е	W.M.	3	SE	SE			
14	S	12	E	W.M.	11	NW	NW			
14	S	13	Е	W.M.	6	NW	NE			
14	S	13	Е	W.M.	6	NE	NW			
14	S	13	Е	W.M.	6	NW	NW			

3. Application T-9663 proposes to change the point of appropriation of Well 3 under the permit to:

Township		Range		Meridian	Sec	1/4 1/4	Lot	DLC	Location
13	S	12	Е	W.M.	16	NW SE			Crater Loop Road Well 3 – 2550 feet North and 2100 feet West from the SE Corner of Section 16.

- Notice of the application for permit amendment was published pursuant to ORS 540.520(5).
 No comments were filed in response to the notice.
- 5. The change would not result in injury to other water rights.
- The change does not enlarge the permit.
- 7. The change does not alter any other terms of the permit.
- 8. Approval of this permit amendment does not grant the permittee permission to trespass on lands not owned by the permittee.

Conclusion of Law

The change in point of appropriation of Well 3 proposed by Permit Amendment Application T-9663 is consistent with the requirements of ORS 537.211.

Now, therefore, it is ORDERED:

The change and subsequent use of water shall be subject to the following conditions:

- The quantity of water diverted at the new point of appropriation (well) shall not exceed the maximum rate and duty allowed for Well 3 under Permit G-11376.
- Prior to water use from the proposed point of appropriation, the permittee shall install a
 meter or other suitable measuring device as approved by the Director. The permittee shall
 maintain the meter or measuring device in good working order. The permittee shall keep a
 complete record of ground water withdrawn.
- 3. Water shall be acquired from the same aquifer as the original point of appropriation.
- 4. All other terms and conditions of Permit G11376 remain the same.
- Permit G-11376, in the name of Crooked River Ranch Water Company, is amended as described herein.

Dated at Salem, Oregon this 20th day of Septem 2004.

Phillip C. Ward,
Acting Director



FAX COVER SHEET

RECEIVED

MAY 0 3 2004

WATER RESOURCES DEPT
SALEM, OREGON

DATE 5-3-04	PAGES W/ COVER _ 🖂
TO: LISA JULIL.	LORD
PHONE:	
FAX PHONE: 503-99	36-0901
FROM: Jim Rocks,	CRRIUC.
MESSAGE: XE (TIT	ached





Memo

RECEIVED WATER RESOURCES DEPT SALEM, OREGON

To:

From:

Jim Rooks, General Mgr.

Date:

May 3, 2004

Subject:

PROPOSED EXTENSION AMENDMENT

Crooked River Ranch Water Company would like to amend the proposed extension date from 2009 to 2008. This is for permit #G-11376. Thanks for your assistance!

Barbara Oakley, 09:23 AM 5/3/04, WATER PERMIT EXTENSION

From: "Barbara Oakley" <Barbara@bendnet.com>
To: "Lisa J Juul" <Lisa.J.JUUL@wrd.state.or.us>

Subject: WATER PERMIT EXTENSION Date: Mon, 3 May 2004 09:23:38 -0700

X-Security: MIME headers sanitized on kettle.wrd.state.or.us See http://www.impsec.org/email-tools/sanitizer-intro.html for details. \$Revision: 1.139 \$Date: 2003-09-07 10:14:23-07

X-Mailer: Microsoft Outlook Express 6.00.2800.1409

Good Morning, Lisa,

I have a question about the 30 day "publishing" of our extension request. I see that it has been published, but if someone were to file a protest, how would we know that? Would it be posted on your website? I haven't heard any complaints, but just curious as to whether there's another website I should be monitoring. Thanks for your help!

30 days end -> May 20, 2004 Comment feriod. Thursday

Barb Oakley, Administrative Assistant Crooked River Ranch Water Company 541-923-1041

Printed for Lisa J Juul < Lisa. J. JUUL @wrd.state.or.us>

To: all-owrd@wrd.state.or.us

From: Cindy Smith < Cindy.S.SMITH@wrd.state.or.us >

Subject: Fwd: CHANGE OF EMAIL ADDRESS

From: "Barb Oakley" < boakley@bendnet.com>

To: <Cindy.S.Smith@wrd.state.or.us> Subject: CHANGE OF EMAIL ADDRESS Date: Sun, 20 Feb 2005 12:06:24 -0800

X-Security: MIME headers sanitized on kettle.wrd.state.or.us See http://www.impsec.org/email-tools/sanitizer-intro.html for details. \$Revision: 1.139 \$Date: 2003-09-07 10:14:23-07

X-Mailer: Microsoft Outlook Express 6.00.2900.2527

X-Spam-Checker-Version: SpamAssassin 2.63 (2004-01-11) on

kettle.wrd.state.or.us

X-Spam-Status: No, hits=-3.7 required=5.0 tests=BAYES_00,FORGED_OUTLOOK_TAGS, HTML_MESSAGE,RCVD_IN_SORBS autolearn=no version=2.63

X-Spam-Level:

Please note that my email has changed from < mailto:Barbara@bendnet.com > Barbara@bendnet.com to < mailto:Barb@crrwc.com > Barb@crrwc.com. If you have any questions please feel free to contact me at 541-923-1041. Thanks!

Barb Oakley, Admin. Assistant Crooked River Ranch Water Company <mailto:Barb@crrwc.com>Barb@crrwc.com

Cindy Smith
Executive Assistant
OR Water Resources Department
725 Summer Street NE, Suite A
Salem, OR 97301
503-986-0876 Phone
503-986-0903 Fax
Cindy.S.Smith@wrd.state.or.us

Water Rights Information Query Results

Name	Application	Permit	Certificate	Decree	Claim	Transfer	Status
CROOKED RIVER RANCH PO BOX 1477 CROOKED RIVER RANCH OR 97760 (details)		G2280				T6828 (Confirming)	NC
CROOKED RIVER RANCH PO BOX 1477 CROOKED RIVER RANCH OR 97760 (details)		G2280	75144			T6604 T6828	NC
CROOKED RIVER RANCH WATER CO. PO BOX 879 CROOKED RIVER RANCH OR 97760 (details)	Court of the court	G11376				T9663	NC
CROOKED RIVER RANCH CO. TERREBONNE OR 97760 (details)	S9258	S7149	64216				NC

Page:1

Download Place of Use Data, Point of Diversion Data, or Owner Data

Definition of codes and abbreviations

Return to the Water Right Information search screen

STATE OF OREGON

COUNTY OF JEFFERSON AND DESCHUTES

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

CROOKED RIVER RANCH WATER COMPANY P.O. BOX 879 CROOKED RIVER RANCH, OREGON 97760

503-548-8939

to use the waters of WELLS 2 & 3 in the CROOKED RIVER BASIN for QUASI-MUNICIPAL USE.

This permit is issued approving Application G-12579. The date of priority is JUNE 18, 1991. The use is limited to not more than 5.0 CUBIC FEET PER SECOND (CFS), BEING 2.5 CFS FROM EACH WELL, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

NW 1/4 NW 1/4, SW 1/4 SE 1/4, SECTION 24, T 13 S, R 12 E, W.M.; WELL 2 - 680 FEET SOUTH AND 780 FEET EAST FROM NW CORNER, SECTION 24, WELL 3 - 80 FEET NORTH AND 480 FEET EAST FROM S 1/4 CORNER, SECTION 24.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

NW 1/4 NW 1/4 S 1/2 SW 1/4 SECTION 4 E 1/2 NE 1/4 SE 1/4 SW 1/4 SE 1/4 SECTION 5 NE 1/4 NE 1/4 NW 1/4 SECTION 8 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 9 S 1/2 NW 1/4 SW 1/4 S 1/2 SE 1/4 SECTION 10 SW 1/4 SW 1/4 SECTION 13 SW 1/4 NE 1/4 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 14 ALL SECTION 15 ALL SECTION 16 E 1/2 NE 1/4 E 1/2 SE 1/4 SECTION 17 N 1/2 SECTION 21

```
N 1/2
NW 1/4 SW 1/4
N 1/2 SE 1/4
SE 1/4 SE 1/4
 SECTION 22
   NE 1/4
E 1/2 NW 1/4
E 1/2 SW 1/4
   SE 1/4
 SECTION 23
   NW 1/4
   S 1/2
 SECTION 24
    ALL
 SECTION 25
    ALL
 SECTION 26
    E 1/2
N 1/2 NW 1/4
SE 1/4 NW 1/4
NE 1/4 SW 1/4
S 1/2 SW 1/4
 SECTION 27
N 1/2 NE 1/4
SW 1/4 NE 1/4
   NW 1/4
E 1/2 SW 1/4
   SE 1/4
 SECTION 34
    ALL
 SECTION 35
N 1/2 NE 1/4
SW 1/4 NE 1/4
   W 1/2
   SE 1/4
 SECTION 36
```

TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.

S 1/2 SW 1/4 SW 1/4 SE 1/4 SECTION 31

TOWNSHIP 13 SOUTH, RANGE 13 EAST, W.M.

N 1/2 NE 1/4 N 1/2 NW 1/4 SW 1/4 NW 1/4 SECTION 1 N 1/2 NE 1/4 SE 1/4 NE 1/4 W 1/2 SW 1/4 SE 1/4 SW 1/4 SECTION 2 ALL SECTION 3 NW 1/4 NW 1/4 SECTION 11

TOWNSHIP 14 SOUTH, RANGE 12 EAST, W.M.

NW 1/4 NE 1/4 N 1/2 NW 1/4 SECTION 6 TOWNSHIP 14 SOUTH, RANGE 13 EAST, W.M.

Within one year from the date the Water Resources Commission adopts rules describing the schedules, standards and procedures for water conservation management plans by water suppliers, Crooked River Ranch Water Company shall submit a plan which is consistent with said rules.

Application G-12579

Water Resources Department

PERMIT G-11376

Within one year of permit issuance, Crooked River Ranch Water Company shall prepare a plan/timetable for the Water Resources Commission which shall indicate the steps which the Water Company intends to pursue to obtain a long-term water supply.

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the wells at all times. When required by the department, the permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before November 18, 1992, and shall be completed on or before October 1, 1993. Complete application of the water shall be made on or before October 1, 1994.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

Issued this date, NOVEMBER 18, 1991.

/e/ "ILLIAM H. YOUNG

Water Resources Department William H. Young Director

AMENDED by special order v. 51 pg. 1235

Extension "Final Order" Checklist

Application # G-12579/Permit # G-11376 Permit Holder's Name Crooked River Ranch Water Co.
Permit Holder's Name Crooked River Ranch Water Co. Attn: James Rooks, PO Box 1388, Crooked River Ranch, OR 97760
This Final Order is processed under: Div. 315 Rules -or- Div. 320 Rules
1. Date Extension Request submitted: 4-3-2000
$\sqrt{2}$. Date permit was issued: $11-18-91$
✓3. Original "B" Date from permit:
4. Original "C" Date from permit:/ O - / - 94 (Date for complete application of water)
√5. Extension PFO Date: 5-25-2004
√6. WRD recommends extending "B" Date to: 10-1-2008 and extending the "C" Date to: 10-1-2008
8. Protest Deadline Date from PFO: $7-9-2004$
9. Any written Protests or written Comments received within the Protest period? Yes No CC: William 9. Sheridan, Jr. Bruce Estes
Reviewer's Name: Date: 7-13-04 See
S:\groups\wr\extensions\forms and templates\ext_final order_checklist.wpd

From: "Tim Wallin" <Timothy.WALLIN@wrd.state.or.us>

To: "Sarah Henderson" <Sarah.A.HENDERSON@wrd.state.or.us>

Cc: "Steve Brown" < Stephen.C.BROWN@wrd.state.or.us>

Subject: FW: WATER TRANSFER
Date: Thu, 11 Mar 2004 09:26:00 -0800

X-Security: MIME headers sanitized on kettle.wrd.state.or.us See http://www.impsec.org/email-tools/sanitizer-intro.html for details. \$Revision: 1.139 \$Date: 2003-09-07 10:14:23-07

X-Mailer: Microsoft Outlook IMO, Build 9.0.6604 (9.0.2911.0)

Importance: Normal

-->

Sarah – would you respond to Barbara at your convenience? Regular mail is fine. You may want to mention that she should expect to hear from Steve Brown soon regarding the status of proof (or more correctly the lack thereof) on their previous transfer.

Tim Wallin

Field Services - Transfer

Water Resources Department

725 Summer St NE, Suite A

Salem OR 97301-1271

voice: 503.986.0891 fax: 503.986.0903 http://www.wrd.state.or.us

----Original Message----

From: Barbara Oakley [mailto:Barbara@bendnet.com]

Sent: Thursday, March 11, 2004 9:17 AM


To: Tim Wallin

Subject: WATER TRANSFER

Good Morning, Tim,

Thanks for meeting with us Tuesday. We learned a lot and feel it was a very productive meeting. I am preparing the letter now to request an expedite of our paper work. Who do I address this to? I will email the letter and follow it up with a hard copy to be put in the mail today, or I can fax it. Which would you prefer? What is the fax number? Also, do you have a file number for the paperwork we just submitted? Thanks!!

Barb Oakley, Administrative Assistant Crooked River Ranch Water Company 541-923-1041



Jerry Sauter, CWRS Water Resources Department 158 12th Street NE Salem, OR 97301-4172

Re: Application #G-12579, Permit #G-11376

Dear Mr. Sauter:

Crooked River Ranch Water Company has perfected their water rights and submitted a "Claim of Beneficial Use Site Report" to WRD earlier this week. According to Bruce Estes, CWRE, he was able to establish that beneficial use was met prior to 10/1/98. Since we have applied for our certificate, we are writing this letter to withdraw our application for the extension of time on our water permit.

If you have any questions, please contact me at 541-923-1041.

Sincerely,

James Rooks, General Manager

Crooked River Ranch Water Company

RECEIVED

G-12579

AUG 1 5 2003

WATER RESOURCES DEPT. SALEM, OREGON

G-12579



August 8, 2003

Jerry Sauter, CWRS Water Resources Department 158 12th Street NE Salem, OR 97301-4172

Re: Application #G-12579, Permit #G-11376

Dear Mr. Sauter:

Crooked River Ranch Water Company has perfected their water rights and submitted a "Claim of Beneficial Use Site Report" to WRD earlier this week. According to Bruce Estes, CWRE, he was able to establish that beneficial use was met prior to 10/1/98. Since we have applied for our certificate, we are writing this letter to withdraw our application for the extension of time on our water permit.

If you have any questions, please contact me at 541-923-1041.

Sincerely,

James Rooks, General Manager

Crooked River Ranch Water Company

RECEIVED

AUG 1 5 2003

WATER RESOURCES DEPT. SALEM, OREGON



P.O. Box 1388 Crooked River Ranch, OR 97760





Jerry Sauter, CWRS Water Resources Department 158 12th Street NE Salem, OR 97301-4172

612579

STATE OF OREGON

COUNTY OF CROOK

ORDER APPROVING AN ADDITIONAL POINT OF APPROPRIATION

Pursuant to ORS 537.211, after notice was given and no objections were filed, and finding that no injury to existing water rights would result, this order approves, as conditioned or limited herein, PERMIT AMENDMENT T-7828 submitted by

CROOKED RIVER RANCH WATER COMPANY P.O. BOX 1388 CROOKED RIVER RANCH, OREGON 97760.

The permit to be modified is Permit G-11376 with a date of priority of JUNE 18, 1991. The permit allows the use of WELLS 2 AND 3, in the CROOKED RIVER BASIN, for QUASI-MUNICIPAL USE. The amount of water to which this permit is entitled is limited to an amount actually beneficially used and shall not exceed 5.0 CUBIC FOOT PER SECOND (CFS), BEING 2.5 CFS FROM EACH WELL, if available at the original wells; NW¼ NW¼, SW½ SE¼, SECTION 24, T 13 S, R 12 E, W.M.; WELL 2 - 680 FEET SOUTH AND 780 FEET EAST FROM THE NW CORNER OF SECTION 24, WELL 3 - 80 FEET NORTH AND 480 FEET EAST FROM THE S½ CORNER OF SECTION 24, or its equivalent in case of rotation, measured at the well.

The use shall conform to any reasonable rotation system ordered by the proper state officer.

The authorized place of use is as follows:

NW¼ NW¼	N½
S½ SW¼	NW1/4 SW1/4
SECTION 4	N½ SE¼
	SE¼ SE¼
E% NE% SE% SW%	SECTION 22
SE¼	NE¼
SECTION 5	E½ NW¼
	E½ SW¼
NE1/4	SE¼
NE¼ NW¼	SECTION 23
SECTION 8	
	NW1/4
NW¼ NW¼	S½
S% NW% S%	SECTION 24
SECTION 9	ALI
	SECTION 25

S% NW%	ALL
SW1/4	SECTION 26
S½ SE¼	
SECTION 10	E½
	N¼ NW¼
SW1/4 SW1/4	SE¼ NW¼
SECTION 13	NE¼ SW¼
	S½ SW¼
SW1/4 NE1/4	SECTION 27
NW¼ NW¼	
S½ NW¾	N½ NE¼
S½	SW¼ NE¼
SECTION 14	NW1/4
	E½ SW¼
ALL	SE¼
SECTION 15	SECTION 34
ALL	ALL
SECTION 16	SECTION 35
E% NE%	N½ NE¾
E½ SE¼	SW¼ NE¾
SECTION 17	W½
	SE¼
N½	SECTION 36
CHOMPOST OF	

TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.

SECTION 21

S% SW% SW% SE% SECTION 31

TOWNSHIP 13 SOUTH, RANGE 13 EAST, W.M.

N½ NE¼ ALL
N½ NW¼ SECTION 3
SW¼ NW¼
SECTION 1 NW½ NW½
SECTION 11
N½ NE¼
SE¼ NE¼
W½ SW¼
SE¼ SW¼
SECTION 2

TOWNSHIP 14 SOUTH, RANGE 12 EAST, W.M.

NW% NE% N% NW% SECTION 6

TOWNSHIP 14 SOUTH, RANGE 13 EAST, W.M.

This use may be regulated if analysis of data available discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of this right or as those quantities may be reduced.

The right to use water for the above purpose is restricted to beneficial use on the lands or place of use described.

The applicant proposes an additional point of appropriation to:

WELL 4 - NE% SE%, SECTION 16, T 13 S, R 12 E, W.M.; 990 FEET SOUTH AND 680 FEET WEST FROM THE E% CORNER OF SECTION 16.

THIS CHANGE TO AN EXISTING WATER PERMIT MAY BE MADE PROVIDED THE FOLLOWING CONDITIONS ARE MET BY THE WATER USER:

- The quantity of water diverted at the new point of appropriation (well), together with the quantity diverted at the old points of appropriation, shall not exceed the quantity of water lawfully available from the original points of appropriation.
- Water shall be acquired from the same aquifer as the original points of appropriation.
- 3. All other terms and conditions of the permit remain the same.

Permit G-11376, in the name of CROOKED RIVER RANCH WATER COMPANY is amended as described herein.

affixed_	WITNESS the signature OCT 30 1997	of	the	Water	Resources	Director,
					0	

Martha O. Pagel, Director

Barbara Oakley, 04:27 PM 5/19/03 -0700, Re: PERMIT EXTENSION

From: "Barbara Oakley" <Barbara@eagleslair.net>
To: "Lisa J Juul" <Lisa.J.JUUL@wrd.state.or.us>

Subject: Re: PERMIT EXTENSION
Date: Mon, 19 May 2003 16:27:20 -0700
X-Security: MIME headers sanitized on funnel

See http://www.impsec.org/email-tools/sanitizer-intro.html for details. \$Revision: 1.133 \$Date: 2002-01-05 17:09:21-08

X-Mailer: Microsoft Outlook Express 6.00.2800.1106

We are hoping that we can do this in another 90 days. So lets go with that for now. Thanks! Barb

---- Original Message ----

From: Lisa J Juul
To: Barbara Oakley

Sent: Monday, May 19, 2003 4:12 PM Subject: Re: PERMIT EXTENSION

Hi Barbara,

No problem. How much longer do you think you might need? 90 days? Longer?

-Lisa

At 03:52 PM 5/19/03 -0700, you wrote:

Is it possible to get another extension on our water permit? We have an extension to June 18, but trying to get the engineers and water rights experts going has been a delay to us. This is for permit G-11376. Thanks!

Barb Oakley Crooked River Ranch Water Company 541-548-2353

Lisa J. Juul Water Rights Specialist Water Rights & Adjudications Division Oregon Water Resources Department 158 - 12th Street NE Salem, Oregon 97301-4172

Phone # (503) 378-8455, extension 272 FAX # (503) 378-6203

Homepage/Website Address - http://www.wrd.state.or.us

Printed for Lisa J Juul <Lisa.J.JUUL@wrd.state.or.us>

File# G-12579



Water Resources Department

Commerce Building 158 12th Street NE Salem, OR 97301-4172 503-378-3739 FAX 503-378-8130

May 7, 2003

Crooked River Ranch Water Company P.O. Box 1388 Crooked River Ranch, OR 97760

Dear Crooked River Ranch Water Company:

My letter of March 27, 2003, provided you and the Crooked River Ranch Club and Maintenance Association a brief summary of the evolution of the irrigation water right, Permit G-2280, associated with Well #2. In addition to the diversion of up to 0.06 cfs for irrigation of 4.4 acres under remaining right Certificate 75144(Permit G-2280), Well #2 also is an authorized point of appropriation under that portion of Permit G-11376 held by Crooked River Ranch Water Company (CRRWC), for quasi-municipal use.

In 1997, CRRWC filed a permit amendment for G-11376 (T-7828) requesting to add Well #4, as an additional point of appropriation, to Wells #2 and #3. An order of the Water Resources Director entered October 30, 1997, and recorded in Special Order Volume 51, Page 1235, approved the additional point of appropriation. The order limited use under Permit G-11376 to a cumulative total of 5.0 cfs with the quantity not to exceed 2.5 cfs from any single well.

CRRWC has requested several extensions of time to complete the appropriation of water and application of water to beneficial use under the terms of amended Permit G-11376. On December 18, 2002, the Department requested CRRWC complete and return a new application for extension of time for quasi-municipal and municipal water use permits consistent with the Department's OAR Chapter 690, Division 315 administrative rules on permit extensions. CRRWC has not completed and returned the new application form.

Sincerely,

Tom Paul

Administrator, Field Services Division

c: Kyle Gorman, South Central Region Manager Crooked River Ranch Club and Maintenance Association John H. Hammond, Jr.



File# G-12579

MAR 1 0 2003
WATER RESOURCES DEPT.
SALEM, ORFGON

March 5, 2003

Water Resources Department attn: Lisa Juul Commerce Building 158 12th St. NE Salem, OR 97301-4172

Re: Permit #G11376, Application File #G12579

Dear Ms. Juul:

Crooked River Ranch Water Company is requesting a 90 day extension on submitting our request for a permit extension on the above permit. We are in the midst of researching and trying to clarify water rights issues and need to have extra time to complete this project.

If there are any problems in granting this extension, please contact us as soon as possible at (541)548-2353, or email my Admin Assistant, Barb Oakley, at Barbara@eagleslair.net.

Thank you for your assistance in this matter.

Sincerely,

James Rooks, General Manager Crooked River Ranch Water Company



P.O. Box 1388 Crooked River Ranch, OR 97760





Water Resources Department attn: Lisa Juul Commerce Building 158 12th St. NE Salem, OR 97301-4172

Heliabrida Hellamor Heliabrid Hardada heliabridada

Lisa J Juul, 02:48 PM 3/11/03 -0800, Re: PERMIT EXTENSION

Page 1 of 1 File# G-12579

X-Sender: juullj@mailhub.wrd.state.or.us

X-Mailer: QUALCOMM Windows Eudora Version 5.1

Date: Tue, 11 Mar 2003 14:48:06 -0800

To: "Barbara Oakley" <Barbara@eagleslair.net>
From: Lisa J Juul <Lisa.J.JUUL@wrd.state.or.us>

Subject: Re: PERMIT EXTENSION Cc: Lisa.J.JUUL@wrd.state.or.us

X-Security: MIME headers sanitized on funnel

See http://www.impsec.org/email-tools/sanitizer-intro.html for details. \$Revision: 1.133 \$Date: 2002-01-05 17:09:21-08

Hi Barb,

I did receive your request for more time to complete the extension application. Your request for an additional 90 days (from March 18, 2003) to submit the application is approved.

I haven't been sending out confirmations on these.... so, I hope this e-mail will suffice.

If you have any more questions, please let me know, Lisa

At 02:28 PM 3/11/03 -0800, you wrote:

Hi Lisa!

Crooked River Ranch Water Company sent a letter, last week, I think, requesting an extension to submit our permit extension. Will we receive a confirmation or notice of approval? The original extension was due March 18, which is next week. We just want to be sure that we are going to be ok. Thanks for your help!

Barb Oakley, CRRWC 541-548-2353

Lisa J. Juul Water Rights Specialist Water Rights & Adjudications Division Oregon Water Resources Department 158 - 12th Street NE Salem, Oregon 97301-4172

Phone # (503) 378-8455, extension 272 FAX # (503) 378-6203 Homepage/Website Address - http://www.wrd.state.or.us



Water Resources Department

Commerce Building 158 12th Street NE Salem, OR 97301-4172 (503) 378-3739 FAX (503) 378-8130 www.wrd.state.or.us

December 18, 2002

CROOKED RIVER RANCH WATER CO. PO BOX 1388 CROOKED RIVER RANCH OR 97760

REFERENCE: Permit #G11376 (Application File #G12579) and the Adoption of New Administrative Rules for Municipal and Quasi-Municipal Water Use Permit Extensions

Dear Municipal and/or Quasi-Municipal Water Use Permit Extension Applicant:

The Water Resources Commission has adopted new administrative rules that govern the processing of Municipal and Quasi-Municipal permit extension requests. The new rules are contained in Oregon Administrative Rules Chapter 690, Division 315 (OAR 690-315-0070 through 690-315-0100). If you wish to view a copy of the new Chapter 690, Division 315 Extension Rules, you may access the document from the Department's web page at:

http://www.wrd.state.or.us/cgi-bin/notices.pl?new_oars

The Department is preparing to implement the new Division 315 extension rules. As part of this process, we assessed pending permit extension applications and determined there is not sufficient information to meet the requirements of the new Division 315 standards. The Department, therefore, must receive the following:

 Please complete and return the enclosed new "Application for Extension of Time for Quasi-Municipal and Municipal Water Use Permits." Note that the Department has also enclosed a copy of your previously submitted Extension of Time application and related attachments for your use.

You may also access the "Application for Extension of Time for Quasi-Municipal and Municipal Water Use Permits" on the Department's website at:

http://www.wrd.state.or.us/publication/forms/index.shtml

Please submit this information by March 18, 2003.

December 18, 2002 Page two of two

If you have an urgent need for the Department to process your extension request, please describe in a cover letter the circumstances that necessitate prompt review.

You may contact me by telephone at 503-378-8455, extension 272 if you have any questions concerning the new rules or our request for additional information.

11.

Water Rights Specialist Water Rights Section

enclosures

cc: Application File #G12579 (Permit #G11376)

1,	CROOKED	RIVER	RANCH WATE	R COMPANY		
	NAME					
	РО ВОХ	1388	CROOKED	RIVER RANCH,	OR 97760	541-923-1041
	ADDRESS			CITY	STATE ZIP	PHONE

owner of record, or duly authorized agent, of Application No. G-12579, Permit No. G-11376, do hereby request that the time in which to:

Complete the construction of diversion/appropriation works and/or purchase and installation of the equipment necessary to the use of water, which time now expires on October 1, 1999, be extended to October 1, 2006

and/or the time in which to:

Accomplish beneficial use of water to the full extent under the terms of the permit, which time now expires on October 1, 1999, be extended to October 1, 2006.

NOTE: The extension of time requested should be long enough to finish the project. Should this request be approved, it will be the Department's expectation that you will complete your project within the new time period allowed. Future extensions may not be granted.

Attached is an instruction sheet to assist you in completing the information on the permit extensions application form. Oregon Water Law and Administrative Rules requires this information to be considered by the Water Resources Department when reviewing a permit extension. All items must be completed or the application will be returned. Please feel free to provide the Department with any additional information that would aid us in making our decision. Please use additional sheets of paper as needed to fully respond to the questions.

After reviewing the application form and the instruction sheet, if you have any questions, please contact the Department at 1-800-624-3199, or locally in the Salem vicinity at (503) 378-3739, and request assistance from the Water Rights Division, permit extensions personnel.

1-Did water system construction/well drilling begin within the time specified in the permit [yes/no]?

2-Has construction of diversion/appropriation works, distribution system, and use of water, if any, been accomplished consistent with the limitations and conditions of this permit [yes/no]? Yes

A) Please describe how you have complied with each applicable permit condition (NOTE: the instruction sheet for permit extension applications provides some direction as to what is an "applicable" condition at time of permit extension review). A Water Management and Conservation Plan is approximately half completed. A 20 Year Master Plan was completed in 1997.

the land of the

B) If you have not complied with all applicable conditions, please explain the reasons why and indicate a date certain, in the near future, by which time you will be in compliance with applicable conditions. Three managers in 18 months has disrupted the flow of information regarding projects that needed to be completed. Present management was not aware of this deadline until receipt of a letter from OWRD on 9/17/99. As plans are underway to expand the system, we are asking that this deadline be extended until 10/1/2006.

- 3-I have accomplished the following described works, purchases and installation of equipment necessary to the use of water under said permit:
- A) Within the past year or, if a prior extension was authorized, during the last permit extension period:

 The well #4 project was completed 12/95 at a cost of \$404,000. At that time, we had 1028 meter connections and that number has increased to 1237 meters. The 20 Year Plan was completed at a cost of \$25,500. An additional \$90,360 has been spent for repairs to well #2 and the cistern, the purchase of a chlorination system and an emergency use generator, and emergency repairs to well #4 when the shaft broke.
- B) Prior to the past year or, if a prior extension was authorized, prior to the last extension period:

 Added approximately 100 meters to existing line. Excavated and prepared site for third well (well #4). Had two working (on line) wells completed. Aggresively pursued 800 homesites available to be on (then) current line for hook up.

C) I have accomplished beneficial use of water under the permit to the extent of (amount of water used or acres irrigated): Total water usage from wells #2, #3 and #4:

or doros irribatoa)	Total water usage from wells #2, #3 and #4;
10/95 - 9/96	25,670,595 cubic feet
10/96 - 9/97	26,168,084 cubic feet
10/97 - 9/98	27,689,435 cubic feet
10/98 - 9/99	29,201,495 cubic feet

Total residential water use 62,874,429 cubic feet Total irrigation water use 45,855,180 cubic feet

4-Cost of project to date \$519,860. Estimated remaining cost to complete the project \$3,000,000
5-Please list the reasons why the project was not constructed, and/or water not beneficially used within permit time limits under the appropriate categories below. Please provide supporting information for each reason identified.
A) The project is of a size and scope that the original intent was to phase it in over a period longer than the timeframes allowed in the permit. Although well #4 was completed and went on line to provide adequate water to the existing 1600 lots in our service area, the growth of CRR prompted a plan to increase services to 1932 lots in 2003, and to include all 2630 lots in CRR by the year 2017 (see enclosed charts). In 1997 a high growth, high demand projection of 6% was actually a 6.3% increase in growth and demand. B) Financing and/or cash-flow needs to develop the project precluded completion of the project within authorized timeframes. Expansion of our service area will cost an estimated \$3 million, or approximately \$250,000 per year, except for one year when needed improvements will cost approximately \$525,000.
C) Good faith attempts to comply with permit conditions and/or to acquire permits from other agencies, or otherwise comply with government regulations, delayed completion of the project. N/A
D) Acts of God or other unforeseen events delayed full development of the water system and use of water. The unforeseen cost increases of repairs and equipment in the last few years was not adequately planned for by this company.
6-Please identify the economic market or markets to which beneficial use of water under the permit is responding. Active water meter connections have increased over 5% per year.

1079 meters to 1122 meters

10/95 - 9/96 1020 meters to 1071 meters

10/95 - 9/97

s hav
ion of will
ds?
ecent

8-Will the income or use from the water development project authorized by this permit provide reasonable returns against the investment in the project? Yes. The fees collected from the expansion of our service area will provide the necessary funds to bring our aging water system up to date. Once the expansion is complete, the additional revenue from water rates will maintain the system.

9-If the extension request is denied, is the current level of water use economically feasible?

We have 396 remaining water sites today. At the present rate of growth, these will be sold within the next 5 to 7 years. We can increase our service area by 272 meters when the first expansion phase is completed. If we are unable to expand, an annual revenue from connection fees of approximately \$84,000 to \$118,000 (at the present fee) will be ended.

I am the permittee, or have authorization from the permittee, to apply for an extension of time under this permit. I understand that false or misleading statements in this extension application are grounds for the Department to suspend processing of the request and/or reason to deny the extension.

Signature

10/12/99

Date

MAIL COMPLETED APPLICATION AND STATUTORY FEE OF \$ 100 TO:

WATER RIGHT PERMIT EXTENSIONS WATER RESOURCES 158 12TH ST NE SALEM, OREGON 97310

m:\exchange\leep\extfrm98 revised: June 21, 1999 Table 6-1
Crooked River Ranch Water Company
Capital Improvement Program (CIP)

			1				E	stimated	Ca	pital Cost	du	ring Year	of Constru	ction	1(3)	
CIP Proj ID #(II)	Project Title	Estimated Capital Cost in 1997 Dollars ⁽²⁾		1998		1999		2000		2001		2002	2003	20	004 to 2010 ⁽⁴⁾	2011 to 2014 ⁽⁵⁾
	Source	A Second														
SO-1	Convert Well #2 to Production Status	\$34,000	\$	36,040												
SO-2	New Well #5 (Scenario C2)	\$1,160,500												\$	2,078,279	
SO-3	Annual Source Renewal and Replacement	\$7,500	\$	7,950	\$	8,427	\$	8,933	\$	9,469	\$	10,037	\$10,639	\$	80,588	\$71,897
WQ-1	Continuous Disinfection Well #4	\$29,000		30,740											1000,000	
WQ-2	Continuous Disinfection Well #2	\$29,000	\$	30,740												
	Storage															
ST-1	Resurface Tower	\$187,000	\$	198,220												
ST-2	Tower Overflow Drainage Improvements	\$20,500	*	200,220		23,034										
ST-3	Tower Security Fencing	\$21,000				23,596										
ST-4	Cistern Repair	\$10,500		11,130	Ψ	20,000										
ST-5	New 1.8 MG Reservoir	\$1,350,000	4	11,150												
~	21011 210 2100 2100 2100	\$1,000,000												\$	2,417,644	
	Distribution					4										
DI-1	Annual Distribution Piping Extensions	\$180,000	4	190,800	\$	202,248		214,383	\$	227,246		040.001	*****			
DI-2	Annual Pipe Renewal and Replacement	\$15,000		15,900	\$	16,854	\$	17,865	\$	The Property of the Street	4	240,881	\$255,333		1,934,116	\$1,725,522
		410,000	*	10,500	4	10,004	φ	17,000	Ф	18,937	\$	20,073	\$21,278	\$	161,176	\$143,793
	Operation & Management														141	
OM-1	New Meter for Standpipe Customers	\$1,000	•	1,060												
OM-2	Annual Meter Renewal and Replacement	\$1,000			\$	1,124		1 101		1 000			45.00			
	The state of the s	\$1,000	4	1,000	4	1,124	Þ	1,191	4	1,262	2	1,338	\$1,419	\$	10,745	\$9,586
Notes:	TOTAL	3,046,000	\$	523,640	\$	275,282		\$242,372	- 9	\$256,914		\$272,329	\$288,669		\$6,682,548	\$1,950,798

Notes:

(2) ENR CCI for Seattle for May 1997 = 6,466.29

(3) Costs escalated at estimated

6 percent per year

(4) Costs estimated for 2007

(5) Costs estimated for 2012

⁽¹⁾ SO: Source, WQ: Water Quality, ST: Storage, DI: Distribution, OM: Operation and Management

Table 3-2 Water Demand Forecast


Water Demand			
Scenario	1997	2003	2017
High (610% Growthy High Demand)	建筑的地位的	是一种的一种。	然出现政权政权
Number of Connections [Meters]"	1,147	1,627	3.679(2)
Average Demand [gpd](3)	422,096	621,514	1,405,378
[gpm]	293	432	976
Peak Demand [gpd] (2)	970,362	1,428,353	3,229,819
[gpm]	674	992	2,243
Medium (48% Growth Avoical Demand)	Melecular		
Number of Connections [Meters]"	1,147	1,477	2,662
Average Demand [gpd] (3)	422,096	543,536	979,616
[gpm]	293	377	680
Peak Demand [gpd] (3)	970,362	1,249,542	2,252,052
[gpm]	674	868	1,564
Eow (20% Growth Low Demand)	地區的自然	温器和 如阿尔蒙特	《公司的 》
Number of Connections [Meters]"	1,147	1,292	1,704
Average Demand (gpd) (3)	422,096	231,268	305,016
[gpm]	293	161	212
Peak Demand [gpd] (2)	970,362	532,304	702,048
(gpm)	674	370	488
Total Number of Lots within Service Area	1,660	1,932	2,630

(1) The number of connections for 1997 was provided by CRRWC. Number of connections for 2003 and 2017 was calculated using the equation N = n(1+%) where N is the future number of connections, n is the current number of connections, percentage is the growth rate, and y is the number of years.

(2) The number of connections in 2017 exceeds the 2,630 total number of lots at the Ranch. This estimate includes the potential for re-zoning at the Ranch thereby creating more lots, or that at 6.0% growth rate the Ranch reaches the 2,630 buildout prior to 2017.

(3) Average demand and peak demand are calculated by multiplying the number of connections by Meter Demands. Meter demands are as follows:

Trend	Meter Demand (gpmd)
High Usage	点。 位于 位于 位于 位于 位于 位于 位于 位于 位于 位于
Average Day	382
Peak Day	878
Typical Usage of the	多語論語圖圖與新聞的
Average Day	368
Peak Day	846
Llow Usage History	计划的过程数据数据数据的的程序
Average Day	179
Peak Day	412








Exhibit 3-2 Growth Projections





APPLICATION FOR EXTENSION OF TIME TO THE WATER RESOURCES DIRECTOR OF OREGON

	CROOKED RIVER RA						
F	PO BOX 1388	CROOKED	RIVER	RANCH,	OR	97760	541-923-1041
AI	DDRESS		C	TY	ST	ATE ZIP	PHONE
	record, or duly author equest that the time in		Applicat	ion No. <u>G-</u>	-125	79, Permi	t No. <u>G-11376</u> , do
equipmen	ete the construction of nt necessary to the use er 1, 2006,	diversion/app of water, whi	ropriation ch time r	n works ar low expire	nd/or s on (purchase-a October 1,	nd installation of the 1999, be extended
and/or th	e time in which to:						
	plish beneficial use of on October 1, 1999						rmit, which time now
request		e the Departi	ment's ex	epectation	that	you will o	e project. Should this complete your project
	d is an instruction sho ns application form.				he in	formation	on the permit
	tion to be considered			ces			g a permit
	n. All items must be			ica	No		feel free to
	the Department with Please use additiona			nat nee	N	oner	king our uestions.
contact	viewing the application the Department at 1-assistance from the V	800-624-3199	, or loca	lly in the			estions, please at (503) 378-3739, and onnel.
1-Did wa	ater system construction	on/well drillin	g begin v	vithin the t	ime s	specified in	the permit [yes/no]?
	onstruction of diversion ished consistent with t						use of water, if any, been /no]? Yes

RECEIVED

OCT 1 8 1999

APPLICATION FOR EXTENSION OF TIME TO THE WATER RESOURCES DIRECTOR OF OREGON

	NAME						
	PO BOX 1388	CROOKED	RIVER	RANCH,	OR	97760	541-923-1041
	ADDRESS		С	ITY	ST	ATE ZIP	PHONE
	of record, or duly author request that the time in		Applicat	tion No. <u>G</u> -	-125	79, Permi	t No. <u>G-11376</u> , do
equip	mplete the construction of ment necessary to the use tober 1, 2006,	f diversion/app e of water, whi	ropriation ch time r	n works ar now expire	nd/or s on (purchase a	and installation of the 1999, be extended
and/or	the time in which to:						
	omplish beneficial use of es on October 1, 1999						ermit, which time now
NOT	F. The extension of tim						
reque	est be approved, it will be the new time period a	be the Departi	ment's ex	xpectation	that	you will	
reque within Attac exten inform	est be approved, it will in the new time period a hed is an instruction shall sions application form. mation to be considered	be the Departi illowed. Futur neet to assist y Oregon Wat I by the Water	ment's ex e extensi ou in cor er Law a r Resour	xpectation ions may i mpleting t and Admir ces Depar	that not be he in: nistra	you will of granted formation ative Rule of when re	complete your project on the permit s requires this eviewing a permit
Attac exten infor exten provi	est be approved, it will in the new time period a hed is an instruction sh sions application form.	be the Departi allowed. Futur neet to assist you Oregon Wat I by the Water completed or h any addition	ment's extension in cor er Law ar Resour the appl	xpectation ions may impleting to and Admir ces Departication with mation that	that not be the instra tmen Il be at wo	you will of granted formation ative Rule of when returned aid us	complete your project on the permit s requires this eviewing a permit Please feel free to s in making our
Attace exten informexten providecisi	est be approved, it will in the new time period a hed is an instruction shall sions application form. mation to be considered sion. All items must be de the Department with	be the Departiculowed. Future neet to assist your oregon Water of the Water completed or hany addition hal sheets of particular form and -800-624-3199	ment's extension in correr Law at Resour the application information apper as a the instruction, or local	mpleting to and Admin ces Depar lication wi mation that needed to	that not be he in nistra tmen ill be at wo fully eet, if Salen	you will of granted formation ative Rule of when returned, aid us respond to you have a vicinity	on the permit s requires this eviewing a permit Please feel free to in making our to the questions. any questions, please at (503) 378-3739, and
Attace exten information decision of the contact of	the new time period and the new time period and the new time period and the distance and instruction shadons application form. In the desired sion. All items must be detended the Department with items and the desired sion. Please use additional reviewing the application of the Department at 1 test assistance from the desired water system construction.	be the Departiculowed. Future delet to assist your oregon Water Support of the Water of the any addition and sheets of particular form and 1-800-624-3199 Water Rights	ment's extension in correct Law as Resour the application in formation in the instruction of local Division	mpleting to and Admin ces Depar lication wi mation that needed to ruction she lly in the S	that not be he ini nistra tmen Il be at wo fully eet, if Salen xtens	you will of granted formation attive Rule of the when returned aid us respond to you have a vicinity ions persons	on the permit s requires this eviewing a permit Please feel free to in making our to the questions. any questions, please at (503) 378-3739, and onnel.

RECEIVED

OCT 1 8 1999

 A) Please describe how you have complied with each instruction sheet for permit extension application. 	is provi	des some dire	ction	as t	o what	is an
"applicable" condition at time of permit extension						
Conservation Plan is approximately	half	completed	. A	20	Year	Master
Plan was completed in 1997.						

B) If you have not complied with all applicable conditions, please explain the reasons why and indicate a date certain, in the near future, by which time you will be in compliance with applicable conditions. Three managers in 18 months has disrupted the flow of information regarding projects that needed to be completed. Present management was not aware of this deadline until receipt of a letter from OWRD on 9/17/99. As plans are underway to expand the system, we are asking that this deadline be extended until 10/1/2006.

3-I have accomplished the following described works, purchases and installation of equipment necessary to the use of water under said permit:

A) Within the past year or, if a prior extension was authorized, during the last permit extension period:

The well #4 project was completed 12/95 at a cost of \$404,000. At that
time, we had 1028 meter connections and that number has increased to
1237 meters. The 20 Year Plan was completed at a cost of \$25,500. An
additional \$90,360 has been spent for repairs to well #2 and the cistern,
the purchase of a chlorination system and an emergency use generator,
and emergency repairs to well #4 when the shaft broke.

B) Prior to the past year or, if a prior extension was authorized, prior to the last extension period:

Added approximately 100 meters to existing line. Excavated and prepared site for third well (well #4). Had two working (on line) wells completed. Aggresively pursued 800 homesites available to be on (then) current line for hook up.

C) I have accomplished beneficial use of water under the permit to the extent of (amount of water used or acres irrigated): Total water usage from wells #2, #3 and #4:

	0 /	THE PERSON NAMED IN	The state of the s
10/95	- 9/96	25,670,595	cubic feet
10/96	- 9/97	26,168,084	cubic feet
10/97	- 9/98	27,689,435	cubic feet
10/98	- 9/99	29,201,495	cubic feet
Total	regidential	water use	62 874 429 cubic foot

Total irrigation water use 45,855,180 cubic feet

WATER 18 IL

4-Cost of project to date \$519,8	860. Estimated rem	aining cost	to complete the pro	oject\$3,000,000)
5-Please list the reasons why the permit time limits under the appreach reason identified.	project was not co opriate categories l	nstructed, ar pelow. Plea	nd/or water not ben se provide support	eficially used with ing information for	nin r
A) The project is of a size and so the timeframes allowed in the per to provide adequate wa the growth of CRR prom 2003, and to include a charts). In 1997 a hig actually a 6.3% increa	mit. Although ter to the ex pted a plan t 11 2630 lots h growth, hic	well #4 cisting co increa in CRR	was complete 1600 lots in ase services by the year 2 d projection	our service to 1932 lots 2017 (see enc	n line area, _in
B) Financing and/or cash-flow no authorized timeframes. Expans \$3 million, or approxi when needed improvemen	ion of our se mately \$250,0	orvice a	rea will cost year, except	an estimated	d
C) Good faith attempts to comply agencies, or otherwise comply winner.					
D) Acts of God or other unforese water. The unforeseen colast few years was not	st increases	of repa	irs and equip	ment in the	-
6-Please identify the economic m responding. <u>Active water</u> 10/95 - 9/96	arket or markets to meter connec 1020 meters	tions h	ave increased	under the permit i	s year.
10/95 - 9/97	1079 meters				
	Page	3 of 5		RECEIV	/ED

OCT 1 8 1999

A) Has there been any change in this market since the permit was issued? Added connections have increased water usage from 3% to 10.4% every year, for an average water usage increase of 5% per year. A high growth, high demand projection of 6% has been exceed, and may continue for several years. B) Have these changes, if any, affected the economic feasibility of your project? New connection fees have been used for capital improvements since the founding of the company, and when our service area is built out, these funds will no longer be available. To continue capital improvements without seeking alternative financing, our service area must be expanded. 7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.	10/97 - 9/98	1128 meters to 1164 meters 1165 meters to 1237 meters
increased water usage from 3% to 10.4% every year, for an average water usage increase of 5% per year. A high growth, high demand projection of 6% has been exceed, and may continue for several years. B) Have these changes, if any, affected the economic feasibility of your project? New connection fees have been used for capital improvements since the founding of the company, and when our service area is built out, these funds will no longer be available. To continue capital improvements without seeking alternative financing, our service area must be expanded. 7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.	10/98 - 9/99	1165 meters to 1257 meters
B) Have these changes, if any, affected the economic feasibility of your project? New connection fees have been used for capital improvements since the founding of the company, and when our service area is built out, these funds will no longer be available. To continue capital improvements without seeking alternative financing, our service area must be expanded. 7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.	increased water usage water usage increase of	from 3% to 10.4% every year, for an average f 5% per year. A high growth, high demand
fees have been used for capital improvements since the founding of the company, and when our service area is built out, these funds will no longer be available. To continue capital improvements without seeking alternative financing, our service area must be expanded. 7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.	projection of 6% has be	een exceed, and may continue for several years.
fees have been used for capital improvements since the founding of the company, and when our service area is built out, these funds will no longer be available. To continue capital improvements without seeking alternative financing, our service area must be expanded. 7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.		
the company, and when our service area is built out, these funds will no longer be available. To continue capital improvements without seeking alternative financing, our service area must be expanded. 7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.	B) Have these changes, if any, aff	fected the economic feasibility of your project? New connection
7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.	the company, and when	our service area is built out, these funds will
7-Are there other present competing demands for water in your community? Yes. There are approximately 300 private wells in areas outside our service area. A) Has there been any change in these demands for water since the permit was issued? As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.		
A) Has there been any change in these demands for water since the permit was issued? Yes. As growth increases at CRR outside of our service area, more private wells are drilled every year. B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.		
B) Are you aware of alternative sources of water that may be able to satisfy the competing demands? No.		
No.	growth increases at CR	R outside of our service area, more private
No.	D) Are you cure of alternative a	recurses of water that may be able to estiate the compating demands?
C) Are you aware of any adverse affects on your source of water that may have been caused by recent		
C) Are you aware of any adverse affects on your source of water that may have been caused by recent		
changes in use of water in your community? No.		e affects on your source of water that may have been caused by recent community?No.

8-Will the income or use from the water development project authorized by this permit provide reasonable returns against the investment in the project? Yes. The fees collected from the expansion of our service area will provide the necessary funds to bring our aging water system up to date. Once the expansion is complete, the additional revenue from water rates will maintain the system.

9-If the extension request is denied, is the current level of water use economically feasible?

We have 396 remaining water sites today. At the present rate of growth, these will be sold within the next 5 to 7 years. We can increase our service area by 272 meters when the first expansion phase is completed. If we are unable to expand, an annual revenue from connection fees of approximately \$84,000 to \$118,000 (at the present fee) will be ended.

I am the permittee, or have authorization from the permittee, to apply for an extension of time under this permit. I understand that false or misleading statements in this extension application are grounds for the Department to suspend processing of the request and/or reason to deny the extension.

Signature

10/12/99

Date

MAIL COMPLETED APPLICATION AND STATUTORY FEE OF \$ 100 TO:

WATER RIGHT PERMIT EXTENSIONS WATER RESOURCES 158 12TH ST NE SALEM, OREGON 97310

m:\exchange\leep\extfrm98 revised: June 21, 1999

RECEIVED

OCT 1 8 1999

Table 6-1
Crooked River Ranch Water Company
Capital Improvement Program (CIP)

							Es	timated (Cap	oital Cost	du	ring Year	of Construc	tion	7(3)	
CIP Proj ID #(1)	Project Title	Estimated Capital Cost in 1997 Dollars ⁽²⁾		1998		1999		2000		2001		2002	2003	20	04 to 2010 ⁽⁴⁾	2011 to 2014 ⁽⁵⁾
64	Source			-2000									-			
SO-1	Convert Well #2 to Production Status	\$34,000	\$	36,040											0.070.070	
SO-2	New Well #5 (Scenario C2)	\$1,160,500		2				0.000		0.400	4	10.000	410 000	4	2,078,279	671 007
SO-3	Annual Source Renewal and Replacement	\$7,500	196,00	7,950	\$	8,427	\$	8,933	2	9,469	\$	10,037	\$10,639	D.	80,588	\$71,897
WQ-1	Continuous Disinfection Well #4	\$29,000		30,740												
WQ-2	Continuous Disinfection Well #2	\$29,000	\$	30,740												
	Storage															
ST-1	Resurface Tower	\$187,000	\$	198,220												
ST-2	Tower Overflow Drainage Improvements	\$20,500			\$	23,034										
ST-3	Tower Security Fencing	\$21,000			\$	23,596										
ST-4	Cistern Repair	\$10,500	\$	11,130												
ST-5	New 1.8 MG Reservoir	\$1,350,000												\$	2,417,644	
	Distribution															
DI-1	Annual Distribution Piping Extensions	\$180,000	\$	190,800	\$	202,248	\$	214,383	\$	227,246	\$	240,881	\$255,333	\$	1,934,116	\$1,725,522
DI-2	Annual Pipe Renewal and Replacement	\$15,000	\$	15,900	\$	16,854	\$	17,865	\$	18,937	\$	20,073	\$21,278	\$	161,176	\$143,793
	Operation & Management															
OM-1	New Meter for Standpipe Customers	\$1,000	\$	1,060												
OM-2	Annual Meter Renewal and Replacement	\$1,000		1,060	\$	1,124	\$	1,191	\$	1,262	\$	1,338	\$1,419	\$	10,745	\$9,586
	TOTAL	3,046,000	\$	523,640	- 1	\$275,282	_	\$242,372		\$256,914		\$272,329	\$288,669	_	\$6,682,548	\$1,950,798

Notes:

- (1) SO: Source, WQ: Water Quality, ST: Storage, DI: Distribution, OM: Operation and Management
- (2) ENR CCI for Seattle for May 1997 = 6,466.29
- (3) Costs escalated at estimated

6 percent per year

- (4) Costs estimated for 2007
- (5) Costs estimated for 2012

RECEIVED

OCT 1 8 1999

WATER RESOURCES DEPT. SALEM, OREGON

1,704

305,016

212

702,048

488

2,630

Water Demand	Forecast		
Scenario	1997	2003	2017
High (6:0% Growth, High Demand)	建设设置	新工作的	対記る政化が対
Number of Connections [Meters] (1)	1,147	1,627	3.679(2)
Average Demand [gpd] (3)	422,096	621,514	1,405,378
[gpm]	293	432	976
Peak Demand [gpd] (3)	970,362	1,428,353	3,229,819
[gpm]	674	992	2,243
Medium (4:3% Growth, Typical Demand)	局部開源	THE PROPERTY OF	PREPARE TO SERVICE STATE OF THE PERSON OF TH
Number of Connections [Meters]	1,147	1,477	2,662
Average Demand [gpd] (3)	422,096	543,536	979,616
[gpm]	293	377	680
Peak Demand [gpd](3)	970,362	1,249,542	2,252,052
[gpm]	674	868	1.564

1,292

231,268

161

532,304

370

1,932

1,147

422,096

293

970,362

674

1,660

Table 3-2

(1) The number of connections for 1997 was provided by CRRWC. Number of connections for 2003 and 2017 was calculated using the equation N = n(1+%) where N is the future number of connections, n is the current number of connections, percentage is the growth rate, and y is the number of years.

[gpm]

(2) The number of connections in 2017 exceeds the 2,630 total number of lots at the Ranch. This estimate includes the potential for re-zoning at the Ranch thereby creating more lots, or that at 6.0% growth rate the Ranch reaches the 2,630 buildout prior to 2017.

(3) Average demand and peak demand are calculated by multiplying the number of connections by Meter Demands. Meter demands are as follows:

Trend	Meter Demand (gpmd)
High Usage	and the same of th
Average Day	382
Peak Day	878
Typical Usage	至語。時報語語語(1954年
Average Day	368
Peak Day	846
Low Usage	可持續的可能可能可能可能可能可能可能可能可能可能可能可能可能可能可能可能可能可能可能
Average Day	179
Peak Day	412

Low (2:0% Growth; Low Demand)

Total Number of Lots within Service Area

Number of Connections [Meters]"


Average Demand [gpd](3)

Peak Demand [gpd](3)

RECEIVED


OCT 1 8 1999

WATER RESOURCES DEPT. SALEM, OREGON





WATER RESOURCES DEPT. SALEM, OREGON







Exhibit 3-3 Water Demand Forecast (Peak Day)



High Growth Scenario -- Medium Growth Scenario -- Low Growth Scenario

Legend

Crooked River Ranch Water 13845 S.W. Commercial Loop P.O. Box 1388 Crooked River Ranch, OR 97760

> OREGON WATER RESOURCES DEPT. ATTN.: DALLAS MILLER 158 12TH STREET NE SALEM, OR 97310-0210



Water Resources Department

Commerce Building 158 12th Street NE Salem, OR 97310-0210 (503) 378-3739 FAX (503) 378-8130

October 19, 1999

CROOKED RIVER RANCH JAMES ROOKS PO BOX 1388 CROOKED RIVER RANCH, OR 97760

REFERENCE: File G 12579

Dear Applicant:

Regarding your request for an extension of time of permit G 11376. Before we can process the request for an extension of time it will be necessary for you to submit the required \$ 100 fee. The extension cannot be considered filed until we receive that fee.

If you have questions please contact me at the address below or phone (503)378-3739 ext. 272.

Sincerely,

Dallas Miller

Water Rights Specialist

allo mille

cc: Watermaster, District 11



Water Resources Department

Commerce Building 158 12th Street NE Salem, OR 97310-0210 (503) 378-3739 FAX (503) 378-8130

September 15, 1999

CROOKED RIVER RANCH WATER CO PO BOX 1388 CROOKED RIVER RANCH OR 97760

REFERENCE: File G-12579

This letter is in regard to your water use Permit G-11376. As we pointed out to you in our January 20, 1999 letter, your claim of beneficial use must be received in this office by October 1, 1999.

Oregon Administrative Rule 690-14-190 states: "The claim of beneficial use shall be submitted to the Department within one year after the use was reported..as being complete...Failure to comply with this section shall cause the Director to initiate permit cancellation proceedings as provided by ORS 537.260."

The "claim" consists of a site report and map of the developed use prepared by a Certified Water Rights Examiner, which accompany a request from the permittee for issuance of a certificate of water right.

You are hereby notified that unless your claim is received on or before October 1, 1999 your permit will be canceled without further notice.

If you have any questions, please contact the Water Rights Section.

Sincerely,

DALLAS MILLER Water Rights Specialist

DM:jh

cc:

Kyle Gorman, Watermaster

Bruce Estes, CWRE

CERTIFIED - RETURN RECEIPT REQUESTED



Water Resources Department

Commerce Building 158 12th Street NE Salem, OR 97310-0210 (503) 378-3739 FAX (503) 378-8130

January 20, 1999

CROOKED RIVER RANCH WATER CO PO BOX 1388 CROOKED RIVER RANCH OR 97760

REFERENCE: File G-12579

The date for the complete application of water to a beneficial use for your water use Permit G-11376 was October 1, 1998. To date we have not received notice that your project was completed.

If the project was completed, you should promptly submit the notice of complete application of water. If you were unable to complete the project within the time allowed, you may wish to request an extension of the time limits.

Water Right Certificate

In order to obtain a certificate of water right, you are required by law to hire a certified water right examiner to conduct the final proof survey of the completed use. This must be done within one year after the use is reported as being complete or within one year after the beneficial use date allowed in the permit, whichever occurs first. Accordingly, the map and claim of beneficial use must be received in this office on or before October 1, 1999. A list of certified water right examiners is enclosed for your information.

Upon receipt of the map and claim of beneficial use, the information will be reviewed and a brief field inspection may be conducted by a representative of this office. Following that, a proposed certificate of water right will be mailed to you for review.

Extension of Time
If you wish to apply for an extension of time, please fill out the enclosed form. Permit extension rules, adopted by the Water Resources Commission in October 1998, require that the Department consider this information when determining whether or not to approve an extension request. You should request to extend your permit for the amount of time necessary to fully complete your project and put the water to beneficial use. Should the permit extension be approved, it is the Department's expectation that it will be the last extension granted. Copies of the new extension rules will be furnished upon request.

If you are no longer interested in the project, please let us know. We will provide forms for you to authorize the cancellation of the permit.

If you have any questions, please contact me at extension 272, at 503-378-3739, or toll-free 1-800-624-3199.

Sincerely,

DALLAS S. MILLER Water Rights Specialist

DSM:jh

enclosure

cc:

Kyle Gorman, Watermaster Bruce Estes, CWRE

Oregon Water Resources Department



State of Oregon
Water Resources Department
158 12th Street NE, Salem, OR 97310
1(800)624-3199 • (\$03)378-8455
www.wrd.state.ocus

Fax Transmittal

TO:	TIM	ZIMA	1 ERMA	N		
FAX: 503	598 7	758	DATE: M	195-15-2	2400 PAGES: 14	
FROM:		RESE	ARCH	Div.	@ 201	
COMMENTS:			-0		ASPLIC	
-	K	G-12		2087	1701216	
				VR	RANCH.	
IMPOR	TANT M	ESSAGE				7
VED. 20	201 Date 5	-/O Time 10:	PM STICKER HERE	ces	Water Rights & Adjudications Water Rights Information	
1/09 <	2 IMMERI	Y	NOTES		Adjudications	
5031-68	34-4111	FAX MOBILE	PLEASE		Hydroelectric Certificates/Final Proofs	
REA CODE NUMBI	98 - 7	58 LL	RETURNED YOUR CALL		Hearings/Contested Cases	
WELL		ORTZAND	WILL CALL AGAIN	nt	N	
G11257	9 OWEZ	-	CAME TO SEE YOU		Northwest Region District 16 Watermaster	
	Col	7	WANTS TO SEE YOU	vices	Transfers	
1997	11 / / / / / .	0 //	LOOK FOR FAX	V.		

FAX: 503-378-2496

1essage _

Signed

FAX: 503-378-8130

FAX: 503-378-6203



5-120 M - File 6-11376

Water Resources Department

Commerce Building 158 12th Street NE Salem, OR 97310-0210 (503) 378-3739 FAX (503) 378-8130

June 3, 1998

Constance Albrecht, Manager Crooked River Ranch Water Company P.O. Box 1388 Crooked River Ranch, OR 97760

Subject: Water Right Permit #G-11376, Water Management and Conservation Plan

Dear Ms. Albrecht:

I received your request for an extension for submittal of Crooked River Ranch's Water Management and Conservation Plan. It sounds like your organization is going through many changes and has taken on some relevant projects to assess your water system, collect data and implement a new rate structure. Because of the work to date and the commitment you have made to completing the plan, we are extending your submittal date to <u>August 31, 1998.</u>

Enclosed are the conference materials that we spoke of. Included is a copy of Oregon Administrative Rule 690-86 which details the plan requirements. Also included is a water management plan outline which takes you step by step through the plan's requirements. Other information includes population projections, information on conservation water pricing and integrated resource planning, funding and technical resource, and other conservation information. Please note that I am available to provide assistance to you during plan preparation. Feel free to call me, I can be reached at (503)378-8455 ext. 241.

Sincerely,

Rebecca Geisen

Senior Water Resources Planner

Attachments

c: Bob Main/Kyle Gorman - Watermaster's Office

Water Rights File G-11376

MAY 1 8 1998

Request for Extension of the Due Date for Submitting Water Management and Conservation Plans

WATER RESOURCES DEPT. SALEM, OREGON

Name of Entity: Crooked River Ranch Water & Application No: Contact Person: Constance Albrecht manager Phone No: (541)923-1041
Address: P.O. Box 1388 City: Crooked River Ranch, Oregon Zip Code: 97760
Status of Water Management and Conservation Plan (Discuss what has been accomplished to date.)
(1) Company recently completed a 20-year Master Flan: the Board Ras met + prioritized projects.
users now pay the same per 100 cuft, not less than others (3) Discussion with largest user in dystem about
(Briefly discuss why the extension is being requested:) Los Osa Entension Certic
been hined and were in the middle of a
Construction project, Too.
Schedule for Plan Completion
(Prepare a timeline to complete your plan. After reviewing the elements contained in the "Plan Outline" form available from OWRD, discuss the availability of the information needed to
The Company has excellent data (all computer Led)
from lack of the nearly 1200 meters in system
and year engineering & demand dated to
populations projections from 20-year muster plan -
Requested New Due Date: 8 31 98
(Call our offices, if more than nine months from original due date is desired.)
By: Constant Other Date: 5/15/98
Signature of Authorized Representative, title
Printed Name, title

Return to: Water Resources Department, 158 12th Street NE, Salem, Oregon 97310

attr: Reberan Geiser

	Application	No. G. G12579	*	FEES PAID	
FILE#: G 12579		No. G G11376	Date (6/8/1/	Amount 8200.00	Re
CROOKED RIVER RANCH WATER CO.			9/20/91	# 300.00	7
PO BOX 879 1388 CROOKED RIVER RANCH, OR 97760	Certificate	No			
	Deach	ites V	***************************************		
	Stream In	dex, Page No.	***************************************		
		9.4		Cert. Fee EES REFUNDI	ED.
Date filed	12 Cro	e Ke d	Date	Amount	C
Priority					
Action suspended until C94	4		SIGNMENTS	1	- 1
Action suspended until	Date	To Whom	Address	Volum	le
Return to applicant			•		
Date of approval	***************************************			***************************************	
CONSTRUCTION Date for beginning NOV 1 8 1992	£ Sc. 1		REMARKS		
Date for completion OCT 1 1993 '98	B Sent +	o new add 10/2-1/9	-3		
Extended to					
Divinded to	***************************************				
Date for application of water 10CT 1 1994 '76	BC 10-	1-98		***************************************	
Extended to	***************************************				
	APP "	H			
PROGRESSIMION OF WORK		PGEMIT 6-11376 PG	CRINGS THE USE OF WA	TER	
PROSECUTION OF WORK	From WE	FULS Z \$ 3. IF ANOT	HTH WOUL IS DEVEL	DPGD,	
Form "A" filed started			water would be N		
Form "B" filed		•	•		
Form "C" filed					
FINAL PROOF					
Blank mailed	***************************************				
Proof received					
Date certificate issued					



February 17, 1994

W A T E R R E S O U R C E S D E P A R T M E N T

CROOKED RIVER RANCH WATER COMPANY PO BOX 1388 CROOKED RIVER RANCH OR 97760

REFERENCE: File G-12579

We have received your application for extension of the time limits to complete construction and make complete application of water under Permit G-11376. We also have your check in the amount of \$100.

The application indicates reasonable diligence toward completion of the proposed project. The time limits to complete construction and make complete application of water are extended to October 1, 1998. The order approving the extension was entered February 9, 1994.

Permit G-11376 describes the use of water from Wells 2 & 3. If another well is developed, a permit for the use of water would be needed.

If you have any questions, please contact the Water Rights Section at 378-3739.

TES: jh

enclosure



File No	G12579
rue No	

Application for Extension of Time

RECEIVED

TO THE WATER RESOURCES DIRECTOR OF OREGON

NOV - 3 1993

DEPT.

I, Crooked River Ranch Water Company SALEM, OREGON
P.O Box 1388
Mailing Address
Crooked River Ranch, Oregon 97760
record owner of water permit NoG11376, do hereby request that the time in which to:
Complete the construction of works and/or purchase and installation of the equipment necessary to
the use of water, which time now expires on October 1, 1993, be extended to October 1, 1998
and/or the time in which to
accomplish beneficial use of water to the full extent now intended under the terms of said permit, which time
now expires on October 1, 19_93 be extended to October 1, 1998.
I have accomplished the following described works and/or purchase and installation of equipment
necessary to the use of water under said permit:
(1) within the past year Have added approximately 100 meters to existing line.
Have excavated and prepared site for third well.
Have agressivly pursued 800 homesites available to be on current line for hookup.
(2) prior to this past year Added approximately 100 meters to existing line
Have 2 working (on line) wells completed.
(3) and have accomplished beneficial use of water to the extent of (IF FOR IRRIGATION, STATE HOW MANY
ACRES HAVE BEEN IRRIGATED) Have 2 wells completed and on line with 950 meters
AND I HOLL OF THE WALL OF THE WALL OF THE WALL OF THE CETS
now active.
(If additional space is required, attach separate sheet)
William D. Howarth President (If signing tot a corporation please Identify your title)
Dated 10-29-93
MAIL COMPLETED APPLICATION AND STATUTORY FEE

OF \$100.00 FOR EACH PERMIT TO:

Water Resources Department 3850 Portland Road N.E. Salem, Oregon 97310

1. ZWENS QUIL-MUNI SCES

(KERMUND)

2. Z WELLS ORILLED

PUMUS INSTALLED

850 USEKS

3. PLAN/TIMETABLE ?

4. NOT STATED, PROBABLY ICES

5. 20%

*

6. NOTHING GIVEN

7. No

8. NO

9. NO, STILL SELLING ADMESTITES

10. NO

11/12 NO INFO

NOTHING SINCE.

OK 6C-10-1-98

Amphi

STATE OF OREGON

RECEIPT # 106525 WATER RESOURCES DEPARTMENT 3850 PORTLAND ROAD NE

SALEM, OR 97310 378-8455/378-8130 (FAX)

ECEIVED FRO	M: LICEKED KIL	EF	APPLICATION	2115
Y: /	Valle Water 1	011 9011	PERMIT	
			TRANSFER	
ASH: C	HECK: # OTHER: (IDENTIFY)			
	× 34 15		TOTAL REC'D	Is ///
01-00-0	WRD MISC CASH ACCT			_
842.010	ADJUDICATIONS			S
831.087	PUBLICATIONS/MAPS			S
	PARKING FEES Name/month			S
	OTHER: (IDENTIFY)			S
DEDUC	TION OF EXPENSE			
NEDUC	TION OF EXPENSE	CASH AC	CT.	s
CC	OST CENTER AND OBJECT CLASS	VOUCHE	R#	3
03-00-0	WRD OPERATING ACCT			
	MISCELLANEOUS:			
840.001	COPY FEES			S
850.200	RESEARCH FEES		F	S
880.109	MISC REVENUE: (IDENTIFY)	LXIIIS	1 H	s / (t - c
520,000	OTHER (P-6) (IDENTIFY)			S
	WATER RIGHTS:	EXAM FEE		RECORD FEE
842.001	SURFACE WATER	s	842.002	s
842.003	GROUND WATER	S	842.004	s
842.005	TRANSFER	S	842.006	s
	WELL CONSTRUCTION	EXAM FEE		LICENSE FEE
842.022	WELL DRILL CONSTRUCTOR	S	842.023	S
	LANDOWNER'S PERMIT		842.024	S
	OTHER (IDENTIFY)			
	WELL CONST START FE		Towns and	
842.013	WELL CONST START FEE	S	CARD #	
45 00 0	MONITORING WELLS	S	CARD #	
	LOTTERY PROCEEDS			F-
864.000	LOTTERY PROCEEDS			S
07-00-0	HYDRO ACTIVITY	LIC NUMBER		-
842.011	POWER LICENSE FEE(FW/WRD)			S
842.115	HYDRO LICENSE FEE(FW/WRD)			s
042,113	THE EIGENSE PEE(PW/WHD)			-
	HYDRO APPLICATION			s
	THE REPORTED AT LOCATION			



August 13, 1991

Mike Mattick Applications & Permits Section Water Resources Department 3850 Portland Road N.E. Salem, Oregon 97310

Re: Ground Water Application #G 12579, Crooked River Ranch Water Co., 5 cfs, Quasi-municipal, Crooked River Basin, Jefferson County.

Dear Mr. Mattick:

We are concerned about the possible adverse effects of this proposed withdrawal of ground water on the Crooked River. Where within the basin is this proposed withdrawal located? Is the ground water source hydrologically connected to flows in the Crooked River or any of its tributaries?

The Crooked River has moderate to severe withdrawal problems which are causing stream quality problems. Segments of the Crooked River are Water Quality Limited for bacteria, solids and nutrients. The river is so polluted it is currently unable to support designated beneficial uses. If the proposed use of ground water further depletes the Crooked River's flows, it will also exacerbate water quality problems in the River. If this is the case, this application will probably not be in the public interest.

In addition, the Crooked River is a tributary of the Deschutes scenic waterway. If the proposed source of ground water effects Crooked River flows it will also effect Deschutes River flows. If so, a permit can be issued only if the Department determines that there is water available for this use without adversely affecting the recreational flows for the Deschutes scenic waterway.

Finally, the Department's water availability analysis finds that generally there is no water available for surface water withdrawals between June and October. If this proposed use effects surface water flows, any permit issued must be conditioned upon surface water availability.

Thank you. Call if you have any questions.

Sincerely, Russell

Karen Russell

Legal Affairs Coordinator

c. Jim Myron



WATER
RESOURCES
DEPARTMENT

October 11, 1991

Crooked River Ranch Water Company P.O. Box 879 Crooked River Ranch, Oregon 97760

REFERENCE: File G-12579

Your application for a permit to use the public waters has been reviewed.

A "draft" permit is enclosed for your consideration. In the preparation of this draft permit, our staff has considered any public or agency comments received, as well as all pertinent Oregon laws, administrative rules and Commission policies.

We are now ready to recommend the issuance of a permit approving your request to use water. The draft permit enclosed contains all of the conditions and limitations that would appear on your permit, if issued.

Please review the draft permit <u>carefully</u>. If you are satisfied that the draft adequately describes your proposed use of water, and the terms are acceptable to you, please sign the draft copy in the spaces(s) provided and return it to us within 30 days. When we receive your signed draft, we will issue your permit as quickly as possible.

If you do not agree with, or cannot accept one or more of the terms or conditions as stated in the enclosed draft, you should advise us immediately. In this event, we will then advise you of any options which may be available to you.

If you have any questions, please contact the Water Rights Section at 378-3066.

enclosure

311



COUNTY OF JEFFERSON AND DESCHUTES

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

CROOKED RIVER RANCH WATER COMPANY P.O. BOX 879 CROOKED RIVER RANCH, OREGON 97760

503-548-8939

to use the waters of WELLS 2 & 3 in the CROOKED RIVER BASIN for QUASI-MUNICIPAL USE.

This permit is issued approving Application G-12579. The date of priority is JUNE 18, 1991. The use is limited to not more than 5.0 CUBIC FEET PER SECOND (CFS), BEING 2.5 CFS FROM EACH WELL, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

NW 1/4 NW 1/4, SW 1/4 SE 1/4, SECTION 24, T 13 S, R 12 E, W.M.; WELL 2 - 680 FEET SOUTH AND 780 FEET EAST FROM NW CORNER, SECTION 24, WELL 3 - 80 FEET NORTH AND 480 FEET EAST FROM S 1/4 CORNER, SECTION 24.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

NW 1/4 NW 1/4 S 1/2 SW 1/4 SECTION 4 E 1/2 NE 1/4 SE 1/4 SW 1/4 SE 1/4 SECTION 5 NE 1/4 NE 1/4 NW 1/4 SECTION 8 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 9 S 1/2 NW 1/4 SW 1/4 S 1/2 SE 1/4 SECTION 10 SW 1/4 SW 1/4 SECTION 13 SW 1/4 NE 1/4 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 14 ALL SECTION 15 ALL SECTION 16 E 1/2 NE 1/4 E 1/2 SE 1/4 SECTION 17 N 1/2 SECTION 21

PAGE TWO

```
N 1/2
             NW 1/4 SW 1/4
             N 1/2 SE 1/4
             SE 1/4 SE 1/4
               SECTION 22
                NE 1/4
             E 1/2 NW 1/4
              E 1/2 SW 1/4
                 SE 1/4
               SECTION 23
                 NW 1/4
                 S 1/2
               SECTION 24
                  ALL
               SECTION 25
                  ALL
               SECTION 26
                 E 1/2
             N 1/2 NW 1/4
             SE 1/4 NW 1/4
             NE 1/4 SW 1/4
              S 1/2 SW 1/4
              SECTION 27
             N 1/2 NE 1/4
             SW 1/4 NE 1/4
                NW 1/4
              E 1/2 SW 1/4
                 SE 1/4
               SECTION 34
                  ALL
               SECTION 35
             N 1/2 NE 1/4
             SW 1/4 NE 1/4
                 W 1/2
                 SE 1/4
               SECTION 36
TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.
              S 1/2 SW 1/4
             SW 1/4 SE 1/4
               SECTION 31
TOWNSHIP 13 SOUTH, RANGE 13 EAST, W.M.
             N 1/2 NE 1/4
             N 1/2 NW 1/4
SW 1/4 NW 1/4
               SECTION 1
             N 1/2 NE 1/4
             SE 1/4 NE 1/4
             W 1/2 SW 1/4
             SE 1/4 SW 1/4
               SECTION 2
                  ALL
               SECTION 3
             NW 1/4 NW 1/4
              SECTION 11
TOWNSHIP 14 SOUTH, RANGE 12 EAST, W.M.
             NW 1/4 NE 1/4
             N 1/2 NW 1/4
               SECTION 6
TOWNSHIP 14 SOUTH, RANGE 13 EAST, W.M.
```

Within one year from the date the Water Resources Commission adopts rules describing the schedules, standards and procedures for water conservation management plans by water suppliers, Crooked River Ranch Water Company shall submit a plan which is consistent with said rules.

山南台山

PAGE THREE

Within one year of permit issuance, Crooke River Ranch Water Company shall prepare a plan/timetable for the Water Resources Commission which shall indicate the steps which the Water Company intends to pursue to obtain a long-term water supply.

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the wells at all times. When required by the department, the permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before , and shall be completed on or before October 1, 1993. Complete application of the and shall be water shall be made on or before October 1, 1994.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

Issued this date,.

Water Resources Department William H. Young Director

I\We,	2579. By signature below, I\We
Signature\Title	Date
Signature\Title	Date



Application No. 6.12579

Permit No. G11376

Department of Human Resources WATER RESOURCES DEPT.

HEALTH DIVISION

SALEM, OREGON

1400 SW 5th AVENUE, PORTLAND, OREGON 97201

(503) 229-6307

TDD-NONVOICE: (503) 229-5497

February 19, 1991

Ken Wolf Crooked River Ranch P.O. Box 1388 Crooked River Ranch, OR 97760

Dear Mr. Wolf:

RE: Water Sanitary Survey Jefferson County

On January 24, 1991 a field visit was conducted for the enclosed sanitary survey. Please review the survey and inform me if there are any corrections needed.

The overall system appears to be in good repair and operated very well.

The following requirements and recommendations are based on the field inspection and a review of the records.

- 1. According to the new Total Coliform Rule, you are required to identify your routine and repeat sampling location in a sampling plan. The plan will be reviewed on a future visit.
- 2. Monitoring for radiological contaminants shall be completed for well #3.
- Monitoring shall be conducted for sodium and corrosivity for 3. both sources.
- Because of population change, bacteria sampling is increased 4. to 2 per month.
- 5. It is recommended that you seal the holes in the pump bases.
- 6. It is recommended that you contact a professional engineer to revise the master plan for your system.

AN EQUAL OPPORTUNITY EMPLOYER

Ken Wolf February 19, 1991 Page 2

Thank you for your assistance in preparing this report. If you have any questions call.

Sincerely,

John R. Straughan, P.E. Regional Manager Drinking Water Section

John RSt aug le

JRS:jc

cc: Jefferson County Health Department



Application No. 6-12579 RECEIVED Permit No.

Department of Human Resources

JUN 1 8 1991

WATER RESOURCES DEPT. SALEM OREGON

HEALTH DIVISION

1400 SW 5th AVENUE, PORTLAND, OREGON 97201

(503) 229-6310

TDD-NONVOICE: (503) 229-5497

COMPLIANCE STATUS REPORT

To: U.S. BANCORP MORTGAGE ATTN: TERESA 103 N.W. OREGON AVENUE BEND, OR 97701 A review of our records at your requestions of the compliance of the compli	System ID #: 4100 County: JEFF	rater system is [4] in	n f the
Compliance, [] not in compliance with Oregon State Health Division. 1. Water Quality Compliance: Contaminant Type 1. Microbiological 2. Inorganic Chemicals 3. Organic Chemicals 4. Turbidity 5. Radiological 6. VOC's (Volatile Organic Chemicals) II. Plan Review 1. [12 Existing water system constructed Not Applicable.	A.Monitoring Current Yes No	B. Complied with MCL Yes No	· ·
2. [] New water system constructed after [] Plans Received Date: [] Plans Not Approved Date:	er August 21, 1981: [] Plans Ap [] Certific	oproved Date: sation Received Date:	
PREPARED BY: PREPARED BY: Drinking Water Section	Date: _	3/4/5/	
cc: Water System County Health Dept.	Water System Fil Reading File	е	*

AN EQUAL OPPORTUNITY EMPLOYER

Application No. 6-12579

SANITARY SURVEY REPORT OREGON HEALTH DIVISION DRINKING WATER PROGRAM COMMUNITY WATER SYSTEMS SUPPLY NAME: CROOKED RIVER RANCH

ID NUMBER : 4100862 COUNTY : JEFFERSON

SURVEYED BY: JOHN STRAUGHAN

DATE : 1/24/90

Sheets Attached:

П

Narrative Summary/Recommendations

Inventory Master Data

Water System Schematic

Location Map(s)

□ Storage/Distribution

Booster Pumps/Production Data

n Certification

Monitoring/Water Quality

Additional Attachments:

WELL LOGS, CODE SHEETS

Narrative Summary:

Jefferson county bounded by the Deschutes River, the Crooked River and Deschutes county. The water system relies on an 800 gpm well for their source and the golf course well as an emergency source. There are two reservoirs which have a combined volume of 800,000 gallons. The water system was started as a development about 1973, Therefore system is relatively new and in good repair.

Requirements/Recommendations:

REQUIREMENTS:

1. Prepare a sampling plan for the water system.

 Complete monitoring for radiological contaminates, sodium and corrosivity as per monitoring section.

RECOMMENDATIONS:

1. Seal holes in well pump bases.


 Contact a professional engineer to prepare a master plan for the water system.

Rev. 08/89

Page 1 of 11

	ID NUMBER	: 410086	2	_		_
Date of Last Survey:	*	(MM/	DD/YY)	7/3	30/86	5
System Type:					C	
Ownership of System:	3,4,5)		2			
Population Served:	umber)	1	200			
Number of Connections:		(Total N		(500	
Twelve-Month Period:		(10001	,		T	
Year-Round Residents					Y	
	istia	(P.	T,S,0)		R	
Primary Service Character	istic:				4	
Secondary Service Charact Number of Sources:	eristic.	(Total N	umber		2	
Counties Served (Refer to	Codes):		/)		16	
Emergency Systems Availab	lo (Namo & TD Num					
PWS	Te (Name & ID Nam	(41	1		_	
PWS	-	(41			_	
PWS		(41			_	
Percent Ground:		(47	(8)	1	.00	
			(%)	1	_	
Percent Surface:						
Percent Purchased Ground			(%)		-	
Percent Purchased Surface			(%)		- v	
Active:			(Y/N)		Y	
Activate Date			DD/YY)		-	
Deactivate Date	5-2-1		DD/YY)		-	
Deactivate Reason:		,N,O,P,R,			_	
Number of Tanks in Supply		(Total N			2	
Number of Gallons in Stor	age:	(Total N	umber)	800	,000	'
City/State/Zip Contact Name/Phone Comments Legal (Owner) Address City/State/Zip Contact Name/Phone	CROOKED RIVER KEN WOLF 9 OPERATOR PO BOX 1388 CROOKED RIVER DICK BROWNLEY	23 1041 RANCH, O			-	
Comments		TER ASSOC	IATION			
Supply Address City/State/Zip Contact Name/Phone Comments	SAME	i.				
OURCE DATA (Sources for Source ID - Source Name	Individual Compl * Type		**	voc	*** SOC	SW
A WELL #2	G	41	P	Y	- ,	N
B WELL #3	G	41	E	Y	-	N
С		41				
D		41				
* (S)urface/(G)round/(I ** (P)ermanent/(S)eason	1/(E) mergency/(O)	ther/(I)n		ound		
	amination - (Y)es	1 / 1 7 7 1				-

. .



SUPPLY NAME: CROOKED RIVER RANCH ·LOCATION MAP (USGS QUAD SHEET) ID NUMBER : 4100862 Quadrangle Map USGS Map Name - OPAL CITY, OREG USGS Map Number - 44121-D2-TF-024 STEELHEAD FALLS, OREG 44121-D3-TF-024 Page 4 of 11 ID NUMBER : 4100862

Source ID/Detail ID - Well Detail Name

A	A	WELL #2	
В	A	WELL #3	

Well Data:

Detail ID Letter: Well/Spring/Stream: W W	
Source/Detail Status: (P/S/E/O/I) P E	
Treatment Objective/Process: () A A	
Treatment Objective/Process: ()	
Treatment Objective/Process: ()	
Treatment Objective/Process: ()	
Capacity: (GPM) 3000 2500	
Latitude: Degrees () 44 44	
Minutes () 26 25	
Seconds () 05 20	
Longitude: Degrees () 123 123	
Minutes () 14 14	
Seconds () 48 10	
Location Map Included (USGS): (Y/N) Y Y	
Well Log Attached: (Y/N) Y N	
Depth of Well: (FT.) 429 494	
Year of Installation: (19) - 49	
Casing Diameter: (IN.) 16 16	
Grout Seal: (Y/N) Y Y	
Gravel Pack: (Y/N) N N	
Openings - Screens/Slots/Torch: (S/L/T)	
Length of Open Interval: (FT.) 28 35	
Depth to Top of Intake: (FT.) 353 307	
Water Level Device: (Y/N) Y Y	
Static Water Level: (FT.) 280 286	
Pumping Water Level: (FT.) 282 288	

Pump Data:

Pump Type:	(VT,SU,CE,SJ,DJ,OT)	VT	VT	
Pump Setting:	(FT.)	319	380	
Capacity:	(GPM)	800	475	
At TDH:	(FT.)	580	570	
Discharge Pressure:	(PSI)	105	80	
Horsepower:	(HP)	150	100	
Date Pump Pulled:	(19)	-	-	
Bearing Lubrication - (Oil/Water): (O/W)	W	W .	
Pump Base Sealed:	(Y/N)	Y	Y	
Comments:				

A restroom is located 50 feet from well #3. Well #3 is located at the golf course.

В

В

Comments: Vunerability is bases on the minimum well seals (20 feet), presumed continuity of the permeable zones in the basalts, and the high pumping rates which may capture contaminates from up gradient.

Org/Inorg/Micro/Pesti/Turbi

Comments:

Page 6 of 11

ORAGE/DISTRIBUTION	17 No. of State (40)	SUPPLY NAME: CROOKED RIVER RANCH ID NUMBER : 4100862						
Storage ID No. Name		Materi (C/S/W		Con. Date (YEAR)	Volume (GAL)			
1 CLUB HOUSE ROAD 2 HIGH CONE DR 3 4 5 6		C S		74 77	100,000			
Total Volume of Storage:	,				800,000			
Storage Details:	-			_				
Storage ID Number:	*	1	2					
Type: Ground Level Tank	/17 /111	17	w					
Elevated Tank	(Y/N) (Y/N)	N	Y					
Pressure Tank	(Y/N)	N	N					
Hatch:	+-//		-	4				
Locked	(Y/N)	Y	Y					
Watertight	(Y/N)	Y.	Y					
Curbing Features:	(Y/N)	Y	Y					
Used for Contact Time	(Y/N)	N	N					
Separate Inlet/Outlet	(Y/N)	Y	N					
Drain to Daylight	(Y/N)	Y	Y					
Flap Valve	(Y/N)	Y	Y					
Overflow	(Y/N)	Y	Y					
Screened Vent	(Y/N)	Y	Y					
Fence/Gate	(Y/N)	Y	N					
Water Level Gage Bypass Piping	(Y/N) (Y/N)	N	Y					
Cathodic Protection	(Y/N)	N	N					
Maintenance:	1 -//	.,						
Painting	(Y/N)	N	Y					
Approved Coating	(Y/N)	Y	Y					
Routine Cleaning	(Y/N)	Y Y	Y					
Routine Inspection Comments: Reservoir #2 is schedule spring.	(Y/N) ed to be] inspected	this			
Distribution: Adequate Pressure (20 psi)					(Y/N) N			
Depth of Cover Adequate:					(Y/N) Y			
Blow Offs or Hydrants:					(Y/N) Y			
Flushing and Inspection:					(Y/N) Y			
Piping Looped:					(Y/N) Y (Y/N) Y			
Adequate Valving: Valve Location and Turning	1.				(Y/N) Y (Y/N) Y			
Individual Booster Pumps:	, •				(Y/N) N			
Master Plan on File:					(Y/N) N			
Plan Review Waiver:					(Y/N) N			
Comments:					, , ,			

BOOSTER PUMPS/PRODUCTION DATA

SUPPLY NAME: CROOKED RIVER RANCH

ID NUMBER : 4100862

ster I	Cump ID Location	in	System	HP	GPM	Suc/Dis PSI	Aux Powe (Y/N
		_		1			1
1	CLUB HOUSE			15	125	96	N N
2	CLUB HOUSE			25	250 250	96 96	N
3.	CLUB HOUSE			25	75	96	Y
4	CLUB HOUSE	RD	RESERVOIR		/3	30	-
5							
7							
8							
9							
10							
11			*				
12							
13							
14							
15							
16							
17							
18 19							
20							
21							
22							
23							
24							
25							
26							
27	-						
28							
29 30							

Comments:

-	- 44				-		
PT	O	ดบ	_ 1	on	Da	La	=

0	Year	Maximum Day (GPD)	Average Day (GPD)
	90	530,900	262,900
1	86	496,400	193,000
	83	463,750	202,000
1	82	30000000	172,000

Capacity	Neede	ed:				
Capacity	Avail	lable:				
Capacity	With	Largest	Unit	Out	of	Service:
Capacity	Under	Standby	Powe	er:		
Comments:						

(GPM)	370
(GPM)	1270
(GPM)	470
(GPM)	-

TIFICATION	SUPPLY NAME: ID NUMBER :	4100862	RIVER RANCH	
ross Connection Control Progra Responsible Person/Department Name		Departmen	nt ·	
KEN WOLF		WATER	2	
Name of Certified Inspector(s):			
KEN WOLF INSPECTOR	R			
Program Information: Inspections/Reinspections Annual Device Testing - (Conference Record Keeping Comments:	ertified Teste	r)	(Y/N) (Y/N) (Y/N)	
Operator Certification: Classification Needed for Sy Water Treatment - (WT 1-4) Water Distribution - (WD 1		(Level)		
Classification Needed for Sy Water Treatment - (WT 1-4)		(Level)	- WD-1 WT#) (WD#)	
Classification Needed for Sy Water Treatment - (WT 1-4) Water Distribution - (WD 1 Name/Certification:		(Level)		
Classification Needed for Sy Water Treatment - (WT 1-4) Water Distribution - (WD 1 Name/Certification: Name		(Level)	WT#) (WD#)	

MONITORING/WATER QUALITY

SUPPLY NAME: CROOKED RIVER RANCH

ID NUMBER : 4100862 A

Monitoring and Water Quality:

Parameter	Required Frequency	Current (Y/N)	Met MCLs (Y/N)	
Coliform Bacteria Turbidity	2/MONTH	<u>Y</u>	<u>Y</u>	Date of
Secondary Corrosivity	NONE ONCE			Next Test (_NOW_)
Inorganics	3 YEARS	Y	Y	9/2/92
Organics			-	-
Radionuclides	4 YEARS	Y	Y	10/5/91
VOC - Regulated	3 YEARS	Y	Y	BY 4/93
VOC - Unregulated	3 YEARS	Y	Y	BY 4/93
SOC - Regulated	-	-	-	-
SOC - Unregulated	-	-	-	-
THMs	-	-	-	-
Sodium	3 YEARS	=	-	NOW

Laboratories Used:

Name Lab Number

CENTURY TESTING LAB

Comments:

- With population change bacteria sampling is increased to 2 samples per month.
- 2. Sampling for sodium and corrosivity should be completed during your next scheduled inorganic chemical analysis.

MONITORING	/WATED	OHALTTV
TIONTION	HATER	OOMPITI

SUPPLY NAME: CROOKED RIVER RANCH

ID NUMBER : 4100862 B

Monitoring and Water Quality:

Parameter	Required Frequency	Current (Y/N)	Met MCLs (Y/N)	
Coliform Bacteria Turbidity	2/MONTH	Y -	Y _	Data as
Secondary Corrosivity	NONE ONCE			Date of Next Test (_NOW_)
Inorganics	3 YEARS	Y	Y	9/7/91
Organics Radionuclides	- VENDO	-	- N	NOM -
VOC - Regulated	4 YEARS 3 YEARS	N	N Y	BY 4/93
VOC - Unregulated	3 YEARS	Y	Y	BY 4/93
SOC - Regulated	-	Ē	2	
SOC - Unregulated	-	-	-	_
THMs	- 1	-	-	-
Sodium	3 YEARS	-	-	NOW

Laboratories Used:

Name

Lab Number

CENTURY TESTING LAB

Comments:

Sampling shall be completed for radiological contaminates. Sampling for sodium and corrosivity should be completed during your next scheduled inorganic chemical analysis.

GRREWELL LCG

WELL NO. 2 NOT: TO SCALE

AUTO TRANSPORM START

1'-2' TOPSOIL 2'-4' GREY LIMESTONE . 4'-28' MEDIUM HARD BLACK ROCK -28-33' RAVELING RED ROCK 33'-39' SOFT BLACK ROCK -39' - 48' HARDER BLACK ROCK 48'-56' SOFT RED ROCK 56'- 61' HARDER BLACK ROCK -61'- 69' BLACK ROCK, CREVICES 69'- 78' HARDER BLACK ROCK -78'- 83' HARD GREY ROCK 83'- 119' MEDIUM HARD BLACK ROCK 119'-187' GREY SANDSTONE WITH BOULDERS 187'- 193' SOFT YELLOW ROCK-193'- 206' SORT POROUS BLACK ROCK -206'- 224' CEMENTED GRAVEL ---224' -229' YELLOW SAND, CLAY & GRAVEL-229' - 242' MEDIUM HARD BROWN ROCK -242' - 244' SOFT RED ROCK -244'-262 MEDIUM HARD BROWN ROCK -262-265' SOFT YELLOW ROCK ---265'- 276' FAIRLY SOFT GREY ROCK-276- 308' HARD GREY ROCK -308'- 312' SOFT GREY ROCK -3/6'- 323' SOFTER GREY ROCK -323' - 326' SOFT POROUS BLACK ROCK 326'-338" MEDIUM HARD GREY ROCK 353'- 357' SOFT POROJS BLACK FOCK- WATER CAFT SPE. BOOK - DELICES !!

5 NO7 119'-187' GREY SANDSTONE WITH BOULDERS >

187'-193' SOFT YELLOW ROCK-193'- 206' SOFT POROUS BLACK ROCK -206'- 224' CEMENTED GRAVEL ---

224' -229' YELLOW SAND, CLAY & GRAVEL-229' - 242' MEDIUM HARD BROWN ROCK -

242'- 244' SOFT RED ROCK ----244'-262' MEDIUM HARD BROWN FOUN' -

262-265' SOFT YELLOW ROCK ----

265'- 276' FAIRLY SOFT GREY ROCK-

276-. 308' HARD GREY ROCK -

308'- 312' SOFT GREY ROCK -

3/6'- 323' SOFTER GREY ROCK --

323' - 326' SOFT POROUS BLACK ROCK 326'-338" MEDIUM HARD GREY ROCK .-

353'- 357' SOFT POROUS BLACK ROCK- WATER

357'- 381' SOFT GREY ROCK, CREVICES -1

381' - 406' SOFT BROWN POROUS ROCK. CARRYING WATER.

406' - 412' MEDIUM HARD GREY ROCK-

412' - 413' VERY HARD GREY ROCK -

- 1. REMOVE EXISTING 2" CONCRETE SLAB. INSTALL " CONCRETE SLAB WIT WIRE MESH REINFORCING.
- 2. EXTEND 16" & CASING 18" TO 21" TO PROVIDE 24" FROM TOP OF CASING FINISHED FLOOR SLAB, FULL DEPTH WELD.
- 3. INSTALL 2" & WELL VENT WITH SCREENED RETURN BEND. WELD 2" & PIPE TO FLACEMENT OF NEW CONCRETE SUPPORT: (22)
- 4. INSTALL NIR LINE TO GROFT LEVEL . HOUNT DEPTH GAGE (READING IN FT. CF.
- 5. DRILL EXISTING CONS. SUPPORT & SET 8- 34" x 12" STL. DOWELS WITH EADY.
- 6 INSTALL S" STL. RETURN LINE FROM PRESSURE RELIEF WALLS TO

Log of well #3 drilled for A. Wardman, at Crooked Myor Ranch, by R. J. Strauner Drilling Co., completed June 4, 1949.

0---lft., Top Soil. 13/17/2506 1 .---]] ft., Porous black rock. 11--18 ft., Hard gray rock. 18--32 ft., Soft yollow rock. .32--44 ft., Hard groy rock. 44--51 ft., Soft red rock. . 51--57 ft., Hard Brey rock. 57--62 ft., Soft rod rock. 62--71 ft., Vory hard groy rock. Soft porous black rock. 71--80 ft., 80--122 ft., Hard grey rock. 122-126 ft., Soft gray rock. 126-133 ft., Porous black rook. 133-140 ft., Hard groy rock. Soft yollew clay. 140-142 ft., Poronte black rock. 142-153 ft., 153-157 ft., Hard grey rock. 157-159 ft., Soft yallow rock. Cemented gravel, yellow binder. 159-169 ft., 169-173 ft., Large boulders. 173-183 ft., Hard groy rock. 183-188 ft., Comented gravel, grey binder. 188-201 ft., Hard groy rock. 201-205 ft., Soft brown rock. 205-214 ft., Hard grey rock. 214-232 ft., Softer grey rock. 232-258 ft., Very hard groy rock. 258-261 ft., Soft gway rock. Crevices, hard gray rock. 261-279 ft., 279-289 ft., Porous gray rock. 289-307 ft., Hard grey rock. Soft groy rock, broken. Water-bearing formation. 307-313 ft., Hardor grey rock, crovices. Bailing test at 313-324 ft., 318 ft. dopth showed 10 g.p.m. 324-329 ft., Soft groy rock, broken, lle perceity. Hard groy rock. 327-338(ft., 338-345 ft., Semi-porous black rock. 345-352 ft., Vory hard gray rock. 352-356 ft., Soft porous groy rock, water-bearing. 356-372 ft., Hard gray rock. 372-387 ft., Soft brown rock; crovices. 387-394 ft., Mod. hard gray rock. Soft perous black rock, water-bearing. 394-40] ft., Med, herd grey rock. 401-408 ft., Gray sundatione. 108-414 ft., 414-420 ft., Porona gray rock. 420-436 ft., Gray amidatone. Brown rock, medica hara. 435-440 ft., 440-45] It., Porous rod reck. Poroug Plack rock. 451-458 ft.

1-2 7/-3

Log of well Rib drilled for A. Wardman, at Crocked River Ranch, by R. J. Strauger Drilling Co., completed June 4, 1949.

458-461 ft., Hard gray rock.
461-463 ft., Softer gray rock.
463-466 ft., Gray sandsions.
466-476 ft., Porous gray rock.
478-492 ft., Very perous black rock, water-bearing.
492-494 ft., Bard black rock.

At depth of 438ft., well was tested, meximum flow being 600 g.p.m., with 120 ft. Grew-down.

At dopth of 494 ft., total dopth of well, tost was as follows:

Static level---286 ft.
545 g.p.m.--287 ft.
1100 g.p.m.--268 ft., drawdown of 2 ft. from static level.

Surface pipe, 20 ft. of 16" O.D. pipe.

SANITARY SURVEY INVENTORY CODES - DRINKING WATER PROGRAM

Service Area Codes

Co	de				Des	cription		
	Secondary							
R	1		Residential - C	itv	or '	Town		
R	2		Residential - Mobile Home Park					
R	3		Residential - Subdivision					
R	4		Residential - R	ural	Re	sidential		
10			Residential - C	thor	. Itc	31ucilo1u1		
R	9					- 1		
T	1		Transient - Rec	reat	TOH	dl dl		
T	2		Transient - Ser					
T	3		Transient - Sum	mer	Cam	p	Contraction of the	
T	4		Transient - Res	taur	ant	, Tavern,	or Gr	ocery
T	5		Transient - Hig	hway	Re	st Area		
T	5		Transient - Hot	el,	Mot	el, or Bed	l & Br	eakfast
T	9		Transient - Oth					
S	1		Semi-Residentia	1 -	Sch	ool		
S	1 2		Semi-Residentia					
S	3		Semi-Residentia	1 -	Med	ical Facil	itv	
C	4		Semi-Residentia	1 -	Indi	etrial or	Agri	cultural
S S S			Semi-Residentia	1	Dan	Caro Cont	ar	Carcarar
5	5 9 1						.CI	
	9		Semi-Residentia					
0			Other - Interst					
0	2		Other - Wholesa	ler	(se	lls water)		
0	9		Other - Other					
			County C					
01 Baker	c		Douglas			ke	28	
02 Bento	on	11	Gilliam	20	La	ne	29	Tillamook
03 Clack	camas	12	Grant	21	Li	ncoln	30	Umatilla
04 Clats	sop	13	Harney	22	Li	nn	31	Union
	nbia		Hood River			lheur	32	
06 Coos			Jackson	24		rion	33	
	c		Jefferson	25		rrow	34	
			Josephine			ltnomah		
			Klamath		Po		36	
	nutes 37 Delegat			21	PO	I.K.	30	Idmiiii
	*	-		-			Use C	
Dea	activation	Rea	son Codes		A	Forest (F	risti	ne)
					В	Irrigated	Crop	s
Code		Rea	ison		C	Non-Irrig		
	System aba	ndor	ned		D	Pasture		-
			cannot contact			Light Ind	lustry	
			with another II		F	Heavy Ind		
			consolidated		G	Urban Sev		
			monitoring PWS	10	Н			
		ICTA	monitoring PWS			Rural On-		10 (4/4) / / /
	other				I	Urban On-		sewage
			from inventory		J	Rangeland		
			with new ID	1		Managed I		
S S	system dis	cont	inued			Commercia		
U	Inqualifie	d as	a PWS		M	Recreation	onal t	Jse
	ther			-				
						Sto	rage 1	Гуре
	Pump	Code	9			G -	Groun	ad
7m 17								
	Turbine		J Shallow Jet				Eleva	
SU Subme	rsible	D	J Deep Jet			P -	Press	sure
	ifugal		T Other					

SANITARY SURVEY INVENTORY CODES - DRINKING WATER PROGRAM

Owner Characteristic Codes

1 - Federal Government

2 - Private

3 - State Government

4 - Local Government

5 - Mixed Public/Private

System Type

C - Community

N - Non-community

P - Non-transient/Non-community

S - State

Disinfectant Codes

SH	Calcium Hypochlorite Sodium Hypochlorite	CG	Chloramines Chlorine Gas	CD	Ozone Chlorine Dioxide
UV	Ultraviolet Radiation	OT	Other	NO	None

Recharge Area Formula

π	-	3	1	4	1	6	

n	-	Aquifer Porosity	Average	2	Ra	ang	je
		Unconsolidated Materials		*		-	
		Sand	(0.35)		(0.25	-	0.50)
		Gravel					
		Sand and Gravel Mix	(0.22)		(0.10	-	0.35)
		. Consolidated Materials					
		Fractured Basalt	(0.27)		(0.05	-	0.50)
		Sandstone				-	0.30)
H	-	Open Interval or Length of Well	Screen		(ft)		

6-12579 RECEIVED JUL 0 1 1991 WATER RESOURCES DEPT. SALEM, OREGON

Crooked River Ranch Water Company P.O. Box 1388 Crooked River Ranch, Or. 97760

Water Resources Department 3850 Portland Rd. NE Salem. Or. 97310.

June 29, 1991

Dear Sir:

Please add the attached Land Use Information form, signed by Deschutes County Planning Department, to our application file.

> Sincerely, Shirley Harris

Shirley Harris, Secretary

Crooked River Ranch Water Company

Deschutes Co.



Note to Local Governments

The person presenting the attached request for land use information is applying for a water right. The Water Resources Department requires its applicants to obtain land use information in order to meets its obligation to be compatible with comprehensive plans. The Department will not accept applications which do not include this completed land use information form or the receipt stub on the bottom of the attached form.

You have 60 days to fill out and return this form to the applicant or the Department. Otherwise the Department may proceed with processing the water right application without your input.

Besides land use information, there are many other submittal requirements for a water right application. If the applicant meets all these and pays a fee, the application is officially accepted. The Department is required to give public notice of all officially accepted applications.

Your county or city will receive a copy of this public notice. You will have 30 days to notify the Department of any concern, including conflicts between the proposed water use and your comprehensive plan. If you do not respond to the notice, the Department may presume that issuing the water right is compatible with your comprehensive plan.

Local governments are encouraged to take advantage of the 30 day notice period and use the 60 day land use information period, if needed, to gather documentation should there be a compatibility concern.

If you have any questions, please phone Roberta Jortner or Rick Bastasch at 378 - 3671.

Water Resources Department 3850 Portland Rd. NE Salem, OR 97310 August 1990

Land Use Information Form: Permits, Hydroelectric Licenses, Water Uses in Addition to Classified Uses

This information is needed to de required by ORS 197.180. The to evaluate the water use applicative diverted, conveyed, and/or used	ation. DO NOT FILL OUT.	BIIL WIII USO	uno and on	s to be	CEIVED
Address: P.O. Bo, Cily: Crooked River Rance	4 State: or Zip: 977	60 Day P	hone: <u>548</u>	3-8939 WATER	UL 0 1 1991
Please provide information as rediverted or used. (Attach extra sirrigation uses within irrigation disponderies for the tax lot information.)	sheets as necessary.) Ap Istricts, may substitute exis	olicants for	municipal u	58,01	.EM, OREGON
	signation/Zoning I Residential/RR-5)	Water ·	All That Apply Water onveyed	Water Use	
•					
Please list all countles and cities and/or used. The following section must be completed will be locally planning agency must complete the complete section. For Local Government Use Countries to the complete section. Local government planning offinot be completed while the appropriate section. Please mall the complete section.	completed by a planning of ated entirely within city if a this form. Please requesting the complete the replicant walts, please sign a pleted form directly to the	ficial from emits. In this extra form	ach county s case, only s as needed this form. he receipt a sources De	the city listed the city d.	
(3850 Portland Rd. NE, Salen below. If the form is not comp the water use.	leted within 60 days, the D	epartment	may take ac	etion to approv	e
a) Check the appropriate box	below and provide request	ed Informat	ion.		
Land uses to be se involve discretionary la attach documentation	are not regulated by your are not regulated by your are not regulated by your are not expressed water using use approvals as listed to of applicable local land	eomprehens Go to ses (Includir In the table use appro	sive plan. Co section b) ng proposed below. No vals which	Olte applicable on reverse side on struction; ote: Please have already	de.)
been obtained. (Rec	ord of Action plus any ac	companyli	ng findings	is sufficient.)
Type of	0, 11, 10, 11, 1	Pleas	e check the b	ox that applies:	
Land Use Approvals Needed (e.g.; plan amendments, rezones, conditional use permits, etc.)	Cite Most Significant, Applicable Plan Policies & Ordinance Section Reference	Already Obtained	Already Denled	Being Pursue Satisfactorily	
		· · · ·	-		
-		-	-	-	

(For Local Use Continued)		
b) Please provide printed name and written signature. Name: Nanca Kincard Title: Assistant Planner Signature: Manager	Date: 6/26 Phone: 388.6	191
Local governments are invited to express special land use con to the Department regarding this proposed use of water below, additional information call Roberta Jortner or Rick Bastasch at	cerns or make recom , or on a separate she 378-3671,	mendations eet. For
Additional Comments:		

Description of Water Use

Note to Applicant: This sheet will provide local planning staff with a basic description of your proposed water use.

Please fill out this sheet before bringing the attached land use form to your local planning office. It will help local planning offices complete your land use information form quickly.

Note to Local Planning Officials: Please Initial this sheet. Do not separate it from the land use information form. If needed, please make a separate copy for your records.

Applicant Name: Crooked River Ronch

Address: P.O. Box 879

Crooked River Ranch, OR 97760

JUL 0 1 1991

Phone: 548-8939

WATER RESOURCES DEPT.

	SALEM, OREGON
Please indicate what you will use the water for. Check all boxes the and fill in the blanks with key characteristics of the project	at apply
 Irrigation (crop type, golf course, nursery or greenhouse):	
Livestock (type of livestock, feedlot, slaughterhouse):	4.
Residential (# units, single or multi-family, # lots if partition or subdivision):	
Commercial (i.e., retail, office, restaurant, gas station, hotel, service, etc.):	
Industrial (i.e., factory, pulp mill, research and development, processing, etc.):	dyr r
Institutional (i.e., school, library, etc.):	
Mining (aggregate, metal, open pit, placer, etc.):	
Recreation (park, campsite, pond, etc.)	•
Fish and Wildlife (pond, hatchery, etc.)	8 4
Hydropower (dam, reservoir, power generating or transmitting facilities): Other (Name and list key characteristics): Rugsi - Municipal	

Indicate sources for the proposed water use below:	Indicate the estimated quantity of water the use will require.
Surface Water Name sources:	Cubic feet per second Gallons per minute Acre-Feet
☐ Reservoir or pond ☐ Ground Water	

Water Resources Department, 3850 Portland Rd. NE, Salem, OR 97310

Phone: 378-3671

Version: 8/30/90

Land Use Information Form: Permits, Hydroelectric Licenses, Water Uses in Addition to Classified Uses This Information is needed to determine compatibility with local comprehensive plans as required by ORS 197.180. The Water Resources Department will use this and other information to evaluate the water use application. DO NOT FILL OUT. THIS FORM IF water is to be diverted, conveyed, and/or used only on federal lands. diverted, conveyed, and/or used only on federal lands. Applicant's Name: Crooked Address: P.O. Box 879. Ranch State: OR Zip: 97760 Day Phone: 548-8939 City: Crooked River Please provide information as requested below for all tax lots on or through which water will be diverted or used. (Attach extra sheets as necessary.) Applicants for municipal use, or irrigation uses within irrigation districts, may substitute existing and proposed service area boundaries for the tax lot information requested below. . Check All That Apply Water Water Water Tax Lot or Local Plan Designation/Zoning (e.g. Rural Residential/RR-5) Conveyed Use I.D.# Diverted Please list all counties and cities within which water is proposed to be diverted, conveyed, and/or used. (Jefferson) and Deschates Counties The following section must be completed by a planning official from each county and city listed unless your project will be located entirely within city limits. In this case, only the city planning agency must complete this form. Please request extra forms as needed. For Local Government Use Only Local government planning officials are to complete the remainder of this form. If this form can not be completed while the applicant walts, please sign and detach the receipt as instructed below. Please mail the completed form directly to the Water Resources Department (3850 Portland Rd. NE, Salem, OR, 97310) within 60 days of the date of receipt as shown below. If the form is not completed within 60 days, the Department may take action to approve the water use. a) Check the appropriate box below and provide requested information. Land uses to be served by proposed water uses (including proposed construction) are allowed outright or are not regulated by your comprehensive plan. Cite applicable ordinance section(s): . Go to section b) on reverse side. Land uses to be served by proposed water uses (including proposed construction) involve discretionary land use approvals as listed in the table below. Note: Please attach documentation of applicable local land use approvals which have already been obtained. (Record of Action plus any accompanying findings is sufficient.) Please check the box that applies: Type of Land Use Approvals Needed Cite Most Significant, Applicable Plan Policies & Ordinance Section References (e.g.: plan amendments, rezones, Already Obtained Being Pursued conditional use permits, etc.) Satisfactorily (over) Receipt for Request for Land Use Information. WRD Applicant Name:_ This receipt must be signed by a local government representative and returned to the applicant for inclusion in the WRD application IF the local government can not provide the above requested land use information while the applicant walts. City or County: Je Herson Phone: 415-3147 Staff Contact: Muc

Signature: Char

Date of Information Request: 6-19-91

Version: 8/27/90

For Local Use Contli	nued)				
Name: C Title: I	harles A.	McGassu McGassu rector A. McJu	ure.	Date: 6 Phone: 4	-13-91
Local governments a to the Department re additional informatio	are invited to e garding this p n call Roberta	express special la proposed use of v a Joriner or Rick b	and use concer vater below, or Bastasch at 37	ns or make r on a separa 8-3671.	ecommendations te sheet. For
Additional Comme	nts:			1	,
, ,	•		· · · · · · · · · · · · · · · · · · ·		
				<u> </u>	

Description of Water Use

ugm

Indicate sources for the proposed water use below:	Indicate the estimated quantity of water the use will require.
Surface Water Name sources: Reservoir or pond Ground Water	Cubic feet per second Gallons per minute Acre-Feet

Water Resources Department, 3850 Portland Rd. NE, Salem, OR 97310

Phone: 378-3671

Version: 8/30/90

MEMORANDUM

DATE:	7/3	
TO:	Application	on/ Permit Section
FROM:	Groundwate	er Section by Sauch Meyer (signature)
SUBJECT:	Application	on # G-12579
The appl reviewed October 1	under the	eferenced above and available data has been guidelines of the Director's policy memo of
	that the category:	proposed groundwater use falls within the
-		The proposed well will be located less than 1/4 mile from the nearest stream, and significant surface water interference will exist.
		The proposed well will be located less than 1/4 mile from the nearest stream, but significant surface water interference will not exist.
CATE	GORY 2A -	The proposed well will be located more than 1/4 mile from the nearest stream, and significant surface water interference will not exist.
CATE	GORY 2B -	The proposed well will be located more than 1/4 mile from the nearest stream, but significant surface water interference will exist at the nearest point on the stream.
REMARKS:_		
-		

Ю:	•	Water Right	s Section			9/3	, 1991
ROI	M:	Groundwate	r/Hydrology Section	on	Sarceh 1. Reviewer's N	neyer	_
UBJ	ECT:	Application	G- <u>12579</u>	-	Reviewer's N	ame	
	PER surface	THE Desch	Basin rules e and taps a groun	, one or more of dwater source	of the proposed PO hydraulically conne	A's is within exted to the sur	mile of a face water.
١.	a. b.	will, or ? will not }	have the potentia source, namely	al for substantia	ve determined that I interference with Looked River It the surface water	the nearest su	rface water ; or
		iThe p iiThe p iii. The p	ermit should conta ermit should conta ermit should be co	in condition #(in special cond nditioned as inc	s); tion(s) as indicated licated in item 4 be the surface water	l in "Remarks' elow; or	below;
3.	a b	will, or > will not > can, if prope iThe p iiThe p	likely be available available rly conditioned, available ermit should contain the contain	le in the amour oid injury to ex in condition #(s in special condi	ts requested withoutsting rights or to	ut injury to pri the groundwate I in "Remarks"	or rights; or er resource;
1.	a	THE PERM surface;	IT should allow gro	oundwater produ	action from no deep	er than	_ft. below land
	b		ould allow ground	water production	n from no shallowe	er than	_ft. below land
		The permit s reservoir bet Well reconstr One or more	ween approximately fuction is necessary POA's commingle	y ft. a to accomplish a 2 or more so	ion only from the ind ft. bel one or more of the urces of water. Tortion of water to be	low land surface e above condit The applicant r	ce; ions. nust select one
EMA	ARKS:						
	-						

ELL CONSTRUCTION (If more than one well doesn't meet standards, attach an additional sheet.)

STATE OF OREGON

COUNTY OF JEFFERSON AND DESCHUTES

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

CROOKED RIVER RANCH WATER COMPANY P.O. BOX 879 CROOKED RIVER RANCH, OREGON 97760

503-548-8939

2=3 to use the waters of TWO WELLS in the CROOKED RIVER BASIN for QUASI-MUNICIPAL, JUL

This permit is issued approving Application G-12579. The date of priority is JUNE 18, 1991. The use is limited to not more than 5.0 CUBIC FEET PER SECOND (CFS), BEING 2.5 CFS FROM EACH WELL, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

NW 1/4 NW 1/4, SW 1/4 SE 1/4, SECTION 24, T 13 S, R 12 E, W.M.; WELL 2 - 680 FEET SOUTH AND 780 FEET EAST FROM NW CORNER, SECTION 24, WELL 3 -80 FEET NORTH AND 480 FEET EAST FROM S 1/4 CORNER, SECTION 24.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

> NW 1/4 NW 1/4 S 1/2 SW 1/4 SECTION 4 E 1/2 NE 1/4 SE 1/4 SW 1/4 SE 1/4 SECTION 5 NE 1/4 NE 1/4 NW 1/4 SECTION 8 NW 1/4 S 1/2 SECTION 9 S 1/2 NW 1/4 SW 1/4 S 1/2 SE 1/4 SECTION 10 SW 1/4 SW 1/4 SECTION 13 SW 1/4 NE 1/4 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 14 ALL SECTION 15 ALL

SECTION 16 E 1/2 NE 1/4 E 1/2 SE 1/4 SECTION 17 N 1/2 SECTION 21

NUNW 5/2 8NW

PAGE TWO

西河南南山

```
N 1/2
             NW 1/4 SW 1/4
              N 1/2 SE 1/4
              SE 1/4 SE 1/4
               SECTION 22
                 NE 1/4
              E 1/2 NW 1/4
              E 1/2 SW 1/4
                 SE 1/4
               SECTION 23
                 NW 1/4
                  S 1/2
               SECTION 24
                   ALL
               SECTION 25
                   ALL
               SECTION 26
                   ALL
               SECTION 27
              N 1/2 NE 1/4
              SW 1/4 NE 1/4
                 NW 1/4
              E 1/2 SW 1/4
                 SE 1/4
               SECTION 34
                   ALL
               SECTION 35
              N 1/2 NE 1/4
              SW 1/4 NE 1/4
                  W 1/2
                 SE 1/4
               SECTION 36
TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.
              S 1/2 SW 1/4
             SW 1/4 SE 1/4
SECTION 31
TOWNSHIP 13 SOUTH, RANGE 13 EAST, W.M.
              N 1/2 NE 1/4
N 1/2 NW 1/4
             SW 1/4 NW 1/4
                SECTION 1
                 NE 1/4
                 SW-1/4
                SECTION 2
                   ALL
               SECTION 3
             NW 1/4 NW 1/4
               SECTION 11
TOWNSHIP 14 SOUTH, RANGE 12 EAST, W.M.
             NW 1/4 NE 1/4
              N 1/2 NW 1/4
               SECTION 6
TOWNSHIP 14 SOUTH, RANGE 13 EAST, W.M.
```

The well sha

The well shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times. When required by the department, the permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

画图似证证

PAGE THREE

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before , and shall be completed on or before October 1, 1993. Complete application of the water shall be made on or before October 1, 1994.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

Issued this date,.

Water Resources Department William H. Young Director

Application G-12579 Water Resources Department PERMIT G-Volume 2 Crooked River & Misc. Basin 5 G-12579.

District 11

Mgmt Cordes

Application No. 6-12579



JUN 1 8 1991

WATER RESOURCES DEPARTMENT

State of Oregon WATER RESOURCES DEPT.

SALEM, OREGON

Application for a Permit to Appropriate Ground Water

If development is less than one mile from a natural stream, give the following: Distance from development to stream: Well #2 400' Well #3 Elevation difference between streambed and development: 150 # (well # 2) NOTE: Wells must be constructed according to standards set by the department for the and maintenance of water wells. If the well is already constructed, please enclose a condriller's log with this application, and skip to Section 2 below. Well #2 Diameter of well: Well #3 Type and size of well casing: #2 Estimated depth to water: #2 Type of access port or measuring device: pipe plug in well come	application fo	or a permit to appr	opriate the fol	lowing describ	ed ground wat	ters of the State of
Distance from development to stream: Well #2 1400' Well #3 Elevation difference between streambed and development: 150'± (well be NOTE: Wells must be constructed according to standards set by the department for the and maintenance of water wells. If the well is already constructed, please enclose a condition of the analysis of with this application, and skip to Section 2 below. Well #2 Diameter of well: Well #3 Depth in feet: #3 Type and size of well casing: #2 Estimated depth to water: #2 #3 Type of access port or measuring device: pipe plue in well cape	EVELOPME	NT (number of we	lls, tile lines, i	nfiltration gal	leries, etc.): _	2 wells
Distance from development to stream: Well #2 1400' Well #3 Elevation difference between streambed and development: 150'± (well be NOTE: Wells must be constructed according to standards set by the department for the and maintenance of water wells. If the well is already constructed, please enclose a condriller's log with this application, and skip to Section 2 below. Well #2 Diameter of well: Well #3 Depth in feet: #3 Type and size of well casing: #2 Estimated depth to water: #2 Type of access port or measuring device: pipe plue in well cape						
Elevation difference between streambed and development: 150 ± (will be NOTE: Wells must be constructed according to standards set by the department for the and maintenance of water wells. If the well is already constructed, please enclose a condition of the well is already construc	pment is less t	than one mile from	a natural stre	am, give the fo	llowing:	
NOTE: Wells must be constructed according to standards set by the department for the and maintenance of water wells. If the well is already constructed, please enclose a condriller's log with this application, and skip to Section 2 below. Well #2 #2 Diameter of well: Well #3 Depth in feet: #3 Type and size of well casing: #2 #3 No. of feet: #2 Estimated depth to water: #2 #3 Type of access port or measuring device: pipe plug in well case	Distance from	n development to s	tream: Well	#2 1400'	Well =	*3 2000'
and maintenance of water wells. If the well is already constructed, please enclose a condriller's log with this application, and skip to Section 2 below. Well #2 #2 Diameter of well: Well #3 Depth in feet: #3 Type and size of well casing: #2 #3 No. of feet: #2 Estimated depth to water: #2 #3 Type of access port or measuring device: pipe plug in well case	Elevation diff	ference between st	reambed and a	development:_	150'± (will	be provided la
Diameter of well: Well *3 Depth in feet: *3 Type and size of well casing: *2 *3 No. of feet: *2 Estimated depth to water: *2 *3 Type of access port or measuring device: pipe plus in well cape	itenance of wo	ater wells. If the w	vell is already	constructed, pl	ease enclose a	the construction copy of the wel
Type and size of well casing: #2 #3 No. of feet: #2 Estimated depth to water: #2 #3 Type of access port or measuring device: pipe plue in well cape	We	11 #2			# 2	
Estimated depth to water: #2 #3 Type of access port or measuring device: pipe plug in well cape	of well: We	11 *3		_ Depth in fee	et: #3	
Type of access port or measuring device: pipe plug in well cape	size of well c	asing: #2	,#3	N	o. of feet: #2	,#3
	depth to water	er: <u></u> #2	,#3	_		
	ccess port or	measuring device:	pipe pl	ug in wel	1 caps	
Wells to be drilled by:	be drilled by:					
Address:	Address:					
If the water well is flowing artesian, describe your water control and conservation work		ving artesian, desc	ribe your wate	er control and	conservation v	vorks:

If for more than	one use, give the quantity of water from each source for each use;
If for DOMEST	IC use, state the number of households to be supplied;
If for MUNICII and an estimate of to be provided w	PAL OR QUASI-MUNICIPAL use, state the present population to be served, of the future requirements; (List population projections, water needs, anticipated area eater.)
775 cur	rent hook ups. System opproved by State Health
Depart mer Future exp If for MINING	t for 1600 lots. All 1600 lots have metered occess passion for all 2600 lots not on wells. use, state the nature (gold, silver, etc.) of the mines to be served;
	ION, or other land area use, state the TOTAL number of acres to be developed
	Irrigation
	Other (describe)
onstruction of d ump and motor. ther).	OF WATER DELIVERY SYSTEM: Include dimensions and type of iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, dripe the size of th
onstruction of d ump and motor. ther). The sy	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very
onstruction of dump and motor. ther). The sy extensive	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them
onstruction of doump and motor. ther). The sy extensive	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very
onstruction of dump and motor. ther). The sy extensive	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them
onstruction of dump and motor. ther). The sy extensive	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them
onstruction of dump and motor. ther). The sy extensive	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them
onstruction of dump and motor. ther). The sy extensive	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them
onstruction of dump and motor. ther). The sy extensive through	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them delivery system to the lots and community center.
onstruction of doump and motor. ther). The sy extensive through	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir them delivery system to the lots and community center. HEDULE: (List month and year)
eonstruction of doump and motor other). The sy extensive through PROJECT SCI	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, drip stem is in place for 1600 lots now. This is a very project from the two wells into reservoir then delivery system to the lots and community center. HEDULE: (List month and year) ed date construction work will begin Wells complete
PROJECT SCI Propos	iversion works, length and dimensions of supply ditches or pipelines, size and type. If for irrigation, describe the type of system (i.e., flood, wheel line, hand line, dristem is in place for 1600 lots now. This is a very project from the two wells into reservoir them delivery system to the lots and community center. HEDULE: (List month and year)

NOTE: A map prepared by a Certified Water Right Examiner (CWRE) and a complete legal description of the subject property are required under ORS 537.140 and OAR 690 as a part of your application. The legal description may be copied from your deed, title insurance policy, or land sales contract.

Application No. 6-12579

RECEIVED

Permit No.

Annex A

WATER RESOURCES DEPT. SALEM, OREGON

NW/a NW/a 5/2 SW/9 Section 4

AII Section 15

A11 Section 25

P9 1

E/2 NE /A SE1/4 SIV1/4

Section 16

A11

A11 Section 26

SEZ Section 5

E/2 NE/9 E/2 SEY9 Section 17

A11 Section 27

NEVA NEYA NIJYA Section 8

NYE Section 21 N/2 NE/4 SWY4 NEYA NWY E/2 SW/4 SEYA Section 34

NU% 5/2 Section 9

N/2 NW1/4 SW1/9 N1/2 SEXA SEYA SEYA Section 22

A11 Section 35

S/2 NU% SW1/4 S/2 SEYA Section 10

NE /4 E/2 NW/4 E1/2 SW1/4 SE 1/9 Section 23

N'/2 NE 1/4 SWYA NEYA W/2 3E 1/9 Section 36 T. 135, R.12.E., W.M.

341/4 3W/4 Section, 13

> NW14 51/2 Section 24

5 W/4 NE/4 NW1/4 NW1/4 3 1/2 NW1/4 SW1/4 SE 1/4 Section 14

RECEIVED

JUN 1 8 1931

P92

WATER RESOURCES DEPT. SALEM, OREGON

5/2 SW/4 SW1/4 SE1/4 Section 31 HUID T. 135, R.13E, W.M.

> N/2 NEYA N/2 NW/9 SW/ NW/4 Section 1

> > NEYA 31/1/4 Section 2

All Section 3

NU/4 NW/4 Section 11 T. 145, R. 12E, W.M.

NUYA NEYA N/2 NW/9 Section 6 T. 14 S., R. 13 E., W. 11.

		ons for correction to (check X CWRE		KS section)
- L. T				
b) Ii in	n the event any defic extructions for correc	tencies are noted involving to ction to (check one):	he <u>application</u> , please return the <u>app</u>	lication with
-	X Applicant ec	$+b \rightarrow CWRE$	Other (Identify in REMARI	KS section)
the an a	all lands involved (i water) under your o uttached sheet, the no posed development.	ncluding the proposed diver wnership? <u>N A</u> wnes and mailing addresses	sion site, place of use, and access for f not, list in the REMARKS section i of the legal owners of all property inv	r conveying below, or on volved in the
Res	ources Department t	ng a certificate of water right he results of a pump test mee ump test results every ten yea	, the permit holder must submit to the ting the department's standards. The rs thereafter.	: Water : Director wil
REMA	RKS:			
-				_
=				
associa acknow keeping	ted with this water us ledged land-use plan	se must be in compliance wit n. It is possible the land use acknowledged plan. Your cit	te of water without waste. By law, the statewide land-use goals and any look you propose may not be allowed if it yor county planning agency can adv	is not in
	Signature of Ap	eb Brouxles		/
	Simple of Co.	-Applicant if any	Date	

e foregoing appl	lication, together with the accompanying informa-
ority, this applic	cation must be returned with the requested
-	, 19
day of	, 19
_	Water Resources Director
Ву:	
office of the Wa	ter Resources Director at <u>S'aler</u> , , 19 <u>9</u> (, at <u>3:00</u> o'clock, <u>L</u> M
	day of

A:APPFORM 9/89

Crooked River Ranch Water Company

P.O. Box 1388 Crooked River Ranch Oregon 97760 923-1041



Application No. 6 12579 Permit No. G11376

> State of Oregon Water Resources Department

June 10, 1991

Appropriate Persons:

The Crooked River Ranch Water Company is a user owned community system that was begun about 1973. The current Board of Directors just recently became aware of the need to apply for water rights as a Quasi-Municipal supplier.

This application is intended to correct a situation that we have no better explaination for than perhaps oversight by the original developer and past Boards.

Our system is fully described in the enclosed Sanitary Survey Report prepared by the Oregon State Health Division. We sincerely hope this application is complete and will meet with your early approval.


Sincerely,

Dick Brownlee, President

Crooked River Ranch Water Company

BECEIVED

STATE OF OREGON



COUNTY OF JEFFERSON AND DESCHUTES

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

CROOKED RIVER RANCH WATER COMPANY P.O. BOX 879
CROOKED RIVER RANCH, OREGON 97760

503-548-8939

to use the waters of WELLS 2 & 3 in the CROOKED RIVER BASIN for QUASI-MUNICIPAL USE.

This permit is issued approving Application G-12579. The date of priority is JUNE 18, 1991. The use is limited to not more than 5.0 CUBIC FEET PER SECOND (CFS), BEING 2.5 CFS FROM EACH WELL, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

NW 1/4 NW 1/4, SW 1/4 SE 1/4, SECTION 24, T 13 S, R 12 E, W.M.; WELL 2 - 680 FEET SOUTH AND 780 FEET EAST FROM NW CORNER, SECTION 24, WELL 3 - 80 FEET NORTH AND 480 FEET EAST FROM S 1/4 CORNER, SECTION 24.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

NW 1/4 NW 1/4 S 1/2 SW 1/4 SECTION 4 E 1/2 NE 1/4 SE 1/4 SW 1/4 SE 1/4 SECTION 5 NE 1/4 NE 1/4 NW 1/4 SECTION 8 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 9 S 1/2 NW 1/4 SW 1/4 S 1/2 SE 1/4 SECTION 10 SW 1/4 SW 1/4 SECTION 13 SW 1/4 NE 1/4 NW 1/4 NW 1/4 S 1/2 NW 1/4 S 1/2 SECTION 14 ALL SECTION 15 ALL SECTION 16 E 1/2 NE 1/4 E 1/2 SE 1/4 SECTION 17 N 1/2 SECTION 21

NOV - 8 1331

WATER PAGE TWO

N 1/2 NW 1/4 SW 1/4 N 1/2 SE 1/4 SE 1/4 SE 1/4 SECTION 22 NE 1/4 E 1/2 NW 1/4 E 1/2 SW 1/4 SE 1/4 SECTION 23 NW 1/4 S 1/2 SECTION 24 ALL SECTION 25 ALL SECTION 26 E 1/2 N 1/2 NW 1/4 SE 1/4 NW 1/4 NE 1/4 SW 1/4 S 1/2 SW 1/4 SECTION 27 N 1/2 NE 1/4 SW 1/4 NE 1/4 NW 1/4 E 1/2 SW 1/4 SE 1/4 SECTION 34 ALL SECTION 35 N 1/2 NE 1/4 SW 1/4 NE 1/4 W 1/2 SE 1/4 SECTION 36

TOWNSHIP 13 SOUTH, RANGE 12 EAST, W.M.

S 1/2 SW 1/4 SW 1/4 SE 1/4 SECTION 31

TOWNSHIP 13 SOUTH, RANGE 13 EAST, W.M.


N 1/2 NE 1/4 N 1/2 NW 1/4 SW 1/4 NW 1/4 SECTION 1 N 1/2 NE 1/4 SE 1/4 NE 1/4 W 1/2 SW 1/4 SE 1/4 SW 1/4 SECTION 2 ALL SECTION 3 NW 1/4 NW 1/4 SECTION 11

TOWNSHIP 14 SOUTH, RANGE 12 EAST, W.M.

NW 1/4 NE 1/4 N 1/2 NW 1/4 SECTION 6

TOWNSHIP 14 SOUTH, RANGE 13 EAST, W.M.

Within one year from the date the Water Resources Commission adopts rules describing the schedules, standards and procedures for water conservation management plans by water suppliers, Crooked River Ranch Water Company shall submit a plan which is consistent with said rules.



Within one year of permit issuance, Crooke River Ranch Water Company shall prepare a plan/timetable for the Water Resources Commission which shall indicate the steps which the Water Company intends to pursue to obtain a long-term water supply.

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the wells at all times. When required by the department, the permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before , and shall be completed on or before October 1, 1993. Complete application of the water shall be made on or before October 1, 1994.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

Issued this date,.

Water Resources Department William H. Young Director

I We, Crooked Rever Karch Witer Co., hereby understand and agree that this draft permit describes the full extent of water use that will be allowed approving Application G-12579. By signature below, I\We agree to the proposed terms and conditions for this draft permit. Treside

MMA

EL Secritor







didipplialitimididiplipliplibilitimitologiani
G-12579
CROOKED RIVER RANCH CLUB
MAINTENANCE ASSOCIATION
5195 SW CLUBHOUSE RD
TERREBONNE OR 97760