



## **Water Right Application Superseding Initial Review**

May 15, 2026

DAMON C. JONES  
60570 WOODSIDE RD  
BEND OR 97702

Reference: Application G-19112

**This Superseding Initial Review is to provide adequate public notice in accordance with Oregon Administrative Rule (OAR) 690-310-0090.**

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Water Resources Department (Department) must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Department has made the following preliminary determinations:

### **Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:**

1. Application G-19112 proposes the appropriation of 0.056 cubic foot per second (CFS), further limited to 6.0 acre-feet (AF) annually, of water from a well in Deschutes River Basin for nursery use on 3.7 acres from January 1 through December 31 of each year.
2. On February 14, 2022, the applicant amended the application and reduced the area proposed for nursery use from 3.7 acres to 2.6 acres.
3. The proposed use is not prohibited by law or rule except where otherwise noted below.
4. Nursery use is an allowable use under the Deschutes Basin Program (OAR 690-505-0400).

**Please note:** Applications are evaluated using the statutes and rules in effect at the time the application is accepted as complete unless subsequent statutes and rules specify otherwise. If not otherwise noted, all citations in this initial review refer to the rules and statutes in effect at the time the application is accepted as complete. To view the rules relevant for this application, please visit: <https://secure.sos.state.or.us/oard/displayCompilations> and navigate to Chapter 690 (Water Resources Department). To view the statutes relevant for this application, please visit: [https://www.oregonlegislature.gov/bills\\_laws/Pages/ORSarchive.aspx](https://www.oregonlegislature.gov/bills_laws/Pages/ORSarchive.aspx).

5. An assessment of groundwater availability has been completed by the Department. A copy of this assessment is in the file and can be viewed on the Department’s website. Groundwater for the proposed use is not over-appropriated.
6. If properly conditioned (and if authorized), the proposed use of groundwater will not injure other water rights.
7. The proposed use is located within the Deschutes Scenic Waterway, as designated under Oregon Revised Statute (ORS) 390.826, and within the Deschutes Ground Water Study Area (DGWSA). Groundwater appropriations within the DGWSA have the potential for substantial interference with surface water rights as described in OAR 690, Division 9, and will measurably reduce Scenic Waterway flows. Without mitigation, the Department is required by law to deny groundwater permit applications in the DGWSA. Mitigation may be provided to offset impacts to Scenic Waterway flows and senior surface water rights. OAR 690-505-0600(1)-(3).
8. Pursuant to OAR 690-505-0500(1), there is a 200.00 CFS cap on the amount of new groundwater use that may be allocated within the Deschutes Ground Water Study Area. Under the current rules, once the cap is reached, the Department will not be able to propose issuance on any new permits.
9. The Department has determined the mitigation obligation is 6.5 acre-feet (AF) annually. The required mitigation is based on nursery use on 2.6 acres. The mitigation obligation is calculated based on a consumptive-use factor of 2.5 AF per acre.
10. The Department has determined that mitigation for the proposed use must be located in the Middle Deschutes River Zone of Impact (located anywhere in the Middle Deschutes Basin above river mile 125).
11. On February 14, 2022, the Department received the applicant’s Response to Notice of Mitigation Obligation Credit or Project Option, wherein the applicant acknowledged that they intend to provide mitigation in the amount of 6.5 AF within the Middle Deschutes River Zone of Impact (located anywhere in the Middle Deschutes Basin above river mile 125).
12. On September 6, 2022, the Department received a Documentary Evidence Form that showed the applicant has obtained suitable mitigation in the amount of 6.524 AF through mitigation project MP-91.
13. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.

<b>Summary of Preliminary Determinations</b>
<b>The appropriation of 0.056 CFS, further limited to 6.0 AF annually, of water from a well in Deschutes River Basin for nursery use on 2.6 acres from January 1 through December 31 may be allowable.</b>

**Public Comment:**

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

**At this time, you must decide whether to proceed or to withdraw the application.**

- To Proceed - If you choose to proceed with the application, you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period and receipt of the NOMO form, the Department will complete a public interest review and issue a Proposed Final Order.
- To Withdraw - You may withdraw the application and fees in excess of \$465 will be returned. You must notify the Department **in writing** by **May 29, 2026**. For your convenience you may use the enclosed "STOP PROCESSING" form.

**If a permit is issued, it will likely include the following conditions:**

1. Construction of the well shall begin within seven years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting:**
  - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
  - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
  - C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
  - D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

#### 4. Groundwater Level Measurement, Reporting, and Shut-Off Condition:

For each well on this authorization, beginning on the permit signature date for existing wells or in the year well construction is completed for new wells, and each year thereafter, the permit holder must report a static water-level measurement (“measurement”) taken in March. The measurement is required whether the well is used or not. If pumping is to commence following completion of the well and prior to the next March, then a measurement must be made at least one week following well completion and before pumping commences.

Measurements must be properly reported within 30 days of measurement using forms specified by the Department. A measurement will be properly reported if the submission includes all required information as listed in the document attached. Measurements must be made with equipment that is accurate to the standards specified in Oregon Administrative Rule (OAR) 690-217-0045. Measurements must be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed land surveyor, licensed well constructor, pump installer licensed by the Construction Contractors Board, or Department staff. The Department is not responsible for regular measurement of the static water level, but Department staff may measure the well during the normal course of groundwater level monitoring or to confirm the submitted measurement(s).

For each well on this permit, the Department will establish a reference groundwater level using the best available data. The reference level is intended to represent the highest elevation (shallowest depth) static water level that has been measured or can be reasonably estimated to have existed within each well at any time before its reference level is set. If Annual High Water Levels have been increased measurably by human activity, then the Department may set a different reference level using best available information. If the permit holder fails to measure and report the static water level within 12 months of permit issuance, or of completion of the well(s), then Department staff will estimate the static water level using available data, including measurements in surrounding wells. In case the permit is amended or the subsequent certificate is transferred, the Department may establish a new reference level for any new or additional wells under new permits or certificates issued under this right. The reference level for a new or additional well should reflect the highest static water level in that well or, if that measurement occurred after the time represented by the original reference level, then the water level that would have been measured in that well, if the well existed and was measured at the time represented by the original reference level.

All water use authorized under this permit must immediately stop if any of the following occur:

- A. Any annual high elevation static groundwater level in any well on this permit declines 25 or more feet below the reference level for that well, or
- B. Groundwater levels are not measured and properly reported as specified above for any completed well that is authorized on the permit for two consecutive years, or
- C. Hydraulic interference contributes to a decline of 25 or more feet in any neighboring well with senior priority, at any time during the year.

The Department will determine when any of the above conditions have occurred and may order the permit holder to stop all water use under this permit. The permit holder is also responsible for stopping all water use if they become aware that any of the conditions have occurred, even without notice from the Department. Following such a stop, water use under this permit will not be allowed and may only resume once the permit holder receives notice from the Department. If the permit holder fails to stop use, then the Department may take control of the controlling works of any wells authorized under this permit and may reduce the amount of groundwater pumped until the unlawful use is eliminated.

The permit holder acknowledges that one or more of the conditions requiring stoppage of use may occur prior to any use of any well on this permit.

The Department may allow the permit holder to pause annual water level measurement and reporting requirements from some of the permitted wells if measurements from those wells are redundant with other data being collected by the Department. The permit holder must receive written notification of such an allowance before stopping measurements. If this happens, the Department may reinstate the measurement requirements at any time.

**5. Scenic Waterway:**

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced. However, the use of groundwater allowed under the terms of this permit will not be subject to regulation for Scenic Water Way flows, provided the required mitigation is maintained.

**6. Well Identification Tag:**

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

**7. Groundwater Mitigation Conditions:**

- A. Mitigation Obligation: 6.5 AF of mitigation water in the Middle Deschutes Zone of Impact (located anywhere in the Middle Deschutes Basin above river mile 125).
- B. Mitigation Source: obtain 6.5 AF of mitigation water or equivalent mitigation credits that meet the requirements of OAR 690-505-0610(2)-(5).
- C. Mitigation water must be legally protected instream in the Middle Deschutes Zone of Impact (located anywhere in the Middle Deschutes Basin above river mile 125) for the life of the permit and subsequent certificate(s). Regulation of the use and/or cancellation of the permit, or subsequent certificate(s) will occur if the required mitigation is not maintained.

- D. The permittee shall provide additional mitigation if the Department determines that average annual consumptive use of the subject appropriation has increased beyond the originally mitigated amount.
- E. If mitigation is from a secondary right for stored water from a storage project not owned or operated by the permittee, the use of water under this right is subject to the maintenance and terms and conditions of a valid contract or satisfactory replacement, with the owner/operator of the storage project, a copy of which must be on file in the records of the Water Resources Department.
- F. Failure to comply with these mitigation conditions shall result in the Department regulating the groundwater permit, or subsequent certificate(s), proposing to deny any permit extension application for the groundwater permit, and proposing to cancel the groundwater permit, or subsequent certificate(s).

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at [www.oregon.gov/ODA](http://www.oregon.gov/ODA) to learn more about the plans and how they may affect the proposed water use.

**For Further Information:**

Feel free to contact me at [Nick.A.Reece@water.oregon.gov](mailto:Nick.A.Reece@water.oregon.gov) or 971-719-1058 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Nick Reece, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

*Nick Reece*

Nick Reece  
Water Right Application Specialist  
Oregon Water Resources Department

Enclosure: Application Process Description  
Stop Processing Request Form

G-19112  
Proposed to Approve

# APPLICATION FACT SHEET

Application File Number: G-19112

Applicant: DAMON C. JONES

County: DESCHUTES

Watermaster: JEREMY GIFFIN, #11, CR

Priority Date: APRIL 19, 2021

Source: A WELL IN DESCHUTES RIVER BASIN

Use: NURSERY USES ON 2.6 ACRES

Quantity: 0.056 CUBIC FOOT PER SECOND, FURTHER LIMITED TO 6.0 ACRE-FEET ANNUALLY

Period of Use: JANUARY 1 THROUGH DECEMBER 31

Basin Name & Number: DESCHUTES, #5

WAB: DESCHUTES R > COLUMBIA R - AB BUCKHORN CAN

## WELL LOCATION(S):

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
18 S	12 E	WM	21	NW SE	210 FEET SOUTH AND 260 FEET EAST FROM C1/4 CORNER, SECTION 21

## PLACE OF USE:

Twp	Rng	Mer	Sec	Q-Q	Acres
18 S	12 E	WM	21	SW NE	0.1
18 S	12 E	WM	21	NW SE	2.5

**PUBLIC NOTICE DATE: May 19, 2026**

**14 DAY STOP PROCESSING DEADLINE DATE: May 29, 2026**

**30 DAY COMMENT DEADLINE DATE: June 18, 2026**

## **APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS**

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our website at: [www.oregon.gov/owrd](http://www.oregon.gov/owrd)

### **1. Pre-application considerations**

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

### **2. Application filing**

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

### **3. Initial Review (IR)**

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.

### **4. Proposed Final Order (PFO)**

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

### **5. Final Order (FO)**

- If no protest is filed, Final Order is issued.

#### ***The protest process***

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- Proposed Order;
- period of time to file exceptions; or
- possible hearing by Water Resources Commission.
- Final Order is issued.

#### ***Permit holder responsibilities***

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.

**STOP PROCESSING REQUEST FORM**

**FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS**

---

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-19112**.

After reviewing the Initial Review for my application, I request that processing be stopped, and fees in excess of \$465 be returned. I understand that without a valid permit, I may not legally use the water as requested in my application.

Signature \_\_\_\_\_ Date \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

Under ORS 537.150(5) and 537.620(5), timely submission of this request authorizes that the water right application process be stopped, and fees in excess of \$465 be returned.

- This notice must be received by the Water Resources Department no later than:

**May 29, 2026**

- Return the notice to:

OWRD, Water Right Services Division  
STOP PROCESSING  
725 Summer Street, NE - Suite A  
Salem, OR 97301-1266

---