

Application No. 42343
 Permit No. 31723
 Certificate No. 39510

Stream Index, Page No. 12-22P

Name ALDO U. MARCA AND ROSE MARCA
 By Rt. 1 Box 4090
 Address Coquille, Oregon 97423

Date filed June 13, 1966

Priority June 13, 1966 for 0.58 cfs February 3, 1967 for 0.01 cfs
 Action suspended until OK 9/1
from spring

Returned to applicant _____

Date of approval March 23, 1967

CONSTRUCTION

Date for beginning March 23, 1968

Date for completion October 1, 1968

Extended to _____

Date for application of water October 1, 1969

Extended to _____

PROSECUTION OF WORK

Form "A" filed _____

Form "B" filed _____

Form "C" filed Completed

FINAL PROOF

Blank mailed OCT 29 1973

Proof received NOV 21 1973

Date certificate issued _____

FEES PAID

Date	Amount	Receipt No.
<u>6-13-66</u>	<u>17.40</u>	<u>10022</u>
<u>11-1-73</u>	<u>\$1.50</u>	<u>3726S</u>

FEES REFUNDED

Date	Amount	Check No.


ASSIGNMENTS

Date	To Whom	Address	Volume	Page

REMARKS

0.59 cfs from a spring and Fat Elk Creek (Coquille River) for domestic use of one family
irrigation and use in dairy barn and stock being 0.01 cfs for domestic, 0.01 cfs for
stock and dairy barn from spring and 0.57 cfs for irrigation of 45.4 acres from creek

T.28S., R.13W., W.M.



FINAL PROOF SURVEY
UNDER

Application No. 42343 Permit No. 31723
IN NAME OF

ALDO U. & ROSE MARCA

Surveyed 18 JULY 1972, by L.E. GOULD

STATE OF OREGON
COUNTY OF COOS
Proof of Appropriation of Water

RECEIVED

NOV 1 1973

STATE ENGINEER
SALEM, OREGON

ALDO U. & ROSE MARCA

of **Route 1, Box 4090, Coquille**
has applied beneficially the waters of
a spring and Fat Elk Creek

97423
, State of Oregon ,

a tributary of **Coquille River** for the purpose of
domestic use of one family, irrigation of 45.2 acres, use in a dairy barn, and
stock

under Permit No. **31723** of the State Engineer, and that the use of said waters has been
completed under the terms of said permit; that the priority of the
right dates from **June 13, 1966** for 0.58 cubic foot per second, February 3, 1967
for 0.01 cubic foot per second from spring for stock and use in a dairy barn

that the amount of water for the purposes aforesaid, has been actually beneficially used in the
amount of

**0.59 cubic foot per second, being 0.01 cubic foot per second for domestic, 0.01
cubic foot per second for stock and use in a dairy barn from spring, and 0.57
cubic foot per second for irrigation from Fat Elk Creek.**

or its equivalent in case of rotation, measured at the point of diversion from the stream.

The point of diversion is located in the **SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 13; SW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 14; SE $\frac{1}{4}$ NE $\frac{1}{4}$,
Section 14, T. 28 S., R. 13 W., W. M., Spring - 1690 feet South and 2010 feet West,
Fat Elk Creek - 2640 feet South and 800 feet East and 2230 feet South, all from ***

The amount of water used for irrigation, together with the amount secured under any other
right existing for the same lands, shall be limited to **one-eightieth** of one cubic foot per second
per acre, or its equivalent for each acre irrigated and shall be further limited to
a diversion of not to exceed **2 $\frac{1}{2}$ acre feet per acre** for each acre irrigated during
the irrigation season of each year,

and shall

conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the place of use under the right, and to which such right is appurtenant, is
as follows:

**16.5 acres SW $\frac{1}{4}$ NW $\frac{1}{4}$
Section 13**

**Domestic, Stock, Use in a dairy barn, and 0.1 acre SW $\frac{1}{4}$ NE $\frac{1}{4}$
28.6 acres SE $\frac{1}{4}$ NE $\frac{1}{4}$
Section 14**

T. 28 S., R. 13 W., W. M.

* NE Corner, Section 14.

I have read the above and foregoing proof of appropriation of water; I know the contents
thereof, and that the facts therein stated are true.

IN WITNESS WHEREOF, I have hereunto set my hand this 31 day of October,

1973

Aldo Marca and Rose Marca

Info: Mr. Marca

West Div. Pt.: Pumps directly from Fat Elk Creek.

Fat Elk Creek is a Ditch excavated for drainage by U.S. Soil Conservation.

Pump: 10 H.P. Louis Allis, 3 ph. 1750 R.P.M. $\Rightarrow .55 \text{ cfs @ } 45 \text{ psi}$
Belt Dr. Byron Jackson Cent. 4" x 4"

Pulleys 6' on motor, 6" on pump.

Pipe: 1280' 4" Alum.
840' 3" " "

Heads: 21 R.B. #30 - $\frac{3}{16} \times \frac{3}{32}$ All at one Time.

Lift: Suction 6'-8' Disch. 0'

East Div. PT.: Directly from Fat Elk Creek.

Pump: 10 H.P. G.E., 3 ph., 1740 R.P.M. $\Rightarrow .55 \text{ cfs @ } 45 \text{ psi}$
Dir. Dr. Berkeley Cent., 3" x 2 1/2"

Pipe: 450' 4" Alum.

160' 4" " "

1160' 3" " "

TOTAL
54 HEADS $\Rightarrow 1.02 \text{ cfs @ } 45 \text{ psi}$

Heads: 33 R.B. #30 - $\frac{3}{16} \times \frac{3}{32}$

Lift: Suction 6'-8' Disch. 0'

Spring: Has a pool approx. 8' x 8' x 2' at head of small draw

Dom. use
of 1 family.
Stock 65 head cows
Use in Milk House.

Pipe: 460' ^{1"} Plastic (Spr. to Res.)

Res: Concrete 9' x 7' x ^{52"} Deep. Inside.

Pump: 1/2 H.P. Century, 1 ph., 3500 R.P.M.
Dir. Dr. Myers Cent. 1 1/4" x 3/4"

Pipe: 150' 3/4" To H. & Barn. (Stock drink from trough in barn.)

July 18, 1972 R. E. Gould

Field Engineer

40 gal. pressure tank
on - 40 p.s.i. off 75 p.s.i.

01728

42343

Application No.
Permit No.

ATTACHMENT :

Area -- Application for water use permit.

Items 4, 5, 6(4) and 7(c) described as follows:

DIVERSION No. 1, Domestic Water-- The point of diversion is located 1,000 ft. North and 2,058 ft. West from the SE corner of the SE $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28S, Rge. 13 WWM being within the SW $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28S, Rge. 13 WWM. The water will flow by gravity from the source through 440 ft. of 1" plastic pipe to the storage tank. A $\frac{1}{2}$ HP electric motor driven pump will deliver water to the house, about 10 ft. lift, through 230 ft. of $\frac{3}{4}$ " pipe and to the barn, no lift, through 200 ft. of $\frac{3}{4}$ " pipe. The entire system is within the SW $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28 S., Rge. 13 WWM.

DIVERSION NO. 2, Irrigation -- The point of diversion is located 450 ft. north from the SE corner of the SE $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28S, Rge. 13 WWM, being approximately on the east line of the SE $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28S, Rge. 13 WWM. A 10 HP electric motor driven centrifugal pump will lift water approximately 8 ft. and deliver from the source westerly through 1260 ft. of $\frac{1}{2}$ " mainline pipe terminating in the SE $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28S, Rge. 13 WWM.

DIVERSION NO 3, Irrigation-- The point of diversion is located 760 ft. east from the SE corner of the SE $\frac{1}{4}$ of the NE $\frac{1}{4}$ of Sec. 14, Twp. 28 S, Rge. 13 WWM, being approximately on the south line of the SW $\frac{1}{4}$ of the NW $\frac{1}{4}$ of Sec. 13, Twp 28 S, Rge 13, WWM. A 10 HP electric motor driven centrifugal pump will lift water approximately 8 ft. and deliver from the source easterly through 450 ft. of $\frac{1}{2}$ " mainline pipe terminating in the SW $\frac{1}{4}$ of the NW $\frac{1}{4}$ of Sec. 13, Twp 28 S., Rge. 13 WWM.

OR-6
App. 2/23/55

UNITED STATES DEPARTMENT OF AGRICULTURE
Soil Conservation Service
Oregon


Water Use and Diversion
LOCATION OF A.C.P. PRACTICES
Program Year 1966

Operator Aldo U. Marca

APPROX. Scale: 660 ft = 1 in.
A.C.P. Farm No. _____

County COOS

Section 14 & 13 Township 28 So. Range 13 W., W.M. Aerial Photo No. COB-2N-104



Tracing:
by Carl Holland, Jr.

Application No. 42343
Permit No. 31723

RECEIVED
JUN 13 1966
STATE ENGINEER
SALEM OREGON

RECEIVED
JUN 13 1966
STATE ENGINEER
SALEM OREGON

October 29, 1973

Aldu U. and Rose Marca
Route 1, Box 4090
Coquille, OR 97423


Dear Mr. and Mrs. Marca;

Enclosed is the final proof in connection with the incomplete water right represented by your permit number 31723.

The data contained in the proof, which is based on an inspection and survey of your project made by a representative of this department, defines the extent to which your water right has been completed within the terms of your permit. The proof should be dated and signed by you and returned to this office.

Upon receipt of the proof, properly executed and accompanied by the statutory recording fee of \$1.50, a certificate of water right will be issued confirming the right thereunder and, after being recorded in the county records, will be forwarded to you.

Very truly yours,



CHRIS L. WHEELER
State Engineer

Form 117

tml

Enclosure

The enclosed map may be retained for your own records.

42343

April 3, 1967

Aldo U. & Rose Marca
Route 1, Box 4090
Coquille, Oregon

Dear Sir and Madam:

42343, permit No. 31723 with a blueprint.

February 6, 1967

Aldo U. Marca and Rose Marca
Rt. 1 Box 4090
Coquille, Oregon

Dear Sir and Madame:

This will acknowledge receipt of the returned application No. 42343, including the stock use for dairy with the addition of 0.02 cubic feet of water per second for this use.

The additional use has received the new date of priority of February 3, 1967, and this application is now in satisfactory form for approval by issuance of a permit.

Very truly yours,

CHRIS L. WHEELER
State Engineer

By
Larry W. Jebousek
Assistant

LWJ:dly

January 31, 1967

Aldo U. Marca and Rose Marca
Rt. 1 Box 4090
Coquille, Oregon

Dear Sir and Madame:

I am sorry for the long delay in processing your application for issuance of a permit.

However, before the permit can be issued, the application must be signed by both of the applicants on the space provided immediately following item No. 14.

The application map indicates the water from the spring is also to be piped to the barn.

Domestic use is generally accepted to mean household use and for such animals as are essential to the proper sustenance of the family. It would then probably include a milk cow, a few chickens, etc., but not a dairy or beef herd.

I am returning your application and the map for correction and completion. The application is endorsed so that in order to retain its date of priority, it must be returned on or before March 31, 1967.

Very truly yours,

CHRIS L. WHEELER
State Engineer

By
Larry W. Jebousek
Assistant

LWJ:dly
Enclosures

October 31, 1966

Everett Isenhart
Langlois Oregon

Dear Mr. Isenhart:

Our records show an application No. 42343 in the name of Aldo U. and Rose Marca of Coquille, Oregon, for the appropriation of 0.01 cubic foot of water per second from a spring in the SW $\frac{1}{4}$ NE $\frac{1}{4}$ of Section 14, for domestic use and the appropriation of 0.5675 cubic foot of water per second from Fat Elk Creek in the SW $\frac{1}{4}$ NW $\frac{1}{4}$ of Section 13 for the irrigation of 45.4 acres. This application was filed June 13, 1966, and no permit has yet been issued.

Very truly yours,

CHRIS L. WHEELER
State Engineer

By
Larry W. Jebousek
Assistant

LMJ:hls

Langlois, Ore.
Oct. 28, 1966.

State Engineer,
Salem, Oregon.

RECEIVED
OCT 31 1966
STATE ENGINEER
SALEM OREGON

Dear Sir:

Will you please let me know if any water permits have been issued or applications for water permits have been made for either irrigation, domestic or stock use together, if any, the names of those holding said permits or making applications for permits on the following described property:

The NE $\frac{1}{4}$ of Sec. 14, Twp. 28 South, Range 13 West of the Willamette Meridian in Coos County, Oregon.

Yours Truly,
Everett Isenhardt

42343

June 17, 1966

Aldo U. & Rose Marca
Route 1, Box 4090
Coquille, Oregon

Dear Sir and Madam:

This will acknowledge your application to appropriate 0.5775 cubic feet of water per second from a spring and Fat Elk Creek for the irrigation of 45.4 acres, a map, legal description, and the fees of \$27.40 for which our receipt No. 10022 is enclosed.

This application has been filed and numbered 42343 and is in satisfactory form for approval by issuance of a permit.

Very truly yours,

CHRIS L. WHILLER
State Engineer

By
Larry W. Jebousek
Assistant

LMJ:hls
Enclosure



STATE OF OREGON
STATE ENGINEER
WATER RESOURCES DEPARTMENT
516 PUBLIC SERVICE BUILDING
SALEM 97310

REFER TO
FILE NO. 42343

January 31, 1967

RECEIVED
FEB 3 1967
STATE ENGINEER
SALEM, OREGON

Aldo U. Marca and Rose Marca
Rt. 1 Box 4090
Coquille, Oregon

Dear Sir and Madame:

I am sorry for the long delay in processing your application for issuance of a permit.

However, before the permit can be issued, the application must be signed by both of the applicants on the space provided immediately following item No. 14. — / —

The application map indicates the water from the spring is also to be piped to the barn.


*Application
Corrected to
show Dairy
use —*

Domestic use is generally accepted to mean household use and for such animals as are essential to the proper sustenance of the family. It would then probably include a milk cow, a few chickens, etc., but not a dairy or beef herd.

I am returning your application and the map for correction and completion. The application is endorsed so that in order to retain its date of priority, it must be returned on or before March 31, 1967.

Very truly yours,

CHRIS L. WHEELER
State Engineer

By 
Larry W. Jebousek
Assistant

LWJ:dly
Enclosures

OR-8
App. 2/23/55

UNITED STATES DEPARTMENT OF AGRICULTURE
Soil Conservation Service
Oregon


Water Use and Diversion
LOCATION OF A.C.P. PRACTICES
Program Year 1966

Operator Aldo U. Marca

APPROX. Scale: 660 ft = 1 in.
A.C.P. Farm No. _____

County COOS

Section 14 & 13 Township 28 So. Range 13 W., W.M. Aerial Photo No. COB-2N-104



Tracing:
by Carl Holland, Jr.

RECEIVED
FEB 3 1967
STATE ENGINEER
SALEM OREGON

RECEIVED
JUN 13 1966
STATE ENGINEER
SALEM OREGON

Application No.
Permit No.

42343
31723

14 13

23 24

M-1140