

**CLAIM OF
BENEFICIAL USE
for Transfer New or Additional
POA Only**



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem, Oregon 97301-1266
(503) 986-0900
www.oregon.gov/OWRD

A fee of \$345 must accompany this form for transfers where the application was submitted on July 9, 1987, or later.

Enter the date the transfer application was submitted:

May 22, 2023

A separate form shall be completed for each transfer.

This form is subject to revision. **Begin each new claim** by checking for a new version of this form at:

<https://www.oregon.gov/OWRD/Forms/Pages/default.aspx>

The completion of this form is required by OAR 690-014-0100(1) and 690-014-0110(4).

Please type or print in dark ink. If this form is found to contain errors or omissions, it may be returned to you. **Every item must have a response.** If any requested information does not apply to the claim, insert "NA." **Do not delete or alter any section of this form unless directed by the form.** The Department may require the submittal of additional information from any water user or authorized agent.

"Section 8" of this form is intended to aid in the completion of this form and should not be submitted.

A claim of beneficial use includes both this report and a map. If the map is being mailed separately from this form, please include a note with this form indicating such.

If you have questions regarding the completion of this form, please call 503-986-0900.

The Department has a Reimbursement Authority program that allows it to enter into a voluntary agreement with an applicant for expedited services. Under such an agreement, the applicant pays the cost to hire additional staff that would not otherwise be available. This program means a certificate may be issued in about a month. For more information on this program see:

<https://www.oregon.gov/OWRD/programs/WaterRights/RA/Pages/default.aspx>

**SECTION 1
GENERAL INFORMATION**

Type of Authorized Change

This Claim is being submitted for a transfer where the only authorized change was a change in point(s) of appropriation or additional point(s) of appropriation, or a combination of both.

If additional changes were authorized, you will need to select a different form.

Received by OWRD

AUG 12 2026

Salem, OR

YES

1. File Information

APPLICATION #

T-14251

Revised 7/1/2025

Transfer POA Only - Page 1 of 14

WR

2. Property Owner (current owner information)

APPLICANT/BUSINESS NAME Raymond and Marguerite Gannon		PHONE NO.	ADDITIONAL CONTACT NO.
ADDRESS 27011 SW Petes Mountain Rd			
CITY West Linn	STATE OR	ZIP 97068	E-MAIL

If the current property owner is not the transfer holder of record, it is recommended that an assignment be filed with the Department. ***Each transfer holder of record must sign this form.***

3. Transfer holder of record (this may, or may not, be the current property owner)

TRANSFER HOLDER OF RECORD Willamette Tree Wholesale Inc. c/o Ray Gannon			
ADDRESS New address: PO Box 9466 Please update			
CITY Salem	STATE OR	ZIP 97305	

4. Date of Site Inspection:

June 3, 2026 July 1, 2026
--

5. Person(s) interviewed and description of their association with the project:

NAME	DATE	ASSOCIATION WITH THE PROJECT
Ramiro Acevedo	June 3, 2026 July 1, 2026	Plant manager

6. County

Marion county

7. If any property described in the place of use of the transfer final order is excluded from this report, identify the owner of record for that property (ORS 537.230(5)):

OWNER OF RECORD NA		
ADDRESS		
CITY	STATE	ZIP

Add additional tables for owners of record as needed

Received by OWRD
AUG 12 2026
Salem, OR

SECTION 2
SIGNATURES

CWRE Statement, Seal and Signature

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge.

Seal and Signature




CWRE NAME Doann Hamilton		PHONE NO. (503) 349-6946 cell	ADDITIONAL CONTACT NO. 503-931-0210
ADDRESS 15333 Pletzer Rd. SE			
CITY Turner	STATE OR	ZIP 97392	E-MAIL doann@mcgillwaterrights.com

Received by OWRD
AUG 12 2026
Salem, OR

Transfer Holder of Record Signature or Acknowledgement

Each transfer holder of record must sign this form in the space provided below.

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge. I request that the Department issue a water right certificate.

SIGNATURE	PRINT OR TYPE NAME	TITLE	DATE
	Ray Gannon	President	7/29/26

SECTION 3 CLAIM DESCRIPTION

Note: The Claim only needs to describe the new or additional point(s) of appropriation. This Claim does not need to provide information for the original point(s) of appropriation unless the original point of appropriation is either a new or additional point of appropriation on another right involved in this transfer.

1. New or additional point of appropriation name or number:

POINT OF APPROPRIATION (POA) NAME OR NUMBER (CORRESPOND TO MAP)	WELL LOG ID # FOR ALL WORK PERFORMED ON THE WELL (IF APPLICABLE)	WELL TAG # (IF APPLICABLE)	SOURCE (IF LISTED IN TRANSFER FINAL ORDER)
Well 3	MARI 70766	L-144161	A well, tributary of Willamette River
Well 4	MARI 4888, MARI 72001	L-156262	A well, tributary of Willamette River

Attach each well log available for the well (include the log for the original well and any subsequent alterations, reconstructions, or deepenings)

If well logs are available, items A and B below can be deleted

Received by OWRD
AUG 12 2026
Salem, OR

SECTION 2
SIGNATURES

CWRE Statement, Seal and Signature

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge.

Seal and Signature 
--

CWRE NAME Doann Hamilton		PHONE NO. (503) 349-6946 cell	ADDITIONAL CONTACT NO. 503-931-0210
ADDRESS 15333 Pletzer Rd. SE			
CITY Turner	STATE OR	ZIP 97392	E-MAIL doann@mcgillwaterrights.com

Received by OWRD
AUG 12 2026
Salem, OR

2. Variations:

Was the use developed differently from what was authorized by the transfer final order, or extension final?

YES

If yes, describe below.

(e.g. "The order allowed three new/additional points of appropriation. The water user only developed one of the points.")

1. The authorized Well 2 (MARI 4897) was not performing well and has not been used; therefore, Well 2 is not included in this Claim of Beneficial Use.
2. Well 3 (MARI 70766) latitude and longitude is more accurately describe from what is on WRIS as:
45.053544, -122.991992, WGS 84

3. Claim Summary:

CERTIFICATE	NEW OR ADDITIONAL POA NAME OR #	MAXIMUM RATE AUTHORIZED	CALCULATED THEORETICAL RATE BASED ON SYSTEM	AMOUNT OF WATER MEASURED
40295	Well 3	0.38 cfs	2.19 cfs	2.18 cfs
50713		0.85 cfs		
40295	Well 4	0.38 cfs	1.04 cfs	Not measured
50713		0.85 cfs		

SECTION 4a of 4b

SYSTEM DESCRIPTION

Are there multiple new or additional Points of Appropriation (POA)?

YES

If "YES" you will need to copy and complete a separate Section 4.

POA Name or Number this section describes (only needed if there is more than one):

Well 3

Received by OWRD
AUG 12 2026

Salem, OR

A. POA System Information

Provide the following information concerning the point of appropriation. Information provided must describe the equipment used to appropriate water from the point of appropriation.

1. Pump Information:

MANUFACTURER	MODEL	SERIAL NUMBER	TYPE (CENTRIFUGAL, TURBINE OR SUBMERSIBLE)	INTAKE SIZE	DISCHARGE SIZE
Gould	9RC-2 stage	MG4369	Submersible	8 inch	8 inch

2. Motor Information:

MANUFACTURER	HORSEPOWER
Franklin Electric	100 Hp

3. Theoretical Pump Capacity – Pump at Well:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE DEPTH TO WATER FROM THE GROUND SURFACE MEASURED AT THE WELL DURING PUMPING)	LIFT TO PLACE OF USE (THE LIFT FROM THE GROUND SURFACE AT THE WELL TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
100 Hp	80 psi	118 feet (from pump test recorded on well log)	0 feet	2.19 cfs

Reminder: For pump calculations use the reference information at the end of this document.

4. Provide pump calculations:

$$Q \text{ Pump} = \frac{(100 \text{ Hp}) \times (7.04 \text{ ft}^4/\text{sec Hp})}{(118 \text{ ft lift} + 203.2 \text{ ft pressure head})} = 2.19 \text{ cfs}$$

5. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
350,963,100 gallons	350,968,000 gallons	5 minutes	2.18 cfs
Instantaneous meter reading 1,164 gpm (July 1, 2026)			

6. Theoretical Pump Capacity – Pump at Sump:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE LIFT FROM THE WATER SURFACE TO THE PUMP)	LIFT TO PLACE OF USE (THE LIFT FROM THE PUMP TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
NA				

Reminder: For pump calculations use the reference information at the end of this document.

7. Provide pump calculations:

NA

8. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
NA			

9. Additional notes or comments related to the system:

Access port is: ½ inch galvanized vent pipe on the west side of the sanitary seal of the well.

B. Groundwater Source Information (Well and Sump)

1. Is the appropriation from a dug well (sump)?

Received by OWRD

AUG 12 2026

Salem, OR

If "NO", items 4 through 6 relating to this section may be deleted.

Reminder: Construction standards for sumps can be found in OAR 690-210-0400.

2. If the appropriation involves a **SUMP**, provide the following information for each **SUMP**:

LENGTH	WIDTH	AVERAGE DIAMETER	MAXIMUM DEPTH	SURFACE AREA (IN ACRES)	VOLUME IN CUBIC FEET OR ACRE FEET
NA					

3. If the sump is curbed constructed with watertight surface curbing, describe the curbing:

CURBING MATERIAL (CONCRETE, CONCRETE TILES, OR STEEL)	IF CONCRETE, PROVIDE THE THICKNESS OF THE WALL
NA	

C. Additional notes or comments related to the system:

Well 3 will also supply pending:
T-14252 GR modification of GR-3046
Application G-19371

SECTION 4b of 4b

SYSTEM DESCRIPTION

Are there multiple new or additional Points of Appropriation (POA)?

YES

If "YES" you will need to copy and complete a separate Section 4.

POA Name or Number this section describes (only needed if there is more than one):

Well 4

A. POA System Information

Provide the following information concerning the point of appropriation. Information provided must describe the equipment used to appropriate water from the point of appropriation.

1. Pump Information:

MANUFACTURER	MODEL	SERIAL NUMBER	TYPE (CENTRIFUGAL, TURBINE OR SUBMERSIBLE)	INTAKE SIZE	DISCHARGE SIZE
Franklin Electric	6T030325	2M12	Submersible	5 inch	

2. Motor Information:

MANUFACTURER	HORSEPOWER
Franklin Electric	30 Hp

Received by OWRD

AUG 12 2026

Salem, OR

3. Theoretical Pump Capacity – Pump at Well:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE DEPTH TO WATER FROM THE GROUND SURFACE MEASURED AT THE WELL DURING PUMPING)	LIFT TO PLACE OF USE (THE LIFT FROM THE GROUND SURFACE AT THE WELL TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
30 Hp	60	51 feet (from pump test recorded on well log)	0 feet	1.04 cfs

Reminder: For pump calculations use the reference information at the end of this document.

4. Provide pump calculations:

$$Q \text{ Pump} = \frac{(30 \text{ Hp}) \times (7.04 \text{ ft}^4/\text{sec Hp})}{(51 \text{ ft lift} + 152.4 \text{ ft pressure head})} = 1.04 \text{ cfs}$$

5. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
Not running during site visit			

6. Theoretical Pump Capacity – Pump at Sump:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE LIFT FROM THE WATER SURFACE TO THE PUMP)	LIFT TO PLACE OF USE (THE LIFT FROM THE PUMP TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
NA				

Reminder: For pump calculations use the reference information at the end of this document.

7. Provide pump calculations:

NA

8. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
NA			

9. Additional notes or comments related to the system:

Access port is: 1/2 inch plastic plug on the northeast side of the sanitary seal of the well.

B. Groundwater Source Information (Well and Sump)

1. Is the appropriation from a dug well (sump)?

NO

If "NO", items 4 through 6 relating to this section may be deleted.

Reminder: Construction standards for sumps can be found in OAR 690-210-0400.

2. If the appropriation involves a **SUMP**, provide the following information for each **SUMP**:

LENGTH	WIDTH	AVERAGE DIAMETER	MAXIMUM DEPTH	SURFACE AREA (IN ACRES)	VOLUME IN CUBIC FEET OR ACRE FEET
NA					

3. If the sump is curbed constructed with watertight surface curbing, describe the curbing:

CURBING MATERIAL (CONCRETE, CONCRETE TILES, OR STEEL)	IF CONCRETE, PROVIDE THE THICKNESS OF THE WALL
NA	

C. Additional notes or comments related to the system:

Well 4 will also supply pending:
T-14252 GR modification of GR-3046
Application G-19371

Received by OWRD
AUG 12 2026
Salem, OR

SECTION 5 CONDITIONS

All conditions contained in the transfer final order, or any extension final order shall be addressed. Reports that do not address all performance related conditions will be returned.

1. Time Limits:

Describe how the water user has complied with each of the development timelines established in the transfer final order and any extensions of time issued for the transfer:

	DATE FROM TRANSFER	DATE THE NEW AND/OR ADDITIONAL POA(S) WERE READY FOR USE *THIS DATE MUST FALL BETWEEN THE "ISSUANCE DATE" AND THE "COMPLETENESS DATE"
ISSUANCE DATE	May 7, 2025	
COMPLETENESS DATE FROM ORDER (C)	October 1, 2026	June 2026

* MUST BE WITHIN PERIOD BETWEEN TRANSFER FINAL ORDER, OR ANY EXTENSION FINAL ORDER ISSUANCE AND THE DATE TO COMPLETE THE CHANGE

2. Is there an extension final order(s)?

NO

If "NO", you may delete the following table.

3. Measurement Conditions:

a. Does the transfer final order, or any extension final order require the installation of a meter or other approved measuring device?

YES

If "NO", items b through f relating to this section may be deleted.

Reminder: If a meter or approved measuring device was required, the COBU map must indicate the location of the device in relation to the point of appropriation.

b. Has a meter been installed?

YES

c. Meter Information

POA NAME OR #	MANUFACTURER	SERIAL #	CONDITION (WORKING OR NOT)	CURRENT METER READING	DATE INSTALLED
Well 3	McCrometer	23-05228-08	Working	326,833,100 gallons (June 3, 2026)	March 2023
Well 4	Seametrics	Possible 05260459 or 06260207	Working	1,678,351 gallons (July 1, 2026)	June 26, 2026

If a meter has been installed, items d through f relating to this section may be deleted.

4. Recording and reporting conditions

a. Is the water user required to report the water use to the Department? **NO**

If "NO", item b relating to this section may be deleted.

5. Other conditions required by the transfer final order or extension final order:

a. Were there special well construction standards? **NO**

b. Was submittal of a ground water monitoring plan required? **NO**

c. Other conditions? **YES**

If "YES" to any of the above, identify the condition and describe the water user's actions to comply with the condition(s):

c1) Condition:

Water shall be acquired from the same aquifer (water source) as the original point of appropriation.

Compliance:

Certificate 40295

Authorized Well (MARI 4898) develops water within the alluvial aquifer through perforations in the casing within the depth intervals of 85 to 139 feet within layers of sand and gravel with some clay.

Certificate 50713

Authorized Well 1 (MARI 4880) develops water within the alluvial aquifer through perforations in the casing within the depth intervals of 95 to 140 feet with in gravel.

Authorized Well 2 (MARI 4897) develops water within the alluvial aquifer through perforations in the casing within the depth intervals of 90 to 135 feet within layers of sand and gravel with some clay.

Proposed Well 3 (MARI 70766) develops water within the alluvial aquifer through perforations in the casing within the depth intervals of 202.25 to 254 feet within layers of sand and gravel with some clay.

Proposed Well 4 (MARI 4888, 72001) develops water within the alluvial aquifer through

Received by OWRD
AUG 12 2026
Salem, OR

perforations in the casing within the depth intervals of 110 to 160 feet within clay with layers of sand and gravel. And note: the repairs on MARI 72001 only changed the well seal and raise the casing above ground.

It appears this well obtains water from the alluvial aquifer; therefore, this condition has been met.

SECTION 6 ATTACHMENTS

Received by OWRD
AUG 12 2026

Salem, OR

Provide a list of any additional documents you are attaching to this report:

ATTACHMENT NAME	DESCRIPTION
Claim of Beneficial Use Map	Claim of Beneficial Use Map, modified Certificate 40295
Claim of Beneficial Use Map	Claim of Beneficial Use Map, modified Certificate 50713
State Water Well Report – MARI 70766	Well log and driller's notes for MARI 70766 – Well 3
State Water Well Report – MARI 4888	Well log and driller's notes for MARI 4888 – Well 4
State Water Well Report – MARI 72001	Well log and driller's notes for MARI 72001 – Well 4 repairs
BLM Cadastral Map	BLM Cadastral Map T. 6S. R. 3W. showing DLC and Government Lot locations

SECTION 7 CLAIM OF BENEFICIAL USE MAP

For the purpose of this Claim, the map identifying the location of the place of use does not require a new survey. The location of the place of use identified on the Claim map should be based on the original right of record at the time the transfer final order was issued. In transfers approved for additional points of appropriation, the original points must be identified the map based on the original right of record at the time the transfer final order was issued.

In order to properly examine your claim, the Department must have an accurate map that meets the criteria described in OAR 690-014-0170 and OAR 690-305-0010, which are provided below for your convenience:

OAR 690-014-0170 Minimum Requirements for Maps for Permit or Transfer Final Order Claims of Beneficial Use

- (1) Maps submitted by a CWRE as part of the Claim of Beneficial Use shall meet the standards in OAR chapter 690, division 305. In addition, the map shall meet the following criteria:
 - (a) Horizontal accuracy is required only to ten feet for the purpose of locating and quantifying water rights. Maps shall be developed from any standard survey method. Traverse closures are not required.
 - (b) Maps shall clearly designate the place of use and point of diversion or appropriation for each source and use.

- (c) The map shall indicate by description, in relation to the point of diversion or appropriation, the location of any fish screens, by-pass devices, and measuring devices required by the permit or transfer final order.
- (d) The following statement shall be placed on the map: "This map is not intended to provide legal dimensions or locations of property ownership lines."
- (2) A CWRE may make a written request to the Director for a waiver of one or more mapping standards. The Director will determine whether the waiver shall be allowed and will respond to such requests in writing.

OAR 690-305-0010 General Map Criteria

Each map submitted to the Department shall meet the following general criteria in addition to any specific criteria identified in the rules for the relevant water right transaction:


- (1) Drawing
 - (a) The map shall be drafted on paper or polyester film with ink or otherwise printed in an indelible form with sufficient clarity so as to be easily reproduced or scanned. Maps may be submitted electronically in portable document format (pdf) and must be prepared consistent with, and include the same information as, a paper map.
 - (b) The preferred paper size is 8.5 inches by 11 inches and should be no larger than 30 inches by 30 inches. A map greater than 30 inches by 30 inches may be submitted if the Department grants, by mail or electronic means, advance approval of the larger size.
 - (c) Beginning April 1, 2029, regardless of whether the map is submitted electronically, on paper, or on polyester film, for any map that OAR chapter 690 requires be prepared by a Certified Water Right Examiner, a digital file containing the coordinate system and geospatial features of the map as specified by the Department shall be submitted in addition to the map, unless the Department provides a waiver. The digital file shall be submitted as a shapefile or other approved format in a manner required by the Department.
 - (d) A platted and recorded subdivision map, deed description survey map, or county assessor map may be submitted as the application map if all of the required information included in sections (2) and (3) of this rule is clearly shown.
 - (e) An aerial image may be provided in addition to the map to aid the Department in understanding the proposal.
 - (f) The map submitted under subsection (a) shall be the official record of the water right. An aerial image or digital file shall not be the official record of the water right.
- (2) Scale
 - (a) The map shall be drawn to a standard, even-numbered scale and one-inch shall not exceed 1320 feet.
 - (b) The map scale may exceed 1320 feet per inch if the Department grants, by mail or electronic means, advance approval of the requested scale.

- (c) Notwithstanding subsection (a) and (b), for maps identifying the location of a municipal use place of use, one-inch can exceed 1320 feet; provided that the scale is sufficient to identify the quarter-quarters involved in the place of use.
- (3) Features: Features shall be clearly identified and labeled. Unless otherwise indicated in rule, the following features must be included in each map submitted to the Department:
 - (a) Mapping scale.
 - (b) North directional symbol.
 - (c) Legend.
 - (d) General location of main canals, ditches, flumes, pipelines, pumps, or other water delivery features used to transport water from the point(s) of diversion or appropriation to the place use and to include the delivery features at the place of use.
 - (e) Other topographical features such as rivers, creeks, streams, lakes, reservoirs, ponds, roads, or railroads that may be helpful to clarify and identify the location of points of diversion, wells, dams, and places of use.
 - (f) Location and flow direction of the water way if the source is surface water. If multiple water ways exist in the area of the proposed diversion and use, the map must identify the location and flow direction of the additional water ways.
 - (g) Township, range, section, quarter-quarter, and tax lot(s), donation land claims, or government lots where water will be or has been diverted, conveyed, and used. If the map is for municipal use the map:
 - (A) Must identify but does not need to label the quarter-quarters,
 - (B) Does not need to identify or label tax lots, donation land claims, or government lots.
 - (h) Location of each proposed or developed diversion point, well (point of appropriation), or dam by reference to a recognized public land survey corner. For a reservoir without a dam, the center of the reservoir shall be referenced to a recognized public land survey corner.
 - (A) The locations shall be shown by distance and bearing, or by coordinates (distance north or south and distance east or west from the corner). In addition, they shall also include latitude and longitude as established by a global positioning system.
 - (B) Latitude and longitude coordinates shall be expressed as degrees-decimal with five or more digits after the decimal (e.g., 42.53764^o). The datum used to establish the coordinates shall be indicated on the map. Examples of datums include NAD 83, NAD 27 and WGS84.
 - (i) Location of the proposed or developed place of use by township, range, section, and nearest quarter-quarter section.
 - (A) For irrigation or nursery use, the map shall additionally indicate the place of use in each quarter-quarter of a section by shading or hatchuring and indicate the number of acres in each quarter-quarter section, donation land claim, government lot, or other recognized public land survey lines.
 - (B) For places of use that are limited to a point, such as a stock watering tank, the location may also be identified by distance and bearing, or by

coordinates (distance north or south and distance east or west from the corner). In addition, they shall include latitude and longitude as established by a global positioning system.

- (C) Latitude and longitude coordinates shall be expressed as degrees-decimal with five or more digits after the decimal (e.g., 42.53764^o). The datum used to establish the coordinates shall be indicated on the map. Examples of datums include NAD 83, NAD 27 and WGS84.
- (D) Where more than one point of diversion or well is included, the map must clearly identify the place(s) of use served by each point of diversion or well.
- (j) If for a supplemental irrigation application or claim of beneficial use, the location and water right reference number of the underlying primary right, registration or claim.
- (k) Any other information the Department requests and considers necessary to evaluate the water right transaction.

Received by OWRD
AUG 12 2026
Salem, OR



Received by OWRD
AUG 12 2026
Salem, OR

Amended 4/10/2023

Page 1 of 4

**STATE OF OREGON
WATER SUPPLY WELL REPORT**

MARI 70766

WELL I.D. LABEL# L 144161

START CARD # 1058770

ORIGINAL LOG #

2/21/2023

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

(1) LAND OWNER

Owner Well I.D.

First Name RAY AND MARQUERITE Last Name GANNON

Company

Address 27011 SW PETES MOUNTAIN RD.City WEST LINN State OR Zip 97068**(2) TYPE OF WORK**
☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)
(2a) PRE-ALTERATION
 Dia + From To Gauge Stil Plstc Wld Thrd
 Casing: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

Seal:

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other
(4) PROPOSED USE
☐ Domestic ☒ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☒ Other CERT 50713
(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 257.00 ft.**BORE HOLE**

Dia	From	To	Material	From	To	Amt	sacks/ lbs
20	0	36	Bentonite Chips	0	36	44	S
16	36	257				Calculated	44
						Calculated	

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other OAR 690-210-0340

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from 176 ft. to 257 ft. Material GRAVEL Size 3/8 8Explosives used: ☐ Yes Type _____ Amount _____**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount

Actual Amount

(6) CASING/LINER

Casing	Liner	Dia	+	From	To	Gauge	Stil	Plstc	Wld	Thrd
☒	☒	16	☒	2	200	.375	☒	☒	☒	☒
☐	☐	12	☐	176	257	.250	☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐
☐	☐		☐				☐	☐	☐	☐

Shoe ☐ Inside ☒ Outside ☐ Other Location of shoe(s) 200Temp casing ☐ Yes Dia _____ From + _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method

Screens Type v wireMaterial stainless steel

Perf/ Screen	Casing/ Screen	Dia	From	To	Scr/slot width	Slot length	# of slots	Tele/ pipe size
Screen	Casing	12	202.25	254	.22			

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
1125	69	157	4

Temperature 54 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 73 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County MARION Twp 6.00 S N/S Range 3.00 W E/W WMSec 13 NE 1/4 of the NE 1/4 Tax Lot 400

Tax Map Number _____ Lot _____

Lat _____ " or 45.05352274 DMS or DDLong _____ " or -122.99201897 DMS or DD☒ Street address of well ☐ Nearest address3301 BROOKLAKE RD. NE, SALEM, OR, 97303**(10) STATIC WATER LEVEL**

	Date	SWL(psi)	+ SWL(ft)
Existing Well / Pre-Alteration			
Completed Well	<u>1/19/2023</u>		<u>49</u>

Flowing Artesian? ☐ Dry Hole? ☐**WATER BEARING ZONES**Depth water was first found 63.00

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
10/7/2022	63	65			45
10/10/2022	81	87			45
10/13/2022	98	135			46
10/18/2022	140	141			51
10/19/2022	165	177			52

(11) WELL LOG

Ground Elevation _____

Material	From	To
Gravel	0	0.5
Clay, brown, hard	0.5	12
Clay, brown, medium	12	28
Clay, brown, sandy, hard	28	30
Clay, brown, medium, sticky	30	43
Clay, dark gray, soft, sticky	43	53
Silt, dark greenish gray, sandy, hard	53	62
Gravel and sand, siltbound	62	63
Gravel and sand, black, loose	63	65
Clay, dark gray, soft	65	74
Silt, dark gray, sandy, hard	74	81
Gravel and sand, black	81	87
Clay, dark gray, medium, sticky	87	90
Silt, dark gray, medium	90	98
Gravel, cobbles, brown sand	98	135
Clay, greenish gray, soft, some gravel	135	140
Black sand and gravel	140	141
Clay, greenish gray, hard, sticky	141	154
Silt, gray, medium	154	161

Date Started 10/3/2022Completed 1/21/2023**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1704Date 1/22/2023Signed LARRY AMOS (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 783Date 2/21/2023Signed IVAN GROSSEN (E-filed)

Contact Info (optional) _____

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:
New exempt use wells must be submitted with a map and recording fee.

no well drilling took place after static was taken

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 70766

Received by OWRD

2/21/2023

AUG 12 2026

Map of Hole

Salem, OR

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.05352274 Datum: WGS84

Longitude: -122.99201897

Township/Range/Section/Quarter-Quarter Section:
WM6.00S3.00W13NENE

Address of Well:

3301 BROOKLAKE RD. NE, SALEM, OR, 97303

Well Label: 144161

Printed: February 9, 2023

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor



WATER SUPPLY WELL REPORT - continuation page

MARI 70766

2/21/2023

Received by OWRD

AUG 12 2026

Salem, OR

Map of Hole

STATE OF OREGON
WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900

LOCATION OF WELL

Latitude: 45.05352274 Datum: WGS84

Longitude: -122.99201897

Township/Range/Section/Quarter-Quarter Section:

WM6.00S3.00W13NENE

Address of Well:

3301 BROOKLAKE RD. NE, SALEM, OR, 97303

Well Label: 144161

Printed: February 9, 2023

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor



SP-43656-118

Overdrilled existing 10" casing to 21". Pressure grouted 17 bags of cement from 0 - 21". Raised existing 10" from ground level up to 16" above ground level and installed well tag. This work was performed to satisfy requirement pertaining to water right application G-19371. No other alterations or work was performed other than reseat & casing extension

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

Well A
MARI 72001

1/28/2026

Received by OWRD

AUG 12 2026

Salem, OR

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301

(503)986-0900



LOCATION OF WELL

Latitude: 45.05278000 Datum: WGS84

Longitude: -122.99789000

Township/Range/Section/Quarter-Quarter Section:

WM6.00S3.00W13SWNE

Address of Well:

3491 BROOKLAKE RD, SALEM, OR 97305

Well Label: 156262

Printed: January 28, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor



OREGON



Received by OWRD

AUG 12 2026

Salem, OR

Date Received (Date Stamp Here)

OWRD Over-the-Counter Submission Receipt

Applicant Name(s) & Address: Raymond & Marguerite Gannon
27011 SW Petes Mtn. Rd West Linn, OR 9706

Transaction Type: COBU

Fees Received: \$ 345.00

☐ Cash

☒ Check:

Check No. 2689

Name(s) on Check: Will McGill Surveying LLC

Thank you for your submission. Oregon Water Resources Department (Department) staff will review your submittal as soon as possible.

If your submission is determined to be complete, you will receive a receipt for the fees paid and an acknowledgement letter stating your submittal is complete.

If determined to be incomplete, your submission and the accompanying fees will be returned with an explanation of deficiencies that must be addressed in order for the submittal to be accepted.

If you have any questions, please feel free to contact the Department's Customer Service staff at 503-986-0801 or 503-986-0810.

Sincerely,

OWRD Customer Service Staff

Submission received by: Sarah Benham

(Name of OWRD staff)

Instructions for OWRD staff:

- Complete this Submission Receipt and make two (2) copies. Place one copy with the check/cash; and place the other copy with the submission (i.e., the application or other document).
- Date-stamp all pages. (NOTE: Do not stamp check.)
- Give this original Submission Receipt to the applicant.
- Record Submission Receipt information on the "RECEIVED OVER THE COUNTER" log sheet.
- Fold and put one copy of the Submission Receipt with check/cash into the Safe slot. Place the other copy of the Submission Receipt with submission (application/other document) in the top drawer of filing cabinet.