



Water Right Application Initial Review

September 18, 2026

NORWAY DEVELOPMENT COMPANY
ATTN: CARL COFFMAN
PO BOX 387
OREGON CITY OR 97405

Reference: Application G-19484

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Water Resources Department (Department) must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Department has made the following preliminary determinations:

Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:

1. Application G-19484 proposes the appropriation of 0.032 cubic foot per second (CFS), of water from Well 3 (DOUG 54326), Well 4 (DOUG 54325), Well 12 (DOUG 54309), Well 13 (DOUG 54308), Well 16 (DOUG 624), Well 17 (DOUG 55223/58229), and Well 20 (DOUG 58228) in Davis Creek Basin to make up a deficiency in rate for domestic use expanded for 111 households from January 1 through December 31 of each year.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. The application materials indicate the proposed appropriation of 0.032 CFS is to make up a deficiency in rate under water right Permit G-18720.

Please note: Applications are evaluated using the statutes and rules in effect at the time the application is accepted as complete unless subsequent statutes and rules specify otherwise. If not otherwise noted, all citations in this initial review refer to the rules and statutes in effect at the time the application is accepted as complete. To view the rules relevant for this application, please visit: <https://secure.sos.state.or.us/oard/displayCompilations> and navigate to Chapter 690 (Water Resources Department). To view the statutes relevant for this application, please visit: https://www.oregonlegislature.gov/bills_laws/Pages/ORSarchive.aspx.

4. The application proposes domestic use expanded for 111 households including irrigation of up to 0.5 acre of lawn and garden for each household. This is understood to be a request for group domestic use expanded. Group domestic use expanded includes watering up to 0.5 acre of lawn or noncommercial garden, and this amount is in total and not per household. Any permit issued under this application will be limited to watering of a total of 0.5 acre of lawn or noncommercial garden.
5. Domestic use expanded is allowed under the Umpqua Basin Program (OAR 690-516-0005(1)).
6. The proposed groundwater use is not within a designated critical groundwater area. OAR 690-310-0080(1)(a).
7. An assessment of groundwater availability has been completed by the Department. A copy of this assessment is in the file and can be viewed on the Department's website. The proposed groundwater source exhibits Reasonably Stable Groundwater Levels, and the total requested rate of groundwater allocation is obtainable by the expected yield of the well(s). OAR 690-310-0080(1)(b); OAR 690-300-0010(57).
8. The Department has determined that the proposed groundwater use will have the potential for substantial interference (PSI) with Newton Creek, North Umpqua River, and South Umpqua River. OAR 690-009-0040. Therefore, in accordance with OAR 690-300-0010(57)(f) and OAR 690-400-0010(11)(a)(B), surface water availability must be considered. **Surface water is over-appropriated during at least one period of the year.** OAR 690-310-0080(1)(b); OAR 690-300-0010(57); OAR 690-410-0070.
9. If properly conditioned (and if authorized), the proposed use of groundwater will not injure other water rights.
10. The proposed use is not located within or above any state or federal scenic waterway.
11. Because this application will have an impact on surface water flows where sensitive, threatened, or endangered (STE) fish species may be present, this application will be reviewed by the Oregon Department of Fish and Wildlife and the Oregon Department of Environmental Quality. This review may cause your application to be limited, conditioned, or denied. Depending on the proposed use, you may be required to mitigate for potential impacts identified in the review. See the **Division 33 Review** section below for more information.
12. The Department has determined that Well 3 (DOUG 54326), Well 4 (DOUG 54325), Well 12 (DOUG 54309), Well 13 (DOUG 54308), and Well 17 (DOUG 55223/58229), do not meet current minimum well construction standards.
 - a. Well 3: As indicated on the Well Report, the casing is reported to extend from land surface to 22 feet below land surface. To meet minimum construction standards, the casing must extend a minimum of 12 inches above the finished ground surface or pumphouse floor, and a minimum of 12 inches above the local surface runoff level.
 - b. Well 4: As indicated on the Well Report, 10.5 sacks of bentonite were used to seal the well, but a calculated 14 sacks were needed. Additionally, the casing is reported to extend from

land surface to 30 feet below land surface. To meet minimum construction standards, the well must be resealed with an appropriate amount of an approved grout, and the casing must extend a minimum of 12 inches above the finished ground surface or pumphouse floor, and a minimum of 12 inches above the local surface runoff level.

- c. Well 12: As indicated on the Well Report, 7 sacks of bentonite were used to seal the well, but a calculated 9 sacks were needed. To meet minimum construction standards, the well must be resealed with an appropriate amount of an approved grout.
- d. Well 13: As indicated on the Well Report, 13 sacks of bentonite were used to seal the well, but a calculated 18 sacks were needed. To meet minimum construction standards, the well must be resealed with an appropriate amount of an approved grout.
- e. Well 17: As indicated on the Well Reports, 14 sacks of bentonite were used to seal the well, but a calculated 18 sacks were needed. To meet minimum construction standards, the well must be resealed with an appropriate amount of an approved grout.

See the **Minimum Well Construction Standards – Repair Required** section below for more information.

13. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.

14. See **Additional Information Required** section below for deficiencies with the application.

Summary of Preliminary Determinations
The appropriation of 0.032 CFS, of water from Well 3 (DOUG 54326), Well 4 (DOUG 54325), Well 12 (DOUG 54309), Well 13 (DOUG 54308), Well 16 (DOUG 624), Well 17 (DOUG 55223/58229), and Well 20 (DOUG 58228) in Davis Creek Basin to make up a deficiency in rate for domestic use expanded (including not to exceed a total of 0.5 acre noncommercial lawn and garden) for 111 households from January 1 through December 31 is not allowable.

Minimum Well Construction Standards – Repair Required:

Although it is unlikely that a permit will be issued, if the Department’s findings change, prior to the issuance of any Proposed Final Order that may recommend approval, evidence demonstrating compliance with well construction standards must be submitted and approved by the Department. In repairing the well(s), you should work closely with the Department and/or a licensed well constructor to ensure that repairs are carried out in a manner that will not violate well construction or other rules. You are encouraged to contact Tommy Laird of the Department’s Well Construction and Compliance Section at 503-302-8618 to determine how to proceed.

Please submit this information no later than October 22, 2026. If you are unable to submit the information listed above by this date, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time is needed and why you

need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

Please also note that regardless of the outcome of this application, you will need to work with the Department to either repair or abandon the well(s) to comply with the minimum standards for the construction, conversion, alteration, maintenance, and abandonment of water supply wells in order to protect the state's groundwater supply (OAR 690-200).

Additional Information Required:

Although it is unlikely that a permit will be issued, if the Department's findings change, additional information will be required prior to issuance of any Proposed Final Order that may recommend approval. Please provide the following:

- A. The map submitted does not meet the requirements of OAR 690-310-0050(4)(b) and (c). Please provide a single map that shows the location of all main canals, ditches, pipelines, or flumes. The map also needs to label each quarter-quarter section and identify all current tax lots from which water is to be diverted, used and conveyed.
- B. The names and mailing addresses of the owners of any lands not owned by the applicant that are crossed by the proposed ditch, canal or other work, even if the applicant has obtained written authorization or an easement from the owner, as required by OAR 690-310-0040(1)(a)(F).
- C. The Department must receive evidence that you have written authorization or an easement permitting access to lands not owned by you that are crossed by the proposed ditch, canal or other work.

Please submit this information no later than October 22, 2026. If you are unable to submit the information listed above by this date, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time is needed and why you need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

If we do not receive the information requested above or a request for an administrative hold by the above date, the Department may reject the application.

Public Comment:

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

Division 33 Review:

The Department's Division 33 administrative rules (OAR 690-033) establish additional procedures and standards to aid the Department in determining whether a proposed use will impair or be detrimental

to the public interest with regard to STE fish species. This Initial Review does not address the potential impact that your proposed use may have on these species.

You may be required to mitigate for potential impacts identified in the Division 33 review process. Mitigation is often complicated, time consuming, and expensive, and may include, but is not limited to, actions such as replacing the proposed amount of water within the impacted reach through purchasing or transferring an existing water right. Following the Initial Review, you will be notified if mitigation is required due to impacts to STE fish species.

If you choose to pursue mitigation, you will likely need to place your application on administrative hold in order to explore options. There will be an additional fee of \$1,185 required with any mitigation proposal submitted.

At this time, you must decide whether to proceed or to withdraw the application.

- **To Proceed** - If you choose to proceed with the application, you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.
- **To Withdraw** - You may withdraw the application and fees in excess of \$465 will be returned. You must notify the Department **in writing** by **October 2, 2026**. For your convenience you may use the enclosed "STOP PROCESSING" form.

Although it is unlikely that a permit will be issued, if the Department's findings change and a permit is issued, it will likely include the following conditions:

1. Construction of the well shall begin within seven years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting:**
 - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
 - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.

- C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

4. Groundwater Level Measurement, Reporting, and Shut-Off Condition:

For each well on this authorization, beginning on the permit signature date for existing wells or in the year well construction is completed for new wells, and each year thereafter, the permit holder must report a static water-level measurement ("measurement") taken in March. The measurement is required whether the well is used or not. If pumping is to commence following completion of the well and prior to the next March, then a measurement must be made at least one week following well completion and before pumping commences.

Measurements must be properly reported within 30 days of measurement using forms specified by the Department. A measurement will be properly reported if the submission includes all required information as listed in the document attached. Measurements must be made with equipment that is accurate to the standards specified in Oregon Administrative Rule (OAR) 690-217-0045.

Measurements must be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed land surveyor, licensed well constructor, pump installer licensed by the Construction Contractors Board, or Department staff. The Department is not responsible for regular measurement of the static water level, but Department staff may measure the well during the normal course of groundwater level monitoring or to confirm the submitted measurement(s).

For each well on this permit, the Department has established or will establish a reference groundwater level using the best available data. Reference levels already established are specified in the table below. The reference level is intended to represent the highest elevation (shallowest depth) static water level that has been measured or can be reasonably estimated to have existed within each well at any time before its reference level is set. If Annual High Water Levels have been increased measurably by human activity, then the Department may set a different reference level using best available information. If the permit holder fails to measure and report the static water level within 12 months of permit issuance, or of completion of the well(s), then Department staff will estimate the static water level using available data, including measurements in surrounding wells. In case the permit is amended or the subsequent certificate is transferred, the Department may establish a new reference level for any new or additional wells under new permits or certificates issued under this right. The reference level for a new or additional well should reflect the highest static water level in that well or, if that measurement occurred after the time represented by the original reference level, then the water level that would have been measured in that well, if the well existed and was measured at the time represented by the original reference level.

The Department established the following reference levels for the following wells on this permit:

POA Number	Well Name	Well Log ID	Water Level Depth (feet below land surface)	Measurement Date (if applicable)
1	3	DOUG 54326	12.23	3/13/2007
2	4	DOUG 54325	34	9/28/2005
3	12	DOUG 54309	67.49	3/13/2005
4	13	DOUG 54308	83.39	3/13/2007
6	17	DOUG 55223/58229	81.67	5/3/2024
7	20	DOUG 58228	51.5	5/3/2024

All water use authorized under this permit must immediately stop if any of the following occur:

- A. Any annual high elevation static groundwater level in any well on this permit declines 25 or more feet below the reference level for that well, or
- B. Groundwater levels are not measured and properly reported as specified above for any completed well that is authorized on the permit for two consecutive years, or
- C. Hydraulic interference contributes to a decline of 25 or more feet in any neighboring well with senior priority, at any time during the year.

The Department will determine when any of the above conditions have occurred and may order the permit holder to stop all water use under this permit. The permit holder is also responsible for stopping all water use if they become aware that any of the conditions have occurred, even without notice from the Department. Following such a stop, water use under this permit will not be allowed and may only resume once the permit holder receives notice from the Department. If the permit holder fails to stop use, then the Department may take control of the controlling works of any wells authorized under this permit and may reduce the amount of groundwater pumped until the unlawful use is eliminated.

The permit holder acknowledges that one or more of the conditions requiring stoppage of use may occur prior to any use of any well on this permit.

The Department may allow the permit holder to pause annual water level measurement and reporting requirements from some of the permitted wells if measurements from those wells are redundant with other data being collected by the Department. The permit holder must receive written notification of such an allowance before stopping measurements. If this happens, the Department may reinstate the measurement requirements at any time.

5. **Well Identification Tag:**

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at www.oregon.gov/ODA to learn more about the plans and how they may affect the proposed water use.

For Further Information:

Feel free to contact me at Lucinda.R.Vranizan@water.oregon.gov or 971-375-2256 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Lucinda Vranizan, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

Lucinda Vranizan

Lucinda Vranizan
Water Right Application Specialist
Oregon Water Resources Department

Enclosures: Application Process Description
 Stop Processing Request Form

G-19484
WAB: 351 and 71174
Proposed to Deny

APPLICATION FACT SHEET

Application File Number: G-19484

Applicant: NORWAY DEVELOPMENT COMPANY

County: DOUGLAS

Watermaster: SUSAN M. DOUTHIT, #15, SWR

Priority Date: SEPTEMBER 17, 2024

Source: WELL 3 (DOUG 54326), WELL 4 (DOUG 54325), WELL 12 (DOUG 54309), WELL 13 (DOUG 54308), WELL 16 (DOUG 624), WELL 17 (DOUG 55223/58229), AND WELL 20 (DOUG 58228) IN DAVIS CREEK BASIN

Use: DOMESTIC USE EXPANDED FOR 111 HOUSEHOLDS

Quantity: 0.032 CUBIC FOOT PER SECOND

Period of Use: JANUARY 1 THROUGH DECEMBER 31

Basin Name & Number: UMPQUA, #16

WAB: N UMPQUA R > UMPQUA R - AT MOUTH
S UMPQUA R > UMPQUA R - AT MOUTH

Well Location(s):

POA Name	Twp	Rng	Mer	Sec	Q-Q	Measured Distances
WELL 3 (DOUG 54326)	26 S	5 W	WM	31	SW SW	3932 FEET SOUTH AND 5320 FEET WEST FROM NE CORNER, SECTION 31
WELL 4 (DOUG 54325)	26 S	5 W	WM	31	SW SW	3982 FEET SOUTH AND 4920 FEET WEST FROM NE CORNER, SECTION 31
WELL 12 (DOUG 54309)	26 S	5 W	WM	31	NE SW	3857 FEET SOUTH AND 3569 FEET WEST FROM NE CORNER, SECTION 31
WELL 13 (DOUG 54308)	26 S	5 W	WM	31	NE SW	3799 FEET SOUTH AND 2902 FEET WEST FROM NE CORNER, SECTION 31
WELL 16 (DOUG 624)	26 S	5 W	WM	31	NW NE	782 FEET SOUTH AND 1548 FEET WEST FROM NE CORNER, SECTION 31
WELL 17 (DOUG 55223/58229)	27 S	5 W	WM	6	NE NW	5788 FEET SOUTH AND 3309 FEET WEST FROM NE CORNER, SECTION 31
WELL 20 (DOUG 58228)	27 S	5 W	WM	6	NE NW	5768 FEET SOUTH AND 3084 FEET WEST FROM NE CORNER, SECTION 31

Place of Use:

Twp	Rng	Mer	Sec	Q-Q
26 S	5 W	WM	30	SW SE
26 S	5 W	WM	31	NE NE

Twp	Rng	Mer	Sec	Q-Q
26 S	5 W	WM	31	NW NE
26 S	5 W	WM	31	SW NE
26 S	5 W	WM	31	SE NE
26 S	5 W	WM	31	NE NW
26 S	5 W	WM	31	SE NW
26 S	5 W	WM	31	NE SW
26 S	5 W	WM	31	NW SW
26 S	5 W	WM	31	SW SW
26 S	5 W	WM	31	SE SW
26 S	5 W	WM	31	NE SE
26 S	5 W	WM	31	NW SE
26 S	5 W	WM	31	SW SE
27 S	5 W	WM	6	NW NE
27 S	5 W	WM	6	NE NW
27 S	5 W	WM	6	NW NW

PUBLIC NOTICE DATE: September 22, 2026

14 DAY STOP PROCESSING DEADLINE DATE: October 2, 2026

30 DAY COMMENT DEADLINE DATE: October 22, 2026

APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our website at: www.oregon.gov/owrd

1. Pre-application considerations

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

2. Application filing

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

3. Initial Review (IR)

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.

4. Proposed Final Order (PFO)

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

5. Final Order (FO)

- If no protest is filed, Final Order is issued.

The protest process

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- Proposed Order;
- period of time to file exceptions; or
- possible hearing by Water Resources Commission.
- Final Order is issued.

Permit holder responsibilities

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.

STOP PROCESSING REQUEST FORM

FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-19484**.

After reviewing the Initial Review for my application, I request that processing be stopped, and fees in excess of \$465 be returned. I understand that without a valid permit, I may not legally use the water as requested in my application.

Signature _____ Date _____

Signature _____ Date _____

Under ORS 537.150(5) and 537.620(5), timely submission of this request authorizes that the water right application process be stopped, and fees in excess of \$465 be returned.

- This notice must be received by the Water Resources Department no later than:

October 2, 2026

- Return the notice to:

OWRD, Water Right Services Division
STOP PROCESSING
725 Summer Street, NE - Suite A
Salem, OR 97301-1266
