



Water Right Application Initial Review

September 18, 2026

THE DLX
KIRK SCILACCI
45834 HERITAGE RANCH RD
BAKER CITY OR 97814

Reference: Application G-19491

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Water Resources Department (Department) must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Department has made the following preliminary determinations:

Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:

1. Application G-19491 proposes the appropriation of 2.2 cubic feet per second (CFS), further limited to 260.0 acre-feet (AF) annually, of water from twelve wells in Baldock Slough Basin for supplemental irrigation of 1,078.4 acres from June 1 through October 1 of each year.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Irrigation is allowed under the Powder Basin Program (OAR 690-509-0000(1)).
4. The proposed groundwater use is not within a designated critical groundwater area. OAR 690-310-0080(1)(a).
5. An assessment of groundwater availability has been completed by the Department. A copy of this assessment is in the file and can be viewed on the Department's website. The proposed

Please note: Applications are evaluated using the statutes and rules in effect at the time the application is accepted as complete unless subsequent statutes and rules specify otherwise. If not otherwise noted, all citations in this initial review refer to the rules and statutes in effect at the time the application is accepted as complete. To view the rules relevant for this application, please visit: <https://secure.sos.state.or.us/oard/displayCompilations> and navigate to Chapter 690 (Water Resources Department). To view the statutes relevant for this application, please visit: https://www.oregonlegislature.gov/bills_laws/Pages/ORSarchive.aspx.

groundwater source exhibits Reasonably Stable Groundwater Levels, and the total requested rate of groundwater allocation is obtainable by the expected yield of the well(s). OAR 690-310-0080(1)(b); OAR 690-300-0010(57).

6. The Department has determined that the proposed groundwater use will have the potential for substantial interference (PSI) with the Powder River and Baldock Slough. OAR 690-009-0040. Therefore, in accordance with OAR 690-300-0010(57)(f) and OAR 690-400-0010(11)(a)(B), surface water availability must be considered. **Surface water is over-appropriated during at least one period of the year.** OAR 690-310-0080(1)(b); OAR 690-300-0010(57); OAR 690-410-0070.
7. If properly conditioned (and if authorized), the proposed use of groundwater will not injure other water rights.
8. The proposed use is not located within or above any state or federal scenic waterway.
9. Because this application will have an impact on surface water flows where sensitive, threatened, or endangered (STE) fish species may be present, this application will be reviewed by the Oregon Department of Fish and Wildlife and the Oregon Department of Environmental Quality. This review may cause your application to be limited, conditioned, or denied. Depending on the proposed use, you may be required to mitigate for potential impacts identified in the review. See the **Division 33 Review** section below for more information.
10. OAR 690-033-0120(2) prohibits the diversion of water from April 15 through September 30 each year from wells that have PSI with surface water.
11. The proposed place of use for supplemental irrigation is identified on the application as 1,081.6 acres; however, the submitted application map shows 1,078.4 acres. The Department will proceed with processing the application using the mapped 1,078.4 acres unless notified otherwise by the applicant.
12. The application proposes supplemental irrigation of 1,078.4 acres; however, the Department's records show only 1,017.35 acres have primary irrigation rights. Therefore, if authorized, any permit issued under this application will exclude the 61.05 acres without underlying primary rights.
13. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.
14. See **Additional Information Required** section below for deficiencies with the application.

Summary of Preliminary Determinations
The appropriation of 2.2 CFS, further limited to 260.0 AF annually, of water from twelve wells in Baldock Slough Basin for supplemental irrigation of 1,017.35 acres from June 1 through October 1 of each year <u>is unlikely to be allowable</u> .

Additional Information Required:

Although it is unlikely that a permit will be issued, if the Department's findings change, additional information will be required prior to issuance of any Proposed Final Order that may recommend approval. Please provide the following:

- A. The map submitted does not meet the requirements of OAR 690-310-0050(4)(a) and (c). The measured distances provided for Wells N2, N3, N6, S1, S2, and S3 do not match the location of the wells shown on the map. Please provide a map either correcting the listed measured distances or the locations shown of these wells. The map also needs to have each quarter-quarter section labeled.

Please submit this information no later than October 22, 2026. If you are unable to submit the information listed above by this date, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time is needed and why you need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

If we do not receive the information requested above or a request for an administrative hold by the above date, the Department may reject the application.

Public Comment:

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

Division 33 Review:

The Department's Division 33 administrative rules (OAR 690-033) establish additional procedures and standards to aid the Department in determining whether a proposed use will impair or be detrimental to the public interest with regard to STE fish species. This Initial Review does not address the potential impact that your proposed use may have on these species.

You may be required to mitigate for potential impacts identified in the Division 33 review process. Mitigation is often complicated, time consuming, and expensive, and may include, but is not limited to, actions such as replacing the proposed amount of water within the impacted reach through purchasing or transferring an existing water right. Following the Initial Review, you will be notified if mitigation is required due to impacts to STE fish species.

If you choose to pursue mitigation, you will likely need to place your application on administrative hold in order to explore options. There will be an additional fee of \$1,185 required with any mitigation proposal submitted.

At this time, you must decide whether to proceed or to withdraw the application.

- To Proceed - If you choose to proceed with the application, you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.
- To Withdraw - You may withdraw the application and fees in excess of \$465 will be returned. You must notify the Department **in writing** by **October 2, 2026**. For your convenience you may use the enclosed "STOP PROCESSING" form.

Although it is unlikely that a permit will be issued, if the Department's findings change and a permit is issued, it will likely include the following conditions:

1. Construction of the well shall begin within seven years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting:**
 - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
 - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
 - C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
 - D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.
4. **Groundwater Level Measurement, Reporting, and Shut-Off Condition:**

For each well on this authorization, beginning on the permit signature date for existing wells or in the year well construction is completed for new wells, and each year thereafter, the permit holder

must report a static water-level measurement ("measurement") taken in March. The measurement is required whether the well is used or not. If pumping is to commence following completion of the well and prior to the next March, then a measurement must be made at least one week following well completion and before pumping commences.

Measurements must be properly reported within 30 days of measurement using forms specified by the Department. A measurement will be properly reported if the submission includes all required information as listed in the document attached. Measurements must be made with equipment that is accurate to the standards specified in Oregon Administrative Rule (OAR) 690-217-0045.

Measurements must be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed land surveyor, licensed well constructor, pump installer licensed by the Construction Contractors Board, or Department staff. The Department is not responsible for regular measurement of the static water level, but Department staff may measure the well during the normal course of groundwater level monitoring or to confirm the submitted measurement(s).

For each well on this permit, the Department will establish a reference groundwater level using the best available data. The reference level is intended to represent the highest elevation (shallowest depth) static water level that has been measured or can be reasonably estimated to have existed within each well at any time before its reference level is set. If Annual High Water Levels have been increased measurably by human activity, then the Department may set a different reference level using best available information. If the permit holder fails to measure and report the static water level within 12 months of permit issuance, or of completion of the well(s), then Department staff will estimate the static water level using available data, including measurements in surrounding wells. In case the permit is amended or the subsequent certificate is transferred, the Department may establish a new reference level for any new or additional wells under new permits or certificates issued under this right. The reference level for a new or additional well should reflect the highest static water level in that well or, if that measurement occurred after the time represented by the original reference level, then the water level that would have been measured in that well, if the well existed and was measured at the time represented by the original reference level.

All water use authorized under this permit must immediately stop if any of the following occur:

- A. Any annual high elevation static groundwater level in any well on this permit declines 25 or more feet below the reference level for that well, or
- B. Groundwater levels are not measured and properly reported as specified above for any completed well that is authorized on the permit for two consecutive years, or
- C. Hydraulic interference contributes to a decline of 25 or more feet in any neighboring well with senior priority, at any time during the year.

The Department will determine when any of the above conditions have occurred and may order the permit holder to stop all water use under this permit. The permit holder is also responsible for stopping all water use if they become aware that any of the conditions have occurred, even without notice from the Department. Following such a stop, water use under this permit will not be

allowed and may only resume once the permit holder receives notice from the Department. If the permit holder fails to stop use, then the Department may take control of the controlling works of any wells authorized under this permit and may reduce the amount of groundwater pumped until the unlawful use is eliminated.

The permit holder acknowledges that one or more of the conditions requiring stoppage of use may occur prior to any use of any well on this permit.

The Department may allow the permit holder to pause annual water level measurement and reporting requirements from some of the permitted wells if measurements from those wells are redundant with other data being collected by the Department. The permit holder must receive written notification of such an allowance before stopping measurements. If this happens, the Department may reinstate the measurement requirements at any time.

5. Special Groundwater Conditions:

- A. The permittee shall allow Department staff, upon reasonable notice, to access the permitted well(s) during the period of use to take static water level measurements to monitor the impact of use on the resource. To ensure accurate measurements, the permittee may be required to stop use of the well for up to 24 hours before a water level measurement.
- B. Whenever possible, cuttings shall be collected during borehole construction at 10-foot intervals and at changes in formation. A split of each sample shall be submitted to the Department upon completion of each well.

6. Well Identification Tag:

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at www.oregon.gov/ODA to learn more about the plans and how they may affect the proposed water use.

For Further Information:

Feel free to contact me at Lucinda.R.Vranizan@water.oregon.gov or 971-375-2256 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Lucinda Vranizan, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

Lucinda Vranizan

Lucinda Vranizan
Water Right Application Specialist
Oregon Water Resources Department

Enclosures: Application Process Description
 Stop Processing Request Form

G-19491
WABs: 72191, 30920327 and 30920330
Proposed to Deny

APPLICATION FACT SHEET

Application File Number: G-19491

Applicant: THE DLX AND KIRK SCILACCI

County: BAKER

Watermaster: MARCY J. OSBORN, #8, ER

Priority Date: SEPTEMBER 30, 2024

Source: TWELVE WELLS IN BALDOCK SLOUGH BASIN

Use: SUPPLEMENTAL IRRIGATION OF 1,078.4 ACRES

Quantity: 2.2 CUBIC FEET PER SECOND, FURTHER LIMITED TO 260.0 ACRE-FEET ANNUALLY

Period of Use: JUNE 1 THROUGH OCTOBER 1

Basin Name & Number: POWDER, #9

WAB: POWDER R > SNAKE R - AB UNN STR,
POWDER R > SNAKE R - AB ROCK CR, AND
BALDOCK SL > POWDER R - AT MOUTH

Well Location(s):

POA Name	Twp	Rng	Mer	Sec	Q-Q	Measured Distances
N1	7 S	39 E	WM	25	SE NE	3451 FEET NORTH AND 4980 FEET EAST FROM SW CORNER, SECTION 25
N2	7 S	39 E	WM	25	NW SW	209 FEET NORTH AND 311 FEET EAST FROM SW CORNER, NWSW, SECTION 25
N3	7 S	39 E	WM	25	NW SE	1450 FEET NORTH AND 3650 FEET EAST FROM SW CORNER, SECTION 25
N4	7 S	39 E	WM	36	SE NE	3904 FEET NORTH AND 1103 FEET WEST FROM SE CORNER, SECTION 36
N5	7 S	39 E	WM	36	NE SE	1726 FEET NORTH AND 340 FEET WEST FROM SE CORNER, SECTION 36
N6	8 S	39 E	WM	1	NW NW	863 FEET SOUTH AND 4356 FEET WEST FROM SE CORNER, SECTION 36 TOWNSHIP 7 SOUTH, RANGE 39 EAST
N7	7 S	39 E	WM	35	SW SE	326 FEET NORTH AND 2518 FEET WEST FROM NE CORNER, SECTION 2 TOWNSHIP 8 SOUTH, RANGE 39 EAST
N8	7 S	40 E	WM	31	NE SW	2504 FEET NORTH AND 1528 FEET EAST FROM SE CORNER, SECTION 36 TOWNSHIP 7 SOUTH, RANGE 39 EAST
E1	8 S	40 E	WM	5	NE NW	240 FEET SOUTH AND 2489 FEET EAST FROM NW CORNER, SECTION 5
S1	8 S	40 E	WM	7	NE SW	1832 FEET NORTH AND 2256 FEET EAST FROM SW CORNER, SECTION 7

POA Name	Twp	Rng	Mer	Sec	Q-Q	Measured Distances
S2	8 S	40 E	WM	8	SW SW	223 FEET NORTH AND 1068 FEET EAST FROM SW CORNER, SECTION 8
S3	8 S	39 E	WM	12	SE SE	16 FEET NORTH AND 1324 FEET WEST FROM SW CORNER, SECTION 7 TOWNSHIP 8 SOUTH, RANGE 40 EAST

Place of Use:

Twp	Rng	Mer	Sec	Q-Q	Acres
7 S	40 E	WM	31	NE SW	32.0
7 S	40 E	WM	31	NW SW	37.1
7 S	40 E	WM	31	SW SW	31.2
7 S	40 E	WM	31	SE SW	32.6
7 S	40 E	WM	31	NW SE	33.2
7 S	40 E	WM	31	SW SE	35.5
8 S	39 E	WM	1	NE NE	13.3
8 S	39 E	WM	1	SW NE	13.9
8 S	39 E	WM	1	SE NE	14.2
8 S	39 E	WM	1	SW NW	11.0
8 S	39 E	WM	1	SE NW	16.4
8 S	39 E	WM	1	NE SW	21.3
8 S	39 E	WM	1	NW SW	11.6
8 S	39 E	WM	2	NW NE	30.4
8 S	39 E	WM	2	SW NE	30.7
8 S	39 E	WM	2	NE NW	39.0
8 S	39 E	WM	2	SE NW	39.6
8 S	39 E	WM	12	SE NE	40.0
8 S	39 E	WM	12	NE SE	40.0
8 S	39 E	WM	12	SE SE	40.0
8 S	40 E	WM	5	NE NW	37.7
8 S	40 E	WM	5	NW NW	38.1
8 S	40 E	WM	5	SW NW	4.7
8 S	40 E	WM	5	SE NW	26.6
8 S	40 E	WM	6	NE NE	31.4
8 S	40 E	WM	6	NW NE	36.5
8 S	40 E	WM	6	NE NW	32.7
8 S	40 E	WM	6	NW NW	27.7
8 S	40 E	WM	7	SW NW	40.0
8 S	40 E	WM	7	NE SW	40.0
8 S	40 E	WM	7	NW SW	40.0
8 S	40 E	WM	7	SW SW	40.0
8 S	40 E	WM	7	SE SW	40.0
8 S	40 E	WM	8	NW SW	40.0
8 S	40 E	WM	8	SW SW	40.0

PUBLIC NOTICE DATE: September 22, 2026

14 DAY STOP PROCESSING DEADLINE DATE: October 2, 2026

30 DAY COMMENT DEADLINE DATE: October 22, 2026

APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our website at: www.oregon.gov/owrd

1. Pre-application considerations

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

2. Application filing

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

3. Initial Review (IR)

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.

4. Proposed Final Order (PFO)

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

5. Final Order (FO)

- If no protest is filed, Final Order is issued.

The protest process

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- Proposed Order;
- period of time to file exceptions; or
- possible hearing by Water Resources Commission.
- Final Order is issued.

Permit holder responsibilities

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.

STOP PROCESSING REQUEST FORM

FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-19491**.

After reviewing the Initial Review for my application, I request that processing be stopped, and fees in excess of \$465 be returned. I understand that without a valid permit, I may not legally use the water as requested in my application.

Signature _____ Date _____

Signature _____ Date _____

Under ORS 537.150(5) and 537.620(5), timely submission of this request authorizes that the water right application process be stopped, and fees in excess of \$465 be returned.

- This notice must be received by the Water Resources Department no later than:

October 2, 2026

- Return the notice to:

OWRD, Water Right Services Division
STOP PROCESSING
725 Summer Street, NE - Suite A
Salem, OR 97301-1266
