

**CLAIM OF
BENEFICIAL USE
for Transfer New or Additional
POA Only**



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem, Oregon 97301-1266
(503) 986-0900
www.oregon.gov/OWRD

A fee of \$345 must accompany this form for transfers where the application was submitted on July 9, 1987, or later.

Enter the date the transfer application was submitted:

4/4/2022

A separate form shall be completed for each transfer.

This form is subject to revision. **Begin each new claim** by checking for a new version of this form at:

<https://www.oregon.gov/OWRD/Forms/Pages/default.aspx>

The completion of this form is required by OAR 690-014-0100(1) and 690-014-0110(4).

Please type or print in dark ink. If this form is found to contain errors or omissions, it may be returned to you. **Every item must have a response.** If any requested information does not apply to the claim, insert "NA." **Do not delete or alter any section of this form unless directed by the form.** The Department may require the submittal of additional information from any water user or authorized agent.

"Section 8" of this form is intended to aid in the completion of this form and should not be submitted.

A claim of beneficial use includes both this report and a map. If the map is being mailed separately from this form, please include a note with this form indicating such.

If you have questions regarding the completion of this form, please call 503-986-0900.

The Department has a Reimbursement Authority program that allows it to enter into a voluntary agreement with an applicant for expedited services. Under such an agreement, the applicant pays the cost to hire additional staff that would not otherwise be available. This program means a certificate may be issued in about a month. For more information on this program see: <https://www.oregon.gov/OWRD/programs/WaterRights/RA/Pages/default.aspx>

**SECTION 1
GENERAL INFORMATION**

Type of Authorized Change

This Claim is being submitted for a transfer where the only authorized change was a change in point(s) of appropriation or additional point(s) of appropriation, or a combination of both. **YES**
If additional changes were authorized, you will need to select a different form.

1. File Information

APPLICATION #

T-14191

Received
OCT 19 2026
OWRD

2. Property Owner (current owner information)

APPLICANT/BUSINESS NAME Golden Rule Farms, Inc		PHONE No.	ADDITIONAL CONTACT No.
ADDRESS PO Box 255			
CITY Christmas Valley	STATE OR	ZIP 97641	E-MAIL Goldenrulefarms@gmail.com

If the current property owner is not the transfer holder of record, it is recommended that an assignment be filed with the Department. ***Each transfer holder of record must sign this form.***

3. Transfer holder of record (this may, or may not, be the current property owner)

TRANSFER HOLDER OF RECORD Same as above		
ADDRESS		
CITY	STATE	ZIP

4. Date of Site Inspection:

8/13/2026

5. Person(s) interviewed and description of their association with the project:

NAME	DATE	ASSOCIATION WITH THE PROJECT
Tim Puckett	8/13/2026	Transfer Holder

6. County:

Harney

7. If any property described in the place of use of the transfer final order is excluded from this report, identify the owner of record for that property (ORS 537.230(5)):


OWNER OF RECORD Legacy Land & Cattle, LLC		
ADDRESS 1421 NE Granger Ave		
CITY Corvallis	STATE OR	ZIP 97330-9673

Add additional tables for owners of record as needed

SECTION 2
SIGNATURES

CWRE Statement, Seal and Signature

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge.



CWRE NAME Scott D Montgomery		PHONE No. 541-548-5833	ADDITIONAL CONTACT No. 541-420-0401
ADDRESS PO Box 767			
CITY Terrebonne	STATE OR	ZIP 97760	E-MAIL scott@apeands.com

Transfer Holder of Record Signature or Acknowledgement

Each transfer holder of record must sign this form in the space provided below.

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge. I request that the Department issue a water right certificate.

SIGNATURE	PRINT OR TYPE NAME	TITLE	DATE
	Tim Puckett	President	9-25-26

SECTION 3

CLAIM DESCRIPTION

Note: The Claim only needs to describe the new or additional point(s) of appropriation. This Claim does not need to provide information for the original point(s) of appropriation unless the original point of appropriation is either a new or additional point of appropriation on another right involved in this transfer.

1. New or additional point of appropriation name or number:

POINT OF APPROPRIATION (POA) NAME OR NUMBER (CORRESPOND TO MAP)	WELL LOG ID # FOR ALL WORK PERFORMED ON THE WELL (IF APPLICABLE)	WELL TAG # (IF APPLICABLE)	SOURCE (IF LISTED IN TRANSFER FINAL ORDER)
#3	HARN 50143	L11939	Harney Basin
#16	HARN 51555	L38946	Harney Basin

Attach each well log available for the well (include the log for the original well and any subsequent alterations, reconstructions, or deepenings)

2. Variations:

Was the use developed differently from what was authorized by the transfer final order, or extension final?

YES

If yes, describe below.

(e.g. "The order allowed three new/additional points of appropriation. The water user only developed one of the points.")

The order allowed three points of appropriation. The water user only developed two of these.

3. Claim Summary:

NEW OR ADDITIONAL POA NAME OR #	MAXIMUM RATE AUTHORIZED	CALCULATED THEORETICAL RATE BASED ON SYSTEM	AMOUNT OF WATER MEASURED
#3	1/80th of 1 cfs per acre	1.28 cfs	Not running
#16	1/80th of 1 cfs per acre	1.63 cfs	Not running

SECTION 4

SYSTEM DESCRIPTION

Are there multiple new or additional Points of Appropriation (POA)?

YES

If "YES" you will need to copy and complete a separate Section 4.

POA Name or Number this section describes (only needed if there is more than one):

#3 (HARN 50143)

A. POA System Information

Provide the following information concerning the point of appropriation. Information provided must describe the equipment used to appropriate water from the point of appropriation.

1. Pump Information:

MANUFACTURER	MODEL	SERIAL NUMBER	TYPE (CENTRIFUGAL, TURBINE OR SUBMERSIBLE)	INTAKE SIZE	DISCHARGE SIZE
UNK	UNK	10-80-080	Turbine		8"

2. Motor Information:

MANUFACTURER	HORSEPOWER
US Motors	75

3. Theoretical Pump Capacity – Pump at Well:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE DEPTH TO WATER FROM THE GROUND SURFACE MEASURED AT THE WELL DURING PUMPING)	LIFT TO PLACE OF USE (THE LIFT FROM THE GROUND SURFACE AT THE WELL TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
75	40	290'	20'	1.28

Reminder: For pump calculations use the reference information at the end of this document.

4. Provide pump calculations:

$$Q = \frac{7.04 \text{ ft}^3/\text{hp/s} \times \text{hp}}{\text{Total head, ft}} = \frac{(7.04)(75)}{411.6} = 1.28$$

$$\text{Total head} = 101.6' + 290' + 20' = 411.6'$$

5. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
Not running			

6. Theoretical Pump Capacity – Pump at Sump:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE LIFT FROM THE WATER SURFACE TO THE PUMP)	LIFT TO PLACE OF USE (THE LIFT FROM THE PUMP TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
No sump				

Reminder: For pump calculations use the reference information at the end of this document.

7. Provide pump calculations:

NA

8. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
NA			

9. Additional notes or comments related to the system:

B. Groundwater Source Information (Well and Sump)

1. Is the appropriation from a dug well (sump)?

NO

C. Additional notes or comments related to the system:

POA Name or Number this section describes (only needed if there is more than one):

#16 (HARN 51555)

A. POA System Information

Provide the following information concerning the point of appropriation. Information provided must describe the equipment used to appropriate water from the point of appropriation.

1. Pump Information:

MANUFACTURER	MODEL	SERIAL NUMBER	TYPE (CENTRIFUGAL, TURBINE OR SUBMERSIBLE)	INTAKE SIZE	DISCHARGE SIZE
UNK	UNK	UNK	Turbine	12"	8"

2. Motor Information:

MANUFACTURER	HORSEPOWER
GE	100

3. Theoretical Pump Capacity – Pump at Well:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE DEPTH TO WATER FROM THE GROUND SURFACE MEASURED AT THE WELL DURING PUMPING)	LIFT TO PLACE OF USE (THE LIFT FROM THE GROUND SURFACE AT THE WELL TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
100	40	320'	10'	1.63

Reminder: For pump calculations use the reference information at the end of this document.

4. Provide pump calculations:

$Q = 7.04 \text{ ft}^3/\text{s}/\text{hp} \times \text{hp} = (7.04)(100) = 1.63 \text{ cfs}$ Total head, ft 431.6 Total head, ft = 101.6' + 320' + 10' = 431.6'

5. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
Not running			

6. Theoretical Pump Capacity – Pump at Sump:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE LIFT FROM THE WATER SURFACE TO THE PUMP)	LIFT TO PLACE OF USE (THE LIFT FROM THE PUMP TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
No sump				

Reminder: For pump calculations use the reference information at the end of this document.

7. Provide pump calculations:

NA Received OCT 19 2026 OWRD
--

8. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
NA			

9. Additional notes or comments related to the system:

B. Groundwater Source Information (Well and Sump)

1. Is the appropriation from a dug well (sump)?

NO

C. Additional notes or comments related to the system:

SECTION 5 CONDITIONS

All conditions contained in the transfer final order, or any extension final order shall be addressed. Reports that do not address all performance related conditions will be returned.

1. Time Limits:

Describe how the water user has complied with each of the development timelines established in the transfer final order and any extensions of time issued for the transfer:

	DATE FROM TRANSFER	DATE THE NEW AND/OR ADDITIONAL POA(S) WERE READY FOR USE *THIS DATE MUST FALL BETWEEN THE "ISSUANCE DATE" AND THE "COMPLETENESS DATE"
ISSUANCE DATE	4/17/2025	
COMPLETENESS DATE FROM ORDER (C)	10/1/2026	8/13/2026

* MUST BE WITHIN PERIOD BETWEEN TRANSFER FINAL ORDER, OR ANY EXTENSION FINAL ORDER ISSUANCE AND THE DATE TO COMPLETE THE CHANGE

2. Is there an extension final order(s)? NO

3. Measurement Conditions:

a. Does the transfer final order, or any extension final order require the installation of a meter or other approved measuring device? YES

b. Has a meter been installed? YES

c. Meter Information

POA NAME OR #	MANUFACTURER	SERIAL #	CONDITION (WORKING OR NOT)	CURRENT METER READING	DATE INSTALLED
#3	McCrometer	16-07685-08	Not running	064570 AF	2016
#16	McCrometer	09-0932-08	Not running	607795 gal x 100	2009

4. Recording and reporting conditions

a. Is the water user required to report the water use to the Department? NO

b. Have the reports been submitted? NO

If the reports have not been submitted, attach a copy of the reports if available.

5. Other conditions required by the transfer final order or extension final order:

a. Were there special well construction standards? Received NO

b. Was submittal of a ground water monitoring plan required? OCT 19 2026 NO

c. Other conditions? OWRD NO

If "YES" to any of the above, identify the condition and describe the water user's actions to comply with the condition(s):

SECTION 6
ATTACHMENTS

Provide a list of any additional documents you are attaching to this report:

ATTACHMENT NAME	DESCRIPTION
Well logs	HARN 50143 & 51555
Site photos	Time/location stamped photos of irrig. System & place of use

SECTION 7

CLAIM OF BENEFICIAL USE MAP

For the purpose of this Claim, the map identifying the location of the place of use does not require a new survey. The location of the place of use identified on the Claim map should be based on the original right of record at the time the transfer final order was issued. In transfers approved for additional points of appropriation, the original points must be identified the map based on the original right of record at the time the transfer final order was issued.

In order to properly examine your claim, the Department must have an accurate map that meets the criteria described in OAR 690-014-0170 and OAR 690-305-0010, which are provided below for your convenience:

OAR 690-014-0170 Minimum Requirements for Maps for Permit or Transfer Final Order Claims of Beneficial Use

- (1) Maps submitted by a CWRE as part of the Claim of Beneficial Use shall meet the standards in OAR chapter 690, division 305. In addition, the map shall meet the following criteria:
 - (a) Horizontal accuracy is required only to ten feet for the purpose of locating and quantifying water rights. Maps shall be developed from any standard survey method. Traverse closures are not required.
 - (b) Maps shall clearly designate the place of use and point of diversion or appropriation for each source and use.
 - (c) The map shall indicate by description, in relation to the point of diversion or appropriation, the location of any fish screens, by-pass devices, and measuring devices required by the permit or transfer final order.
 - (d) The following statement shall be placed on the map: "This map is not intended to provide legal dimensions or locations of property ownership lines."
- (2) A CWRE may make a written request to the Director for a waiver of one or more mapping standards. The Director will determine whether the waiver shall be allowed and will respond to such requests in writing.

OAR 690-305-0010 General Map Criteria

Each map submitted to the Department shall meet the following general criteria in addition to any specific criteria identified in the rules for the relevant water right transaction:

- (1) Drawing
 - (a) The map shall be drafted on paper or polyester film with ink or otherwise printed in an indelible form with sufficient clarity so as to be easily reproduced or scanned. Maps may be submitted electronically in portable document format (pdf) and must be prepared consistent with, and include the same information as, a paper map.
 - (b) The preferred paper size is 8.5 inches by 11 inches and should be no larger than 30 inches by 30 inches. A map greater than 30 inches by 30 inches may be submitted if the Department grants, by mail or electronic means, advance approval of the larger size.

- (c) Beginning April 1, 2029, regardless of whether the map is submitted electronically, on paper, or on polyester film, for any map that OAR chapter 690 requires be prepared by a Certified Water Right Examiner, a digital file containing the coordinate system and geospatial features of the map as specified by the Department shall be submitted in addition to the map, unless the Department provides a waiver. The digital file shall be submitted as a shapefile or other approved format in a manner required by the Department.
 - (d) A platted and recorded subdivision map, deed description survey map, or county assessor map may be submitted as the application map if all of the required information included in sections (2) and (3) of this rule is clearly shown.
 - (e) An aerial image may be provided in addition to the map to aid the Department in understanding the proposal.
 - (f) The map submitted under subsection (a) shall be the official record of the water right. An aerial image or digital file shall not be the official record of the water right.
- (2) Scale
- (a) The map shall be drawn to a standard, even-numbered scale and one-inch shall not exceed 1320 feet.
 - (b) The map scale may exceed 1320 feet per inch if the Department grants, by mail or electronic means, advance approval of the requested scale.
 - (c) Notwithstanding subsection (a) and (b), for maps identifying the location of a municipal use place of use, one-inch can exceed 1320 feet; provided that the scale is sufficient to identify the quarter-quarters involved in the place of use.
- (3) Features: Features shall be clearly identified and labeled. Unless otherwise indicated in rule, the following features must be included in each map submitted to the Department:
- (a) Mapping scale.
 - (b) North directional symbol.
 - (c) Legend.
 - (d) General location of main canals, ditches, flumes, pipelines, pumps, or other water delivery features used to transport water from the point(s) of diversion or appropriation to the place use and to include the delivery features at the place of use.
 - (e) Other topographical features such as rivers, creeks, streams, lakes, reservoirs, ponds, roads, or railroads that may be helpful to clarify and identify the location of points of diversion, wells, dams, and places of use.
 - (f) Location and flow direction of the water way if the source is surface water. If multiple water ways exist in the area of the proposed diversion and use, the map must identify the location and flow direction of the additional water ways.
 - (g) Township, range, section, quarter-quarter, and tax lot(s), donation land claims, or government lots where water will be or has been diverted, conveyed, and used. If the map is for municipal use the map:
 - (A) Must identify but does not need to label the quarter-quarters,
 - (B) Does not need to identify or label tax lots, donation land claims, or government lots.

- (h) Location of each proposed or developed diversion point, well (point of appropriation), or dam by reference to a recognized public land survey corner. For a reservoir without a dam, the center of the reservoir shall be referenced to a recognized public land survey corner.
 - (A) The locations shall be shown by distance and bearing, or by coordinates (distance north or south and distance east or west from the corner). In addition, they shall also include latitude and longitude as established by a global positioning system.
 - (B) Latitude and longitude coordinates shall be expressed as degrees-decimal with five or more digits after the decimal (e.g., 42.53764^o). The datum used to establish the coordinates shall be indicated on the map. Examples of datums include NAD 83, NAD 27 and WGS84.
- (i) Location of the proposed or developed place of use by township, range, section, and nearest quarter-quarter section.
 - (A) For irrigation or nursery use, the map shall additionally indicate the place of use in each quarter-quarter of a section by shading or hatchuring and indicate the number of acres in each quarter-quarter section, donation land claim, government lot, or other recognized public land survey lines.
 - (B) For places of use that are limited to a point, such as a stock watering tank, the location may also be identified by distance and bearing, or by coordinates (distance north or south and distance east or west from the corner). In addition, they shall include latitude and longitude as established by a global positioning system.
 - (C) Latitude and longitude coordinates shall be expressed as degrees-decimal with five or more digits after the decimal (e.g., 42.53764^o). The datum used to establish the coordinates shall be indicated on the map. Examples of datums include NAD 83, NAD 27 and WGS84.
 - (D) Where more than one point of diversion or well is included, the map must clearly identify the place(s) of use served by each point of diversion or well.
- (j) If for a supplemental irrigation application or claim of beneficial use, the location and water right reference number of the underlying primary right, registration or claim.
- (k) Any other information the Department requests and considers necessary to evaluate the water right transaction.

WELL I.D.# L11939

MAR 27 1997

Harn
50143

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WATER RESOURCES DEPT.

(START CARD) # 83824

Instructions for completing this report are on the back page of this form.

(1) OWNER:

Well Number _____

Name VJ LeforAddress HC 71 Box 463City Burns State OR Zip 97720

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 290 ft.Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
28	0	50	Bentonite	0	18	30 sacks
24	50	95				
14	95	290				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other phased dry & tamped

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from 100 ft. to 0 ft. Size of gravel 3/8 pea

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 24	+1	20	.250	☒	☐	☐	☐
Liner: 14	+1.5	115	.250	☒	☐	☒	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
15	115	1/8x3	5600	14		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump Yield gal/min	☒ Bailer Drawdown	☐ Air Drill stem at	☐ Flowing Artesian Time
50	0		1 hr.

Temperature of water 58° Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Harney Latitude _____ Longitude _____Township 26S N or S Range 30E E or W. WM.Section 1 SW 1/4 NE 1/4Tax Lot 100 Lot _____ Block _____ Subdivision _____Street Address of Well (or nearest address) Weaver Springs Rd

(10) STATIC WATER LEVEL:

22 ft. below land surface. Date 3-21-97

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 30

From	To	Estimated Flow Rate	SWL
30	290	800	22

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Sandy topsoil	0	2	
Sand	2	14	
Clay brn	14	21	
Clay blue	21	30	
Cinders blk & brn	30	52	22
Clay blue	52	77	22
Sand blk/fine caving	77	100	22
Clay, grey	100	140	22
Clay, blk	140	155	22
Clay green	155	172	22
Clay brn hard	172	180	22
Sand/clay blk	180	190	22
Clay grey	190	240	22
Clay green hard	240	245	22
Cinders, grey	245	260	22
Clay cobbles caving	260	275	22
Clay green	275	290	22

Date started 3-6-97 Completed 3-21-97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1424Signed Zachary K. Riley Date 3-21-97

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

HARN 51555

WELL I.D. # L 38946

START CARD # W198686

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number
Name Carpen Ter Ranch LLC
Address 1930 Lewis Street
City Salem State OR Zip 97301

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other

(4) PROPOSED USE
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 320.0 ft. = 320
Explosives used: ☐ Yes ☐ No Type Amount

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
30"	0	20	BENBARK	0	20	120 SACKS
12"	20	320				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☒ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 12" 0 230 260 ☒ ☐ ☐ ☐
Liner: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 230'

(7) PERFORATIONS/SCREENS
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailor ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
1400	20'		3 Hrs.

Temperature of water 54.0 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____
Did the water analysis show not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: MAY 14 2009 APR 23 2009

(9) LOCATION OF WELL (legal description)

County HARNEY
Tax Lot none Lot _____
Township 25 N or S Range 31 E or W WM
Section 31 SW 1/4 NW 1/4

Lat _____° _____' _____" or _____ (degrees or decimal)
Long _____° _____' _____" or _____ (degrees or decimal)

Street Address of Well (or nearest address) _____

(10) STATIC WATER LEVEL

57.5 ft. below land surface. Date 3/20/09

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 70' 85'

From	To	Estimated Flow Rate	SWL
85'	130'	100 Gal.	80'

(12) WELL LOG

Material	From	To	SWL
TOP SOIL	0	2	
Hard pan	2	15	
Sandstone	15	40	
Cinders & Clay	40	48	
Black cinders	48	85	
Blue clay & cinders	85	90	
Sandstone	90	100	80'
Cinders & Clay	100	125	80
Blue clay	125	130	80
Black clay	130	230	80
CINDERSTONE	230	320	57'

Date Started 12/14/08 Completed 3/20/09

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1336 Date 4/14/09

Signed L.H. Ruff



2026-08-13 10:20:23

Lat: 43°20'57.05687", Lon: -119°03'50.07790"

Received
OCT 19 2026
OWRD



2026-08-13 10:28:49

Lat: $43^{\circ}20'44.06862''$, Lon: $-119^{\circ}03'48.22722''$



2026-08-13 10:06:52

Lat: 43°20'46.54380", Lon: -119°03'31.64820"

Received
OCT 19 2026
OWRD



2026-08-13 10:36:59

Lat: 43°20'57.14220", Lon: -119°03'14.52360"



2026-08-13 11:00:14

Lat: 43°22'12.77580", Lon: -119°00'36.72600"



ALL POINTS
ENGINEERING & SURVEYING, INC.
P.O. Box 767 (CRR)
Terrebonne, Oregon 97760

TRANSMITTAL

To: Oregon Water Resources Dept
725 Summer St NE, Suite A
Salem, OR 97301-1266

Date: 9/25/2026
Attention: Certificates
RE: COBU T-14191

☒ Prints ☐ Plans ☐ Plat ☐ Specifications.

Attached is Claim of Beneficial Use on T-14191, Golden Rule Farms.

If you have any questions please don't hesitate to call 541-548-5833 or email me at scott@apeands.com.

Copies	No.	Description
1	1	COBU (13 pages letter bond)
1	2	COBU Map (1 page letter bond)
1	3	Well logs (2 pages letter bond)
1	4	Site photos (5 pages letter bond)
1	7	Check for \$345.00

Signed: _____

Deane Montgoy

Received
OCT 19 2026
OWRD