

**CLAIM OF
BENEFICIAL USE
for Transfer New or Additional
POA Only**



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem, Oregon 97301-1266
(503) 986-0900
www.oregon.gov/OWRD

A fee of \$345 must accompany this form for transfers where the application was submitted on July 9, 1987, or later.

Enter the date the transfer application was submitted:

August 19, 2024

A separate form shall be completed for each transfer.

This form is subject to revision. **Begin each new claim** by checking for a new version of this form at:

<https://www.oregon.gov/OWRD/Forms/Pages/default.aspx>

The completion of this form is required by OAR 690-014-0100(1) and 690-014-0110(4).

Please type or print in dark ink. If this form is found to contain errors or omissions, it may be returned to you. **Every item must have a response.** If any requested information does not apply to the claim, insert "NA." **Do not delete or alter any section of this form unless directed by the form.** The Department may require the submittal of additional information from any water user or authorized agent.

"Section 8" of this form is intended to aid in the completion of this form and should not be submitted.

A claim of beneficial use includes both this report and a map. If the map is being mailed separately from this form, please include a note with this form indicating such.

If you have questions regarding the completion of this form, please call 503-986-0900.

The Department has a Reimbursement Authority program that allows it to enter into a voluntary agreement with an applicant for expedited services. Under such an agreement, the applicant pays the cost to hire additional staff that would not otherwise be available. This program means a certificate may be issued in about a month. For more information on this program see:

<https://www.oregon.gov/OWRD/programs/WaterRights/RA/Pages/default.aspx>

Received by OWRD

OCT 21 2026

Salem, OR

**SECTION 1
GENERAL INFORMATION**

Type of Authorized Change

This Claim is being submitted for a transfer where the only authorized change was a change in point(s) of appropriation or additional point(s) of appropriation, or a combination of both.

YES

If additional changes were authorized, you will need to select a different form.

1. File Information

APPLICATION #

T-14522

Revised 7/1/2025

Transfer POA Only - Page 1 of 12

WR

2. Property Owner (current owner information)

APPLICANT/BUSINESS NAME Massee Farms Bayou LLC / ED Landholdings LLC		PHONE NO. 503-873-4541	ADDITIONAL CONTACT NO.
ADDRESS 7385 Howell Prairie Rd NE			
CITY Silverton	STATE OR	ZIP 97305	E-MAIL ditchene@outlook.com

If the current property owner is not the transfer holder of record, it is recommended that an assignment be filed with the Department. ***Each transfer holder of record must sign this form.***

3. Transfer holder of record (this may, or may not, be the current property owner)

TRANSFER HOLDER OF RECORD ED Landholding LLC c/o Eric Ditchen (Please note: this should have been ED Landholdings)		
ADDRESS 7385 Howell Prairie Rd NE		
CITY Silverton	STATE OR	ZIP 97305

4. Date of Site Inspection:

September 30, 2026

5. Person(s) interviewed and description of their association with the project:

NAME	DATE	ASSOCIATION WITH THE PROJECT
Aram Krueger	September 30, 2026	Field manager

6. County

Marion County

7. If any property described in the place of use of the transfer final order is excluded from this report, identify the owner of record for that property (ORS 537.230(5)):

OWNER OF RECORD NA		
ADDRESS		
CITY	STATE	ZIP

Add additional tables for owners of record as needed

Received by OWRD

OCT 21 2026

Salem, OR

SECTION 2
SIGNATURES

CWRE Statement, Seal and Signature

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge.

Seal and Signature



CWRE NAME Doann Hamilton		PHONE NO. (503) 349-6946 cell	ADDITIONAL CONTACT NO. 503-931-0210
ADDRESS 15333 Pletzer Rd. SE			
CITY Turner	STATE OR	ZIP 97392	E-MAIL Doann@McGillWaterRights.com

Received by OWRD


OCT 21 2026

Salem, OR

Transfer Holder of Record Signature or Acknowledgement

Each transfer holder of record must sign this form in the space provided below.

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge. I request that the Department issue a water right certificate.

SIGNATURE	PRINT OR TYPE NAME	TITLE	DATE
	Eric Ditcher	Member	10/19/26

SECTION 3 CLAIM DESCRIPTION

Note: The Claim only needs to describe the new or additional point(s) of appropriation. This Claim does not need to provide information for the original point(s) of appropriation unless the original point of appropriation is either a new or additional point of appropriation on another right involved in this transfer.

1. New or additional point of appropriation name or number:

POINT OF APPROPRIATION (POA) NAME OR NUMBER (CORRESPOND TO MAP)	WELL LOG ID # FOR ALL WORK PERFORMED ON THE WELL (IF APPLICABLE)	WELL TAG # (IF APPLICABLE)	SOURCE (IF LISTED IN TRANSFER FINAL ORDER)
Well 2	MARI 72116	L-158763	A Well a tributary of Hubbard Lake Drainage System (Willamette River)

Attach each well log available for the well (include the log for the original well and any subsequent alterations, reconstructions, or deepenings)

If well logs are available, items A and B below can be deleted

Received by OWRD

OCT 21 2026

Salem, OR

2. Variations:

Was the use developed differently from what was authorized by the transfer final order, or extension final?

YES

If yes, describe below.

(e.g. "The order allowed three new/additional points of appropriation. The water user only developed one of the points.")

- 1. Well 2 (MARI 72116) latitude and longitude is slightly different from what is describe on WRIS revised to:**

45.077372, -122.998347, WGS 84

3. Claim Summary:

NEW OR ADDITIONAL POA NAME OR #	MAXIMUM RATE AUTHORIZED	CALCULATED THEORETICAL RATE BASED ON SYSTEM	AMOUNT OF WATER MEASURED
Well 2	0.95 cfs	2.11 cfs	Not running during site visit

SECTION 4

SYSTEM DESCRIPTION

Are there multiple new or additional Points of Appropriation (POA)?

NO

If "YES" you will need to copy and complete a separate Section 4.

POA Name or Number this section describes (only needed if there is more than one):

Well 2

A. POA System Information

Provide the following information concerning the point of appropriation. Information provided must describe the equipment used to appropriate water from the point of appropriation.

1. Pump Information:

MANUFACTURER	MODEL	SERIAL NUMBER	TYPE (CENTRIFUGAL, TURBINE OR SUBMERSIBLE)	INTAKE SIZE	DISCHARGE SIZE
Franklin Electric	700 4 stage	Unknown	Submersible	6 inch	6 inch

2. Motor Information:

MANUFACTURER	HORSEPOWER
Franklin Electric	75 Hp

Received by OWRD

OCT 21 2026

Salem, OR

3. Theoretical Pump Capacity – Pump at Well:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE DEPTH TO WATER FROM THE GROUND SURFACE MEASURED AT THE WELL DURING PUMPING)	LIFT TO PLACE OF USE (THE LIFT FROM THE GROUND SURFACE AT THE WELL TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
75 Hp	80 psi	47.5 feet (from pump test recorded on well log)	0 feet	2.11 cfs

Reminder: For pump calculations use the reference information at the end of this document.

4. Provide pump calculations:

$$Q \text{ Pump} = \frac{(75 \text{ Hp}) \times (7.04 \text{ ft}^4/\text{sec Hp})}{(47.5 \text{ ft lift} + 203.2 \text{ ft pressure head})} = 2.11 \text{ cfs}$$

5. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
Not running during site visit			

6. Theoretical Pump Capacity – Pump at Sump:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO GROUND SURFACE (THE LIFT FROM THE WATER SURFACE TO THE PUMP)	LIFT TO PLACE OF USE (THE LIFT FROM THE PUMP TO THE PLACE OF USE)	TOTAL PUMP OUTPUT (IN CFS)
NA				

Reminder: For pump calculations use the reference information at the end of this document.

7. Provide pump calculations:

NA

8. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
NA			

9. Additional notes or comments related to the system:

NA

B. Groundwater Source Information (Well and Sump)

1. Is the appropriation from a dug well (sump)?

NO

If "NO", items 4 through 6 relating to this section may be deleted.

Reminder: Construction standards for sumps can be found in OAR 690-210-0400.

Received by OWRD
OCT 21 2026
Salem, OR

2. If the appropriation involves a **SUMP**, provide the following information for each **SUMP**:

LENGTH	WIDTH	AVERAGE DIAMETER	MAXIMUM DEPTH	SURFACE AREA (IN ACRES)	VOLUME IN CUBIC FEET OR ACRE FEET
NA					

3. If the sump is curbed constructed with watertight surface curbing, describe the curbing:

CURBING MATERIAL (CONCRETE, CONCRETE TILES, OR STEEL)	IF CONCRETE, PROVIDE THE THICKNESS OF THE WALL
NA	

C. Additional notes or comments related to the system:

Note:

Client noted the well is an artesian well in the winter and spring months.

Note:

Water levels can be read through 1/2 inch galvanized pipe through the metal plate on top of the sanitary seal on the east side of the well with a vent cap that has a rubber check ball to restrict any water that could flow out of the port when the water levels are high.

SECTION 5 CONDITIONS

All conditions contained in the transfer final order, or any extension final order shall be addressed. Reports that do not address all performance related conditions will be returned.

1. Time Limits:

Describe how the water user has complied with each of the development timelines established in the transfer final order and any extensions of time issued for the transfer:

	DATE FROM TRANSFER	DATE THE NEW AND/OR ADDITIONAL POA(S) WERE READY FOR USE *THIS DATE MUST FALL BETWEEN THE "ISSUANCE DATE" AND THE "COMPLETENESS DATE"
ISSUANCE DATE	June 23, 2025	
COMPLETENESS DATE FROM ORDER (C)	October 1, 2026	September 2026

* MUST BE WITHIN PERIOD BETWEEN TRANSFER FINAL ORDER, OR ANY EXTENSION FINAL ORDER ISSUANCE AND THE DATE TO COMPLETE THE CHANGE

2. Is there an extension final order(s)?

NO

If "NO", you may delete the following table.

Received by OWRD
OCT 21 2026
Salem, OR

OCT 21 2026

Salem, OR

YES

(new and existing)

3. Measurement Conditions:

- a. Does the transfer final order, or any extension final order require the installation of a meter or other approved measuring device?

If "NO", items b through f relating to this section may be deleted.

Reminder: If a meter or approved measuring device was required, the COBU map must indicate the location of the device in relation to the point of appropriation.

- b. Has a meter been installed?

YES

c. Meter Information

POA NAME OR #	MANUFACTURER	SERIAL #	CONDITION (WORKING OR NOT)	CURRENT METER READING	DATE INSTALLED
Well 1	McCrometer	26-03638-06	Working	6173600 gallons (September 30, 2026)	September 2026*
Well 2	Glo Tech GEM2	GEM 26061224	Working	10,336.07 gallons (September 30, 2026)	September 2026

***Note:**

Well 1 meter is a portable meter attached in the middle of a 10 foot long 6 inch diameter galvanized pipe that can be transported and used on different fields requiring water use to be reported. Initial and final meter readings are recorded once the meter is no longer being used as this site.

If a meter has been installed, items d through f relating to this section may be deleted.

4. Recording and reporting conditions

- a. Is the water user required to report the water use to the Department?

NO

If "NO", item b relating to this section may be deleted.

5. Other conditions required by the transfer final order or extension final order:

- a. Were there special well construction standards?

NO

- b. Was submittal of a ground water monitoring plan required?

NO

- c. Other conditions?

YES

If "YES" to any of the above, identify the condition and describe the water user's actions to comply with the condition(s):

c) Condition:

Water shall be acquired from the same aquifer (water source) as the original point of appropriation.

Compliance:

Original Well 1 (MARI 4776) develops water within the alluvial aquifer through perforations in the casing within the depth intervals of 40 to 90 feet with in layers of blue shale and sand

and gravel.

New Authorized Well 2 (MARI 72116) develops water within the alluvial aquifer through perforations in the casing within the depth intervals of 155 to 230 feet with in layers of cemented gravels.

It appears this well obtains water from the alluvial aquifer; therefore, this condition has been met.

Received by OWRD

OCT 21 2026

Salem, OR

SECTION 6 ATTACHMENTS

Provide a list of any additional documents you are attaching to this report:

ATTACHMENT NAME	DESCRIPTION
Claim of Beneficial Use Map	Claim of Beneficial Use Map, modified Certificate 34795
State Water Well Report – MARI 72116	Well log and driller's notes for MARI 72116 – Well 2
BLM Cadastral Map	BLM Cadastral Map T. 6S. R. 2W. showing DLC and Government Lot locations
BLM Cadastral Map	BLM Cadastral Map T. 6S. R. 3W. showing DLC and Government Lot locations

SECTION 7 CLAIM OF BENEFICIAL USE MAP

For the purpose of this Claim, the map identifying the location of the place of use does not require a new survey. The location of the place of use identified on the Claim map should be based on the original right of record at the time the transfer final order was issued. In transfers approved for additional points of appropriation, the original points must be identified the map based on the original right of record at the time the transfer final order was issued.

In order to properly examine your claim, the Department must have an accurate map that meets the criteria described in OAR 690-014-0170 and OAR 690-305-0010, which are provided below for your convenience:

OAR 690-014-0170 Minimum Requirements for Maps for Permit or Transfer Final Order Claims of Beneficial Use

- (1) Maps submitted by a CWRE as part of the Claim of Beneficial Use shall meet the standards in OAR chapter 690, division 305. In addition, the map shall meet the following criteria:
 - (a) Horizontal accuracy is required only to ten feet for the purpose of locating and quantifying water rights. Maps shall be developed from any standard survey method. Traverse closures are not required.
 - (b) Maps shall clearly designate the place of use and point of diversion or appropriation for each source and use.

- (c) The map shall indicate by description, in relation to the point of diversion or appropriation, the location of any fish screens, by-pass devices, and measuring devices required by the permit or transfer final order.
 - (d) The following statement shall be placed on the map: "This map is not intended to provide legal dimensions or locations of property ownership lines."
- (2) A CWRE may make a written request to the Director for a waiver of one or more mapping standards. The Director will determine whether the waiver shall be allowed and will respond to such requests in writing.

OAR 690-305-0010 General Map Criteria

Each map submitted to the Department shall meet the following general criteria in addition to any specific criteria identified in the rules for the relevant water right transaction:

- (1) Drawing
 - (a) The map shall be drafted on paper or polyester film with ink or otherwise printed in an indelible form with sufficient clarity so as to be easily reproduced or scanned. Maps may be submitted electronically in portable document format (pdf) and must be prepared consistent with, and include the same information as, a paper map.
 - (b) The preferred paper size is 8.5 inches by 11 inches and should be no larger than 30 inches by 30 inches. A map greater than 30 inches by 30 inches may be submitted if the Department grants, by mail or electronic means, advance approval of the larger size.
 - (c) Beginning April 1, 2029, regardless of whether the map is submitted electronically, on paper, or on polyester film, for any map that OAR chapter 690 requires be prepared by a Certified Water Right Examiner, a digital file containing the coordinate system and geospatial features of the map as specified by the Department shall be submitted in addition to the map, unless the Department provides a waiver. The digital file shall be submitted as a shapefile or other approved format in a manner required by the Department.
 - (d) A platted and recorded subdivision map, deed description survey map, or county assessor map may be submitted as the application map if all of the required information included in sections (2) and (3) of this rule is clearly shown.
 - (e) An aerial image may be provided in addition to the map to aid the Department in understanding the proposal.
 - (f) The map submitted under subsection (a) shall be the official record of the water right. An aerial image or digital file shall not be the official record of the water right.
- (2) Scale
 - (a) The map shall be drawn to a standard, even-numbered scale and one-inch shall not exceed 1320 feet.
 - (b) The map scale may exceed 1320 feet per inch if the Department grants, by mail or electronic means, advance approval of the requested scale.

Received by OWRD

OCT 21 2026

Salem, OR

- (c) Notwithstanding subsection (a) and (b), for maps identifying the location of a municipal use place of use, one-inch can exceed 1320 feet; provided that the scale is sufficient to identify the quarter-quarters involved in the place of use.

- (3) Features: Features shall be clearly identified and labeled. Unless otherwise indicated in rule, the following features must be included in each map submitted to the Department:

Received by OWRD

OCT 21 2026

Salem, OR


- (a) Mapping scale.
- (b) North directional symbol.
- (c) Legend.
- (d) General location of main canals, ditches, flumes, pipelines, pumps, or other water delivery features used to transport water from the point(s) of diversion or appropriation to the place use and to include the delivery features at the place of use.
- (e) Other topographical features such as rivers, creeks, streams, lakes, reservoirs, ponds, roads, or railroads that may be helpful to clarify and identify the location of points of diversion, wells, dams, and places of use.
- (f) Location and flow direction of the water way if the source is surface water. If multiple water ways exist in the area of the proposed diversion and use, the map must identify the location and flow direction of the additional water ways.
- (g) Township, range, section, quarter-quarter, and tax lot(s), donation land claims, or government lots where water will be or has been diverted, conveyed, and used. If the map is for municipal use the map:
 - (A) Must identify but does not need to label the quarter-quarters,
 - (B) Does not need to identify or label tax lots, donation land claims, or government lots.
- (h) Location of each proposed or developed diversion point, well (point of appropriation), or dam by reference to a recognized public land survey corner. For a reservoir without a dam, the center of the reservoir shall be referenced to a recognized public land survey corner.
 - (A) The locations shall be shown by distance and bearing, or by coordinates (distance north or south and distance east or west from the corner). In addition, they shall also include latitude and longitude as established by a global positioning system.
 - (B) Latitude and longitude coordinates shall be expressed as degrees-decimal with five or more digits after the decimal (e.g., 42.53764^o). The datum used to establish the coordinates shall be indicated on the map. Examples of datums include NAD 83, NAD 27 and WGS84.
- (i) Location of the proposed or developed place of use by township, range, section, and nearest quarter-quarter section.
 - (A) For irrigation or nursery use, the map shall additionally indicate the place of use in each quarter-quarter of a section by shading or hatchuring and indicate the number of acres in each quarter-quarter section, donation land claim, government lot, or other recognized public land survey lines.
 - (B) For places of use that are limited to a point, such as a stock watering tank, the location may also be identified by distance and bearing, or by

coordinates (distance north or south and distance east or west from the corner). In addition, they shall include latitude and longitude as established by a global positioning system.

- (C) Latitude and longitude coordinates shall be expressed as degrees-decimal with five or more digits after the decimal (e.g., 42.53764^o). The datum used to establish the coordinates shall be indicated on the map. Examples of datums include NAD 83, NAD 27 and WGS84.
- (D) Where more than one point of diversion or well is included, the map must clearly identify the place(s) of use served by each point of diversion or well.
- (j) If for a supplemental irrigation application or claim of beneficial use, the location and water right reference number of the underlying primary right, registration or claim.
- (k) Any other information the Department requests and considers necessary to evaluate the water right transaction.

Received by OWRD
OCT 21 2026
Salem, OR

South, Range N^o 3 West, Willamette Meridian.



Received by OWRD
OCT 21 2026
Salem, OR

Joseph Delores
Notification "436"
Claim "51"
Acres 333.72

Earl D. Jones.
g "504"

H

Augustus Lam
Notification 35
Claim 61

John Albrights.
Not. 393
Claim 67

Received by OMRD

OCT 21 2026

Salern, OR

STATE OF OREGON
WATER SUPPLY WELL REPORT

Well 2
MARI 72116

WELL I.D. LABEL# L 158763
START CARD # 1080877
ORIGINAL LOG #

Page 1 of 3

5/1/2026

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

(1) LAND OWNER

Owner Well I.D. _____
First Name _____ Last Name _____
Company GOLDEN VALLEY FARMS
Address 7385 HOWELL PRAIRIE RD NE
City SILVERTON State OR Zip 97381

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: _____

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 245.00 ft.

BORE HOLE			SEAL			sacks/
Dia	From	To	Material	From	To	lbs
24	0	10	Cement	0	39	176
20	10	39			Calculated	47
16	39	245			Calculated	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☐ Other: _____
Backfill placed from _____ ft. to _____ ft. Material _____
Filter pack from 114 ft. to 245 ft. Material PEA ROCK Size 3/8
Explosives used: ☐ Type _____ Amount _____
Seal Placement Begin Date 4/20/2026 Begin Time 16 40

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+ From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	16	☒ 2	153	0.375	ST	☒		OUT.	242.5
L	12		114	0.250	ST	☒			
L	12		230	0.250	ST	☒			

Temp casing ☒ Yes Dia 20 From + ☒ 1 To 39

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type V-Wire Material Stainless Steel

Perf/ Screen	Casing/ Screen	Dia	From	To	Scr/slot width	Slot length	# of slots	Tele/ Pipe size
Screen	Liner	12	155	194	.135			Pipe Size
Screen	Liner	12	194	204	.03			Pipe Size
Screen	Liner	12	204	230	.135			Pipe Size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Pump	1400	41.5	147	4

Temperature 54 °F Lab analysis ☐ Yes By _____
Water quality concerns? ☐ Yes (describe below) TDS amount 90 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 6.00 S N/S Range 3.00 W E/W WM
Sec 1 NW 1/4 of the SE 1/4 Tax Lot 100
Tax Map Number _____ Lot _____
Lat _____ " or 45.07737000 DMS or DD
Long _____ " or -122.99840000 DMS or DD
☒ Street address of well ☐ Nearest address
2731 WACONDA RD NE, GERVAIS, OR 97026

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration _____
Completed Well 4/23/2026 ☒ 6
Flowing Artesian? ☒ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 17.00

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
12/24/2025	17	21	10		4
1/2/2026	51	57	150		4
4/23/2026	155	227	3000		☒ 6

(11) WELL LOG

Ground Elevation 121.06 FT

Material	From	To
Soil Brown	0	3
Silt Brown	3	17
Silt Brown Sandy	17	21
Gravel Medium with Clay Binder Brown	21	27
Gravel Coarse Cemented Grey	27	29
Gravel Coarse with Clay Binder Grey	29	35
Gravel Coarse Cemented Grey	35	44
Gravel Medium with Clay Grey	44	51
Sand Black Coarse Loose	51	52
Gravel Medium/Coarse Loose Grey	52	57
Gravel Coarse Cemented Brown	57	64
Gravel Medium with Clay Brown	64	77
Gravel Coarse Cemented Brown	77	89
Clay Grey	89	91
Silt Blue Grey Sandy	91	94
Gravel Coarse with Clay Blue	94	99
Clay Grey Blue	99	114
Silt Blue	114	119
Silt Blue Sandy	119	122

Construction Begin Date 12/22/2025 Begin Time 08 00 End Date 4/23/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number _____ Date _____
Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1487 Date 5/1/2026
Signed DANIEL STADELI (E-filed)
Drilling Company: Westerberg Drilling, Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

**WATER SUPPLY WELL REPORT -
continuation page**
MARI 72116
WELL I.D. LABEL# L158763
START CARD # 1080877
5/1/2026
ORIGINAL LOG #
(2a) PRE-ALTERATION

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material From To Amt sacks/lbs

(5) BORE HOLE CONSTRUCTION

BORE HOLE				SEAL				sacks/ lbs
Dia	From	To	Material	From	To	Amt		
							Calculated	
							Calculated	
							Calculated	
							Calculated	

FILTER PACK

From	To	Material	Size

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe Location

(7) PERFORATIONS/SCREENS

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

Water Quality Concerns

From	To	Description	Amount	Units

(10) STATIC WATER LEVEL

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)

(11) WELL LOG

Material	From	To
Sand Grey Fine Dirty	122	129
Clay Blue	129	134
Clay Blue with Gravel	134	141
Silt Blue with Gravel	141	147
Silt Grey Sandy	147	149
Gravel Cemented	149	152
Silt Grey some Gravel	152	155
Gravel Cemented Grey	155	159
Silt Grey	159	160
Gravel Coarse Cemented Grey	160	179
Silt Grey	179	181
Gravel Coarse Grey Loosly Cemented	181	190
Cobbles 6" Minus Loose Grey with Gravel	190	194
Sand Medium with Small Gravel Grey	194	203
Gravel 3" Minus Clean Loose	203	208
Gravel Cemented Grey	208	211
Gravel 3" Minus Semi Cemented	211	213
Gravel 3" Minus Cemented	213	227
Silt Blue Grey	227	235
Silt Packed & Dry Grey	235	245

Received by OWRD

OCT 21 2026

Salem, OR

Name of person(s) who assisted with construction and Trainee License # / Helper #

Assistant Name	Type	#
EVAN HAAS	HELPER WATER	8889025
MIKE HAMILTON	HELPER WATER	8888965

Comments/Remarks

16" Drive shoe cut off @ 237.5' - 242.5'. 12" Pipe size screen is heavy duty construction with 11.5" ID Top of 12" riser has flush 12" drive shoe @ 114' - 115' Tail pipe has 1 1/4" x 2.5" lift bar 12" above 3/8" plate bottom

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72116

5/1/2026

Received by OWRD

OCT 21 2026

Salem, OR

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301

(503)986-0900



LOCATION OF WELL

Latitude: 45.07737000 Datum: WGS84

Longitude: -122.99840000

Township/Range/Section/Quarter-Quarter Section:

WM6.00S3.00W1NWSE

Address of Well:

2731 WACONDA RD NE, GERVAIS, OR 97026

Well Label: 158763

Printed: April 24, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor



OREGON



Received by OWRD

OCT 21 2026

Salem, OR

Date Received (Date Stamp Here)

OWRD Over-the-Counter Submission Receipt

Applicant Name(s) & Address: Massee Farms Bayou LLC d/b/a Landholding
7385 Howell Prairie Rd NE, Silverton OR 97305

Transaction Type: Claim

Fees Received: \$ 345.00

☐ Cash

☒ Check:

Check No. 2737

Name(s) on Check: Will McGill Surveying

Thank you for your submission. Oregon Water Resources Department (Department) staff will review your submittal as soon as possible.

If your submission is determined to be complete, you will receive a receipt for the fees paid and an acknowledgement letter stating your submittal is complete.

If determined to be incomplete, your submission and the accompanying fees will be returned with an explanation of deficiencies that must be addressed in order for the submittal to be accepted.

If you have any questions, please feel free to contact the Department's Customer Service staff at 503-986-0801 or 503-986-0810.

Sincerely,

OWRD Customer Service Staff

Submission received by: Corie Lornien
(Name of OWRD staff)

Instructions for OWRD staff:

- Complete this Submission Receipt and make two (2) copies. Place one copy with the check/cash; and place the other copy with the submission (i.e., the application or other document).
- Date-stamp all pages. (NOTE: Do not stamp check.)
- Give this original Submission Receipt to the applicant.
- Record Submission Receipt information on the "RECEIVED OVER THE COUNTER" log sheet.
- Fold and put one copy of the Submission Receipt with check/cash into the Safe slot. Place the other copy of the Submission Receipt with submission (application/other document) in the top drawer of filing cabinet.