

**Oregon Water Resources Department
Water Rights Division**

Water Rights Application
Number G-17010

Prior to the issuance of a permit, the Department must receive permit recording fees in the amount of \$300.00. Please include your application number on your check made out to the Oregon Water Resources Department.

Proposed Final Order

Summary of Recommendation: The Department recommends that the attached draft permit, for Well 2 and Well 3, be issued with conditions.

Application History

On September 18, 2008, WIPJR1 LLC submitted an application to the Department for the following water use permit:

- Amount of Water: 0.78 cubic foot per second (CFS)
- Use of Water: irrigation use on 140.3 acres
- Source of Water: Well 1, Well 2, and Well 3 in Simpson Creek Basin
- Area of Proposed Use: Marion County within Section 7 and Section 18, Township 8 South, Range 1 West, W.M.

On October 31, 2008, the Department mailed the applicant notice of its Initial Review, determining that "Ground water will not likely be available in the amounts requested from Well 1 without injury to prior rights and/or within the capacity of the resource, therefore the use of 0.78 CFS from Well 1 in Simpson Creek Basin for irrigation use on 140.3 acres may not be allowed. The use of 0.78 CFS from Well 2 and Well 3 in Simpson Creek Basin for irrigation use on 140.3 acres may be allowed during the full period requested, March 1 through October 31 of each year." The applicant did not notify the Department to stop processing the application within 14 days of that date.

On November 4, 2008, the Department gave public notice of the application in its weekly notice. The public notice included a request for comments, and information for interested persons about both obtaining future notices and a copy of the Proposed Final Order. No written comments were received within 30 days.

In reviewing applications, the Department may consider any relevant sources of information, including the following:

- recommendations by other state agencies
- any applicable basin program
- any applicable comprehensive plan or zoning ordinance
- the amount of water available
- the rate and duty for the proposed use
- pending senior applications and existing water rights of record
- designations of any critical ground water areas
- the Scenic Waterway requirements of ORS 390.835
- applicable statutes, administrative rules, and case law
- any general basin-wide standard for flow rate and duty of water allowed
- the need for a flow rate and duty higher than the general standard
- any comments received

Findings of Fact

The Willamette Basin Program allows irrigation.

Well 1, Well 2, and Well 3 in Simpson Creek Basin are not within or above a State Scenic Waterway.

Ground Water Findings Under OAR 690-009

The Department determined, consistent with OAR 690-009-0040(4), that the proposed ground water use will not have the potential for substantial interference with surface water.

In making this determination, the Department considered whether:

- (a) There is a hydraulic connection from the proposed well(s) to any surface water sources.
- (b) The point of appropriation is a horizontal distance less than one-fourth mile from the surface water source;
- (c) The rate of appropriation is greater than five cubic feet per second, if the point of appropriation is a horizontal distance less than one mile from the surface water source;
- (d) The rate of appropriation is greater than one percent of the pertinent adopted minimum perennial streamflow or instream water right with a senior priority date, if one is applicable, or of the discharge that is equaled or exceeded 80 percent of time, as determined or estimated by the Department, and if the point of appropriation is a horizontal distance less than one mile from the surface water source;
- (e) The ground water appropriation, if continued for a period of 30 days, would result in stream depletion greater than 25 percent of the rate of appropriation, if the point of appropriation is a horizontal distance less than one mile from the surface water source.

According to the Department's rules, the potential for substantial interference is assumed if (a) and either (b) or (c) or (d) or (e) are met. For this application, the Department determined that there is no potential for substantial interference, because either (a) is not met, or (b), (c), (d) or (e) are not met, or both.

An assessment of ground water availability has been completed by the Department's Ground Water/Hydrology section. A copy of this assessment is in the file. The proposed water use from Well 1 will not likely be available in the amounts requested without injury to prior rights and/or within the capacity of the resource. However, if properly conditioned, the proposed water use from Well 2 and Well 3 will avoid injury to existing rights and the resource.

The Department finds that the amount of water requested, 0.78 CFS, is an acceptable amount.

The proposed ground water use is not within a designated critical ground water area.

Conclusions of Law

Under the provisions of ORS 537.621, the Department must presume that a proposed use will ensure the preservation of the public welfare, safety and health if the proposed use is allowed in the applicable basin program established pursuant to ORS 536.300 and 536.340 or given a preference under ORS 536.310(12), if water is available, if the proposed use will not injure other water rights and if the proposed use complies with rules of the Water Resources Commission.

The proposed use requested in this application is allowed in the Willamette Basin Program, or a preference for this use is granted under the provisions of ORS 536.310(12).

Water is not available for the proposed use from Well 1. However, water is available from Well 2 and Well 3.

The proposed use will not injure other water rights.

The proposed use complies with other rules of the Water Resources Commission not otherwise described above.

The proposed use complies with the State Agency Agreement for land use.

No proposed flow rate and duty of water higher than the general basin-wide standard is needed.

For these reasons, the required presumption has been established.

Under the provisions of ORS 537.621, once the presumption has been established, it may be overcome by a preponderance of evidence that either:

- (a) One or more of the criteria for establishing the presumption are not satisfied; or
- (b) The proposed use would not ensure the preservation of the public welfare, safety and health as demonstrated in comments, in a protest . . . or in a finding of the department that shows:
 - (A) The specific aspect of the public welfare, safety and health under ORS 537.525 that would be impaired or detrimentally affected; and
 - (B) Specifically how the identified aspect of the public welfare, safety and health under ORS 537.525 would be impaired or be adversely affected.

In this application, all criteria for establishing the presumption have been satisfied, as noted above. The presumption has not been overcome by a preponderance of evidence that the proposed use would impair or be detrimental to the public interest.

The Department therefore concludes that water is available in the amount necessary for the proposed use; the proposed use will not result in injury to existing water rights; and the proposed use would ensure the preservation of the public welfare, safety and health as described in ORS 537.525.

When issuing permits, ORS 537.628(1) authorizes the Department to include limitations and conditions which have been determined necessary to protect the public welfare, safety, and health. The attached draft permit is conditioned accordingly.

Recommendation

The Department recommends that the attached draft permit be issued with conditions.

DATED January 27, 2009



*If you have any questions,
please check the information
box on the last page for the
appropriate names and
phone numbers.*

for Phillip C. Ward, Director
Water Resources Department

Protests

Under the provisions of ORS 537.153(7) (for surface water) or ORS 537.621(8) (for ground water), you can protest this Proposed Final Order. Protests must be received in the Water Resources Department no later than **March 13, 2009**. Protests must be in writing, and must include the following:

- Your name, address, and telephone number;
- A description of your interest in the Proposed Final Order, and, if you claim to represent the public interest, a precise statement of the public interest represented;
- A detailed description of how the action proposed in this Proposed Final Order would impair or be detrimental to your interest;
- A detailed description of how the Proposed Final Order is in error or deficient, and how to correct the alleged error or deficiency;
- Any citation of legal authority to support your protest, if known; and
- If you are not the applicant, the protest fee of \$350 required by ORS 536.050 and proof of service of the protest upon the applicant.
- If you are the applicant, a statement of whether or not you are requesting a contested case hearing. If you do not request a

hearing, the Department will presume that you do not wish to contest the findings of the Proposed Final Order.

- *If you do not protest this Proposed Final Order and if no substantive changes are made in the Final Order, you will not have an opportunity for judicial review, protest or appeal of the Final Order when it is issued.*

Requests for Standing

Under the provisions of ORS 537.153(7) (for surface water) or ORS 537.621(8) (for ground water), persons other than the applicant who support a Proposed Final Order can request standing for purposes of participating in any contested case proceeding on the Proposed Final Order or for judicial review of a Final Order.

Requests for standing must be received in the Water Resources Department no later than **March 13, 2009**. Requests for standing must be in writing, and must include the following:

- The requester's name, mailing address and telephone number;
- If the requester is representing a group, association or other organization, the name, address and telephone number of the represented group;
- A statement that the requester supports the Proposed Final Order as issued;
- A detailed statement of how the requester would be harmed if the Proposed Final Order is modified; and
- A standing fee of \$100.00. If a hearing is scheduled, an additional fee of \$250.00 must be submitted along with a request for intervention.

After the protest period has ended, the Director will either issue a Final Order or schedule a contested case hearing. The contested case hearing will be scheduled only if a protest has been submitted and either:

- upon review of the issues, the director finds that there are significant disputes related to the proposed use of water, or
- the applicant requests a contested case hearing within 30 days after the close of the protest period.

If you do not request a hearing within 30 days after the close of the protest period, or if you withdraw a request for a hearing, notify the

Department or the administrative law judge that you will not appear or fail to appear at a scheduled hearing, the Director may issue a Final Order by default. If the Director issues a Final Order by default, the Department designates the relevant portions of its files on this matter, including all materials that you have submitted relating to this matter, as the record for purpose of proving a prima facie case upon default.

This document was prepared by Jeana Eastman. If you have any questions about any of the statements contained in this document I am most likely the best person to answer your questions. You can reach me at 503-986-0859.

If you have questions about how to file a protest or a request for standing, please refer to the respective sections in this Proposed Final Order entitled "Protests" and "Requests for Standing". If you have previously filed a protest and want to know its status, please contact Patricia McCarty at 503-986-0820.

If you have other questions about the Department or any of its programs please contact our Customer Service Group at 503-986-0801. Address all other correspondence to:

Water Rights Section, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266, Fax: 503-986-0901.

DRAFT

This is not a permit.
STATE OF OREGON

DRAFT

COUNTY OF MARION

DRAFT PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS DRAFT PERMIT IS HEREBY ISSUED TO

WIPJR1 LLC
1410 LAKESIDE COURT SUITE 109
YAKIMA, WA 98902

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-17010

SOURCE OF WATER: WELL 2 AND WELL 3 IN SIMPSON CREEK BASIN

PURPOSE OR USE: IRRIGATION USE ON 140.3 ACRES

MAXIMUM RATE: 0.78 CUBIC FOOT PER SECOND

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: SEPTEMBER 18, 2008

WELL LOCATIONS:

WELL 2: SE $\frac{1}{4}$ SE $\frac{1}{4}$, SECTION 7, T8S, R1W, W.M.; 150 FEET NORTH AND
150 FEET WEST FROM SE CORNER, SECTION 7

WELL 3: NE $\frac{1}{4}$ SE $\frac{1}{4}$, SECTION 7, T8S, R1W, W.M.; 2100 FEET NORTH AND
150 FEET WEST FROM SE CORNER, SECTION 7

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 2.5 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SE $\frac{1}{4}$ SW $\frac{1}{4}$ 9.5 ACRES
NE $\frac{1}{4}$ SE $\frac{1}{4}$ 27.5 ACRES
SW $\frac{1}{4}$ SE $\frac{1}{4}$ 9.5 ACRES
SE $\frac{1}{4}$ SE $\frac{1}{4}$ 39.9 ACRES
SECTION 7

NE ¼ NE ¼ 13.8 ACRES
NW ¼ NE ¼ 26.0 ACRES
NE ¼ NW ¼ 14.1 ACRES
SECTION 18
TOWNSHIP 8 SOUTH, RANGE 1 WEST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the meter(s) in good working order. The permittee shall keep a complete record of the amount of water used each month, and shall submit an annual report which includes the recorded water use measurements to the Department by December 1 of each year. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- B. The permittee shall allow the watermaster access to the meter(s); provided however, where any meter is located within a private structure, the watermaster shall request access upon reasonable notice.

(1) Use of water from any well, as allowed herein, shall be controlled or shut off if the well displays:

- (a) An average water level decline of three or more feet per year for five consecutive years; or
- (b) A total water level decline of fifteen or more feet; or
- (c) A hydraulic interference decline of fifteen or more feet in any neighboring well providing water for senior exempt uses or wells covered by prior rights.

(2) The permittee/appropriator shall be responsible for complying with each of the following requirements for measuring water levels in the well(s).

- (a) Use of water from a new well shall not begin until an initial static water level in the well has been measured and reported to the Department.
- (b) In addition to the measurement required in subsection (a) of this section, a water level measurement shall be made each year during the period March 1 through March 31.

- (c) All water level measurements shall be made by a qualified individual. Qualified individuals are certified water rights examiners, registered geologists, registered professional engineers, licensed land surveyors, licensed water well constructor, licensed pump installer, or the permittee/appropriator.
- (d) Any qualified individual measuring a well shall use standard methods of procedure and equipment designed for the purpose of well measurement. The equipment used shall be well suited to the conditions of construction at the well. A list of standard methods of procedure and suitable equipment shall be available from the Department.
- (e) The permittee/appropriator shall report the record of measurement to the Department on a form available from the Department. The record of measurement shall include both measurements and calculations, shall include a certification as to their accuracy signed by the individual making the measurements, and shall be submitted to the Department within 90 days from the date of measurement. The Department shall determine when any of the declines cited in section (1) are evidenced by the well measurement required in section (2).

The wells shall be cased and sealed into hard basalt below an elevation of 340 feet, or to a sufficient depth to ensure that the open interval is no shallower than the basal portion of the Sentinel Bluffs Member of the Columbia River Basalt Group.

Ground-water production in each well shall be limited to a single aquifer in the Columbia River Basalt Group. The open interval in each well shall be no greater than 100 feet except as noted below. Open interval means the total length of borehole that is not behind sealed casing. The borehole above the open interval shall be continuously cased and continuously sealed to land surface. A larger open interval may be approved by the Department if the applicant can demonstrate, using packer tests or other suitable methods, that the hydraulic heads of water-bearing zones in the proposed open interval are equivalent, or if the applicant can demonstrate that the open interval is part of a continuous zone of interconnected porous materials such as a sequence of pillow lavas or an hyaloclastite complex.

During any pump test required by this permit, observation water-level measurements shall also be made in at least one of the nearest existing wells on the permit. The observation wells shall be idle prior to and during the test. Measurements shall be made at the same times as in the pumped well, shall be accurate to at least 0.1 of a foot, and shall be recorded on the Department's Pump Test Data Sheets or an acceptable substitute. The pump test report shall identify each well by its

corresponding Well ID (well tag number) or OWRD Well Log ID and shall include a map or aerial photo showing the well locations to an accuracy of at least 50 feet.

The permittee shall instruct the well constructor to contact the Ground Water Section of the Water Resources Department prior to drilling each well to arrange for the collection of drill cuttings.

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The well(s) shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

If the riparian area is disturbed in the process of developing a point of appropriation, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR Chapter 635, Division 415, Section 030 adopted November 13, 1991 shall be followed.

The use may be restricted if the quality of downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

Prior to receiving a certificate of water right, the permit holder shall submit to the Water Resources Department the results of a pump test meeting the Department's standards for each point of appropriation (well), unless an exemption has been obtained in writing under OAR 690-217. The Director may require water-level or pump-test data every ten years thereafter.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

Completion of construction and application of the water shall be made within five years of the date of permit issuance. If beneficial use of permitted water has not been made before this date, the permittee may submit an application for extension of time, which may be approved based upon the merit of the application.

Within one year after making beneficial use of water, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner.

Issued _____, 2009

DRAFT - THIS IS NOT A PERMIT

for Phillip C. Ward, Director
Water Resources Department

Mailing List for PFO Copies

Application #G-17010

PFO Date January 27, 2009

Original mailed to applicant:

WIPJR1 LLC, 1410 LAKESIDE COURT SUITE 109, YAKIMA, WA 98902

Copies sent to:

1. WRD - File # G-17010
2. Water Availability: Ken Stahr

PFO and Map Copies sent to:

3. WRD - Watermaster # 16

Copies sent to Other Interested Persons (CWRE, Agent, Well Driller, Commenter, etc.)

4. Boatwright, Corbey, CWRE #208
Boatwright Engineering Inc., 2613 12th Street SE, Salem OR
97302

<p>Copies Mailed</p> <p>By: _____ (SUPPORT STAFF)</p> <p>on: _____ (DATE)</p>

CASEWORKER : jme