

Oregon Water Resources Department
Water Rights Division

Water Rights Application
Number R-87276

Final Order

Appeal Rights

This is a Final Order in other than contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

This statement of judicial review rights does not create a right to judicial review of this order, if judicial review is otherwise precluded by law. Where no changes have been made to a Proposed Final Order on a water right application and no protests have been filed during the protest period, the Final Order is not subject to judicial review.

Application History

On August 27, 2008, Victor Schneider Jr. submitted an application to the Department for a water use permit. The Department issued a Proposed Final Order on May 5, 2009. The protest period closed June 19, 2009, and no protest was filed.

The proposed use would not impair or be detrimental to the public interest.

Order

Application R-87276 is therefore approved as proposed by the Proposed Final Order. Upon resolution of the outstanding issues described below, a permit shall be issued authorizing the proposed water use.

Prior to issuance of a permit, outstanding fees in the amount of \$400 must be paid and Transfer T-10705 must be approved.

Failure to meet this requirement within 60 days from the date of this Final Order may result in the proposed rejection of the application.

If you need to request additional time, your written request should be received in the Salem office of the Department within 60 days of this Final Order. The Department will evaluate the request and determine whether or not the request may be approved.

DATED August 6 , 2009

E. Timothy Wall.

for Phillip C. Ward, Director
Water Resources Department

This document was prepared by Jeana Eastman. If you have any questions about any of the statements contained in this document I am most likely the best person to answer your questions. You can reach me at 503-986-0859.

If you have previously filed a protest and want to know its status, please contact Patricia McCarty at 503-986-0820.

If you have other questions about the Department or any of its programs please contact our Customer Service Group at 503-986-0801.

Address all other correspondence to: Water Rights Section, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266, Fax: 503-986-0901.

DRAFT

This is not a permit.
STATE OF OREGON

DRAFT

COUNTY OF CLACKAMAS

DRAFT PERMIT TO CONSTRUCT A RESERVOIR AND STORE THE PUBLIC WATERS

THIS DRAFT PERMIT IS HEREBY ISSUED TO

VICTOR SCHNEIDER, JR
37485 S HWY 213
MOUNT ANGEL, OR 97362

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: R-87276

SOURCE OF WATER: RUNOFF AND BUTTE CREEK, TRIBUTARIES OF PUDDING RIVER

STORAGE FACILITY: REMEMBRANCE LAKE

PURPOSE OR USE OF THE STORED WATER: MULTIPLE PURPOSE

MAXIMUM VOLUME: 100.0 ACRE FEET EACH YEAR

WATER MAY BE APPROPRIATED FOR STORAGE DURING THE PERIOD: NOVEMBER 1
THROUGH MAY 31

DATE OF PRIORITY: AUGUST 27, 2008

The area submerged by the reservoir, when full, will be 7.3 ACRES and
the maximum height of the dam shall not exceed 29.3 FEET.

DAM LOCATION: SW ¼ NE ¼, SECTION 8, T6S, R1E, W.M.; 2075 FEET SOUTH AND
1200 FEET EAST FROM N1/4 CORNER, SECTION 8

BUTTE CREEK: SW ¼ NE ¼, SECTION 8, T6S, R1E, W.M.; 2110 FEET SOUTH AND
1120 FEET EAST FROM N1/4 CORNER, SECTION 8

THE AREA TO BE SUBMERGED BY THE RESERVOIR IS LOCATED AS FOLLOWS:

NE ¼ NE ¼
NW ¼ NE ¼
SW ¼ NE ¼
SE ¼ NE ¼
SECTION 8

TOWNSHIP 6 SOUTH, RANGE 1 EAST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at the Butte Creek point of diversion.

- B. Before water use may begin under this permit, a staff gage that measures the entire range and stage between full reservoir level and dead pool level must be installed in the reservoir. The staff gage shall be United States Geological Survey style porcelain enamel iron staff gage style A, C, E or I.
- C. The permittee shall maintain such devices in good working order, shall keep a complete record of the amount of water used each month and shall submit a report which includes the recorded water-use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring procedures for review and approval.
- E. The permittee shall allow the watermaster access to the devices; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.

The storage of water allowed herein is subject to the installation and maintenance of an outlet pipe (with a minimum diameter of 8" for any in-channel reservoir). This requirement may be waived if the Department determines other means have been provided to evacuate water when necessary.

The permittee shall pass all live flow outside the storage season described above.

This permit does not provide for the appropriation of water for out-of-reservoir uses, the maintenance of the water level or maintaining a suitable freshwater condition. If any water is used for out-of-reservoir purposes, or any live flow is appropriated to maintain either the water level or a suitable freshwater condition, a secondary water right is required.

The permittee shall install, maintain, and operate fish screening and by-pass devices consistent with current Oregon Department of Fish and Wildlife (ODFW) standards. Fish screening is to prevent fish from entering the proposed diversion while by-pass devices provide adequate upstream and downstream passage for fish. The required screen and by-pass devices are to be in place and functional, and approved in writing by ODFW prior to diversion of any water. The permittee may submit evidence in writing that ODFW has determined screens and/or by-pass devices are not necessary.

The permittee shall not construct, operate or maintain any dam or artificial obstruction to fish passage in the channel of the subject stream without providing a fishway to ensure adequate upstream and downstream passage for fish, unless the permittee has requested and been granted a fish passage waiver by the Oregon Fish and Wildlife Commission. The permittee is hereby directed to contact an Oregon Department of Fish and Wildlife Fish Passage Coordinator, before beginning construction of any in-channel obstruction.

DAM CONDITIONS

All construction shall be performed under the supervision of a registered professional engineer licensed in Oregon.

No embankment fill shall be placed until preparation of the foundation and the excavation of the core trench has been completed and examined in entirety by the engineer of record, or by the Water Resources Dam Safety Engineer, or both.

The constructed works shall conform to the approved plans and specifications on file with the Water Resources Dam Safety program. The engineer of record shall notify the Water Resources Dam Safety program before making any significant change to the approved design prior to or during construction.

No water shall be stored until the Water Resources Department receives written certification from the engineer of record that construction has been completed in accordance with the approved plans and specifications. If final construction deviates from the approved design a set reproducible as constructed drawings, including a revised reservoir capacity graph or table, must accompany the engineer's letter of completion.

Routine maintenance or repair of the dam, its spillway and all appurtenant structures shall be performed to include, but not limited to, the removal of woody vegetation or debris, prompt restoration of areas of erosion or to replace defective equipment necessary for the continued safe operation of the project works.

Except for routine repair and maintenance, design plans and specifications must be prepared by an Oregon licensed professional engineer and approved by the Water Resources Dam Safety program prior to any enlargement, modification, or alteration of the dam, its spillway or any appurtenant structure.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

If the riparian area is disturbed in the process of developing a point of diversion, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR 635-415, shall be followed.

The use may be restricted if the quality of the source stream or downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water allowed herein may be made only at times when sufficient water is available to satisfy all prior rights, including prior rights for maintaining instream flows.

Construction shall be completed and the permitted volume of water shall be stored within five years of the date of permit issuance. If additional time is needed, the permittee may submit an application for extension of time, which may be approved based upon the merit of the application.

Within one year after storage of water, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner.

Issued _____, 2009

DRAFT - THIS IS NOT A PERMIT

for Phillip C. Ward, Director
Water Resources Department