

Kerry Kavanagh

From: Bob Maynard
Sent: Thursday, May 12, 2011 8:20 AM
To: Kris Byrd; Ron Jacobs; Mike Zwart; Kerry Kavanagh
Cc: Ivan Gall
Subject: Application G-17451 Chris Ray

Hi everyone, yesterday 5/11/2011 I inspected MALH 27, which is in application G-17451 for well construction standards. No seal was found on MALH 27, the inspection port was not usable, so it was dug out, it seems that it was basically a dummy port and was for looks only, the landowner torched an opening so that I could get a static water level, but the well has a 10 inch inner casing and the pump has an 8 inch column, so it was impossible to get the e-tape past the first coupler. The landowner then said that he was told that they were unable to get the pump out of the well for some reason, my guess after this inspection that the pump is rust/stuck in the well. The landowner is going to try and get the pump removed before anything else is done on this well, if the pump can not be pulled, there is no reason to repair this well, at that point I recommend abandonment of MALH 27 and drilling a replacement well.

The well is located at N 44.32820 W -117.93938 epa 17.4

I did not attach a well ID tag to this well at time of inspection, I wanted to see what the out come of this well was first. If the pump can be pulled, then when the well is repair the driller will attach a tag
If you have any questions please call, later Bob