Oregon Water Resources Department

Water Right Services Division

Water Rights Application Number S-54855

Final Order Extension of Time for Permit Number S-41444 Permit Holder: City of Umatilla

Permit Information

Application File S-54855/ Permit S-41444

Basin 7 – Umatilla Basin / Watermaster District 5 Date of Priority: October 5, 1976

Authorized Use of Water

Source of Water: The Columbia River, a Tributary of the Pacific Ocean

Purpose or Use: Municipal Use

Maximum Rate: 23.0 Cubic Feet per Second (cfs)

Appeal Rights

This is a final order in other than a contested case. This order is subject to judicial review under ORS 183.484. A request for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either file for judicial review, or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

Application History

Permit S-41444 was issued by the Department on April 27, 1977. The permit called for completion of construction by October 1, 1978, and complete application of water to beneficial use by October 1, 1979. On March 19, 2003, City of Umatilla submitted an application to the Department for an extension of time for Permit S-41444. In accordance with OAR 690-315-0050(2), on June 26, 2012, the Department issued a Proposed Final Order proposing to extend the time to complete construction to October 1, 2055, and the time to fully apply water to beneficial use to October 1, 2055. The protest period closed August 10, 2012, in accordance with OAR 690-315-0060(1). No protest was filed.

Final Order: Permit S-41444 Page 1 of 8

The Department adopts and incorporates by reference the Proposed Final Order dated June 26, 2012.

At time of issuance of the Proposed Final Order the Department concluded that, based on the factors demonstrated by the applicant, the permit may be extended subject to the following conditions:

CONDITIONS

1. <u>Development Limitations</u>

Diversion of any water under Permit S-41444 shall only be authorized upon issuance of a final order approving a Water Management and Conservation Plan(s) (WMCP) under OAR Chapter 690, Division 86 which grants access to water under this extended permit. The required WMCP shall be submitted to the Department within 3 years of this Final Order. Use of water under Permit S-41444 must be consistent with this and subsequent WMCP's approved under OAR Chapter 690, on file with the Department.

The deadline established in the Extension Final Order for submittal of a WMCP shall not relieve a permit holder of any existing or future requirement for submittal of a WMCP at an earlier date as established through other orders of the Department. A WMCP submitted to meet the requirements of this order may also meet the WMCP submittal requirements of other Department orders.

2. Conditions to Maintain the Persistence of Listed Fish

A. Minimum Fish Flow Needs

a. Minimum fish flow needs in the Columbia River as recommended by ODFW are in Table 1, below; flows are to be measured in the Columbia River at McNary Dam. Daily flow reports for McNary Dam are available from the Fish Passage Center (FPC) established by the Northwest Power Planning Council (NPPC) at http://www.fpc.org/currentdaily/flowspil.txt.

Table 1

ODFW'S RECOMMENDED MINIMUM FISH FLOW NEEDS IN THE COLUMBIA RIVER, MEASURED AT MCNARY DAM NEAR UMATILLA, OREGON		
Month	1000 Cubic Feet per Second	
April 10 – June 30	260	
July 1 – August 31	200	

b. Alternate Streamflow Measurement Point

The location of a steamflow measurement point as established in these Conditions to Maintain the Persistence of Listed Fish may be revised if the City provides evidence in writing that ODFW has determined that persistence flows may be measured at an alternate streamflow

Final Order: Permit S-41444 Page 2 of 8

persistence flows may be measured at an alternate streamflow measurement point and provides an adequate description of the location of the alternate streamflow measurement point, and the Water Resources Director concurs in writing.

B. <u>Determining Water Use Reductions – Generally</u>

The maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition is determined in proportion to the amount by which the flows shown in Table 1 are missed based on a seven day rolling average of average of mean daily flows measured in the Columbia River at McNary Dam. The percent of missed target flows is defined as:

$$(1 - [QA/QT]) \times 100\%,$$

where Q_A is the actual flow measured at the designated location based on the seven day rolling average, and Q_T is the target flow (from Table 1).

The percent missed target flows applied to the undeveloped portion of the permit provides the maximum amount of undeveloped water that can be diverted as a result of this fish persistence condition, and is defined as:

$$E - (E \times \% \text{ missed target flows}),$$

where E is the undeveloped portion of the permit as of this extension, being 23.0 cfs.

The maximum amount of undeveloped water that can be diverted as a result of this fish persistence condition may be adjusted by a Consumptive Use Percentage, when applicable, as per Item 2.C., below. The overall reduction to the amount of the undeveloped portion of the permit will not exceed 20%.

When $Q_A \ge Q_T$, the amount of the undeveloped portion of the permit that can be diverted would not need to be reduced as a result of this fish persistence condition.

C. Consumptive Use Percentages for Utilization in Columbia River Calculations

a. <u>Initial Consumptive Use Percentages</u>

The City of Umatilla has not identified any Consumptive Use Percentages based on the return of flows to the Columbia River through effluent discharge. Thus, at this time the City may not utilize Consumptive Use Percentages for the purpose of calculating the maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition.

b. <u>First Time Utilization of Consumptive Use Percentages</u> Utilization of Consumptive Use Percentages for the purpose of calculating the maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition may begin after the issuance of the Final Order for this extension of time.

First time utilization of Consumptive Use Percentages is contingent upon the City (1) providing evidence in writing that ODFW has determined that withdrawal points and effluent discharges are within reasonable proximity to each other, such that fish habitat between the two points is not impacted significantly, and (2) submitting monthly Consumptive Use Percentages and receiving the Water Resources Director's concurrence with the proposed Consumptive Use Percentages. Utilization of Consumptive Use Percentages is subject to an approval period described in 2.C.f., below.

Consumptive Use Percentages submitted to the Department for review must (1) be specified as a percentage (may be to the nearest 1/10 percent) for each month of the year and (2) include a description and justification of the methods utilized to determine the percentages. The proposed Consumptive Use Percentages should be submitted on the Consumptive Use Percentages Update Form provided with the Final Order for this extension of time.

c. Consumptive Use Percentages Updates

Continuing the utilization of Consumptive Use Percentages for the purpose of calculating the maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition beyond an approval period (as described in 2.C.f., below) is contingent upon the City submitting updated Consumptive Use Percentages and receiving the Water Resources Director's concurrence with the proposed Consumptive Use Percentages Updates. Utilization of Consumptive Use Percentages Updates is subject to an approval period described in 2.C.f., below.

The updates to the Consumptive Use Percentages must (1) be specified as a percentage (may be to the nearest 1/10 percent) for each month of the year and (2) include a description and justification of the methods utilized to determine the percentages. The updates should be submitted on the *Consumptive Use Percentages Update Form* provided with the Final Order for this extension of time.

d. <u>Changes to Wastewater Technology and/or Wastewater Treatment Plant Practices</u>

If there are changes to either wastewater technology or the practices at the City's waster water treatment facility resulting in 25% or more reductions in average monthly return flows to the Columbia River, then the Consumptive Use Percentages in effect at that time may no longer be utilized for the purposes of calculating the maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition. The 25% reduction is based on a 10-year rolling average of monthly wastewater return flows to the Columbia River as compared to the average monthly wastewater return flows from the 10 year period just prior to date of the first approval period described in 2.C.f., below.

If such changes to either wastewater technology or the practices at the City's waster water treatment facility occur resulting in 25% reductions, further

utilization of Consumptive Use Percentages is contingent upon the City submitting Consumptive Use Percentages Updates as per 2.C.c., above, and receiving the Water Resources Director's concurrence with the proposed Consumptive Use Percentages.

e. Relocation of the Point(s) of Diversion(s) and/or Return Flows
If the point(s) of diversion(s) and/or return flows are relocated, Consumptive
Use Percentages in effect at that time may no longer be utilized for the
purposes of calculating the maximum amount of the undeveloped portion of
Permit S-41444 that can be diverted as a result of this fish persistence
condition.

After relocation of the point(s) of diversion(s) and/or return flows, further utilization of Consumptive Use Percentages is contingent upon the City (1) providing evidence in writing that ODFW has determined that any relocated withdrawal points and effluent discharge points are within reasonable proximity to each other, such that fish habitat between the two points is not impacted significantly, and (2) submitting Consumptive Use Percentages Updates as per 2.C.c., above, and receiving the Water Resources Director's concurrence with the proposed Consumptive Use Percentages.

f. Approval Periods for Utilization of Consumptive Use Percentages

The utilization of Consumptive Use Percentages for the purpose of calculating the maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition may continue for a 10 year approval period that begins 10 years from the Water Resources Director's most recent date of concurrence with Consumptive Use Percentages Updates as evidenced by the record, unless sections 2.C.d., or 2.C.e. (above) are applicable.

Consumptive Use Percentages (first time utilization or updates) which are submitted and receive the Director's concurrence will begin a new 10 year approval period. The approval period begins on the date of the Water Resources Director's concurrence with Consumptive Use Percentages Updates, as evidenced by the record. The City at its discretion may submit updates prior to the end of an approval period.

C. Examples

Example 1: Target flow met.

On April 15, the last seven mean daily flows in the Columbia River at McNary Dam¹ were 310K, 290K, 280K, 260K, 260K, 240K and 250K cfs. The seven day rolling average (QA) is 270K cfs. The amount of the undeveloped portion of the permit that can be diverted would not be reduced because the 7 day average of mean daily flows is greater than the 260K cfs target flow (QT) for April 15. In this example, $QA \ge QT$.

Example 2: Target flow missed.

Step 1: If on July 15, the average of the last seven mean daily flows (QA) was 170K cfs, and the target flow (QT) is 200K, then the target flow would be missed by 15.0%.

$$(1-(170/200)) \times 100\% = 15.0\%$$

Step 2: Assuming the Consumptive Use Percentage is 62.2%² during the month of July and the utilization of this percentage is authorized, and the target flow is missed by 15.0% (from Step 1), then the amount of the undeveloped portion of the permit that could be diverted would be reduced by 9.3%.

$$(62.2\% \times 15.0\%) / 100 = 9.3\%$$

(If adjustments are not to be made by a Consumptive Use Percentage, then the undeveloped portion of the permit would only be reduced by the % by which the target flow is missed – 15.0% in this example).

- Step 3: The overall reduction of 9.3% of the amount of the undeveloped portion of the permit does not exceed 20%.
- Step 4: The undeveloped portion of this permit as of this extension (E) is 23.0 cfs. Therefore, in this example, the maximum amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition is 20.9 cfs.

$$23.0 - ((23.0 \times 9.3\%) / 100) = 20.9$$

¹ Daily flow data for McNary Dam is available at http://www.fpc.org/currentdaily/flowspil.txt.

² Currently, the City of Umatilla may not utilize Consumptive Use Percentages for the purpose of calculating the amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of this fish persistence condition. The utilization of the Consumptive Use Percentage 65.2% is only for illustrative purposes in this example.

Step 5: Given that the entire permit, being 23.0 cfs, is undeveloped, if the amount of water legally authorized for a diversion at a given point in time (for example, authorization provided through a WMCP) is 5.0 cfs, then 5.0 cfs of water would be available for use by the permit holder.

In this example, the <u>5.0 cfs</u> of undeveloped water is less than the 20.9 cfs maximum undeveloped portion (from Step 4) that can be diverted as a result of this fish persistence condition. Therefore, there would be no required reduction in water use of the undeveloped portion under the permit.

Step 6: If the amount of water legally authorized for a diversion at a given point in time is 21.0 cfs, then of the 23.0 cfs only 21.0 cfs of undeveloped water would be available for use by the permit holder.

In this example, the 21.0 cfs of undeveloped water is greater than the 20.9 cfs maximum undeveloped portion (from Step 4) that can be diverted as a result of this fish persistence condition. Therefore, the amount of undeveloped water diverted by the permit holder would need to be reduced by <u>0.1 cfs</u>.

$$21.0 - 20.9 = 0.1$$

Summary

The applicant has demonstrated good cause for the permit extension pursuant to ORS 537.230, 539.010(5) and OAR 690-315-0080(3).

Order

The extension of time for Application S-54855, Permit S-41444, therefore, is approved subject to conditions contained herein. The deadline for completing construction is extended from October 1, 1999 to October 1, 2055. The deadline for applying water to full beneficial use within the terms and conditions the permit is extended from October 1, 1999 to October 1, 2055.

DATED: August 24, 2012

Dwight French, Water Right Services Division Administrator for


PHILLIP C. WARD, DIRECTOR

If you have any questions about statements contained in this document, please contact Ann L. Reece at (503) 986-0827.

If you have other questions about the Department or any of its programs, please contact our Water Resources Customer Service Group at (503) 986-0900

"Consumptive Use Percentages" Update Form

Date



TO THE WATER RIGHTS ADMINISTRATOR OF THE OREGON WATER RESOURCES DEPARTMENT

Re: Fish Persistence Condition Applicable to:

Application S-54855 / Permit S-41444

Permit Holder: City of Umatilla

Signature

"Consumptive Use Percentages" Updates

1. For each month listed below, provide the consumptive use percentage for the purpose of calculating the maximum total amount of the undeveloped portion of Permit S-41444 that can be diverted as a result of the fish persistence condition on the extension Final Order Dated August 24, 2012.

Month	Consumptive Use Percentage	Month	Consumptive Use Percentage
January	%	July	%
February	%	August	%
March	%	September	%
April	%	October	%
May	%	November	%
June	%	December	%

2.	Provide a description and justification of the methods utilized to determine the percentages
	Please attach additional pages as necessary.

3. The use of these "Consumptive Use Percentages" for the purposes stated above may continue for a 10 year approval period unless further utilization of Consumptive Use Percentages is contingent upon the City submitting Consumptive Use Percentages Updates due to changes in wastewater technology and/or the wastewater treatment plant or due to relocation of the point(s) of diversion(s) and/or return flows.

For OWRD use only				
WRD Concurs with these "Consumptive Use Percentages" Updates	☐ Yes ☐ No			
Approved by: for the Water Resources Director	Date:			