

PUBLIC INTEREST REVIEW FOR GROUNDWATER APPLICATIONS

TO: Water Rights Section Date March 18, 2015

FROM: Groundwater Section J. Hackett
Reviewer's Name

SUBJECT: Application G- 17938 Supersedes review of _____
Date of Review(s)

PUBLIC INTEREST PRESUMPTION; GROUNDWATER

OAR 690-310-130 (1) *The Department shall presume that a proposed groundwater use will ensure the preservation of the public welfare, safety and health as described in ORS 537.525.* Department staff review groundwater applications under OAR 690-310-140 to determine whether the presumption is established. OAR 690-310-140 allows the proposed use be modified or conditioned to meet the presumption criteria. **This review is based upon available information and agency policies in place at the time of evaluation.**

A. GENERAL INFORMATION: Applicant's Name: Patrick Campbell County: Gilliam

A1. Applicant(s) seek(s) 1.34 cfs from 3 well(s) in the John Day Basin,
 _____ subbasin Quad Map: Lone Rock Creek

A2. Proposed use Irrigation Seasonality: April 1 to October 31

A3. Well and aquifer data (attach and number logs for existing wells; mark proposed wells as such under logid):

Well	Logid	Applicant's Well #	Proposed Aquifer*	Proposed Rate(cfs)	Location (T/R-S QQ-Q)	Location, metes and bounds, e.g. 2250' N, 1200' E fr NW cor S 36
1	Proposed	1	CRB	1.34	4S/23E-8 SW-NW	2440' S, 640' E fr NW cor S 8
2	Proposed	2	CRB	1.34	4S/23E-8 SW-NW	1760' S, 1140' E fr NW cor S 8
3	Proposed	3	CRB	1.34	4S/23E-8 NE-NW	1100' S, 1600' E fr NW cor S 8
4						
5						

* Alluvium, CRB, Bedrock

Well	Well Elev ft msl	First Water ft bls	SWL ft bls	SWL Date	Well Depth (ft)	Seal Interval (ft)	Casing Intervals (ft)	Liner Intervals (ft)	Perforations Or Screens (ft)	Well Yield (gpm)	Draw Down (ft)	Test Type
1	1890				±250	0-21	0-21					
2	1880				±250	0-21	0-21					
3	1890				±250	0-21	0-21					

Use data from application for proposed wells.

A4. **Comments:** _____

A5. ☒ **Provisions of the** John Day Basin rules relative to the development, classification and/or management of groundwater hydraulically connected to surface water ☐ **are**, or ☒ **are not**, activated by this application.
 (Not all basin rules contain such provisions.)

Comments: The proposed wells will not produce from Quaternary alluvium, so the pertinent basin rules do not apply.

A6. ☐ **Well(s) #** _____, _____, _____, _____, _____, tap(s) an aquifer limited by an administrative restriction.
 Name of administrative area: _____
 Comments: _____

B. GROUNDWATER AVAILABILITY CONSIDERATIONS, OAR 690-310-130, 400-010, 410-0070

B1. Based upon available data, I have determined that groundwater* for the proposed use:

- a. ☐ is over appropriated, ☐ is not over appropriated, or ☒ cannot be determined to be over appropriated during any period of the proposed use. * This finding is limited to the groundwater portion of the over-appropriation determination as prescribed in OAR 690-310-130;
- b. ☐ will not or ☐ will likely be available in the amounts requested without injury to prior water rights. * This finding is limited to the groundwater portion of the injury determination as prescribed in OAR 690-310-130;
- c. ☐ will not or ☐ will likely to be available within the capacity of the groundwater resource; or
- d. ☒ will, if properly conditioned, avoid injury to existing groundwater rights or to the groundwater resource:
 - i. ☐ The permit should contain condition #(s) 7B, 7N;
 - ii. ☐ The permit should be conditioned as indicated in item 2 below.
 - iii. ☐ The permit should contain special condition(s) as indicated in item 3 below;

- B2.
- a. ☐ Condition to allow groundwater production from no deeper than _____ ft. below land surface;
 - b. ☐ Condition to allow groundwater production from no shallower than _____ ft. below land surface;
 - c. ☐ Condition to allow groundwater production only from the _____ groundwater reservoir between approximately _____ ft. and _____ ft. below land surface;
 - d. ☐ Well reconstruction is necessary to accomplish one or more of the above conditions. The problems that are likely to occur with this use and without reconstructing are cited below. Without reconstruction, I recommend withholding issuance of the permit until evidence of well reconstruction is filed with the Department and approved by the Groundwater Section.

Describe injury –as related to water availability– that is likely to occur without well reconstruction (interference w/ senior water rights, not within the capacity of the resource, etc): _____

B3. **Groundwater availability remarks:** _____

The applicant has proposed three wells that will produce from water-bearing zones in the Columbia River Basalt Group (CRBG). The CRBG consists of a series of lava flows that range up to 2000 feet thick in the vicinity of the proposed wells. Although unconfined ground water occurs near the surface of the basalts, most water occurs in confined aquifers that occupy thin rubble zones (interflow zones) that occur at the contacts between lava flows. The thick interiors of the basalt flows generally have very low porosity and permeability and act as confining beds. This physical geometry generally produces a stack of thin aquifers (interflow zones) separated by thick confining beds (flow interiors).

This is the first groundwater permit application in 4S/23E. Well density in the area is very sparse. The Department's Well Log Database contains only three wells for the entire 36 square mile township. As a result, very little is known about water-level trends and long-term groundwater availability. If a permit is issued it should contain water level measurement and water use reporting conditions.

C. GROUNDWATER/SURFACE WATER CONSIDERATIONS, OAR 690-09-040**C1. 690-09-040 (1): Evaluation of aquifer confinement:**

Well	Aquifer or Proposed Aquifer	Confined	Unconfined
1	Basalt	☒	☐
2	Basalt	☒	☐
3	Basalt	☒	☐
		☐	☐
		☐	☐

Basis for aquifer confinement evaluation: Water-bearing zones in the applicant's proposed wells will likely be confined by dense flow interiors.

C2. 690-09-040 (2) (3): Evaluation of distance to, and hydraulic connection with, surface water sources. All wells located a horizontal distance less than ¼ mile from a surface water source that produce water from an unconfined aquifer shall be assumed to be hydraulically connected to the surface water source. Include in this table any streams located beyond one mile that are evaluated for PSI.

Well	SW #	Surface Water Name	GW Elev ft msl	SW Elev ft msl	Distance (ft)	Hydraulically Connected?			Potential for Subst. Interfer. Assumed?	
						YES	NO	ASSUMED	YES	NO
1	1	Rock Creek	?	1800-1900	185	☒	☐	☐	☐	☒
1	2	Rock Creek	?	1800-1900	300	☒	☐	☐	☐	☒
1	3	Rock Creek	?	1800-1900	425	☒	☐	☐	☐	☒
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐

Basis for aquifer hydraulic connection evaluation: The proposed wells will be open from approximately 1860 to 1610 feet elevation. They will likely produce from one or more shallow water-bearing zones that locally intersect the channel of Rock Creek and are hydraulically connected to the creek.

Water Availability Basin the well(s) are located within: #30620427: ROCK CR > JOHN DAY R – AB WALLACE CAN

C3a. 690-09-040 (4): Evaluation of stream impacts for each well that has been determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. Limit evaluation to instream rights and minimum stream flows that are pertinent to that surface water source, and not lower SW sources to which the stream under evaluation is tributary. Compare the requested rate against the 1% of 80% *natural* flow for the pertinent Water Availability Basin (WAB). If Q is not distributed by well, use full rate for each well. Any checked ☒ box indicates the well is assumed to have the potential to cause PSI.

Well	SW #	Well < ¼ mile?	Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
1	1	☒	☐			☐	0.7	☒	<25%	☒
2	1	☒	☐			☐	0.7	☒	<25%	☒
3	1	☒	☐			☐	0.7	☒	<25%	☒
		☐	☐			☐		☐		☐
		☐	☐			☐		☐		☐
		☐	☐			☐		☐		☐
		☐	☐			☐		☐		☐
		☐	☐			☐		☐		☐
		☐	☐			☐		☐		☐

C3b. **690-09-040 (4):** Evaluation of stream impacts by total appropriation for all wells determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. **Complete only if Q is distributed among wells.** Otherwise same evaluation and limitations apply as in C3a above.

	SW #		Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
			☐			☐		☐		☐
			☐			☐		☐		☐
			☐			☐		☐		☐
			☐			☐		☐		☐

Comments: Modeling in similar circumstances suggests that pumping impacts will be less than 25% of the pumping rate after 30 days of pumping.

C4a. **690-09-040 (5):** Estimated impacts on **hydraulically connected surface water sources greater than one mile** as a percentage of the proposed pumping rate. Limit evaluation to the effects that will occur up to one year after pumping begins. This table encompasses the considerations required by 09-040 (5)(a), (b), (c) and (d), which are not included on this form. Use additional sheets if calculated flows from more than one WAB are required.

Non-Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
(A) = Total Interf.													
(B) = 80 % Nat. Q													
(C) = 1 % Nat. Q													
(D) = (A) > (C)		✓											
(E) = (A / B) x 100		%	%	%	%	%	%	%	%	%	%	%	%

(A) = total interference as CFS; (B) = WAB calculated natural flow at 80% exceed. as CFS; (C) = 1% of calculated natural flow at 80% exceed. as CFS; (D) = highlight the checkmark for each month where (A) is greater than (C); (E) = total interference divided by 80% flow as percentage.

Basis for impact evaluation:

C4b. **690-09-040 (5) (b) The potential to impair or detrimentally affect the public interest is to be determined by the Water Rights Section.**

C5. ☐ **If properly conditioned**, the surface water source(s) can be adequately protected from interference, and/or groundwater use under this permit can be regulated if it is found to substantially interfere with surface water:

- i. ☐ The permit should contain condition #(s) _____;
- ii. ☐ The permit should contain special condition(s) as indicated in "Remarks" below;

C6. SW / GW Remarks and Conditions

References Used:

Gannett, M., 1984, Groundwater assessment of the John Day basin. Oregon Water Resources Department, 99p.

D. WELL CONSTRUCTION, OAR 690-200

D1. Well #: _____ Logid: _____

D2. **THE WELL does not appear to meet current well construction standards based upon:**

- a. ☐ review of the well log;
- b. ☐ field inspection by _____;
- c. ☐ report of CWRE _____;
- d. ☐ other: (specify) _____

D3. **THE WELL construction deficiency or other comment is described as follows:** __________

_____D4. ☐ **Route to the Well Construction and Compliance Section for a review of existing well construction.**

Water Availability Tables

ROCK CR > JOHN DAY R - AB WALLACE CAN
JOHN DAY BASIN

Water Availability as of 3/18/2015

Watershed ID #: 30620427 ([Map](#))Exceedance Level: X

Date: 3/18/2015

Time: 2:08 PM

Water Availability Calculation

Monthly Streamflow in Cubic Feet per Second
 Annual Volume at 50% Exceedance in Acre-Feet

Month	Natural Stream Flow	Consumptive Uses and Storages	Expected Stream Flow	Reserved Stream Flow	Instream Flow Requirement	Net Water Available
JAN	10.70	0.01	10.70	0.00	0.00	10.70
FEB	22.70	0.02	22.70	0.00	0.00	22.70
MAR	45.00	4.11	40.90	0.00	0.00	40.90
APR	27.30	2.12	25.20	0.00	0.00	25.20
MAY	17.10	5.39	11.70	0.00	0.00	11.70
JUN	7.70	4.35	3.35	0.00	0.00	3.35
JUL	1.90	1.45	0.45	0.00	0.00	0.45
AUG	0.90	0.58	0.32	0.00	0.00	0.32
SEP	0.70	0.30	0.40	0.00	0.00	0.40
OCT	1.00	0.14	0.86	0.00	0.00	0.86
NOV	4.10	0.01	4.09	0.00	0.00	4.09
DEC	6.80	0.00	6.80	0.00	0.00	6.80
ANN	19,300.00	1,120.00	18,100.00	0.00	0.00	18,100.00

Well Location Map

G-17938, Campbell

1:24,000 scale

