

DEQ DIVISION 33 APPLICATION REVIEW SHEET

Recommendations for Water Right Applications that may affect the
Habitat of Sensitive, Threatened or Endangered Fish Species, OAR 690-33-310 through 340.

Application #: S 88082 Applicant's Name: Richard Tienhaara

1) Is there a connection to a 303(d) listed water quality limited water body? ☐ NO ☒ YES

Explain: **Spring # 2** flows into Jordan Creek, a tributary of Jack Creek. Water is not available at any time in Jack Creek, any further withdrawals from are likely to impact flows in Jack Creek. Jack Creek is listed for temperature and the Chetco River is listed for temperature, biological criteria, flow modification, and habitat modification.

Spring #1 flows directly into the Pacific Ocean. Water quality and quantity data are not available for the unnamed tributary.

2) What is the potential for this use to impact a water quality limited water body: ☒ HIGH ☐ MEDIUM ☐ LOW

Explain: **Spring # 2** - According to the OWRD May 29, 2015 initial review, surface water is not available at any time of the year. Withdrawals could affect surface water quantity and quality. The Chetco River has an instream water right that has the potential to be injured by the use.

The thermal assimilative capacity of a waterway is flow dependent (when streamflow is reduced, heat capacity is reduced). Reductions in streamflow is likely to exacerbate the temperature impairments. Oregon's biological criteria narrative standard is based on the assemblage of species needed to maintain a healthy resident biological community. Resident biological communities are the local food webs that support fish and other aquatic life. Reduced flows and increased pollutant loads or concentrations may degrade the biological community and therefore result in the diminution of habitat of sensitive, threatened, or endangered fish species.

Spring # 1 – Winchuck River is the only coastal frontal stream south of the Chetco River currently identified as impaired.

3) If the answer to question (2) is HIGH or MEDIUM, will the proposed use still result in diminution of water quality for the habitat of sensitive, threatened, or endangered fish species? ☐ NO ☒ YES

If YES, how? **Spring # 2** - Jack Creek supports runs of Coho Salmon and Chinook Salmon.

Increases in temperature would impact sensitive, threatened, and endangered fish. Fish require different stream temperatures based on their species and life history stage. Oregon's temperature criteria are based on the most sensitive species and life history stage at the location and season of concern. Chetco River stream temperatures limit the habitat of sensitive, threatened, and endangered fish. Any additional thermal loading would further impact the habitat. Flow reductions may impact the thermal assimilative capacity of the waterbody, increasing the concentration of pollutants.

Spring # 1 – NO - DEQ is unable to determine to the resident fish bearing status of the unnamed stream.

4) Can conditions be applied to mitigate the impact of the use?

☐ NO ☒ YES; recommend from Menu of Conditions and skip to question 7.

Spring 2 - DEQ concurs with the OWRD finding of denial based upon water availability. Flow for flow mitigation may be acceptable. Applicant should contact OWRD to discuss flow mitigation options.

Flow mitigation condition: Prior to water use under this permit, the applicant must transfer a permanent water right instream that is of no less volume than the amount identified in the permit. The mitigation flow must be sourced upstream of the groundwater use, and of similar water quality to that of the impacted reach, and must affect the impacted reach year-round.

Spring 1 - Water quality and quantity data are not available for the unnamed tributary.

5) If conditions cannot be identified to offset impacts, would the proposed use affect the Habitat of Sensitive, Threatened, or Endangered Fish Species? ☐ NO ☒ YES

If YES, please explain:

Spring 2 - Increases in temperature would impact sensitive, threatened, and endangered fish. Flow reductions may impact the thermal assimilative capacity of the waterbody, increasing the concentration of pollutants.

Spring 1 - NA

6) If a permit is issued, are there any conditions you would like to see included in the permit?

If **Spring # 2** is approved - flow mitigation condition: Prior to water use under this permit, the applicant must transfer a permanent water right instream that is of no less volume than the amount identified in the permit. The mitigation flow must be sourced upstream of the use, and of similar water quality to that of the impacted reach, and must affect the impacted reach year-round.

Spring # 1 - Before water use may begin under this permit; a totalizing flow meter must be installed at each diversion point.

7) Your recommendation under OAR 690-033-0330 (2): ☒ Approval with conditions
☐ Approval without conditions
☐ Denial

DEQ Representative signature: Pam Blake, ODEQ Date: April 11, 2016

WRD Contact: **Caseworker:** Kim French Water Rights Division, 503-986-0900 / Fax 503-986-0901

MENU OF CONDITIONS FOR WRD, ODFW, DEQ AND AG

The following condition will be included in any permit issued unless ODFW explicitly requests that it be omitted:

The permittee shall not construct, operate or maintain any dam or artificial obstruction to fish passage in the channel of the subject stream without providing a fishway to ensure adequate upstream and downstream passage for fish, unless the permittee has requested and been granted a fish passage waiver or exemption through the Oregon Department of Fish and Wildlife. The permittee is hereby directed to contact an Oregon Department of Fish and Wildlife Fish Passage Coordinator before beginning construction of any in-channel obstruction.

- fishself** The permittee shall install, maintain, and operate fish screening and by-pass devices consistent with current Oregon Department of Fish and Wildlife (ODFW) standards. Fish screening is to prevent fish from entering the proposed diversion while by-pass devices provide adequate upstream and downstream passage for fish. The required screen and by-pass devices are to be in place and functional prior to diversion of any water. Permittee shall obtain written approval from ODFW that the installation of the required screen and by-pass devices meets the state's criteria or the permittee shall submit documentation that ODFW has determined screens and/or by-pass devices are not necessary.
- fishapprove** The permittee shall install, maintain, and operate fish screening and by-pass devices consistent with current Oregon Department of Fish and Wildlife (ODFW) standards. Fish screening is to prevent fish from entering the proposed diversion while by-pass devices provide adequate upstream and downstream passage for fish. The required screen and by-pass devices are to be in place and functional, and approved in writing by ODFW prior to diversion of any water. The permittee may submit evidence in writing that ODFW has determined screens and/or by-pass devices are not necessary.
- fishdiv33** If the riparian area is disturbed in the process of developing a point of diversion, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR 635-415, shall be followed.
- The use may be restricted if the quality of the source stream or downstream waters decrease to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.
- The permittee shall install, maintain, and operate fish screening and by-pass devices consistent with current Oregon Department of Fish and Wildlife (ODFW) standards. Fish screening is to prevent fish from entering the proposed diversion while by-pass devices provide adequate upstream and downstream passage for fish. The required screen and by-pass devices are to be in place and functional, and approved in writing by ODFW prior to diversion of any water. The permittee may submit evidence in writing that ODFW has determined screens and/or by-pass devices are not necessary.
- fishmay** Notwithstanding that ODFW has made a determination that fish screens and/or by-pass devices are not necessary at the time of permit issuance, the permittee may be required in the future to install, maintain, and operate fish screening and by-pass devices to prevent fish from entering the proposed diversion and to provide adequate upstream and downstream passage for fish.
- b52** Water may be diverted only when Department of Environmental Quality sediment standards are being met.
- b5** The water user shall install and maintain adequate treatment facilities meeting current DEQ requirements to remove sediment before returning the water to the stream.
- b51a** The period of use has been limited to _____ through _____.
- b57** Before water use may begin under this permit, a totalizing flow meter must be installed at each diversion point.
- b58** Before water use may begin under this permit, a staff gage that measures the entire range and stage between full reservoir level dead pool storage must be installed in the reservoir. The staff gage shall be United States Geological Survey style porcelain enamel iron staff gage style A, C, E or I. Additionally, before water use may begin under this permit, if the reservoir is located in channel then weirs or other suitable measuring devices must be installed upstream and downstream of the reservoir, and, a gated valve outlet must be installed. A written waiver may be obtained from the local Watermaster if in his judgment the installation of the weir(s) will provide no public benefit.
- futile call** The use of water allowed herein may be made only at times when waters from the (NAME OF SURFACE WATER) would not otherwise flow into a tributary of the _____ River or sufficient water is available to satisfy all prior rights, including rights for maintaining instream flows.
- riparian** If the riparian area is disturbed in the process of developing a point of diversion, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR 635-415, shall be followed.
- wq** The use may be restricted if the quality of the source stream or downstream waters decrease to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.
- fence** The stream and its adjacent riparian area shall be fenced to exclude livestock.
- blv** Water must be diverted to a trough or tank through an enclosed water delivery system. The delivery system must be equipped with an automatic shutoff or limiting flow control mechanism or include a means for returning water to the stream source through an enclosed delivery system. The use of water shall not exceed 0.10 cubic feet per second per 1000 head of livestock.