

MEMO

Aug 29, 2016

FROM: GW: M. Thoma
(Reviewer's Name)

☒ YES☐ NO☒ YES☐ NO

Exercise of this permit is calculated to reduce monthly flows in _____ Scenic Waterway by the following amounts expressed as a proportion of the consumptive use by which surface water flow is reduced.

[illegible]

PUBLIC INTEREST REVIEW FOR GROUNDWATER APPLICATIONS

TO: Water Rights Section

Date August 29, 2016

FROM: Groundwater Section

Michael J Thoma

Reviewer's Name

SUBJECT: Application G- **18322**

Supersedes review of _____

Date of Review(s)

PUBLIC INTEREST PRESUMPTION; GROUNDWATER

OAR 690-310-130 (1) *The Department shall presume that a proposed groundwater use will ensure the preservation of the public welfare, safety and health as described in ORS 537.525.* Department staff review groundwater applications under OAR 690-310-140 to determine whether the presumption is established. OAR 690-310-140 allows the proposed use be modified or conditioned to meet the presumption criteria. **This review is based upon available information and agency policies in place at the time of evaluation.**

A. GENERAL INFORMATION:Applicant's Name: Manu Jones / Southern Algamated DevelopmentCounty: Josephine

A1. Applicant(s) seek(s) 0.07 cfs from 1 well(s) in the Rogue Basin,
Williams Creek subbasin

A2. Proposed use Nursery Seasonality: year-round

A3. Well and aquifer data (attach and number logs for existing wells; mark proposed wells as such under logid):

Well	Logid	Applicant's Well #	Proposed Aquifer*	Proposed Rate(cfs)	Location (T/R-S QQ-Q)	Location, metes and bounds, e.g. 2250' N, 1200' E fr NW cor S 36
1	JOSE 59715	1	Bedrock	0.07	38S/05W-36 SESW	323' N, 2344' E of SW cor S 36
2						
3						

* Alluvium, CRB, Bedrock

Well	Well Elev ft msl	First Water ft bls	SWL ft bls	SWL Date	Well Depth (ft)	Seal Interval (ft)	Casing Intervals (ft)	Liner Intervals (ft)	Perforations Or Screens (ft)	Well Yield (gpm)	Draw Down (ft)	Test Type
1	2360	210	46	11/19/2015	240	0-18	+2-18	0-240	220-240	30		A

Use data from application for proposed wells.

A4. **Comments:** _____

A5. ☒ **Provisions of the** Rogue (OAR 690-515) Basin rules relative to the development, classification and/or management of groundwater hydraulically connected to surface water ☐ **are**, or ☒ **are not**, activated by this application. (Not all basin rules contain such provisions.)

Comments: _____

A6. ☐ **Well(s) #** _____, _____, _____, _____, _____, tap(s) an aquifer limited by an administrative restriction. Name of administrative area: _____

Comments: _____

B. GROUNDWATER AVAILABILITY CONSIDERATIONS, OAR 690-310-130, 400-010, 410-0070

B1. Based upon available data, I have determined that groundwater* for the proposed use:

- a. ☐ is over appropriated, ☐ is not over appropriated, or ☒ cannot be determined to be over appropriated during any period of the proposed use. * This finding is limited to the groundwater portion of the over-appropriation determination as prescribed in OAR 690-310-130;
- b. ☐ will not or ☒ will likely be available in the amounts requested without injury to prior water rights. * This finding is limited to the groundwater portion of the injury determination as prescribed in OAR 690-310-130;
- c. ☐ will not or ☒ will likely to be available within the capacity of the groundwater resource; or
- d. ☒ will, if properly conditioned, avoid injury to existing groundwater rights or to the groundwater resource:
 - i. ☒ The permit should contain condition #(s) 7J (Scenic Waterway); Medium water-use reporting;
 - ii. ☐ The permit should be conditioned as indicated in item 2 below.
 - iii. ☐ The permit should contain special condition(s) as indicated in item 3 below;

- B2.
- a. ☐ Condition to allow groundwater production from no deeper than _____ ft. below land surface;
 - b. ☐ Condition to allow groundwater production from no shallower than _____ ft. below land surface;
 - c. ☐ Condition to allow groundwater production only from the _____ groundwater reservoir between approximately _____ ft. and _____ ft. below land surface;
 - d. ☐ Well reconstruction is necessary to accomplish one or more of the above conditions. The problems that are likely to occur with this use and without reconstructing are cited below. Without reconstruction, I recommend withholding issuance of the permit until evidence of well reconstruction is filed with the Department and approved by the Groundwater Section.

Describe injury –as related to water availability– that is likely to occur without well reconstruction (interference w/ senior water rights, not within the capacity of the resource, etc): _____

- B3. **Groundwater availability remarks:** The applicant's proposed POA is located within the upper reaches of the Cherry Cr. drainage approx. 800 ft above the flatter valley floor of the Williams Creek Valley. There are no OWRD Observation Well data in the area and also no permitted groundwater POAs – the nearest POA is nearly 1 mile away and 600 ft lower in elevation. Given the location of the POA it is unlikely that the proposed use will result in injury to existing groundwater users
- _____
- _____
- _____

C. GROUNDWATER/SURFACE WATER CONSIDERATIONS, OAR 690-09-040**C1. 690-09-040 (1):** Evaluation of aquifer confinement:

Well	Aquifer or Proposed Aquifer	Confined	Unconfined
1	Bedrock of Western Hayfork Terrane	☒	☐
		☐	☐
		☐	☐

Basis for aquifer confinement evaluation: the applicant's well log reports SWL several 10s of feet above 'first water'

C2. 690-09-040 (2) (3): Evaluation of distance to, and hydraulic connection with, surface water sources. All wells located a horizontal distance less than ¼ mile from a surface water source that produce water from an unconfined aquifer shall be assumed to be hydraulically connected to the surface water source. Include in this table any streams located beyond one mile that are evaluated for PSI.

Well	SW #	Surface Water Name	GW Elev ft msl	SW Elev ft msl	Distance (ft)	Hydraulically Connected?			Potential for Subst. Interfer. Assumed?	
						YES	NO	ASSUMED	YES	NO
1	1	Cherry Creek	~2310	1860	3500*	☒	☐	☐	☐	☒
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐

Basis for aquifer hydraulic connection evaluation: GW elevation is above SW elevation suggesting that groundwater is flowing towards and discharging to surface water.

*Distance reported here is to the nearest permitted surface water POD which is also the farthest upstream surface water POD on Cherry Creek. Above this POD Cherry Creek is mapped as intermittent and is not considered a viable surface water source.

Water Availability Basin the well(s) are located within: Williams Cr > Applegate R – At Mouth (ID# 70981)

C3a. 690-09-040 (4): Evaluation of stream impacts for each well that has been determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. Limit evaluation to instream rights and minimum stream flows that are pertinent to that surface water source, and not lower SW sources to which the stream under evaluation is tributary. Compare the requested rate against the 1% of 80% natural flow for the pertinent Water Availability Basin (WAB). If Q is not distributed by well, use full rate for each well. Any checked ☒ box indicates the well is assumed to have the potential to cause PSI.

Well	SW #	Well < ¼ mile?	Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
1	1	☐	☐	NA	-	☐	1.89	☒	**	☒
		☐	☐			☐		☐		☐
		☐	☐			☐		☐		☐

Comments: ** Interference @ 30 d could not be estimated because the terrain (high-relief slopes) and geology (fractured bedrock aquifer) do not meet model assumptions of the widely accepted techniques for determining stream depletion (e.g., Hunt 1999, 2003)

C3b. 690-09-040 (4): Evaluation of stream impacts by total appropriation for all wells determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. **Complete only if Q is distributed among wells.** Otherwise same evaluation and limitations apply as in C3a above.

	SW #	Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
		☐			☐		☐		☐

Comments: _____

- C4a. **690-09-040 (5):** Estimated impacts on **hydraulically connected surface water sources greater than one mile** as a percentage of the proposed pumping rate. Limit evaluation to the effects that will occur up to one year after pumping begins. This table encompasses the considerations required by 09-040 (5)(a), (b), (c) and (d), which are not included on this form. Use additional sheets if calculated flows from more than one WAB are required.

Non-Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													

Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
(A) = Total Interf.													
(B) = 80 % Nat. Q													
(C) = 1 % Nat. Q													
(D) = (A) > (C)		✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
(E) = (A / B) x 100		%	%	%	%	%	%	%	%	%	%	%	%

(A) = total interference as CFS; (B) = WAB calculated natural flow at 80% exceed. as CFS; (C) = 1% of calculated natural flow at 80% exceed. as CFS; (D) = highlight the checkmark for each month where (A) is greater than (C); (E) = total interference divided by 80% flow as percentage.

Basis for impact evaluation:

- C4b. **690-09-040 (5) (b)** The potential to impair or detrimentally affect the public interest is to be determined by the Water Rights Section.

- C5. ☐ **If properly conditioned**, the surface water source(s) can be adequately protected from interference, and/or groundwater use under this permit can be regulated if it is found to substantially interfere with surface water:
- ☐ The permit should contain condition #(s) _____;
 - ☐ The permit should contain special condition(s) as indicated in "Remarks" below;

- C6. **SW / GW Remarks and Conditions:** The applicant's proposed POA would be producing from an aquifer that has been found to be hydraulically connected to Cherry Cr. at a distance of < 1 mile. Because the proposed rate of appropriation is > 1% of the minimum monthly 80%-exceedance flows in the WAB, OAR 690-009 requires the Department to assume the proposed use will have the Potential for Substantial Interference (PSI). If the proposed rate were reduced to < 0.0198 cfs (8.9 gpm) then PSI would not be assumed.

References Used:

Hunt, B. 1999. *Unsteady Stream Depletion from Ground Water Pumping*. Journal of Hydrologic Engineering, Vol 8(1), pp 12-19

Hunt, B. 2003. *Unsteady Stream Depletion when Pumping from a Semiconfined Aquifer*. Journal of Hydrologic Engineering. Vol 8(1), pp 12-19

Wiley, T. J. 2006. *Preliminary Geologic Map of the Sexton Mountain, Murphy, Applegate, and Mount Isabelle 7.5' Quadrangles, Jackson and Josephine Counties, Oregon*. Oregon Dept. of Geology and Mineral Industries. OFR O-06-11

USGS US Topo 7.5-minute map for Tallowbox Mountain, OR 2014. Publication Date: 08/25/2014

D. WELL CONSTRUCTION, OAR 690-200

D1. Well #: _____ Logid: _____

D2. **THE WELL does not appear to meet current well construction standards based upon:**

- a. ☐ review of the well log;
 b. ☐ field inspection by _____;
 c. ☐ report of CWRE _____;
 d. ☐ other: (specify) _____

D3. **THE WELL construction deficiency or other comment is described as follows:** _____

 _____D4. ☐ Route to the Well Construction and Compliance Section for a review of existing well construction.**Water Availability Tables**

WILLIAMS CR > APPELATE R - AT MOUTH

ROGUE BASIN

Water Availability as of 8/29/2016

Watershed ID #: 70981 ([Map](#))

Exceedance Level: 80%

Date: 8/29/2016

Time: 3:30 PM

Water Availability Calculation

Consumptive Uses and Storages

Instream Flow Requirements

Reservations

Water Rights

Watershed Characteristics

Water Availability Calculation

Monthly Streamflow in Cubic Feet per Second

Annual Volume at 50% Exceedance in Acre-Feet

Month	Natural Stream Flow	Consumptive Uses and Storages	Expected Stream Flow	Reserved Stream Flow	Instream Flow Requirement	Net Water Available
JAN	67.30	1.16	66.10	0.00	110.00	-43.90
FEB	110.00	1.56	108.00	0.00	110.00	-1.56
MAR	107.00	1.16	106.00	0.00	110.00	-4.16
APR	62.70	3.75	59.00	0.00	110.00	-51.00
MAY	29.50	5.82	23.70	0.00	65.00	-41.30
JUN	10.30	8.11	2.19	0.00	40.00	-37.80
JUL	4.24	10.80	-6.56	0.00	15.00	-21.60
AUG	2.68	8.94	-6.26	0.00	5.00	-11.30
SEP	1.89	5.92	-4.03	0.00	50.00	-54.00
OCT	2.28	2.06	0.22	0.00	80.00	-79.80
NOV	6.60	0.38	6.22	0.00	80.00	-73.80
DEC	32.30	0.82	31.50	0.00	110.00	-78.50
ANN	54,800.00	3,060.00	52,600.00	0.00	53,300.00	15,200.00

Well Location Map

