

**Oregon Water Resources Department
Water Right Services Division**

Water Rights Application
Number G-18102

Proposed Final Order

Summary of Recommendation: The Department recommends that the attached draft permit be issued with conditions.

Findings of Fact

1. On June 10, 2015, Dennis Flynn Ranch submitted an application to the Department for the following water use permit:
 - Amount of Water: 1.60 cubic feet per second (CFS)
 - Use of Water: primary irrigation of 67.96 acres and supplemental irrigation of 60.0 acres
 - Source of Water: Well 1 (LAKE 52274/L94396) in Crooked Creek Basin
 - Area of Proposed Use: Lake County within Section 31, Township 35 South, Range 21 East, W.M.
2. On August 28, 2015, the Department mailed the applicant notice of its Initial Review, determining that "*Because not all items above are favorable, the appropriation of 1.60 CFS of water from Well 1 (LAKE 52274/L94396) in Crooked Creek Basin for primary irrigation of 67.96 acres and supplemental irrigation of 60.0 acres is not allowable, and it appears unlikely that a permit will be issued unless a suitable mitigation proposal is provided prior to issuance of the Proposed Final Order.*" The applicant did not notify the Department to stop processing the application within 14 days of that date.
3. On September 1, 2015, the Department gave public notice of the application in its weekly notice. The public notice included a request for comments, and information for interested persons about obtaining future notices and a copy of the Proposed Final Order. No written comments were received within 30 days.
4. The Department finds that the proposed partial cancellation of Certificates 55519 and 3633 provides sufficient mitigation to offset impacts on Crooked Creek during the months when surface water is not available.

In reviewing applications, the Department may consider any relevant sources of information, including the following:

- any applicable basin program
- applicable statutes, administrative rules, and case law
- the amount of water available

- the rate and duty for the proposed use
 - any general basin-wide standard for flow rate and duty of water allowed
 - the need for a flow rate and duty higher than the general standard
 - pending senior applications and existing water rights of record
 - any applicable comprehensive plan or zoning ordinance
 - recommendations by other state agencies
 - the Scenic Waterway requirements of ORS 390.835
 - designations of any critical groundwater areas
 - any comments received
5. The Goose & Summer Lake Basin Program allows irrigation (OAR 690-513-0050).
6. An assessment of groundwater availability has been completed by the Department's Groundwater/Hydrology section. A copy of this assessment is in the file. Groundwater will likely be available within the capacity of the resource, and if properly conditioned, the proposed use of groundwater will avoid injury to existing groundwater rights.
7. Groundwater Findings Under OAR 690-009
The Department determined, consistent with OAR 690-009-0040(4), that the proposed groundwater use will have the potential for substantial interference with surface water, namely Crooked Creek.

In making this determination, the Department considered whether:

- A. There is a hydraulic connection from the proposed well(s) to any surface water sources.
- B. The point of appropriation is a horizontal distance less than one-fourth mile from the surface water source;
- C. The rate of appropriation is greater than five cubic feet per second, if the point of appropriation is a horizontal distance less than one mile from the surface water source;
- D. The rate of appropriation is greater than one percent of the pertinent adopted minimum perennial streamflow or instream water right with a senior priority date, if one is applicable, or of the discharge that is equaled or exceeded 80 percent of time, as determined or estimated by the Department, and if the point of appropriation is a horizontal distance less than one mile from the surface water source;
- E. The groundwater appropriation, if continued for a period of 30 days, would result in stream depletion greater than 25 percent of the rate of appropriation, if the point of appropriation is a horizontal distance less than one mile from the surface water source.

For this application, the Department determined that there is the potential for substantial interference because of the following items described above: (A), (B), (D)

8. Because the proposed use of groundwater has the potential for substantial interference with surface water, an assessment of surface water availability has been completed. This assessment compared a calculation of natural streamflow minus the consumptive portion of all relevant rights of record. A copy of this calculation is in the file. This calculation determined that surface water is available for further appropriation (at an 80 percent exceedance probability) September 1 through May 30.
9. In accordance with OAR 690-033-0330, an interagency team reviewed this proposed use for potential adverse impacts on sensitive, threatened and endangered fish populations. This team consisted of representatives from the Oregon Departments of Water Resources (WRD), Environmental Quality (DEQ), Fish and Wildlife (ODFW), and Agriculture. WRD and ODFW representatives included both technical and field staff. The interagency team recommended that additional limitations or conditions of use be imposed on this application as follows:
 - The OWRD Watermaster recommended approval with mitigation.
 - ODFW recommended denial unless suitable mitigation is provided, citing negative impacts to sensitive species; requiring that before water use may begin under any permit issued, a totalizing flow meter must be installed at each diversion point; and that the use may be restricted if the quality of the source stream or downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.
 - DEQ recommended denial unless suitable mitigation is provided, citing diminution of habitat for sensitive, threatened, and/or endangered species.
10. On December 7, 2015, the Department received a mitigation proposal comprising two Affidavits for the Partial Cancellation of a Water Right Certificate, being 2.8 CFS from Crooked Creek for domestic, stock, and irrigation of 69.97 acres under Certificate 55519; and 1.2 CFS from Crooked Creek for irrigation of 30.0 acres under Certificate 3633.
11. Well 1 (LAKE 52274/L94396) in Crooked Creek Basin is not within or above a State Scenic Waterway.
12. The Department finds that the amount of water requested, 1.60 CFS, is an acceptable amount.

13. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.
14. The proposed groundwater use is not within a designated critical groundwater area.

Conclusions of Law

1. Under the provisions of ORS 537.621, the Department must presume that a proposed use will ensure the preservation of the public welfare, safety and health if the proposed use is allowed in the applicable basin program established pursuant to ORS 536.300 and 536.340 or given a preference under ORS 536.310(12), if water is available, if the proposed use will not injure other water rights and if the proposed use complies with rules of the Water Resources Commission.
2. The proposed use requested in this application is allowed in the Goose & Summer Lake Basin Program.
3. Water is **not** available for the proposed use.
4. The proposed use will not injure other water rights.
5. No proposed flow rate and duty of water higher than the general basin-wide standard is needed.
6. The application is in compliance with the State Agency Coordination Program regarding land use.
7. The proposed use complies with rules of the Water Resources Commission not otherwise described above.
8. For these reasons, the required presumption has **not** been established.
9. OAR 690-310-0140(2)(b) states that when the presumption is not established, the Department shall determine whether the proposed use will impair or adversely affect the public welfare, safety and health, and may make specific findings to demonstrate that even though the presumption is not established, the proposed use will not impair or adversely affect the public welfare, safety and health, and propose approval of the application with appropriate modifications or conditions.

To determine whether the proposed use will preserve the public welfare, safety and health, the factors in ORS 537.625(3), shown in *italics* below, have been considered as follows:

- (A) The conservation of the highest use of the water for all purposes, including irrigation, domestic use, municipal water

supply, power development, public recreation, protection of commercial and game fishing and wildlife, fire protection, mining, industrial purposes, navigation, scenic attraction, or any other beneficial use to which the water may be applied for which it may have a special value to the public.

Irrigation is classified under the Goose and Summer Lakes Basin Program, and therefore is one of the highest and best uses.

- (B) The maximum economic development of the waters involved.

Water for irrigation provides economic development of land and impacts the local community by increasing employment, therefore the economic development consideration is met.

- (C) The control of the waters of this state for all beneficial purposes, including drainage, sanitation, and flood control.

Appropriated water will be controlled until beneficial use of water via irrigation, and the proposed use must be made without waste, thus the control and beneficial-use consideration is met.

- (D) The amount of water available for appropriation for beneficial use.

Groundwater is not over-appropriated and will, if properly conditioned, avoid injury to existing groundwater rights or to the groundwater resource.

Although the proposed use has the potential for substantial interference with over-appropriated surface-water sources and surface water is not available during the entire period requested, mitigation provided by the partial cancellation of Certificates 55519 and 3633 will offset impacts of the proposed use on surface-water flows.

- (E) The prevention of wasteful, uneconomic, impractical, or unreasonable use of the waters involved.

The draft permit is conditioned such that wasteful, uneconomic, impractical, or unreasonable use of the waters involved is prevented. The proposed use, as conditioned in the attached draft permit, will require conservation measures and reasonable use of the water.

- (F) All vested and inchoate rights to the waters of this state or to the use of the waters of this state, and the means necessary to protect such rights.

The pending application's priority date and the Department's existing system of regulation are the means necessary to protect existing vested and inchoate rights, thus the protection of rights consideration is satisfied.

(G) The State Water Resources policy.

The Department determined the proposed use is consistent with the State Water Resources Policy formulated under ORS 537.505 to 537.534.

10. The Department therefore concludes that, in accordance with OAR 690-310-0140(2)(b), although the presumption is not established, the proposed use as modified and conditioned in the attached draft permit will ensure the preservation of the public welfare, safety and health.

Recommendation

The Department recommends that the attached draft permit be issued with conditions.

DATED December 20, 2016



E. Timothy Wallin, Water Rights Program Manager
for Thomas M. Byler, Director

Protests

Under the provisions of ORS 537.153(7) (for surface water) or ORS 537.621(8) (for groundwater), you can protest this Proposed Final Order. Protests must be received in the Water Resources Department no later than **February 3, 2017**. Protests must be in writing, and must include the following:

- Your name, address, and telephone number;
- A description of your interest in the Proposed Final Order, and, if you claim to represent the public interest, a precise statement of the public interest represented;
- A detailed description of how the action proposed in the Proposed Final Order would impair or be detrimental to your interest;
- A detailed description of how the Proposed Final Order is in error or deficient, and how to correct the alleged error or deficiency;
- Any citation of legal authority to support your protest, if known;
- To affect the department's determination that the proposed use in this application will, or will not, ensure the preservation of the public welfare, safety and health as described in ORS 537.525, ORS 537.621(2)(b) requires that a protest demonstrate, by a preponderance of evidence any of the following: (a) One or more of the criteria for establishing the presumption are, or are not, satisfied; or (b) The specific aspect of the public welfare, safety and health under ORS 537.525 that would be impaired or detrimentally affected, and specifically how the identified aspect of the public welfare, safety and health under ORS 537.525 would be impaired or be adversely affected;
- If you are the applicant, the protest fee of \$350 required by ORS 536.050; and
- If you are not the applicant, the protest fee of \$700 required by ORS 536.050 and proof of service of the protest upon the applicant.
- If you are the applicant, a statement of whether or not you are requesting a contested case hearing. If you do not request a hearing, the Department will presume that you do not wish to contest the findings of the Proposed Final Order.

Requests for Standing

Under the provisions of ORS 537.153(7) (for surface water) or ORS 537.621(8) (for groundwater), persons other than the applicant who support a Proposed Final Order can request standing for purposes of participating in any contested case proceeding on the Proposed Final Order or for judicial review of a Final Order.

Requests for standing must be received in the Water Resources Department no later than **February 3, 2017**. Requests for standing must be in writing, and must include the following:

- The requester's name, mailing address and telephone number;
- If the requester is representing a group, association or other organization, the name, address and telephone number of the represented group;
- A statement that the requester supports the Proposed Final Order as issued;
- A detailed statement of how the requester would be harmed if the Proposed Final Order is modified; and
- A standing fee of \$200. If a hearing is scheduled, an additional fee of \$500 must be submitted along with a petition for party status.

After the protest period has ended, the Director will either issue a Final Order or schedule a contested case hearing. The contested case hearing will be scheduled only if a protest has been submitted and either:

- upon review of the issues, the director finds that there are significant disputes related to the proposed use of water, or
- the applicant requests a contested case hearing within 30 days after the close of the protest period.

If you do not request a hearing within 30 days after the close of the protest period, or if you withdraw a request for a hearing, notify the Department or the administrative law judge that you will not appear or fail to appear at a scheduled hearing, the Director may issue a Final Order by default. If the Director issues a Final Order by default, the Department designates the relevant portions of its files on this matter, including all materials that you have submitted relating to this matter, as the record for purpose of proving a *prima facie* case upon default.

You may be represented by an attorney at the hearing. Legal aid organizations may be able to assist a party with limited financial resources. Generally, partnerships, corporations, associations, governmental subdivisions or public or private organizations are represented by an attorney. However, consistent with OAR 690-002-0020 and OAR 137-003-0555, an agency representative may represent a partnership, corporation, association, governmental subdivision or public or private organization if the Department determines that appearance of a person by an authorized representative will not hinder the orderly and timely development of the record in this case.

Notice Regarding Service Members: Active duty service members have a right to stay proceedings under the federal Service Members Civil Relief Act. 50 U.S.C. App. §§501-597b. You may contact the Oregon State Bar or the Oregon Military Department for more information. The toll-free telephone number for the Oregon State Bar is: 1 (800) 452-8260. The toll-free telephone number of the Oregon Military Department is: 1 (800) 452-7500. The Internet address for the United States Armed Forces Legal Assistance Legal Services Locator website is: <http://legalassistance.law.af.mil>

This document was prepared by Barbara Poage. If you have any questions about any of the statements contained in this document I can be reached at Barbara.J.Poage@state.or.us or 503-986-0859.

If you have questions about how to file a protest or a request for standing, please refer to the respective sections in this Proposed Final Order entitled "Protests" and "Requests for Standing". If you have previously filed a protest and want to know its status, please contact Patricia McCarty at 503-986-0820.

If you have other questions about the Department or any of its programs please contact our Customer Service Group at 503-986-0801. Address all other correspondence to:

Water Rights Section, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266, Fax: 503-986-0901.

DRAFT

This is not a permit.

DRAFT

STATE OF OREGON

COUNTY OF LAKE

DRAFT PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS DRAFT PERMIT IS HEREBY ISSUED TO

DENNIS FLYNN RANCH
31259 CLOVER FLAT ROAD
LAKEVIEW, OR 97630

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-18102

SOURCE OF WATER: WELL 1 (LAKE 52274/L94396) IN CROOKED CREEK BASIN

PURPOSE OR USE: IRRIGATION OF 67.96 ACRES AND SUPPLEMENTAL IRRIGATION OF 60.0 ACRES

MAXIMUM RATE: 1.60 CUBIC FEET PER SECOND

PERIOD OF USE: APRIL 1 THROUGH OCTOBER 15

DATE OF PRIORITY: JUNE 10, 2015

WELL LOCATION: SE ¼ NW ¼ SECTION 31, T35S, R21E, W.M.; 1395 FEET SOUTH AND 1324 FEET EAST FROM NW CORNER, SECTION 31

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 3.0 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

<u>OO</u>	<u>Primary</u>	<u>Supplemental</u>
SW ¼ SW ¼		21.16 ACRES
SE ¼ SW ¼	24.29 ACRES	
	SECTION 30	
NE ¼ NW ¼	38.0 ACRES	
NW ¼ NW ¼		34.14 ACRES
SW ¼ NW ¼		4.7 ACRES
SE ¼ NW ¼	5.67 ACRES	
	SECTION 31	

TOWNSHIP 35 SOUTH, RANGE 21 EAST, W.M.

Measurement devices, and recording/reporting of annual water use conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
- B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The permittee shall keep a complete record of the volume of water diverted each month, and shall submit a report which includes water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

Static Water Level Conditions

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the permit. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The permittee shall report an initial March static water-level measurement once well construction is complete and annual measurements thereafter. Annual measurements are required whether or not the well is used. The first annual measurement will establish a reference level against which future measurements will be compared. However, the Director may establish the reference level based on an analysis of other water-level data. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The Department may require the discontinuance of groundwater use, or reduce the rate or volume of withdrawal, from the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

Well Construction Condition

Each permitted well shall obtain groundwater solely from the predominantly basalt unit (which may contain some sedimentary layers) that underlies the predominantly basin-fill sediment unit (which may contain some basalt layers). Each well shall have continuous casing and continuous seal from land surface, through the predominantly basin-fill unit, and a minimum of five (5) feet into the predominantly basalt unit.

Dedicated Measuring Tube Condition

Wells with pumps shall be equipped with a minimum 3/4-inch diameter, unobstructed, dedicated measuring tube pursuant to figure 200-5 in OAR 690-200. If a pump has been installed prior to the issuance of this permit, and if static water levels and pumping levels can be measured using an electrical tape, then the installation of the measuring tube

can be delayed until such time that water levels cannot be measured or the pump is repaired or replaced.

Well Identification Tag Condition

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may be subject to cancellation, unless the Department authorizes the change in writing.

If substantial interference with surface water or a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The well(s) shall be constructed and maintained in accordance with the General Standards for the Construction and Maintenance of Water Supply Wells in Oregon. The works shall be equipped with a usable access port adequate to determine water-level elevation in the well at all times.

If the riparian area is disturbed in the process of developing a point of appropriation, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR 635-415, shall be followed.

The use may be restricted if the quality of downstream waters decreases to the point that those waters no longer meet state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

Prior to receiving a certificate of water right, the permit holder shall submit to the Water Resources Department the results of a pump test meeting the Department's standards for each point of appropriation (well), unless an exemption has been obtained in writing under OAR 690-217. The Director may require water-level or pump-test data every ten years thereafter.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

Construction of the well shall be made within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the begin construction deadline is missed.

Complete application of the water shall be made within five years of the date of permit issuance. If beneficial use of permitted water has not been made before this date, the permittee may submit an application for extension of time, which may be approved based upon the merit of the application.

Within one year after making beneficial use of water, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner.

Issued

DRAFT - THIS IS NOT A PERMIT

E. Timothy Wallin, Water Rights Program Manager
for Thomas M. Byler, Director