

Groundwater Review Summary Form

Application # G- 18385

GW Reviewer M. Thome Date Review Completed: 12-19-16

Summary of GW availability and Injury Review:

[] Groundwater for the proposed use is either over appropriated, will not likely be available in the amounts requested without injury to prior water rights, OR will not likely be available within the capacity of the groundwater resource per Section B of the attached review form.

Summary of Potential for Substantial Interference Review:

[] There is the potential for substantial interference per Section C of the attached review form.

Summary of Well Construction Assessment:

[] The well does not appear to meet current well construction standards per Section D of the attached review form. Route through Well Construction and Compliance Section.

This is only a summary. Documentation is attached and should be read thoroughly to understand the basis for determinations and for conditions that may be necessary for a permit (if one is issued).

MEMO

Dec 19, 2016

TO: Application G- 18385

FROM: GW: M. Thomas
(Reviewer's Name)

SUBJECT: Scenic Waterway Interference Evaluation

☐ YES

The source of appropriation is within or above a Scenic Waterway

☐ YES

~~□~~

Use the Scenic Waterway condition (Condition 7J)

☐ Per ORS 390.835, the Groundwater Section is **able** to calculate ground water interference with surface water that contributes to a Scenic Waterway. The calculated interference is distributed below.

☐ Per ORS 390.835, the Groundwater Section is **unable** to calculate ground water interference with surface water that contributes to a scenic waterway; **therefore, the Department is unable to find that there is a preponderance of evidence that the proposed use will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway.**

DISTRIBUTION OF INTERFERENCE

Calculate the percentage of consumptive use by month and fill in the table below. If interference cannot be calculated, per criteria in 390.835, do not fill in the table but check the "unable" option above, thus informing Water Rights that the Department is unable to make a Preponderance of Evidence finding.

Exercise of this permit is calculated to reduce monthly flows in _____ Scenic Waterway by the following amounts expressed as a proportion of the consumptive use by which surface water flow is reduced.

[illegible]

PUBLIC INTEREST REVIEW FOR GROUNDWATER APPLICATIONS

TO: Water Rights Section Date December 19, 2016
 FROM: Groundwater Section Michael J Thoma
 SUBJECT: Application G- 18385 Supersedes review of
 Date of Review(s)

PUBLIC INTEREST PRESUMPTION; GROUNDWATER

OAR 690-310-130 (1) The Department shall presume that a proposed groundwater use will ensure the preservation of the public welfare, safety and health as described in ORS 537.525. Department staff review groundwater applications under OAR 690-310-140 to determine whether the presumption is established. OAR 690-310-140 allows the proposed use be modified or conditioned to meet the presumption criteria. **This review is based upon available information and agency policies in place at the time of evaluation.**

A. GENERAL INFORMATION: Applicant's Name: Michael Kirschnick County: Lane

A1. Applicant(s) seek(s) 0.08 cfs from 1 well(s) in the Willamette Basin,
Long Tom River subbasin

A2. Proposed use Nursery (1 ac) Seasonality: year-round

A3. Well and aquifer data (attach and number logs for existing wells; mark proposed wells as such under logid):

Well	Logid	Applicant's Well #	Proposed Aquifer*	Proposed Rate(cfs)	Location (T/R-S QQ-Q)	Location, metes and bounds, e.g. 2250' N, 1200' E fr NW cor S 36
1	LANE 73023	1	Bedrock	0.08	18S/05W-09 NWSE	1620'N, 2220'W of SE cor S9
2						

* Alluvium, CRB, Bedrock

Well	Well Elev ft msl	First Water ft bls	SWL ft bls	SWL Date	Well Depth (ft)	Seal Interval (ft)	Casing Intervals (ft)	Liner Intervals (ft)	Perforations Or Screens (ft)	Well Yield (gpm)	Draw Down (ft)	Test Type
1	490	50	9	2/15/14	162	0-20	+1-39	2-162	42-162	125		A

Use data from application for proposed wells.

A4. Comments: _____

A5. ☒ Provisions of the Willamette (OAR 690-502) Basin rules relative to the development, classification and/or management of groundwater hydraulically connected to surface water ☐ are, or ☒ are not, activated by this application. (Not all basin rules contain such provisions.)

Comments: _____

A6. ☐ Well(s) # _____, _____, _____, _____, _____, tap(s) an aquifer limited by an administrative restriction.

Name of administrative area: _____

Comments: _____

B. GROUNDWATER AVAILABILITY CONSIDERATIONS, OAR 690-310-130, 400-010, 410-0070

B1. **Based upon available data**, I have determined that groundwater* for the proposed use:

- a. ☐ is over appropriated, ☐ is not over appropriated, or ☒ **cannot be determined to be** over appropriated during any period of the proposed use. * This finding is limited to the groundwater portion of the over-appropriation determination as prescribed in OAR 690-310-130;
- b. ☐ **will not** or ☐ **will** likely be available in the amounts requested without injury to prior water rights. * This finding is limited to the groundwater portion of the injury determination as prescribed in OAR 690-310-130;
- c. ☐ **will not** or ☐ **will** likely to be available within the capacity of the groundwater resource; or
- d. ☒ **will, if properly conditioned**, avoid injury to existing groundwater rights or to the groundwater resource:
- ☒ The permit should contain condition #(s) Medium Water-use Reporting;
 - ☐ The permit should be conditioned as indicated in item 2 below.
 - ☐ The permit should contain special condition(s) as indicated in item 3 below;

- B2. a. ☐ **Condition** to allow groundwater production from no deeper than _____ ft. below land surface;
- b. ☐ **Condition** to allow groundwater production from no shallower than _____ ft. below land surface;
- c. ☐ **Condition** to allow groundwater production only from the _____ groundwater reservoir between approximately _____ ft. and _____ ft. below land surface;
- d. ☐ **Well reconstruction** is necessary to accomplish one or more of the above conditions. The problems that are likely to occur with this use and without reconstructing are cited below. Without reconstruction, I recommend withholding issuance of the permit until evidence of well reconstruction is filed with the Department and approved by the Groundwater Section.

Describe injury –as related to water availability– that is likely to occur without well reconstruction (interference w/ senior water rights, not within the capacity of the resource, etc): _____

- B3. **Groundwater availability remarks:** There are no OWRD Observation Well data in the area of the proposed POA so groundwater over-appropriation cannot be determined. There are also no permitted groundwater POAs within several miles of the proposed POA so injury to existing permitted groundwater users is unlikely. However, the reviewer recommends that a working flowmeter be installed to monitor water use.
- _____
- _____
- _____

C. GROUNDWATER/SURFACE WATER CONSIDERATIONS, OAR 690-09-040**C1. 690-09-040 (1):** Evaluation of aquifer confinement:

Well	Aquifer or Proposed Aquifer	Confined	Unconfined
1	Bedrock of Spencer Fm	☒	☐
		☐	☐

Basis for aquifer confinement evaluation: The applicant's well log along with logs for the surrounding area and of similar depths as the applicant's typically report SWLs above *First Water* indicating confined aquifer conditions.

C2. 690-09-040 (2) (3): Evaluation of distance to, and hydraulic connection with, surface water sources. All wells located a horizontal distance less than ¼ mile from a surface water source that produce water from an unconfined aquifer shall be assumed to be hydraulically connected to the surface water source. Include in this table any streams located beyond one mile that are evaluated for PSI.

Well	SW #	Surface Water Name	GW Elev ft msl	SW Elev ft msl	Distance (ft)	Hydraulically Connected?			Potential for Subst. Interfer. Assumed?	
						YES	NO	ASSUMED	YES	NO
1	1	Middle Fk Coyote Cr	440	~380	11,200*	☒	☐	☐	☐	☒
						☐	☐	☐	☐	☐
						☐	☐	☐	☐	☐

Basis for aquifer hydraulic connection evaluation: GW elevations are estimated to be above SW elevations suggesting groundwater is flowing towards and discharging to surface water.

*The distance to Middle Fork Coyote Cr is to where the creek is considered a viable surface water source, which is where the creek flows into Fern Ridge Reservoir. There are several mapped PODs at the far upstream reaches of this creek and its tributaries near the proposed POA but these are primarily rights for storage and likely intercepting winter runoff, not perennial flows, and thus do not constitute viable surface water sources.

Water Availability Basin the well(s) are located within: Long Tom R > Willamette R – AB Mouth (ID# 114)

C3a. 690-09-040 (4): Evaluation of stream impacts for each well that has been determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. Limit evaluation to instream rights and minimum stream flows that are pertinent to that surface water source, and not lower SW sources to which the stream under evaluation is tributary. Compare the requested rate against the 1% of 80% natural flow for the pertinent Water Availability Basin (WAB). If Q is not distributed by well, use full rate for each well. Any checked ☒ box indicates the well is assumed to have the potential to cause PSI.

Well	SW #	Well < ¼ mile?	Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
		☐	☐			☐		☐		☐

C3b. 690-09-040 (4): Evaluation of stream impacts by total appropriation for all wells determined or assumed to be **hydraulically connected and less than 1 mile** from a surface water source. **Complete only if Q is distributed among wells.** Otherwise same evaluation and limitations apply as in C3a above.

SW #	Qw > 5 cfs?	Instream Water Right ID	Instream Water Right Q (cfs)	Qw > 1% ISWR?	80% Natural Flow (cfs)	Qw > 1% of 80% Natural Flow?	Interference @ 30 days (%)	Potential for Subst. Interfer. Assumed?
	☐			☐		☐		☐

Comments: _____

- C4a. **690-09-040 (5):** Estimated impacts on **hydraulically connected surface water sources greater than one mile** as a percentage of the proposed pumping rate. Limit evaluation to the effects that will occur up to one year after pumping begins. This table encompasses the considerations required by 09-040 (5)(a), (b), (c) and (d), which are not included on this form. Use additional sheets if calculated flows from more than one WAB are required.

Non-Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS		See Comments Below*											
Interference CFS													
Distributed Wells													
Well	SW#	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		%	%	%	%	%	%	%	%	%	%	%	%
Well Q as CFS													
Interference CFS													
(A) = Total Interf.													
(B) = 80 % Nat. Q													
(C) = 1 % Nat. Q													
(D) = (A) > (C)		✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
(E) = (A / B) x 100		%	%	%	%	%	%	%	%	%	%	%	%

(A) = total interference as CFS; (B) = WAB calculated natural flow at 80% exceed. as CFS; (C) = 1% of calculated natural flow at 80% exceed. as CFS; (D) = highlight the checkmark for each month where (A) is greater than (C); (E) = total interference divided by 80% flow as percentage.

Basis for impact evaluation:

*Interference for the proposed use could not be estimated because the terrain (high-relief slopes) and geology (multiple geologic formations are encountered between the proposed POA and surface water) do not meet model assumptions of the widely accepted techniques for determining stream depletion (e.g., Hunt 1999, 2003).

- C4b. **690-09-040 (5) (b)** The potential to impair or detrimentally affect the public interest is to be determined by the Water Rights Section.

- C5. ☐ If properly conditioned, the surface water source(s) can be adequately protected from interference, and/or groundwater use under this permit can be regulated if it is found to substantially interfere with surface water:
- ☐ The permit should contain condition #(s) _____;
 - ☐ The permit should contain special condition(s) as indicated in "Remarks" below;

- C6. **SW / GW Remarks and Conditions:** The applicant's proposed well would be producing from an aquifer that has been found to be hydraulically connected to surface water at a distance of > 1 mile. However, the reviewer is unable to find a preponderance of evidence that the proposed use will have the Potential for Substantial Interference (PSI) with surface water.

References Used:

Hunt, B. 1999. *Unsteady Stream Depletion from Ground Water Pumping*. Journal of Hydrologic Engineering, Vol 8(1), pp 12-19

Hunt, B. 2003. *Unsteady Stream Depletion when Pumping from a Semiconfined Aquifer*. Journal of Hydrologic Engineering. Vol 8(1), pp 12-19

McClaghry, J. D., T. J. Wiley, M. L. Ferns, and I. P. Madin. 2010. *Digital Geologic Map of the Southern Willamette Valley, Benton, Lane, Linn, Marion, and Polk Counties, Oregon*. Oregon Dept. of Geology and Mineral Industries. Open File Report O-10-13.

OWRD Well Log Database – Accessed 12/19/2016.

D. WELL CONSTRUCTION, OAR 690-200

- D1. Well #: _____ Logid: _____
- D2. **THE WELL does not appear to meet current well construction standards based upon:**
- a. ☐ review of the well log;
 - b. ☐ field inspection by _____;
 - c. ☐ report of CWRE _____;
 - d. ☐ other: (specify) _____
- D3. **THE WELL construction deficiency or other comment is described as follows:** _____
- D4. ☐ Route to the Well Construction and Compliance Section for a review of existing well construction.

Water Availability Tables

Water Availability Analysis Detailed Reports						
LONG TOM R > WILLAMETTE R - AB MOUTH WILLAMETTE BASIN						
Water Availability as of 12/19/2016						
Watershed ID #: 114 (Map)				Exceedance Level: 80% ▾		
Date: 12/19/2016				Time: 8:57 AM		
Water Availability Calculation		Consumptive Uses and Storages		Instream Flow Requirements		Reservations
Water Rights		Watershed Characteristics				
Water Availability Calculation Monthly Streamflow in Cubic Feet per Second Annual Volume at 50% Exceedance in Acre-Feet						
Month	Natural Stream Flow	Consumptive Uses and Storages	Expected Stream Flow	Reserved Stream Flow	Instream Flow Requirement	Net Water Available
JAN	568.00	150.00	418.00	0.00	0.00	418.00
FEB	697.00	389.00	308.00	0.00	0.00	308.00
MAR	596.00	556.00	40.20	0.00	0.00	40.20
APR	373.00	250.00	123.00	0.00	0.00	123.00
MAY	215.00	64.60	150.00	0.00	0.00	150.00
JUN	105.00	30.10	74.90	0.00	0.00	74.90
JUL	50.60	47.30	3.27	0.00	0.00	3.27
AUG	35.40	38.40	-2.97	0.00	0.00	-2.97
SEP	32.10	22.10	10.00	0.00	0.00	10.00
OCT	35.30	6.49	28.80	0.00	0.00	28.80
NOV	82.50	6.22	76.30	0.00	0.00	76.30
DEC	364.00	106.00	258.00	0.00	0.00	258.00
ANN	362,000.00	99,700.00	262,000.00	0.00	0.00	262,000.00

