



Oregon

Kate Brown, Governor

Water Resources Department

725 Summer St NE, Suite A

Salem, OR 97301

(503) 986-0900

Fax (503) 986-0904

March 3, 2017

RANDALL RICE
GINA L. RICE
13933 E EVANS CREEK RD
ROGUE RIVER, OR 97537

Reference: File G-18367

Dear Applicant:

**THIS IS NOT A PERMIT AND IS
SUBJECT TO CHANGE AT THE NEXT PHASE OF PROCESSING.**

This letter is to inform you of the preliminary analysis of the water-use permit application and to describe the options. In determining whether an application may be approved, the Department must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Water Resources Department has made the following preliminary determinations:

Initial Review Determinations:

1. The application proposed the appropriation of 0.16 cubic foot per second (CFS) of water from Well 1 (JACK 4441) in Evans Creek Basin for storage of 1.0 acre-foot (AF) of groundwater in Lake Montana in Evans Creek Basin for year-round nursery use on 10.0 acres.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Uses included in nursery use are fully included in irrigation and agriculture uses, both of which are allowed under the Rogue Basin Program (OAR 690-515). Therefore, the appropriation of water from a well (JACK 4441) in Evans Creek Basin for nursery use is allowable.
4. Groundwater will likely be available within the capacity of the resource, and if properly conditioned, the proposed use of groundwater will avoid injury to existing groundwater rights.
5. The Department has determined, based upon OAR 690-009, that the proposed groundwater use will not have the potential for substantial interference with any surface water source.
6. The proposed reservoir site is subject to a wetland determination by the Department of State Lands.

7. The proposed use is located above the Rogue Scenic Waterway, as designated under Oregon Revised Statute 390.826.
8. The Department has determined that Well 1 (JACK 4441) does not meet current minimum well construction standards. The water supply well report indicates that the top terminal height of the well casing is at ground level (0 Feet). In order to meet the minimum well construction standards the top terminal height of the well casing must extend a minimum of 12 inches above the local surface run level. Prior to the issuance of a permit, evidence demonstrating compliance with well construction standards must be submitted and approved by the Department. In repairing the well, you should work closely with the Department and/or a licensed well constructor to ensure that repairs are carried out in a manner that will not violate well construction or other rules. You are encouraged to contact Joel Jeffrey of the Department's Well Construction and Compliance Section at 503-986-0852 to determine how to proceed.

Please also note that regardless of the outcome of this application, you will need to work with the Department to either repair or abandon the well to comply with the minimum standards for the construction, conversion, alteration, maintenance, and abandonment of water supply wells in order to protect the state's groundwater supply (OAR 690-200).

Summary of Initial Determinations

The appropriation of 0.16 CFS of water from Well 1 (JACK 4441) in Evans Creek Basin for storage of 1.0 AF of groundwater in Lake Montana in Evans Creek Basin for year-round nursery use on 10.0 acres is allowable, contingent upon the submittal of evidence demonstrating compliance with current minimum well construction standards for Well 1 (JACK 4441).

Because of these favorable determinations, the Department can now move the application to the next phase of the water-rights application review process, where public interest factors will be evaluated.

Please reference the application number when sending any correspondence regarding the conclusions of this initial review. Comments received within the comment period will be evaluated at the next phase of the process.

To Proceed With the Application:

If you choose to proceed with the application, you do not have to notify the Department. The application will automatically be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.

Withdrawal Refunds:

If you choose not to proceed, you may withdraw the application and receive a refund (minus a \$225 processing charge per application). To accomplish this you must notify the Department in writing by **Friday, March 17, 2017**. For your convenience you may use the enclosed "STOP PROCESSING" form.

If A Permit Is Issued It Will Likely Include The Following Conditions:

1. Measurement Devices, and Recording/reporting of Annual Water Use Conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of diversion. The permittee shall maintain the device in good working order.
- B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The permittee shall keep a complete record of the volume of water diverted each month, and shall submit a report which includes water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

2. Scenic Waterway Condition:

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced.

3. Static Water Level Conditions:

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to obtain, from a qualified individual (see below), and report annual static water-level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

Before Use of Water Takes Place

Initial and Annual Static Water Level Measurements

The Department requires the permittee to report an initial water-level measurement in the month specified above once well construction is complete, and annually thereafter until use of water begins; and

After Use of Water has Begun

Seven Consecutive Annual Static Water Level Measurements

Following the first year of water use, the user shall report seven consecutive annual static water-level measurements. The first of these seven annual measurements will establish the reference level against which future annual measurements will be compared. Based on an analysis of the data collected, the Director may require the user to obtain and report additional annual static water-level measurements beyond the seven year minimum reporting

period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- A. Identify each well with its associated measurement;
- B. Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface;
- C. Specify the method used to obtain each well measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The Department may require the discontinuance of groundwater use, or reduce the rate or volume of withdrawal, from the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

2. Well Identification Tag Condition:

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's Water Quality Program web site at <http://www.oregon.gov/ODA/programs/NaturalResources/Pages/AgWaterQuality.aspx> to learn more about the plans and how they may affect the proposed water use.

If you have any questions:

Feel free to call me at 503-986-0808 if you have any questions regarding the contents of this letter or the application. Please have the application number available if you call. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0801. When corresponding by mail, please use this address: Lisa Graham, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,

A handwritten signature in black ink, appearing to read 'L. Graham', with a long horizontal flourish extending to the right.

Lisa Graham
Water Right Application Caseworker

enclosures: Application Process Description and Stop Processing Request Form

G-18367
WAB 15-No PSI
POU 15-No PSI
GW

APPLICATION FACT SHEET

Application File Number: G-18367

Applicant: RANDALL RICE/GINA L. RICE

County: JACKSON

Watermaster: 13

Priority Date: AUGUST 12, 2016

Source: WELL 1 (JACK 4441) IN EVANS CREEK BASIN; LAKE MONTANA IN EVANS CREEK BASIN

Use: NURSERY USE ON 10.0 ACRES; STORAGE

Quantity: 0.16 CUBIC FOOT PER SECOND; 1.0 ACRE-FOOT

Basin Name & Number: Rogue, #15

Stream Index Reference: Volume 4 EVANS CR

Well Location:

NWNE SECTION 5, T35S, R3W, W.M.; 90 FEET SOUTH AND 1565 FEET WEST FROM NE CORNER, SECTION 5

Dam Location:

NENE SECTION 5, T35S, R3W, W.M.; 60 FEET SOUTH AND 1516 FEET WEST FROM NE CORNER, SECTION 5

Place of Use:

	<u>OO</u>	<u>NURSERY USE</u>	<u>STORAGE</u>
NE ¼ NE ¼		4.9 ACRES	X
NW ¼ NE ¼		5.1 ACRES	
		SECTION 5	
		TOWNSHIP 35 SOUTH, RANGE 3 WEST, W.M.	

14 DAY STOP PROCESSING DEADLINE DATE: Friday, March 17, 2017

PUBLIC NOTICE DATE: Tuesday, March 7, 2017

30 DAY COMMENT DEADLINE DATE: Thursday, April 6, 2017

APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

In order to take and use the waters of Oregon, a citizen must first obtain a permit from the Water Resources Department. The water must be used for beneficial purpose - without waste. To become well-informed about water right topics, weekly public notice, forms and fees please visit our web site at www.wrd.state.or.us

1. Pre-application considerations

- follow instructions in the application packet
- if you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Information Group (WRIG) at 503-986-0801

2. Application filing

- application with fee is received by the Department
- Department determines completeness of application
- if use is not allowed by statute (ORS 538), the application and fees are returned to the applicant
- incomplete application and fees are returned to the applicant
- only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing

3. Initial Review (IR)

- caseworker reviews application by considering basin plans, water availability, statutory restrictions and all other appropriate factors
- caseworker sends IR report to applicant
- contact the caseworker if you have questions about the IR
- seven days after date of the IR, it is included in Department's weekly Public Notice
- public comments must be submitted within 30 days after the Public Notice
- **administrative hold** may be requested in writing by applicant

4. Proposed Final Order (PFO)

- caseworker evaluates application against required criteria and develops draft permit, if appropriate
- PFO includes instructions for filing of protests
- caseworker considers public comments and mails PFO to applicant
- the PFO is included in Department's weekly Public Notice
- public protests to the PFO must be submitted within 45 days after the Public Notice

Stop Processing deadline is within 14 days of Initial Review - use the form below

- applicant may request no further action and fee refund of all but \$225

STOP PROCESSING REQUEST FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

Applicant notification to withdraw Water Right Application # _____

After reviewing the Initial Review for my application, I request that processing be stopped and the fees be refunded (minus a \$225 examination fee.) I understand that without a valid permit I may not legally use the water as requested in my application

Signature _____ date _____

Signature _____ date _____

Under ORS 537.150 (5) and 537.620 (5) timely submission of this request authorizes that the water right application process be stopped and all filing fees (except \$225 examination fee) be returned.

This notice must be received at Water Resources Department by _____

Return the notice to: OWRD, Water Rights Division
STOP PROCESSING
725 Summer Street, NE - Suite A
Salem OR 97301-1271

5. *Final Order (FO)*

- if no protest is filed, Final Order is issued

The protest process

If one or more protests are filed, permit process consists of:

- settlement discussion
- contested case hearing
- proposed order
- period of time to file exceptions
- possible hearing by Water Resources Commission
- final order issued

Permit holder responsibilities

- comply with all water use conditions of the permit
- advise Department of address change or assignment to new permit holder
- if need arises, request extension of time or authorize cancellation of permit
- submit timely claim of beneficial use (COBU) to Department
- most permits require COBU to be prepared by a Certified Water Right Examiner
- permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions