



April 28, 2017

MAI DOAN  
BLUE LOTUS VENTURES LLC  
5105 NE 21ST AVE  
PORTLAND, OR 97211

Reference: File G-18344

Dear Applicant:

**THIS IS NOT A PERMIT AND IS  
SUBJECT TO CHANGE AT THE NEXT PHASE OF PROCESSING.**

This letter is to inform you of the preliminary analysis of the water-use permit application and to describe the options. In determining whether an application may be approved, the Department must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Water Resources Department has made the following preliminary determinations:

Initial Review Determinations:

1. The application proposed the appropriation of 0.16 cubic foot per second (CFS) of water from Well 1 in Bargfeld Creek Basin for year-round nursery use on 6.4 acres.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Uses included in nursery use are fully included in irrigation and agriculture uses, both of which are allowed under the Willamette Basin Program (OAR 690-502). Therefore, the appropriation of water from Well 1 in Bargfeld Creek Basin for nursery use is allowable.
4. Groundwater will likely be available within the capacity of the resource, and if properly conditioned, the proposed use of groundwater will avoid injury to existing groundwater rights.
5. The Department has determined, based upon OAR 690-009, that the proposed groundwater use will have the potential for substantial interference with Bargfeld Creek, an unnamed tributary to Clear Creek, and Clear Creek. Therefore, in accordance with OAR 690-400-0010(11)(a)(B), surface water availability must also be considered.

Surface water is **not** available during the period July 1 through October 31 of each year.

6. The application is subject to Section 4(d) of the Endangered Species Act and as such, subject to review under OAR 690-033 by the Oregon Departments of Agriculture, Fish and Wildlife, and Environmental Quality.

7. The proposed diversion falls within a high priority area for streamflow restoration under the Oregon Plan for Salmon & Watersheds.
8. The proposed use is located above the Clackamas Scenic Waterway (includes S Fk Clackamas & N Fk Clackamas), as designated under Oregon Revised Statute 390.826.
9. Because surface water is not available for the entire period requested, the appropriation of 0.16 CFS of water from Well 1 for year-round nursery use on 6.4 acres is not allowable. However, by providing additional information you may be able to pursue a limited permit. Please refer to the **Additional Information Opportunity** section below for details.

### **Summary of Initial Determinations**

**Because not all items above are favorable, the appropriation of 0.16 CFS of water from Well 1 in Bargfeld Creek Basin for year-round nursery use on 6.4 acres is not allowable, and it appears unlikely that you will be issued a permit. However, by providing additional information you may be able to pursue a limited permit. At this time, you must decide whether to proceed or to withdraw your application as described below.**

#### **Additional Information Opportunity:**

If you would like to use water for year-round nursery use on 6.4 acres, you may amend your application to reduce the proposed rate to **0.056 CFS** and locate your well greater than one-quarter mile from all surface water sources. By reducing the rate and moving the well greater than one-quarter mile from surface water sources, the Department has determined, based upon OAR 690-009, that the proposed groundwater use may not have the potential for substantial interference with surface water. You will need to work with the Department hydrogeology staff for proper well placement.

Please be aware that the reduced rate may be insufficient to meet your needs; if so, you may wish to either withdraw the application or submit an amended map with depicting less acreage as the place-of-use.

**Please submit this information no later than Thursday, June 1, 2017.** If you are unable to submit the information listed above, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time you will need and why you need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed. If we do not receive additional information or a request for an administrative hold by this date, the Department will likely proceed with a Proposed Final Order recommending denial of the application.

At this time, you must decide whether to proceed or to withdraw the application as described below. Please reference the application number when sending any correspondence regarding the conclusions of this initial review. Comments received within the comment period will be evaluated at the next phase of the process.

#### **Withdrawal Refunds:**

If you choose not to proceed, you may withdraw the application and receive a refund (minus a \$225 processing charge per application). To accomplish this you must notify the Department in writing by **Friday, May 12, 2017**. For your convenience you may use the enclosed "STOP PROCESSING" form.

To Proceed With The Application:

If you choose to proceed with the application, you do not have to notify the Department. The application will automatically be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.

If A Permit Is Issued It Will Likely Include The Following Conditions:

1. Measurement Devices, and Recording/Reporting of Annual Water Use Conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
- B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The permittee shall keep a complete record of the volume of water diverted each month, and shall submit a report which includes water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

2. Static Water Level Conditions:

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the permit. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The permittee shall report an initial March static water-level measurement once well construction is complete and annual measurements thereafter. Annual measurements are required whether or not the well is used. The first annual measurement will establish a reference level against which future measurements will be compared. However, the Director may establish the reference level based on an analysis of other water-level data. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and

- D. Certify the accuracy of all measurements and calculations reported to the Department.

The Department may require the discontinuance of groundwater use, or reduce the rate or volume of withdrawal, from the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or  
 B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or  
 C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or  
 D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

3. Water application allowed under this permit shall be by drip irrigation or by an equally efficient method.
4. Scenic Waterway Condition:

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced.

5. Well Identification Tag Condition:

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.


This initial review does not attempt to address various public interest issues such as sensitive, threatened, or endangered fish species. These issues will be addressed as the Department reviews comments from the public and other agencies, and prepares a Proposed Final Order. You should be aware that, if significant public interest issues are found to exist, such a finding could have an impact on the eventual outcome of the application.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's Water Quality Program web site at <http://www.oregon.gov/ODA/programs/NaturalResources/Pages/AgWaterQuality.aspx> to learn more about the plans and how they may affect the proposed water use.

If you have any questions:

Feel free to contact me at [Barbara.J.Poage@oregon.gov](mailto:Barbara.J.Poage@oregon.gov) or 503-986-0859 if you have any questions regarding the contents of this letter or the application. Please have the application number available if you call. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0801. When corresponding by mail, please use this address: Barbara Poage, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,



Barbara Poage  
Water Right Application Caseworker

enclosures: Application Process Description and Stop Processing Request Form

G-18344  
WAB 2-82  
POU 2-82  
GW

# APPLICATION FACT SHEET

Application File Number: G-18344

Applicant: BLUE LOTUS VENTURES LLC

County: CLACKAMAS

Watermaster: 20

Priority Date: JULY 18, 2016

Source: WELL 1 IN BARGFELD CREEK BASIN

Use: NURSERY USE ON 6.4 ACRES

Quantity: 0.056 CUBIC FOOT PER SECOND

Basin Name & Number: Willamette, #2

Stream Index Reference: Volume 23A BARGFELD CR & MISC

Point of Diversion or Well Location(s): SESE SECTION 5, T3S, R3E, W.M.; 520 FEET NORTH AND 430 FEET WEST FROM SE CORNER, SECTION 5

Place of Use:

SE  $\frac{1}{4}$  SE  $\frac{1}{4}$  6.4 ACRES  
SECTION 5  
TOWNSHIP 3 SOUTH, RANGE 3 EAST, W.M.

**14 DAY STOP PROCESSING DEADLINE DATE: Friday, May 12, 2017**

**PUBLIC NOTICE DATE: Tuesday, May 2, 2017**

**30 DAY COMMENT DEADLINE DATE: Thursday, June 1, 2017**

# APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

In order to take and use the waters of Oregon, a citizen must first obtain a permit from the Water Resources Department. The water must be used for beneficial purpose - without waste. To become well-informed about water right topics, weekly public notice, forms and fees please visit our web site at [www.wrd.state.or.us](http://www.wrd.state.or.us)

## 1. Pre-application considerations

- follow instructions in the application packet
- if you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Information Group (WRIG) at 503-986-0801

## 2. Application filing

- application with fee is received by the Department
- Department determines completeness of application
- if use is not allowed by statute (ORS 538), the application and fees are returned to the applicant
- incomplete application and fees are returned to the applicant
- only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing

## 3. Initial Review (IR)

- caseworker reviews application by considering basin plans, water availability, statutory restrictions and all other appropriate factors
- caseworker sends IR report to applicant
- contact the caseworker if you have questions about the IR
- seven days after date of the IR, it is included in Department's weekly Public Notice
- public comments must be submitted within 30 days after the Public Notice
- **administrative hold** may be requested in writing by applicant

## 4. Proposed Final Order (PFO)

- caseworker evaluates application against required criteria and develops draft permit, if appropriate
- PFO includes instructions for filing of protests
- caseworker considers public comments and mails PFO to applicant
- the PFO is included in Department's weekly Public Notice
- public protests to the PFO must be submitted within 45 days after the Public Notice

**Stop Processing deadline is within 14 days of Initial Review - use the form below**  
- applicant may request no further action and fee refund of all but \$225

## STOP PROCESSING REQUEST FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

Applicant notification to withdraw Water Right Application # \_\_\_\_\_

After reviewing the Initial Review for my application, I request that processing be stopped and the fees be refunded (minus a \$225 examination fee.) I understand that without a valid permit I may not legally use the water as requested in my application

Signature \_\_\_\_\_ date \_\_\_\_\_

Signature \_\_\_\_\_ date \_\_\_\_\_

*Under ORS 537.150 (5) and 537.620 (5) timely submission of this request authorizes that the water right application process be stopped and all filing fees (except \$225 examination fee) be returned.*

This notice must be received at Water Resources Department by \_\_\_\_\_

Return the notice to: OWRD, Water Rights Division

STOP PROCESSING

725 Summer Street, NE - Suite A

Salem OR 97301-1271

## 5. *Final Order (FO)*

- if no protest is filed, Final Order is issued

### *The protest process*

If one or more protests are filed, permit process consists of:

- settlement discussion
- contested case hearing
- proposed order
- period of time to file exceptions
- possible hearing by Water Resources Commission
- final order issued

### *Permit holder responsibilities*

- comply with all water use conditions of the permit
- advise Department of address change or assignment to new permit holder
- if need arises, request extension of time or authorize cancellation of permit
- submit timely claim of beneficial use (COBU) to Department
- most permits require COBU to be prepared by a Certified Water Right Examiner
- permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions