



Oregon
Kate Brown, Governor

Water Resources Department
725 Summer St NE, Suite A
Salem, OR 97301
(503) 986-0900
Fax (503) 986-0904

Water Right Application Initial Review

October 6, 2017

MAX MURRAY
17875 SE WEBFOOT RD
DAYTON OR 97114

Reference: G-18442

Application G-18442 proposes the appropriation of 0.05 cubic foot per second (CFS) of water from Well 50641 (YAMH 50641/L10112) in Yamhill River Basin in for year-round nursery use on 2.5 acres.

Summary

Because of the favorable determinations described herein, the appropriation of 0.05 CFS of water from Well 50641 (YAMH 50641/L10112) in Yamhill River Basin for year-round nursery use on 2.5 acres is allowable, contingent on receiving an updated map requested in the **Additional Information Required** section. Application G-18442 can move to the next phase of the water-rights application review process, which includes a public interest review. This initial review does not address various public interest issues or public comments. These issues will be addressed as the Department reviews comments from the public and other agencies, and prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

Proceed

If you choose to proceed with the application you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.

Withdraw

You may withdraw the application and receive a refund (minus a \$260 processing charge per application). You must notify the Department in writing by **Friday, October 20, 2017**. For your convenience you may use the enclosed "STOP PROCESSING" form.

Initial Review Preliminary Determinations (OAR 690-310-0080)

1. The application proposed the appropriation of 0.05 CFS of water from Well 50641 (YAMH 50641/L10112) in Yamhill River Basin for year-round nursery use on 2.5 acres.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Uses included in nursery use are fully included in irrigation and agriculture uses, both of which are allowed under the Willamette Basin Program (Oregon Administration Rule (OAR) 690-502). Therefore, the appropriation of water from Well 50641 (YAMH 50641/L10112) for nursery use is allowable.
4. The Department has determined, based upon OAR 690-009, that the proposed groundwater use will not have the potential for substantial interference with any surface water source.
5. Groundwater will likely be available within the capacity of the resource, and if properly conditioned (and if authorized), the proposed use of groundwater will avoid injury to existing groundwater rights.
6. The proposed use is not located within or above any state or federal scenic waterway.
7. The point of appropriation is not located within a Critical, Limited or Withdrawn Groundwater Area.
8. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright. ORS 537.621(3)(b); OAR 690-310-0150(2)(b)

Additional Information Required

Additional information is required to process your application prior to issuance of any Proposed Final Order that may recommend permit approval. Please provide the following item:

- A map identifying the number of acres to be used for nursery use in each quarter-quarter section. The acreage must be clearly indicated on the map and identified by **shading or hatching**. The application map does not show the number of acres within each quarter-quarter section. On the enclosed copy of your application map, please show the number of acres to be used in each quarter-quarter section by shading or hatching.

Please submit the requested information listed above no later than November 9, 2017. If the Department does not receive the item listed above by November 9, 2017, the Department may issue a Proposed Final Order that recommends denial.

If a Permit is Issued it will Likely Include the Following Conditions:

1. Construction of the well shall begin within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the begin construction deadline is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Measurement Devices, and Recording/Reporting of Annual Water Use Conditions:**
 - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order,
 - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
 - C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
 - D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

4. **Static Water Level Conditions:**

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to obtain, from a qualified individual (see below), and report annual static water-level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

Before Use of Water Takes Place

Initial and Annual Static Water Level Measurements:

The Department requires the permittee to report an initial water-level measurement in the month specified above once well construction is complete, and annually thereafter until use of water begins; and

After Use of Water has Begun

Reference Static Water Level Determination:

Following the first year of water use, the user shall report one static water-level measurement in the month specified above which will establish the reference level against which future annual measurements will be compared. The Director may require the user to obtain and report additional static water levels after the reference level has been determined. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- A. Identify each well with its associated measurement;
- B. Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface;
- C. Specify the method used to obtain each well measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

5. Well Identification Tag Condition:


Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's Water Quality Program web site at <http://www.oregon.gov/ODA/programs/NaturalResources/Pages/AgWaterQuality.aspx> to learn more about the plans and how they may affect the proposed water use.

If you have any questions:

Feel free to contact me at Kim.R.French@oregon.gov or 503-986-0816 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0801. When corresponding by mail, please use this address: Kim French, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,



Kim French
Water Right Application Specialist

enclosures: Application Process Description and Stop Processing Request Form

G-18442
WAB: No PSI

APPLICATION FACT SHEET

Application File Number: G-18442

Applicant: MAX MURRAY

County: YAMHILL

Watermaster: JOEL PLAHN, 16, NWR

Priority Date: JANUARY 23, 2017

Source: WELL 50641 (YAMH 50641/L10112)

Use: NURSERY USE ON 2.5 ACRES

Quantity: 0.05 CUBIC FOOT PER SECOND

Basin Name & Number: WILLAMETTE, #2

Well Location(s):

POA Name	Twp	Rng	Mer	Sec	Q-Q	Measured Distances
WELL 50641 (YAMH 50641/L10112)	5 S	3 W	WM	18	SE SE	360 FEET NORTH AND 640 FEET WEST FROM SE CORNER, SECTION 18

Place of Use:

Twp	Rng	Mer	Sec	Q-Q	Acres
5 S	3 W	WM	18	SE SE	2.5

PUBLIC NOTICE DATE: Tuesday, October 10, 2017

14 DAY STOP PROCESSING DEADLINE DATE: Friday, October 20, 2017

30 DAY COMMENT DEADLINE DATE: Thursday, November 9, 2017

APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our web site at www.wrd.state.or.us

1. Pre-application considerations

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0801.

2. Application filing

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

3. Initial Review (IR)

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Contact the Caseworker if you have questions about the IR.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.
- **An administrative hold** may be requested in writing by Applicant.

4. Proposed Final Order (PFO)

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

5. Final Order (FO)

- If no protest is filed, Final Order is issued.

The protest process

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- proposed Order;
- period of time to file exceptions; or
- Possible hearing by Water Resources Commission.
- Final Order is issued.

Permit holder responsibilities

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.

Stop processing deadline is within 14 days of Initial Review - use the form below
Applicant may request no further action and fee refund of all but \$260

**STOP PROCESSING REQUEST FOR
GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR
APPLICATIONS**

Applicant notification to withdraw Water Right Application G-18442

After reviewing the Initial Review for my application, I request that processing be stopped and the fees be refunded (minus a \$260 examination fee.) I understand that without a valid permit I may not legally use the water as requested in my application

Signature _____ Date _____

Signature _____ Date _____

Under ORS 537.150 (5) and 537.620 (5) timely submission of this request authorizes that the water right application process be stopped and all filing fees (except \$260 examination fee) be returned.

This notice must be received at Water Resources Department by

Friday, October 20, 2017

Return the notice to:

OWRD, Water Rights Division
STOP PROCESSING
725 Summer Street, NE - Suite A,
Salem OR, 97301-1271