

Permit No. 13262

13516

Application No. 17561

County Josephine

PROOF OF APPROPRIATION OF WATER

1. Name J. H. Pomeroy 2. Address Kerby, Oregon & 333 Montgomery St. San Francisco, Calif
3. Source of supply Illinois River
- Tributary of _____
4. Amount of water 2.0 c.f.s. 5. Priority date September 1, 1938
6. Use Supplemental Irrigation
7. Location of point of diversion, SW $\frac{1}{4}$ NW $\frac{1}{4}$ & SW $\frac{1}{4}$ SW $\frac{1}{4}$ Sec. 4, Twp. 39 S, Range 8 W, W. M. 33
(Legal Subdivision)
SE $\frac{1}{4}$ NW $\frac{1}{4}$ & NE $\frac{1}{4}$ SW $\frac{1}{4}$ Sec. 9, Twp. 39 S, Range 8 W, W. M. 33
8. The description of land given below corresponds to that found in your permit covering land to be irrigated, or, if for other purposes, the place of use. In the blank column on the right, headed "No. acres actually irrigated", fill in the number of acres you have irrigated in each of the tracts described:

Township	Range	Section	Forty-acre Tract	No. Acres Described in Permit	No. Acres Actually Irrigated
38 S	8 W	33	NE $\frac{1}{4}$ NW $\frac{1}{4}$	10 ✓	10 ✓
			SE $\frac{1}{4}$ NW $\frac{1}{4}$	15 ✓	15 ✓
			NE $\frac{1}{4}$ SW $\frac{1}{4}$	10 ✓	10 ✓
39 S	8 W	4	NW $\frac{1}{4}$ NW $\frac{1}{4}$	5 ✓	5 ✓
			SE $\frac{1}{4}$ NE $\frac{1}{4}$	5 ✓	5 ✓
		5	NE $\frac{1}{4}$ SE $\frac{1}{4}$	10 ✓	10 ✓
			SE $\frac{1}{4}$ SE $\frac{1}{4}$	10 ✓	10 ✓
		9	SW $\frac{1}{4}$ NW $\frac{1}{4}$	10 ✓	10 ✓
			NW $\frac{1}{4}$ SW $\frac{1}{4}$	5 ✓	5 ✓
		8	NE $\frac{1}{4}$ NE $\frac{1}{4}$	10 ✓	10 ✓
			SE $\frac{1}{4}$ NE $\frac{1}{4}$	10 ✓	10 ✓
				100	100 ✓

This column must be filled in if water is used in irrigation

ok for certif

If for irrigation, this appropriation shall be limited to 1/50th of one cubic foot per second or its equivalent for each acre irrigated throughout the irrigation season from April 1st to November 1st of each year, and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

(Attach separate sheet if necessary)

DESCRIPTION OF WORKS

9. (a) If a dam has been constructed, give description: Height, No dams ft.; length on top, ft.; length on bottom ft.; material used and character of construction,

(b) Give description of headgate: Width, ft.; depth, ft.; material used and character of construction, Control by valve in pipe and engine throttle

(c) Size of canal: Width on top (at waterline) 3 ft.; width on bottom, 2 ft.; depth of water, 0.8 ft.; grade, 4 ft. fall per 1,000 ft. Actual capacity, 5.6 sec.-ft. Give general description: Earth ditch.

(d) Pipe line: Description of intake, 8" suction pipe inserted into pools of river

Length of pipe, ²⁸⁰⁰2800 ft.; size at intake, 8 in.; size at 2800 ft. from intake, 8 in.; size at place of use, 8 in. Difference in elevation between intake and place of use, 18 ft.

Is grade uniform? No Actual capacity of pipe line, 5+ sec.-ft.

Give general description: Portable steel pipe. Also 1200 ft. of 4 inch Ames sprinkling and perforated pipe.
(Material: Steel, wrought, cast iron, wood stave, etc.)

(e) Pumping plant: Give size and type of pump, 8" centrifugal

Suction lift, 8 ft.; discharge lift, 10 ft. Type of motor used Gas. Waukesha

Horse power rating, 22 H. P. Actual capacity of pump, 2.2 sec.-ft.

10. During what months is water beneficially used? April 1 to Oct. 1

11. State character of soil Kerby gravelly loam

Kind of crops raised Alfalfa, pasture.

12. Does the accompanying map, filed with your application, show correctly the point of diversion, area of land irrigated, or place of use? Yes

13. If not, wherein is such map in error?

14. Domestic use: Give number of families actually using water at this time

15. If for power, mining, municipal, manufacturing, storage or any other purpose than irrigation, give extent and method of such use

AFFIDAVIT OF APPROPRIATOR

STATE OF OREGON,

County of Josephine

} ss.

I, J. H. Pomeroy, being first duly sworn, deposit and say that I have read the above and foregoing proof of appropriation of water; that I know the contents thereof, and that the facts therein stated are true.

IN WITNESS WHEREOF, I have hereunto set my hand this 29th day of November, 1940.

J. H. Pomeroy

Subscribed and sworn to before me this 29th day of November, 1940.

Beal Couch

Notary Public for Oregon

[Notarial Seal]

My commission expires July 1, 1944.

AFFIDAVIT OF WITNESSES

STATE OF OREGON,

County of

} ss.

We,, and

of, being first duly sworn, depose and say that we are well acquainted with the facts and conditions set forth in the foregoing statement relative to proof of appropriation of water under Permit No.....; that we and each of us have been over and upon each tract described in said proof, and from such personal inspection have knowledge that all necessary ditches, dams and other diversion and distributing works have been constructed, and water used as stated therein; that we have carefully read such proof of appropriation, and that each and every statement contained therein is true to the best of our knowledge and belief.

Subscribed and sworn to before me this day of, 194.....

Notary Public for Oregon

[Notarial Seal]

My commission expires

REPORT OF PERSON MAKING INSPECTION

(For use by representative of State Engineer)

I, Tom R. Pearce, do hereby certify that I have made an inspection of the works described herein and in Permit No. 13262, on the 29th day of Nov., 1940, and found the foregoing statements and descriptions of works to be accurate. In my opinion the appropriation has been completed to the extent of 2.0 c.f.s. and I recommend the issuance of water right certificate for this amount.

(Quantity of water in second-feet or acre-feet)

NOTICE TO INSPECTORS

If conditions do not justify the above report by you, please return the proof without your signature, with a full report by letter.

Tom R. Pearce

(Name)

Watermaster District No. 16

(Title)


PROOF OF APPROPRIATION

Permit No.

Recording fee paid

Receipt No.

RECEIVED
DEC 5 1940
STATE ENGINEER
SALEM, OREGON



11
2
2