



**FINDINGS OF FACT**

**Application History**

1. On November 7, 2017, R D Mac Inc. filed a complete application for the following water use:

Source	WELL 1 (UNIO 50216/L11111) AND WELL 2 (UNIO 50715/L16197) IN GRANDE RONDE RIVER BASIN
Use	INDUSTRIAL/MANUFACTURING USE
Rate	2.23 CUBIC FEET PER SECOND (CFS)
County	UNION COUNTY
Place of Use	SECTION 15, TOWNSHIP 3 SOUTH, RANGE 38 EAST, W.M.

2. On March 22, 2019, the Department mailed the applicant notice of its Initial Review, determining that **“The appropriation of 2.23 CFS of water from Well 1 (UNIO 50216/L11111) and Well 2 (UNIO 50715/L16197) in Grande Ronde River Basin for industrial use January 1 to December 31 of each year is not allowable.”** The applicant did not notify the Department to stop processing the application within 14 days of that date.
3. On March 26, 2019, the Department gave public notice of the application in its weekly notice. The public notice included a request for comments, and information for interested persons about obtaining future notices and a copy of the Proposed Final Order.
4. The proposed use is located above the Willowa-Grande Ronde State Scenic Waterway, as designated under ORS 390.826. The Department has determined, based upon OAR 690-310-0260, that there is a preponderance of evidence that the proposed use of groundwater will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife. The one CFS limit prescribed in OAR 690-310-0260(5) has been exceeded for the months of March through November. Therefore, **water is not available** for the proposed use as requested. 537.621(3)(a); OAR 690-310-0260(9)(a)
5. The Department gave the applicant the opportunity to provide mitigation during the months of March through November, in accordance with provisions of ORS 390.835(9), to overcome the finding that water is not available pursuant to OAR 690-310-0260.
6. The mitigation obligation for the proposed use, as conditioned in the attached permit, is 104 acre-feet per year, which represents the Department’s determination of the consumptive portion of the proposed use in acre-feet. The applicant proposed to meet the mitigation obligation by filing Transfer Application T-13129, which is a permanent instream transfer.
7. The Department determined that the proposed mitigation will offset the calculated impact to the scenic waterway.

**Presumption Criteria (a) - Consistency with Basin Program**

8. The proposed use is allowed under Grande Ronde Basin Program OAR 690-508-0010(1)(a). ORS 537.621(3)(b); OAR 690-310-0150(2)(b)

**Presumption Criteria (b) - Water Availability**

9. An assessment of groundwater availability has been completed by the Department's Groundwater Section. A copy of this assessment is in the file and can be viewed on the Department's website. Groundwater will likely be available within the capacity of the resource, and if properly conditioned (and if authorized), the proposed use of groundwater will avoid injury to existing groundwater rights. ORS 537.621(3)(c); OAR 690-310-0150(2)(c)

**Presumption Criteria (c) - Injury Determination**

10. The proposed use, if authorized, will not injure other water rights. ORS 537.621(3)(d); OAR 690-310-0150(2)(e)

**Presumption Criteria (d) - Whether the use complies with rules of the Commission**

11. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates an approved land-use decision has been obtained, and that either no administrative appeals were received, or all such appeals have concluded. ORS 537.621(3)(b); OAR 690-310-0150(2)(b)
12. The Department has determined that the proposed groundwater use will not have the potential for substantial interference with surface water. ORS 537.621(3)(b); OAR 690-009-0040(4)
13. The proposed groundwater use is not within a designated critical groundwater area. ORS 537.620(4)(a), 537.621(3)(a); OAR 690-310-0150(2)(a)
14. No written comments were received by the close of the comment period. OAR 690-310-0140(3)(a)
15. The proposed use does comply with rules of the Water Resources Commission not otherwise described above, pursuant to OAR 690-310-0260, however, the mitigation provided during the months of March through November under instream Transfer T-13129, will ensure the maintenance of the free-flowing character of the scenic waterway in quantities necessary for recreation, fish, and wildlife. Therefore, the proposed use will not impair or adversely affect the public interest.

**Determination of Presumption and whether the proposed use will impair or adversely affect the public welfare, safety and health under ORS 537.525**

16. Based on the review of the presumption criteria (a)-(d) above, the presumption has been established. ORS 537.621(2); OAR 690-310-0150(2)(g)

**Other Criteria and Requirements**

17. The amount requested, 2.23 CFS, is necessary for the proposed use. ORS 537.621(3)(c); OAR 690-310-0150(2)(d)
18. The applicant proposed methods to measure the amount of water appropriated, prevent damage to aquatic life and riparian habitat, prevent discharge of contaminated water to a surface stream, or to prevent damage to public uses of any affected surface waters. These measures are adequate at this time. OAR 690-310-0150(2)(j)

**CONCLUSIONS OF LAW**


1. The proposed use, as conditioned, would ensure the preservation of the public welfare, safety and health as described in ORS 537.525.

NOTE: When issuing permits, ORS 537.628(1) authorizes the Department to include limitations and conditions which have been determined necessary to protect the public welfare, safety and health.

**PROPOSED ORDER**

The Department recommends approval of Application G-18577 and issuance of a permit consistent with the attached draft permit.

DATED March 24, 2020



---

Dwight French  
Water Right Services Administrator, for  
Thomas M. Byler, Director  
Oregon Water Resources Department

## Protests

Under the provisions of ORS 537.153(7) (for surface water) or ORS 537.621(8) (for groundwater), you can protest this Proposed Final Order. Protests must be received by the Water Resources Department no later than **May 8, 2020**. Protests must be in writing, and must include the following:

- Your name, address, and telephone number;
- A description of your interest in the Proposed Final Order, and, if you claim to represent the public interest, a precise statement of the public interest represented;
- A detailed description of how the action proposed in the Proposed Final Order would impair or be detrimental to your interest;
- A detailed description of how the Proposed Final Order is in error or deficient, and how to correct the alleged error or deficiency;
- Any citation of legal authority to support your protest, if known;
- To affect the Department's determination that the proposed use in this application will, or will not, ensure the preservation of the public welfare, safety and health as described in ORS 537.525, ORS 537.621(2)(b) requires that a protest demonstrate, by a preponderance of evidence any of the following: (a) One or more of the criteria for establishing the presumption are, or are not, satisfied; or (b) The specific aspect of the public welfare, safety and health under ORS 537.525 that would be impaired or detrimentally affected, and specifically how the identified aspect of the public welfare, safety and health under ORS 537.525 would be impaired or be adversely affected;
- If you are the applicant, a protest fee of \$410 required by ORS 536.050; and
- If you are not the applicant, a protest fee of \$810 required by ORS 536.050 and proof of service of the protest upon the applicant.
- If you are the applicant, a statement of whether or not you are requesting a contested case hearing.

## Requests for Standing

Under the provisions of ORS 537.153(7) (for surface water) or ORS 537.621(8) (for groundwater), persons other than the applicant who support a Proposed Final Order can request standing for purposes of participating in any contested case proceeding on the Proposed Final Order or for judicial review of a Final Order.

Requests for standing must be received in the Water Resources Department no later than **May 8, 2020**. Requests for standing must be in writing, and must include the following:

- The requester's name, mailing address and telephone number;
- If the requester is representing a group, association or other organization, the name, address and telephone number of the represented group;
- A statement that the requester supports the Proposed Final Order as issued;
- A detailed statement of how the requester would be harmed if the Proposed Final Order is modified; and

- A standing fee of \$230. If a hearing is scheduled, an additional fee of \$580 must be submitted along with a petition for party status.

After the protest period has ended, the Director will either issue a Final Order or schedule a contested case hearing. The contested case hearing will be scheduled only if a protest has been submitted and either:

- upon review of the issues, the director finds that there are significant disputes related to the proposed use of water, or
- the applicant requests a contested case hearing within 30 days after the close of the protest period.

If you do not request a hearing within 30 days after the close of the protest period, or if you withdraw a request for a hearing, notify the Department or the administrative law judge that you will not appear or fail to appear at a scheduled hearing, the Director may issue a Final Order by default. If the Director issues a Final Order by default, the Department designates the relevant portions of its files on this matter, including all materials that you have submitted relating to this matter, as the record for purpose of proving a *prima facie* case upon default.

You may be represented by an attorney at the hearing. Legal aid organizations may be able to assist a party with limited financial resources. Generally, partnerships, corporations, associations, governmental subdivisions or public or private organizations are represented by an attorney. However, consistent with OAR 690-002-0020 and OAR 137-003-0555, an agency representative may represent a partnership, corporation, association, governmental subdivision or public or private organization if the Department determines that appearance of a person by an authorized representative will not hinder the orderly and timely development of the record in this case.

**Notice Regarding Servicemembers:** Active duty service members have a right to stay proceedings under the federal Servicemembers Civil Relief Act. For more information contact the Oregon State Bar at 800-452-8260, the Oregon Military Department at 503-584-3571, or the nearest United States Armed Forces Legal Assistance Office through <http://legalassistance.law.af.mil>. The Oregon Military Department does not have a toll free telephone number.

- 
- If you have any questions about statements contained in this document, please contact Kim French at 503-986-0816 or [Kim.R.French@oregon.gov](mailto:Kim.R.French@oregon.gov).
  - If you have questions about how to file a protest or if you have previously filed a protest and you want to know the status, please contact Patricia McCarty at 503-986-0820.
  - If you have any questions about the Department or any of its programs, please contact our Water Resources Customer Service Group at 503-986-0900.
  - Address any correspondence to :      Water Right Services Division  
725 Summer St NE, Suite A  
Salem, OR 97301-1266  
Fax: 503-986-0901
-

**DRAFT**

**This is not a permit.**

**DRAFT**

STATE OF OREGON

COUNTY OF UNION

**DRAFT PERMIT TO APPROPRIATE THE PUBLIC WATERS**

THIS DRAFT PERMIT IS HEREBY ISSUED TO

R D MAC INC.  
60831 MCALISTER RD  
LA GRANDE OR 97850

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-18577

SOURCE OF WATER: WELL 1 (UNIO 50216/L11111) AND WELL 2 (UNIO 50715/L16197) IN GRANDE RONDE RIVER BASIN

PURPOSE OR USE: INDUSTRIAL/MANUFACTURING USE

MAXIMUM RATE: 2.23 CUBIC FEET PER SECOND

MAXIMUM ANNUAL VOLUME: 104 ACRE-FEET PER CALENDAR YEAR

PERIOD OF USE: JANUARY 1 THROUGH DECEMBER 31

DATE OF PRIORITY: NOVEMBER 7, 2017

WELL LOCATION:

POA Name	Twp	Rng	Mer	Sec	Q-Q	Measured Distances
WELL 1	3 S	38 E	WM	15	SW NE	2621 FEET SOUTH AND 1266 FEET EAST FROM N1/4 CORNER, SECTION 15
WELL 2	3 S	38 E	WM	15	SW NE	2384 FEET SOUTH AND 427 FEET EAST FROM N1/4 CORNER, SECTION 15

THE PLACE OF USE IS LOCATED AS FOLLOWS:

Twp	Rng	Mer	Sec	Q-Q
3 S	38 E	WM	15	NE NE
3 S	38 E	WM	15	NW NE
3 S	38 E	WM	15	SW NE
3 S	38 E	WM	15	SE NE
3 S	38 E	WM	15	NE SE
3 S	38 E	WM	15	NW SE

**1. Water Use Measurement, Recording, and Reporting Condition:**

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
- B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

**2. Static Water Level Condition:**

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the permit. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The permittee shall report an initial March static water-level measurement once well construction is complete and annual measurements thereafter. Annual measurements are required whether or not the well is used. The first annual measurement will establish a reference level against which future measurements will be compared. However, the Director may establish the reference level based on an analysis of other water-level data. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor, or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.



The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

**3. Scenic Water Way Condition:**

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced. However, the use of ground water allowed under the terms of this permit will not be subject to regulation for Scenic Waterway flows, provided the required mitigation is maintained.

**4. Well Identification Tag Condition:**

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

**STANDARD CONDITIONS**

- 1. Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.
- 2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may be subject to cancellation, unless the Department authorizes the change in writing.

3. If substantial interference with surface water or a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.
4. The well(s) shall be constructed and maintained in accordance with the General Standards for the Construction and Maintenance of Water Supply Wells in Oregon. The works shall be equipped with a usable access port adequate to determine water-level elevation in the well at all times.
5. Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.
6. Prior to receiving a certificate of water right, the permit holder shall submit to the Water Resources Department the results of a pump test meeting the Department's standards for each point of appropriation (well), unless an exemption has been obtained in writing under OAR 690-217. The Director may require water-level or pump-test data every ten years thereafter.
7. This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.
8. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.
9. Construction of the well shall begin within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
10. Complete application of the water shall be made within five years of the date of permit issuance. If beneficial use of permitted water has not been made before this date, the permittee may submit an application for extension of time, which may be approved based upon the merit of the application.
11. Within one year after complete application of water to the proposed use, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner.

Issued \_\_\_\_\_

**DRAFT - THIS IS NOT A PERMIT**

Dwight French  
Water Right Services Division Administrator, for  
Thomas M. Byler, Director  
Oregon Water Resources Department

# Mailing List for PFO Copies

---

Application G-18577

PFO Date March 24, 2020

**Original mailed via CERTIFIED MAIL to applicant:**

R D MAC INC.  
60831 MCALISTER RD  
LA GRANDE OR 97850

Copies Mailed

By: \_\_\_\_\_  
(SUPPORT STAFF)

on: \_\_\_\_\_  
(DATE)

**Sent via auto email:**

1. Agent – Bill Hopp - [bill@cwhopp.com](mailto:bill@cwhopp.com)
2. WRD – Watermaster #, 6 Shad L. Hattan
3. WRD – Jason Spriet ER
4. Agent/Attorney – Elizabeth Howard, [ehoward@schwabe.com](mailto:ehoward@schwabe.com)
5. CWRE – Greg Blackman, [greg@bgbsurveyors.com](mailto:greg@bgbsurveyors.com)
6. DOJ – Anika Marriott, [Anika.E.Marriott@oregon.gov](mailto:Anika.E.Marriott@oregon.gov)

**Copies sent to:**

1. WRD - File # G-18577
2. WRD – SW Section (INCLUDE COPY OF YELLOW SHEET)

Application Specialist: Kim French