



## Water Right Application Initial Review

April 10, 2020

PALMER FAMILY TRUST  
C/O GENE MIRANDA  
PO BOX 1130  
CAVE JUNCTION OR 97523

Reference: Application G-18886

This document is to inform you of the preliminary analysis of the water-use permit application and to describe your options. In determining whether an application may be approved, the Department must consider the factors listed below, all of which must be favorable to the proposed use if it is to be allowed. Based on the information supplied, the Water Resources Department has made the following preliminary determinations:

### **Preliminary Determinations under Oregon Administrative Rule (OAR) 690-310-0080:**

1. Application G-18886 proposes the appropriation of 0.18 cubic foot per second (CFS) of water from Well 3 (JOSE 60693/L134498) in Kelly Creek Basin for year-round nursery use on 2.0 acres, and irrigation of 16.0 acres April 1 through October 31 of each year.
2. The proposed use is not prohibited by law or rule except where otherwise noted below.
3. Uses included in nursery use are included in irrigation and agriculture use, both of which are allowed under the Rogue Basin Program (OAR 690-515-0050).
4. Groundwater will likely be available within the capacity of the resource, and if properly conditioned (and if authorized), the proposed use of groundwater will avoid injury to existing groundwater rights.
5. The Department has determined, based upon OAR 690-009, that the proposed groundwater use will not have the potential for substantial interference with any surface water source.
6. The proposed use is located above the Illinois Scenic Waterway, as designated under Oregon Revised Statute 390.826. The Department has determined, based upon OAR 690-310-0260, that there **is a preponderance of evidence** that the proposed use of groundwater will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife. The one CFS limit prescribed in OAR 690-310-0260(5) has been exceeded. Therefore, water is not available for the proposed use as requested. Please refer to the **Additional Information Opportunity** section below for details.
7. The point of appropriation is not located within a critical, limited, or withdrawn groundwater area.

8. Documentation has been submitted from the relevant land-use planning jurisdiction that indicates the proposed use is allowed outright.

Summary of Preliminary Determinations
<p><b>The appropriation of 0.18 CFS of water from Well 3 (JOSE 60693/L134498) in Kelly Creek Basin for nursery use (irrigation and agriculture use) on 2.0 acres and irrigation of 16.0 acres may be allowable, contingent on the submission of additional required information. See <u>Additional Information Required</u> section below.</b></p>

Not all determinations herein are favorable; therefore **it is unlikely that Application G-18886 will be approved.**

**Additional Information Required**

As noted above, the Department has determined that there is a preponderance of evidence that the proposed use of groundwater will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife. When the Department makes this finding, the Department must deny the application unless:

- (a) mitigation is provided in accordance with provisions of ORS 390.835(9); or
- (b) evidence to overcome the finding is submitted.

If you would like to pursue a permit under this application, you may submit a mitigation proposal or evidence to overcome the finding. The Department will consider the information and determine if the proposal will ensure the maintenance of the free-flowing character of the scenic waterway in quantities necessary for recreation, fish and wildlife.

**Please submit the information no later than May 14, 2020.** If you are unable to submit the information listed above, you may request an administrative hold for up to an additional 180 days. You must submit the request in writing, stating how much more time you will need and why you need additional time. If an administrative hold is granted, your application will not be processed further until the requested information is received or the extended deadline has passed.

If we do not receive the items requested above or a request for an administrative hold by this date, the Department will likely proceed with a Proposed Final Order recommending denial of the application.

**Public Comment & Further Review:**

Public interest issues and/or public comments will be addressed as the Department prepares a Proposed Final Order. If significant public interest issues are identified, they could have an impact on the eventual outcome of the application.

**At this time, you must decide whether to proceed or to withdraw the application.**

- To Proceed - If you choose to proceed with the application you do not have to notify the Department. The application will be placed on the Department's Public Notice to allow others the

opportunity to comment. After the comment period the Department will complete a public interest review and issue a Proposed Final Order.

- To Withdraw - You may withdraw the application and receive a refund (minus a \$260 examination fee per application). You must notify the Department **in writing** by **April 22, 2020**. For your convenience you may use the enclosed "STOP PROCESSING" form.

**If a permit is issued, it will likely include the following conditions:**

1. Construction of the well shall begin within five years of the date of permit issuance. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may not be valid, unless the Department authorizes the change in writing.
3. **Water Use Measurement, Recording, and Reporting Condition:**
  - A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the device in good working order.
  - B. The permittee shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
  - C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
  - D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

**4. Static Water Level Condition:**

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to obtain, from a qualified individual (see below), and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

**Before Use of Water Takes Place**

Initial and Annual Measurements

The Department requires the permittee to report an initial water level measurement in the month specified above once well construction is complete and annually thereafter until use of water begins; and

### **After Use of Water has Begun**

#### Seven Consecutive Annual Measurements

Following the first year of water use, the user shall report seven consecutive annual static water level measurements. The first of these seven annual measurements will establish the reference level against which future annual measurements will be compared. Based on an analysis of the data collected, the Director may require the user to obtain and report additional annual static water level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- A. Identify each well with its associated measurement; and
- B. Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method used to obtain each well measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water level measurements reveal an average water level decline of three or more feet per year for five consecutive years; or
- B. Annual water level measurements reveal a water level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water level measurements reveal a water level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

**5. Scenic Water Way Condition:**

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced.

**6. Well Identification Tag Condition**


Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

The water source identified in the application may be affected by an Agricultural Water Quality Management Area Plan. These plans are developed by the Oregon Department of Agriculture (ODA) with the cooperation of local landowners and other interested stakeholders, and help to ensure that current and new appropriations of water are done in a way that does not adversely harm the environment. You are encouraged to explore ODA's website at <https://www.oregon.gov/ODA/programs/NaturalResources/AgWQ/Pages/AgWQPlans.aspx> to learn more about the plans and how they may affect the proposed water use.

**For Further Information:**

Feel free to contact me at [Kim.R.French@oregon.gov](mailto:Kim.R.French@oregon.gov) or 503-986-0816 if you have any questions regarding the contents of this letter or the application. Please include the application number in all correspondence. General questions about water rights and water use permits should be directed to our customer service staff at 503-986-0900. When corresponding by mail, please use this address: Kim French, Oregon Water Resources Department, 725 Summer St NE Ste A, Salem OR 97301-1266. Our fax number is 503-986-0901.

Sincerely,



Kim French  
Water Right Application Specialist  
Oregon Water Resources Department

Enclosures: Application Process Description and Stop Processing Request Form

G-18886  
WAB: NO PSI

# APPLICATION FACT SHEET

Application File Number: G-18886

Applicant: PALMER FAMILY TRUST

County: JOSEPHINE

Watermaster: SCOTT C. CECILIANI, 14, SWR

Priority Date: DECEMBER 9, 2019

Source: WELL 3 (JOSE 60693/L134498) IN KELLY CREEK BASIN

Use: NURSERY USE ON 2.0 ACRES AND IRRIGATION OF 16.0 ACRES

Quantity: 0.18 CUBIC FOOT PER SECOND

Basin Name & Number: ROGUE, #15

WAB: E FK ILLINOIS R > ILLINOIS R - AT MOUTH

Well Location(s):

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
39 S	7 W	WM	30	SW NE	200 FEET NORTH AND 130 FEET EAST FROM C1/4 CORNER, SECTION 30

Place of Use:

NURSERY USE					
Twp	Rng	Mer	Sec	Q-Q	Acres
39 S	7 W	WM	30	NW NE	2.0

IRRIGATION					
Twp	Rng	Mer	Sec	Q-Q	Acres
39 S	7 W	WM	30	NW NE	4.0
39 S	7 W	WM	30	SW NE	12.0

**PUBLIC NOTICE DATE: April 14, 2020**

**14 DAY STOP PROCESSING DEADLINE DATE: April 22, 2020**

**30 DAY COMMENT DEADLINE DATE: May 14, 2020**

## **APPLICATION PROCESS DESCRIPTION FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR APPLICATIONS**

In order to use the waters of Oregon, an application must be submitted and a permit obtained from the Water Resources Department. The water must be used for beneficial purpose without waste. For more information about water right topics, weekly public notice, forms and fees please visit our web site at [www.oregon.gov/OWRD](http://www.oregon.gov/OWRD)

### ***1. Pre-application considerations***

- Follow instructions in the application packet.
- If you have questions about completing an application or would like to arrange a pre-application conference contact the Department's Water Rights Customer Service Group at (503) 986-0900.

### ***2. Application filing***

- Application with fee is received by the Department.
- Department determines completeness of application.
- If use is not allowed by statute (ORS 538), the application and fees are returned to the applicant.
- An incomplete application and fees are returned to the applicant.
- Only a complete application receives a tentative priority date, is assigned a caseworker, and moves forward for processing.

### ***3. Initial Review (IR)***

- Caseworker reviews application by considering basin plans, water availability, statutory restrictions, and all other appropriate factors.
- Caseworker sends IR report to Applicant.
- Contact the Caseworker if you have questions about the IR.
- Four days after date of the IR, it is included in Department's weekly Public Notice.
- Public comments must be submitted within 30 days after the Public Notice.
- **An administrative hold** may be requested in writing by Applicant.

### ***4. Proposed Final Order (PFO)***

- Caseworker evaluates application against required criteria and develops draft permit, if appropriate.
- PFO includes instructions for filing of protests.
- Caseworker considers public comments and mails PFO to Applicant.
- The PFO is included in Department's weekly Public Notice.
- Public protests to the PFO must be submitted within 45 days after the Public Notice.

### ***5. Final Order (FO)***

- If no protest is filed, Final Order is issued.

### *The protest process*

If one or more protests are filed, the process consists of:

- settlement discussion;
- contested case hearing;
- proposed Order;
- period of time to file exceptions; or
- Possible hearing by Water Resources Commission.
- Final Order is issued.

### *Permit holder responsibilities*

- Comply with all water use conditions of the permit.
- Advise Department of address change or assignment to new permit holder.
- If need arises, request extension of time or authorize cancellation of permit.
- Submit timely claim of beneficial use (COBU) to the Department.
- Most permits require COBU to be prepared by a Certified Water Right Examiner.
- Permits may be canceled by the permit holder or by the Department for failure to comply with or one or more permit conditions.



**STOP PROCESSING REQUEST FORM**  
**FOR GROUNDWATER, SURFACE WATER AND REGULAR RESERVOIR**  
**APPLICATIONS**

---

- Stop processing deadline is within 14 days of Initial Review.

Applicant notification to withdraw Water Right Application **G-18886**.

After reviewing the Initial Review for my application, I request that processing be stopped and fees be refunded (minus a \$260 examination fee). I understand that without a valid permit I may not legally use the water as requested in my application.

Signature \_\_\_\_\_ Date \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

- Under ORS 537.150 (5) and 537.620 (5), timely submission of this request authorizes that the water right application process be stopped and all filing fees (except \$260 examination fee) be returned.
- This notice must be received by the Water Resources Department no later than:

**April 22, 2020**

- Return the notice to:

OWRD, Water Right Services Division  
STOP PROCESSING  
725 Summer Street, NE - Suite A  
Salem, OR 97301-1271

---

# Mailing List for IR Copies

---

Application G-18886

IR Date: April 10, 2020

**Original and map mailed to applicant:**

PALMER FAMILY TRUST  
C/O GENE MIRANDA  
PO BOX 1130  
CAVE JUNCTION OR 97523

Copies Mailed
By: _____ (SUPPORT STAFF)
On: _____ (DATE)

**Sent via auto email:**

1. Applicant - gene-miranda@hotmail.com
2. WRD – Watermaster #14, Scott C. Ceciliani
3. WRD - Jake Johnstone SWR
4. ODFW
5. DEQ

**Copies sent to:**

1. WRD - File G-18886
2. WRD – SW Section (INCLUDE COPY OF YELLOW SHEET)

Application Specialist: Kim French