

WATER WELL REPORT

STATE OF OREGON

RECEIVED

APR 02 2007

WATER RESOURCES DEPT
SALEM, OREGON

State Well No.

State Permit No.

(1) OWNER:

Name Roger Skoe

Address 3385 6th Ave. So.

City Salem

State Or

(2) TYPE OF WORK (check):

New Well ☐ Deepening ☒ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
Cable ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal ☐ Wildfire ☐ Reclamation ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☐
Diam from 0 ft. to 200 ft. Gauge 250
Diam from 0 ft. to 0 ft. Gauge 0

LINER INSTALLED:

7 OD Diam from 100 ft. to 230 ft. Gauge 186

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Torch

Size of perforations 1/4 in. by 8 in.
40 perforations from 212 ft. to 222 ft.
perforations from 0 ft. to 0 ft.
perforations from 0 ft. to 0 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.
Diam Slot Size Set from ft. to ft.
Diam Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller

Yield: 130 gal/min with 49 ft. drawdown after 2 hrs

Air test: 0 gal/min with 0 ft. drawdown after 0 hrs

Bailer test 0 gal/min with 0 ft. drawdown after 0 hrs

Artesian flow 0 g.p.m.

Temperature of water 0 Depth artesian flow encountered 0 ft

(9) CONSTRUCTION:

Special standards Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 19 ft

Diameter of well bore to bottom of seal 12 in.

Diameter of well bore below seal 0 in.

Number of sacks of cement used in well seal 18 sacks

How was cement grout placed? Pressure grouted from

10 ft. to land surface.

Was pump installed? ☒ Yes ☐ No Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plug Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas

Driller's well number 199

NE 4 NE 4 Section 23 T. 45 R. 1E W.M.

Tax Lot # 1700

Lot

Blk

Subdivision

Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 103 ft.

Static level 72 ft. below land surface. Date 9-25-

Artesian pressure 0 lbs. per square inch. Date

(12) WELL LOG:

Depth drilled 230 ft. Depth of completed well 230 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
To soil	0	2	
Clay, brown	2	27	
Clay, blue	27	31	
Clay, gravel, blue, med.	31	36	
Gravel, compacted	36	64	
Clay, brown	64	67	
Gravel, compacted	67	97	
Clay, brown	97	101	
Clay, blue	101	103	
*Sand, brown	103	108	
Clay, brown	108	111	
Clay, blue	111	157	
*Sandstone, soft, black	157	169	
Clay, blue	169	192	
*Sandstone, soft, black	192	195	
Clay, blue	195	212	
*Sandstone, black	212	227	
Clay, blue	227	230	

Work started 9-14 1981 Completed 9-25 1981

Date well drilling machine moved off of well 9-25 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Bob Kern Date 9-29 1981

(Drilling Machine Operator)

Drilling Machine Operator's License No. 994

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name D & G Drilling (Type or print)

Address 10030 S. Hagsburg Rd. Canby, Or.

[Signed] George J. Hainsworth

Contractor's License No. 637 Date 9-29 1981

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion.

SP-12658-690