

Application #	5-83246	WRD Reviewer	Cony M.
Transfer #			
Date Received	12-23-2020		
CWRE Name	Daniel Scalas		

Fees Required:

YES NO A fee of \$200 must accompany this form for any transfers including a water right with a priority date of July 9, 1987, or later.

Fill in App
or Transfer
Number

~~X~~ Map on polyester film (OAR 690-014-0170(1) & 310-0050(1)(b))

~~X~~ Application & permit #; or transfer # (OAR 690-014-0100(1))

~~X~~ Disclaimer (OAR 690-014-0170(5))

~~X~~ North arrow (OAR 690-310-0050(2)(c))

~~X~~ CWRE stamp and signature (OAR 690-014 & 310-0050)

~~X~~ Appropriate scale (1" = 1320', 1" = 400', or the original full-size scale of the county assessor map) (014 & 310)

~~X~~ Township, range, section, and tax lot numbers (OAR 690-310-0050(4))

~~X~~ On form provided by the Department (OAR 690-014-0100(1))
~~X~~ Application & permit #: or transfer # (OAR 690-014)
~~X~~ Ownership information (OAR 690-014)
~~X~~ Date of survey (OAR 690-014)
~~X~~ Person interviewed (OAR 690-014)
~~X~~ County (OAR 690-014)
~~X~~ CWRE stamp and signature (OAR 690-014-0100)
~~X~~ Signature(s) of all permittee of transfer holder (OAR 690-014-0100)

MONEY SLIP																																											
DATE: _____	RECEIPT #: _____																																										
RECEIVED FROM _____ CASH ☐ CHECKS ☐ OTHER (IDENTIFY) _____ ☐ TREASURY ☐ 27% DISC CASH/CCY _____ 0407 COPIES _____ OTHER (IDENTIFY) _____ Amount From _____ Payable _____ Received Via _____ TOTAL DEBIT IS _____																																											
0453 Insured 1.0000 0200 Multi-Purpose Mount Plan 0200 Comp. Value _____ NOB FINANCIAL ONE YEAR CONTRACTORS AGENT																																											
<table border="0" style="width: 100%;"> <tr> <td style="width: 10%;">0407</td> <td style="width: 70%;">INSURANCE/</td> <td style="width: 20%;"></td> </tr> <tr> <td>0410</td> <td>COPY & TAPE FEES</td> <td></td> </tr> <tr> <td>0408</td> <td>RESEARCH FEES</td> <td></td> </tr> <tr> <td>0409</td> <td>INSURANCE IDENTIFY</td> <td></td> </tr> <tr> <td>0412</td> <td>DISCOUNT (SEE IDENTIFY)</td> <td></td> </tr> <tr> <td>0404</td> <td>EXTENSION OF TIME</td> <td></td> </tr> <tr> <td>0401</td> <td>WATER RIGHTS</td> <td></td> </tr> <tr> <td>0401</td> <td>SURFACE WATER</td> <td></td> </tr> <tr> <td>0401</td> <td>GROUND WATER</td> <td></td> </tr> <tr> <td>0401</td> <td>TRANSFER</td> <td></td> </tr> <tr> <td>0410</td> <td>WELL CONSTRUCTION</td> <td></td> </tr> <tr> <td>0410</td> <td>WELL DRILL CONTRACTOR</td> <td></td> </tr> <tr> <td>0410</td> <td>LANDOWNER'S PERMIT</td> <td></td> </tr> <tr> <td>0401</td> <td>OTHER (IDENTIFY)</td> <td></td> </tr> </table>		0407	INSURANCE/		0410	COPY & TAPE FEES		0408	RESEARCH FEES		0409	INSURANCE IDENTIFY		0412	DISCOUNT (SEE IDENTIFY)		0404	EXTENSION OF TIME		0401	WATER RIGHTS		0401	SURFACE WATER		0401	GROUND WATER		0401	TRANSFER		0410	WELL CONSTRUCTION		0410	WELL DRILL CONTRACTOR		0410	LANDOWNER'S PERMIT		0401	OTHER (IDENTIFY)	
0407	INSURANCE/																																										
0410	COPY & TAPE FEES																																										
0408	RESEARCH FEES																																										
0409	INSURANCE IDENTIFY																																										
0412	DISCOUNT (SEE IDENTIFY)																																										
0404	EXTENSION OF TIME																																										
0401	WATER RIGHTS																																										
0401	SURFACE WATER																																										
0401	GROUND WATER																																										
0401	TRANSFER																																										
0410	WELL CONSTRUCTION																																										
0410	WELL DRILL CONTRACTOR																																										
0410	LANDOWNER'S PERMIT																																										
0401	OTHER (IDENTIFY)																																										
NOB FINANCIAL 0407 HYDROLOGICAL INC.																																											
<table border="0" style="width: 100%;"> <tr> <td style="width: 10%;">0403</td> <td style="width: 70%;">POWER LICENSE FEE (POWER)</td> <td style="width: 20%;"></td> </tr> <tr> <td>0403</td> <td>HYDRO LICENSE FEE (HYDRO)</td> <td></td> </tr> <tr> <td></td> <td>HYDRO APPLICATION</td> <td></td> </tr> </table>		0403	POWER LICENSE FEE (POWER)		0403	HYDRO LICENSE FEE (HYDRO)			HYDRO APPLICATION																																		
0403	POWER LICENSE FEE (POWER)																																										
0403	HYDRO LICENSE FEE (HYDRO)																																										
	HYDRO APPLICATION																																										
SPECIAL INSTRUCTIONS: _____																																											

☐ RETURN TO APPLICANT - LETTER ATTACHED

Pump Test Required?	YES	NO	Pump Test Submitted?	YES	NO*
---------------------	-----	----	----------------------	-----	-----

S:\groups\wr\Customer Service Group\Checklists\COBU Checklist-Permits and Transfers-20180201.docxCOBU Checklist-Permits and Transfers-20180209

**CLAIM OF
BENEFICIAL USE
for Surface Water Permits
claiming more than 0.1 cfs**



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem, Oregon 97301-1266
(503) 986-0900
www.oregon.gov/OWRD

**A fee of \$200 must accompany this form for permits
with priority dates of July 9, 1987, or later.**

A separate form shall be completed for each permit.

In cases where a permit has been amended through the permit amendment process, a separate claim for the permit amendment is not required. Incorporate the permit amendment into the claim for the permit.

This form is subject to revision. **Begin each new claim** by checking for a new version of this form at:
<https://www.oregon.gov/OWRD/Forms/Pages/default.aspx>

Go to "Resources for Water Right Examiners (CWRE)" Page
<https://www.oregon.gov/OWRD/programs/WaterRights/COBU/Pages/default.aspx>
The completion of this form is required by OAR 690-014-0100(1) and 690-014-0110(4).

Please type or print in dark ink. If this form is found to contain errors or omissions, it may be returned to you. **Every item must have a response.** If any requested information does not apply to the claim, insert "NA." **Do not delete or alter any section of this form unless directed by the form.** The Department may require the submittal of additional information from any water user or authorized agent.

"Section 8" of this form is intended to aid in the completion of this form and should not be submitted.

If you have questions regarding the completion of this form, please call 503-986-0900 and ask for the Certificate Section.

The Department has a program that allows it to enter into a voluntary agreement with an applicant for expedited services. Under such an agreement, the applicant pays the cost to hire additional staff that would not otherwise be available. This program means a certificate may be issued in about a month. For more information on this program see
<https://www.oregon.gov/OWRD/programs/WaterRights/RA/Pages/default.aspx>

**SECTION 1
GENERAL INFORMATION**

RECEIVED
DEC 23 2020
OWRD

1. File Information:

APPLICATION # S-87246	PERMIT # S-55258	PERMIT AMENDMENT # T-13343
---------------------------------	----------------------------	--------------------------------------

2. Property Owner (current owner information):

APPLICANT/BUSINESS NAME George Stroemple		PHONE NO.	ADDITIONAL CONTACT No.
ADDRESS PO Box 1810			
CITY Lake Oswego	STATE OR	ZIP 97305	E-MAIL grstroemple@gmail.com

If the current property owner is not the permit holder of record, it is recommended that an assignment be filed with the Department. *Each permit holder of record must sign this form.*

3. Permit or holder of record (this may, or may not, be the current property owner):

PERMIT HOLDER OF RECORD Same as above		
ADDRESS		
CITY	STATE	ZIP

ADDITIONAL PERMIT HOLDER OF RECORD		
ADDRESS		
CITY	STATE	ZIP

4. Date of Site Inspection:

8/13/2020

5. Person(s) interviewed and description of their association with the project:

NAME	DATE	ASSOCIATION WITH THE PROJECT
George Stroemple	8/13/2020	Owner

6. County:

Harney

7. If any property described in the place of use of the permit final order is excluded from this report, identify the owner of record for that property (ORS 537.230(5)):

OWNER OF RECORD		
ADDRESS		
CITY	STATE	ZIP


Add additional tables for owners of record as needed

RECEIVED
DEC 23 2020
OWRD

SECTION 2 SIGNATURES

CWRE Statement, Seal and Signature

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge.




CWRE NAME Daniel B. Scalas		PHONE NO. 541-884-4666	ADDITIONAL CONTACT NO.
ADDRESS 1435 Esplanade Ave.			
CITY Klamath Falls	STATE OR	ZIP 97601	E-MAIL dscalas@adkinsengineering.com

Permit Holder of Record Signature or Acknowledgement

Each permit holder of record must sign this form in the space provided below.

The facts contained in this Claim of Beneficial Use are true and correct to the best of my knowledge. I request that the Department issue a water right certificate.

SIGNATURE	PRINT OR TYPE NAME	TITLE	DATE
	George Stroemple	Owner	11/19/20

RECEIVED
DEC 23 2020
OWRD

SECTION 3 CLAIM DESCRIPTION

RECEIVED
DEC 23 2020
OWRD

1. Point of diversion name or number:

POINT OF DIVERSION (POD) NAME OR NUMBER (CORRESPOND TO MAP)
POD 1

2. Point of diversion source and tributary:

POD NAME OR NUMBER	SOURCE	TRIBUTARY
POD 1	Stonehouse Creek	Wildhorse Creek

3. Developed use(s), period of use, and rate for each use:

POD NAME OR NUMBER	USES	IF IRRIGATION, LIST CROP TYPE	SEASON OR MONTHS WHEN WATER WAS USED	ACTUAL RATE OR VOLUME USED (CFS, GPM, OR AF)
POD 1	Primary Irrigation	Pasture	April 1 to June 30	3.64 CFS
Total Quantity of Water Used				3.64 CFS

4. Provide a general narrative description of the distribution works. This description must trace the water system from each point of diversion to the place of use:

Water is diverted from POD 1 by a 7.9 HP pump. From the pump, water is conveyed approximately 780' northeast through 3" aboveground PVC piping where the water is then dispersed to the authorized places of use through flood irrigation.

Reminder: The map associated with this claim must identify the location of the point(s) of diversion, Donation Land Claims (DLC), Government Lots (GLot), and Quarter-Quarters (QQ).

5. Variations:

Was the use developed differently from what was authorized by the permit, or permit amendment final order? If yes, describe below.

YES

(e.g. "The permit allowed three points of diversion. The water user only developed one of the points." or "The permit allowed 40.0 acres of irrigation. The water user only developed 10.0 acres.")

The permit allowed 12.0 acre-feet of water from Stonehouse Pond from March 1 through October 31. Stonehouse Pond was not developed.

6. Claim Summary:

POD NAME OR #	MAXIMUM RATE AUTHORIZED	CALCULATED THEORETICAL RATE BASED ON SYSTEM	AMOUNT OF WATER MEASURED	USE	# OF ACRES ALLOWED	# OF ACRES DEVELOPED
POD 1	12.0 AF from Stonehouse Pond	0.0 AF	N/A	Primary Irrigation	34.0	0.0
POD 1	0.57 CFS from Stonehouse Creek	3.64 CFS	N/A	Primary Irrigation	34.0	34.0

SECTION 4
SYSTEM DESCRIPTION

RECEIVED

DEC 23 2020

Are there multiple PODs?

NO

A. Place of Use

OWRD

1. Is the right for municipal use?

NO

TWP	RNG	MER	SEC	QQ	GLOT	DLC	USE	IF IRRIGATION, # PRIMARY ACRES	IF IRRIGATION, # SUPPLEMENTAL ACRES
35S	33E	WM	15	SE NE			Primary Irrigation	17.0	
35S	33E	WM	15	NE SE			Primary Irrigation	17.0	
Total Acres Irrigated								34.0	

Reminder: The map associated with this claim must identify Donation Land Claims (DLC), Government Lots (GLOT), Quarter Quarters (QQ), and if for irrigation, the number of acres irrigated within each projected DLC, GLOT, and QQ.

B. Diversion and Delivery System Information

Provide the following information concerning the diversion and delivery system. Information provided must describe the equipment used to transport and apply the water from the point of diversion to the place of use.

1. Is a pump used?

YES

2. Pump Information:

MANUFACTURER	MODEL	SERIAL NUMBER	TYPE (CENTRIFUGAL, TURBINE OR SUBMERSIBLE)	INTAKE SIZE	DISCHARGE SIZE
Multiquip	QP3THX	Unknown	Centrifugal	3"	3"

3. Motor Information:

MANUFACTURER	HORSEPOWER
Multiquip	7.9

4. Theoretical Pump Capacity:

HORSEPOWER	OPERATING PSI	LIFT FROM SOURCE TO PUMP	LIFT FROM PUMP TO PLACE OF USE	TOTAL PUMP OUTPUT (IN CFS)
7.9	0	0.0'	14.35'	3.64 CFS

5. Provide pump calculations:

See Attachment C for theoretical pump calculations.

6. Measured Pump Capacity (using meter if meter was present and system was operating):

INITIAL METER READING	ENDING METER READING	DURATION OF TIME OBSERVED	TOTAL PUMP OUTPUT (IN CFS)
N/A			

Reminder: For pump calculations use the reference information at the end of this document.

7. Is the distribution system piped?

NO

8. Mainline Information:

MAINLINE SIZE	LENGTH	TYPE OF PIPE	BURIED OR ABOVE GROUND
3"	780'	PVC	Above Ground

9. Lateral or Handline Information:

LATERAL OR HANDLINE SIZE	LENGTH	TYPE OF PIPE	BURIED OR ABOVE GROUND
N/A			

10. Sprinkler Information:

SIZE	OPERATING PSI	SPRINKLER OUTPUT (GPM)	TOTAL NUMBER OF SPRINKLERS	MAXIMUM NUMBER USED	TOTAL SPRINKLER OUTPUT (CFS)
N/A					

Reminder: For sprinkler output determination use the reference information at the end of this document.

11. Drip Emitter Information:

SIZE	OPERATING PSI	EMITTER OUTPUT (GPM)	TOTAL NUMBER OF EMITTERS	MAXIMUM NUMBER USED	TOTAL EMITTER OUTPUT (CFS)
N/A					

12. Drip Tape Information:

DRIPPER SPACING IN INCHES	GPM PER 100 FEET	TOTAL LENGTH OF TAPE	MAXIMUM LENGTH OF TAPE USED	TOTAL TAPE OUTPUT (CFS)	ADDITIONAL INFORMATION
N/A					

13. Pivot Information:

MANUFACTURER	MAXIMUM WETTED RADIUS	OPERATING PSI	TOTAL PIVOT OUTPUT (GPM)	TOTAL PIVOT OUTPUT (CFS)
N/A				

C. Storage

1. Does the distribution system include in-system storage (e.g. storage tank, bulge in system / reservoir)?

NO

RECEIVED

DEC 23 2020

D. Gravity Flow Pipe

(THE DEPARTMENT TYPICALLY USES THE HAZEN-WILLIAM'S FORMULA FOR A GRAVITY FLOW PIPE SYSTEM)

1. Does the system involve a gravity flow pipe?

OWRD

NO

E. Gravity Flow Canal or Ditch

(THE DEPARTMENT TYPICALLY USES MANNING'S FORMULA FOR CANALS AND DITCHES)

1. Is a gravity flow canal or ditch used to convey the water as part of the distribution system?

NO

F. Additional notes or comments related to the system:

--

SECTION 5 CONDITIONS

All conditions contained in the permit, permit amendment, or any extension final order shall be addressed. Reports that do not address all performance related conditions will be returned.

1. Time Limits:

Permits and any extension final orders contain any or all of the following dates: the date when the actual construction work was to begin, the date when the construction was to be completed, and the date when the complete application of water to the proposed use was to be completed. These dates may be referred to as ABC dates. Describe how the water user has complied with each of the development timelines established in the permit or permit extension of time:

	DATE FROM PERMIT	DATE ACCOMPLISHED*	DESCRIPTION OF ACTIONS TAKEN BY WATER USER TO COMPLY WITH THE TIME LIMITS
ISSUANCE DATE	7/9/2020		
BEGIN CONSTRUCTION (A)	N/A	N/A	N/A
COMPLETE CONSTRUCTION (B)	10/1/2020	8/5/2020	All infrastructure installed.
COMPLETE APPLICATION OF WATER (C)	10/1/2020	8/5/2020	Full beneficial use of water applied to authorized lands.

* MUST BE WITHIN PERIOD BETWEEN PERMIT OR ANY EXTENSION FINAL ORDER ISSUANCE AND THE DATE TO COMPLETELY APPLY WATER

2. Is there an extension final order(s)? YES

a. Did the Extension Final Order require the submittal of Progress Reports? YES

b. Were the Progress Reports submitted? YES

3. Measurement Conditions:

a. Does the permit, permit amendment, or any extension final order require the installation of a meter or approved measuring device? YES

Reminder: If a meter or approved measuring device was required, the COBU map must indicate the location of the device in relation to the point of diversion.

b. Has a meter been installed? NO

c. Meter Information

POD NAME OR #	MANUFACTURER	SERIAL #	CONDITION (WORKING OR NOT)	CURRENT METER READING	DATE INSTALLED
N/A					

d. If a meter has not been installed, has a suitable measuring device been installed and approved by the Department?

RECEIVED ^{YES}

DEC 23 2020

OWRD

e. If "YES", provide a copy of the letter approving the device, if available. If the letter is not available provide the name and title of the Water Resources Department employee approving the measuring device, and the approximate date of the approval:

NAME	TITLE	APPROXIMATE DATE
N/A		

f. Measurement Device Description

DEVICE DESCRIPTION	CONDITION (WORKING OR NOT)	DATE INSTALLED
IEI EZ Ramp Flume	Working	8/5/2020

4. Recording and reporting conditions:

- a. Is the water user required to report the water use to the Department? YES
- b. Have the reports been submitted? YES

If the reports have not been submitted, attach a copy of the reports if available.

5. Fish Screening:

- a. Are any points of diversion required to be screened to prevent fish from entering the point of diversion? NO

6. By-pass Devices:

- a. Are any points of diversion required to have a by-pass device to prevent fish from entering the point of diversion? NO

7. Other conditions required by permit, permit amendment final order, or extension final order:

- a. Was the water user required to restore the riparian area if it was disturbed? YES
- b. Was a fishway required? NO
- c. Was submittal of a water management and conservation plan required? NO
- d. Other conditions? YES

If "YES" to any of the above, identify the condition and describe the water user's actions to comply with the condition(s):

- The permittee shall not construct, operate or maintain any dam or artificial obstruction to fish passage in the channel of the subject stream without providing a fishway to ensure adequate upstream and downstream passage for fish, unless the permittee has requested and been granted a fish passage waiver by the Oregon Fish and Wildlife Commission. The permittee is hereby directed to contact an Oregon Department of Fish and Wildlife Fish Passage Coordinator, before beginning construction of any in-channel obstruction.
 - No dams or artificial obstructions to fish passage in the channel of the subject stream have been constructed or installed.

RECEIVED

DEC 23 2020

OWRD

SECTION 6
ATTACHMENTS

Provide a list of any additional documents you are attaching to this report:

ATTACHMENT NAME	DESCRIPTION
Attachment A	Copy of Permit S-55258
Attachment B	Time Extension Final Order
Attachment C	Theoretical Pump Capacity Calculations
Attachment D	Claim of Beneficial Use Map (on mylar)
Attachment E	Claim of Beneficial Use Map (paper copy)
Attachment F	Harney County Tax Map T35S-R33E

RECEIVED

DEC 23 2020

OWRD

SECTION 7

CLAIM OF BENEFICIAL USE MAP

The Claim of Beneficial Use Map must be submitted with this claim. Claims submitted without the Claim of Beneficial Use map will be returned. The map shall be submitted on poly film at a scale of 1" = 1320 feet, 1" = 400 feet, or the original full-size scale of the county assessor map for the location.

Provide a general description of the survey method used to prepare the map. Examples of possible methods include, but are not limited to, a traverse survey, GPS, or the use of aerial photos. If the basis of the survey is an aerial photo, provide the source, date, series and the aerial photo identification number.

The Claim of Beneficial Use Map was prepared from field measurements, NAIP 2020 aerial photography, Harney County tax maps, and Oregon GLO maps.

Map Checklist

Please be sure that the map you submit includes ALL the items listed below.
(Reminder: Incomplete maps and/or claims may be returned.)

- ☒ Map on polyester film
- ☒ Appropriate scale (1" = 400 feet, 1" = 1320 feet, or the original full-size scale of the county assessor map)
- ☒ Township, Range, Section, Donation Land Claims, and Government Lots
- ☒ If irrigation, number of acres irrigated within each projected Donation Land Claims, Government Lots, Quarter-Quarters
- ☒ N/A Locations of fish screens and/or fish by-pass devices in relationship to point of diversion
- ☒ Locations of meters and/or measuring devices in relationship to point of diversion or appropriation
- ☒ Conveyance structures illustrated (pumps, reservoirs, pipelines, ditches, etc.)
- ☒ Point(s) of diversion or appropriation (illustrated and coordinates)
- ☒ Tax lot boundaries and numbers
- ☒ Source illustrated if surface water
- ☒ Disclaimer ("This map is not intended to provide legal dimensions or locations of property ownership lines")
- ☒ Application and permit number or transfer number
- ☒ North arrow
- ☒ Legend
- ☒ CWRE stamp and signature

RECEIVED

DEC 23 2020

OWRD

ATTACHMENT A
Copy of Permit S-55258

RECEIVED

DEC 23 2020

OWRD

STATE OF OREGON

COUNTY OF HARNEY

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

GEORGE STROEMPLE
PO BOX 1810
LAKE OSWEGO, OR 97035

This superseding permit is issued to describe a change in point of diversion and a change in place of use proposed under Permit Amendment Application T-13343 and approved by Special Order Vol. 117, Page 53, entered JUL 09 2020, and to describe an extension of time for complete application of water approved August 14, 2015. This permit supersedes Permit S-54618.

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: S-87246

SOURCE OF WATER: STONEHOUSE POND CONSTRUCTED UNDER PERMIT R-14734,
A TRIBUTARY OF STONEHOUSE CREEK; STONEHOUSE CREEK, A TRIBUTARY OF
WILDHORSE CREEK

PURPOSE OR USE: IRRIGATION OF 34.0 ACRES

MAXIMUM QUANTITY: 12.0 ACRE FEET FROM STONEHOUSE POND; 0.57 CUBIC
FOOT PER SECOND FROM STONEHOUSE CREEK

PERIOD OF USE: STONEHOUSE POND - MARCH 1 THROUGH OCTOBER 31;
STONEHOUSE CREEK - MARCH 1 THROUGH JUNE 30

DATE OF PRIORITY: JULY 31, 2008

POINT OF DIVERSION LOCATION:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
35 S	33 E	WM	15	NW SE	STONEHOUSE CREEK - 1890 FEET NORTH AND 1510 FEET WEST FROM THE SE CORNER OF SECTION 15

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-SIXTIETH of one cubic foot per second and 2.5 acre-feet for each acre irrigated during the irrigation season of each year.

RECEIVED

DEC 23 2020

OWRD

THE PLACE OF USE IS LOCATED AS FOLLOWS:

IRRIGATION					
Twp	Rng	Mer	Sec	Q-Q	Acres
35 S	33 E	WM	15	SE NE	17.0
35 S	33 E	WM	15	NE SE	17.0
TOTAL					34.0

RECEIVED

DEC 23 2020

OWRD

Permit Amendment T-13343 Conditions:

Water use measurement conditions:

- a. Before water use may begin under this order, the water user shall install a Parshall Flume, or, with prior approval of the Director, another suitable measuring device, at each point of appropriation (new and existing).
- b. The water user shall maintain the Parshall Flume or measuring devices in good working order.
- c. The water user shall allow the Watermaster access to the Parshall Flume or measuring devices; provided however, where the Parshall Flume or measuring devices are located within a private structure, the Watermaster shall request access upon reasonable notice.

The quantity of water diverted at the new point of diversion, (Proposed POD), shall not exceed the quantity of water lawfully available at the original point of diversion (Authorized POD).

Water shall be acquired from the same surface water source as the original point of diversion.

The former place of use shall no longer be irrigated as part of this permit.

Extension of Time Conditions:

Checkpoint Condition

The permit holder must submit a completed Progress Report Form to the Department by May 1, 2020.

- (a) At each checkpoint, the permit holder shall submit and the Department shall review evidence of the permit holder's diligence towards completion of the project and compliance with terms and conditions of the permit and extension. If, after this review, the Department determines the permit holder has not been diligent in developing and perfecting the water use permit, or complied with all terms and conditions, the Department shall modify or further condition the permit or extension to ensure future compliance, or begin cancellation proceedings on the undeveloped portion of the permit pursuant to ORS 537.260 or 537.410, or require submission of a final proof survey pursuant to ORS 537.250;
- (b) The Department shall provide notice of receipt of progress reports in its weekly notice and shall allow a 30 day comment period for each report. The Department shall provide notice of its determination to anyone who submitted comments.

RECEIVED

23 2020

OWRD

Original Permit Conditions:**Measurement, recording and reporting conditions:**

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter or other suitable measuring device as approved by the Director at each point of diversion. The permittee shall maintain the meter or measuring device in good working order, shall keep a complete record of the amount of water used each month, and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

Any effluents or return flows shall not interfere with other beneficial uses of the receiving stream as a result of the use of this permit.

Notwithstanding that Oregon Department of Fish and Wildlife has made a determination that fish screens and/or by-pass devices are not necessary at the time of permit issuance, the permittee may be required in the future to install, maintain, and operate fish screening and/or by-pass devices to prevent fish from entering the proposed diversion, and to provide adequate upstream and downstream passage for fish.

The permittee shall not construct, operate or maintain any dam or artificial obstruction to fish passage in the channel of the subject stream without providing a fishway to ensure adequate upstream and downstream passage for fish, unless the permittee has requested and been granted a fish passage waiver by the Oregon Fish and Wildlife Commission. The permittee is hereby directed to contact an Oregon Department of Fish and Wildlife Fish Passage Coordinator, before beginning construction of any in-channel obstruction.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

If the riparian area is disturbed in the process of developing a point of diversion, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with

ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR 635-415, shall be followed.

The use may be restricted if the quality of the source stream or downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water allowed herein may be made only at times when sufficient water is available to satisfy all prior rights, including prior rights for maintaining instream flows.

The original permit was issued April 22, 2010. Completion of construction and application of the water was to be made within five years of the date of permit issuance. By Extension of Time Final Order dated August 14, 2015, the deadline for completion of construction and complete application of water to the use was extended to October 1, 2020.

Within one year after making beneficial use of water, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner.

Issued at Salem, Oregon this JUL 09 2020


 Lisa J. Jaramillo, Transfer and Conservation Section Manager for
 THOMAS M. BYLER, DIRECTOR
 Oregon Water Resources Department

RECEIVED
 DEC 23 2020
OWRD


Section 15, T35S, R33E, W.M.,
Harney County, Oregon

RECEIVED
JAN 03 2020
OWRD

PERMIT AMENDMENT APPLICATION
Permit S-54618
Application S-87246

RECEIVED
DEC 23 2020
OWRD

George Stroemple



EXPLANATION

FROM LANDS (F)



PROPOSED PLACE OF USE
PRIMARY IRRIGATION - 4.5 A
PRIORITY: 7/31/2008

TO LANDS (T)



PROPOSED PLACE OF USE
PRIMARY IRRIGATION - 4.5 A
PRIORITY: 7/31/2008

REMAINING LANDS (R)



PROPOSED PLACE OF USE
PRIMARY IRRIGATION - 29.5 A
PRIORITY: 7/31/2008



POINT OF DIVERSION (POD)



SCALE



1 INCH = 1320 FEET

January 2, 2020

This map is not intended to provide legal
dimensions or locations of property
ownership lines

Figure 1

SKOOKUM
WATER ASSOCIATES INC

1626 VICTORIAN WAY
EUGENE, OR 97401
(503) 319-8926

RECEIVED

DEC 23 2020

OWRD

ATTACHMENT B
Time Extension Final Order

Oregon Water Resources Department
Water Right Services Division

Water Rights Application
Number S-87246

RECEIVED

DEC 23 2020

OWRD

FINAL ORDER

Extension of Time for Permit Number S-54618
Permit Holder: George Stroemple

Permit Information

Application:	S-87246
Permit:	S-54618
Basin:	12 – Malheur Lake / Watermaster District 10
Date of Priority:	July 31, 2008
Source of Water:	Stonehouse Pond constructed under Permit R-14734, a tributary of Stonehouse Creek; Stonehouse Creek, a tributary of Wildhorse Creek
Purpose of Use:	Irrigation of 34.0 Acres
Maximum Rate:	12.0 Acre-Feet (AF) from Stonehouse Pond; 0.57 cubic foot per second (cfs) from Stonehouse Creek

This Extension of Time request is being processed in accordance with Oregon Revised Statute 537.230 and 539.010(5), and Oregon Administrative Rule Chapter 690, Division 315

Appeal Rights

This final order is subject to judicial review by the Court of Appeals under ORS 183.482. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.482(1). Pursuant to ORS 536.075 and OAR 137-003-0675, you may petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

Application History

Permit S-54618 was issued by the Department on April 22, 2010. The permit called for completion of construction by April 22, 2015 and complete application of water to beneficial

use by April 22, 2015. On May 1, 2015, George Stroemple submitted to the Department an Application for Extension of Time for Permit S-54618. In accordance with OAR 690-315-0050(2), on June 16, 2015, the Department issued a Proposed Final Order proposing to extend the time to complete construction from 2015 to October 1, 2020 and the time to apply water to full beneficial use from 2015 to October 1, 2020. The protest period closed July 31, 2015, in accordance with OAR 690-315-0060(1). No protest was filed.

FINDINGS OF FACT

The Department adopts and incorporates by reference the findings in the Proposed Final Order dated June 16, 2015.

At time of issuance of the Proposed Final Order the Department concluded that, based on the factors demonstrated by the applicant, the permit may be extended subject to the following conditions.

CONDITIONS

1. Checkpoint Condition

The permit holder must submit a completed Progress Report Form to the Department by **May 1, 2020**. *A form is enclosed with this Final Order.*

(a) At each checkpoint, the permit holder shall submit and the Department shall review evidence of the permit holder's diligence towards completion of the project and compliance with terms and conditions of the permit and extension. If, after this review, the Department determines the permit holder has not been diligent in developing and perfecting the water use permit, or complied with all terms and conditions, the Department shall modify or further condition the permit or extension to ensure future compliance, or begin cancellation proceedings on the undeveloped portion of the permit pursuant to ORS 537.260 or 537.410, or require submission of a final proof survey pursuant to ORS 537.250;

(b) The Department shall provide notice of receipt of progress reports in its weekly notice and shall allow a 30 day comment period for each report. The Department shall provide notice of its determination to anyone who submitted comments.

RECEIVED

DEC 23 2020

CONCLUSION OF LAW


OWRD

The applicant has demonstrated good cause for the permit extension pursuant to ORS 537.230, 539.010(5) and OAR 690-315-0040(2).

ORDER

The extension of time for Application S-87246, Permit S-54618, therefore, is approved subject to conditions contained herein. The deadline for completing construction is extended from April 22, 2015 to October 1, 2020. The deadline for applying water to full beneficial use within the terms and conditions of the permit is extended from April 22, 2015 to October 1, 2020.

DATED: August 14, 2015



Dwight French

Water Right Services Division Administrator, for
Thomas M. Byler, Director
Oregon Water Resources Department

-
- If you have any questions about statements contained in this document, please contact Permit Extension Specialist at (503) 986-0825.
 - If you have other questions about the Department or any of its programs, please contact our Water Resources Customer Service Group at (503) 986-0900
-

RECEIVED

DEC 23 2020

OWRD

ATTACHMENT C
Theoretical Pump Capacity Calculations

Pump Capacity Calculation Sheet

using Department designed formula:

Date: 8/17/2020

$(\text{hp})(\text{efficiency}) / (\text{lift} + \text{psi head}) = \text{capacity in cfs}$

Efficiency:

Centrifugal = 6.61

Turbine = 7.04

Data Entry (fill in underlined blanks)

HP = 7.9
Efficiency = 6.61
Lift = 14.35
PSI = 0

Results Calculated

(hp)(efficiency) = 52.219
Head based on psi = 0.0
Total dynamic head = 14.4
(head + lift)

Pump Capacity = 3.64 cubic feet per second

RECEIVED

DEC 23 2020


OWRD

ATTACHMENT D
Claim of Beneficial Use Map (on mylar)

RECEIVED

DEC 23 2020

OWRD



LEGEND	
	SECTION LINE
	1/4 1/4 LINE
	TAX LOT LINE
	DITCH/CREEK
	⊙ ROAD
	ABOVE GROUND PIPE
	FLOW DIRECTION
	SECTION CORNER
TL 0000	TAX LOT NUMBER
	POD
	PARSHALL FLUME
	IRRIGATED UNDER PERMIT S-55258
	IRRIGATED ACRES
	1/4 1/4 SECTION

RECEIVED

DEC 23 2020



OWRD

NOTES:

1. THIS MAP WAS PREPARED FROM FIELD MEASUREMENTS, NAIP 2020 AERIAL PHOTOGRAPHY, HARNEY COUNTY TAX MAPS, AND OREGON GLO MAPS.
2. THE PURPOSE OF THIS MAP IS TO IDENTIFY THE LOCATION OF THE WATER RIGHT ONLY, AND IS NOT INTENDED TO PROVIDE DIMENSIONS OR LOCATION OF PROPERTY LINES.
3. DATE OF PRIORITY FOR THIS WATER RIGHT IS JULY 31, 2008.

POD LOCATION:

POD 1: T35S, R33E, SECTION 15, W.M.; 1890' NORTH & 1510' WEST FROM THE SOUTHEAST CORNER OF SECTION 15.



AL ADKINS
ENGINEERING & SURVEYING

o / 541.884.4666
w / AdkinsEngineering.com

1435 ESPLANADE AVENUE, KLAMATH FALLS, OR 97601

SERVING S. OREGON & N. CALIFORNIA

ENGINEERING • SURVEYING • PLANNING • TESTING

CLAIM OF BENEFICIAL USE AND FINAL PROOF MAP

FOR


GEORGE STROEMPLE
T35S, R33E, SEC. 15, WM
HARNEY COUNTY, OREGON
PERMIT S-55258
APPLICATION S-87246

ATTACHMENT E
Claim of Beneficial Use Map (paper copy)

RECEIVED

DEC 23 2020

OWRD



LEGEND	
	SECTION LINE
	1/4 1/4 LINE
	TAX LOT LINE
	DITCH/CREEK
	☒ ROAD
	ABOVE GROUND PIPE
	FLOW DIRECTION
	SECTION CORNER
	TAX LOT NUMBER
	POD
	PARSHALL FLUME
	IRRIGATED UNDER PERMIT S-55258
	IRRIGATED ACRES
	1/4 1/4 SECTION

RECEIVED

DEC 23 2021



OWRD

NOTES:

1. THIS MAP WAS PREPARED FROM FIELD MEASUREMENTS, NAIP 2020 AERIAL PHOTOGRAPHY, HARNEY COUNTY TAX MAPS, AND OREGON GLO MAPS.
2. THE PURPOSE OF THIS MAP IS TO IDENTIFY THE LOCATION OF THE WATER RIGHT ONLY, AND IS NOT INTENDED TO PROVIDE DIMENSIONS OR LOCATION OF PROPERTY LINES.
3. DATE OF PRIORITY FOR THIS WATER RIGHT IS JULY 31, 2008.

POD LOCATION:

POD 1: T35S, R33E, SECTION 15, W.M.; 1890' NORTH & 1510' WEST FROM THE SOUTHEAST CORNER OF SECTION 15.



AL ADKINS
ENGINEERING & SURVEYING

o / 541.884.4666
w / AdkinsEngineering.com

1435 ESPLANADE AVENUE, KLAMATH FALLS, OR 97601

SERVING S. OREGON & N. CALIFORNIA

ENGINEERING • SURVEYING • PLANNING • TESTING

CLAIM OF BENEFICIAL USE AND FINAL PROOF MAP

FOR
GEORGE STROEMPLE
T35S, R33E, SEC. 15, WM
HARNEY COUNTY, OREGON
PERMIT S-55258
APPLICATION S-87246

ATTACHMENT F
Harney County Tax Map T35S-R33E

RECEIVED

DEC 23 2020

OWRD

T.35S. R.33E. W.M.

HARNEY COUNTY

1" = 2000'


THIS MAP WAS PREPARED FOR
ASSESSMENT PURPOSE ONLY

0 2,000 4,000
SCALE IN FEET

35S 33E

& INDEX

CANCELLED NO.
400
1400



RECEIVED

DEC 23 2020

OWRD

PRINTED ON
Jul 15, 2010

35S 33E
& INDEX