

**690-200-0028 Designated Special Area Standards**

**(1) Special Area Standards for the Construction and Alteration of Water Supply Wells in the Lakeview Area**

**(A) As used in this rule and illustrated in Figure 200-3, “The Lakeview Area” includes the area located in Sections 4, 5, 8 and 9 of Township 39 South, Range 20 East of the Willamette Meridian, Lake County, Oregon.**

**Beginning at a point on the West line of Section 4, said point bears South 1°40'45" East - 2245.31 feet from the Northwest Corner of Section 4; thence South 89°54'45" East- 1907.04 feet to the West right of way line of the Fremont Logging Road; thence South 39°26'40" East along the West right of way line of the Fremont Logging Road - 3095.16 feet; thence South 1°53'14" East - 617.32 feet to the South line of Section 4; thence continuing in Section 9 - South 00°13'8" West parallel to the North South centerline of Section 9- 2649.14 feet to the East West centerline of Section 9; thence South 89°45'31" West along the East West centerline of Section 9 - 3782.55 feet more or less to the West line of Section 9; thence West along the East West centerline of Section 8 - 1320.00 feet more or less to the center East 1/16 corner of Section 8; thence North 2640.00 feet more or less to the East 1/16 corner common to Sections 5 and 8; thence North 1°41'33" West - 2630.48 feet more or less to the center East 1/16 corner of Section 5; thence North 1°40'45" West - 410.32 feet; thence South 59°54'45" East - 1307.02 feet more or less to the point of beginning.**

**(B) Any new, altered, deepened or converted well in the sedimentary units (clay, sand, silt, gravel) in the Lakeview Area shall be cased and sealed according to OAR 690, Division 210 with the following additional requirements:**

**(a) Unperforated casing and seal shall extend from land surface to a depth of 250 feet below land surface, and**

**(b) Perforated casing may extend below the seal.**

**Bold** text is proposed new language that was proposed in the hearing draft rules.  
No changes are proposed to the hearing draft rules.

FINAL PROPOSED RULES

Special Area Well Construction Standards – Lakeview Area

OAR Chapter 690, Division 200

March 12, 2004

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24

**(C) Liner installed in any new, altered, deepened or converted well in the sedimentary units (clay, sand, silt, gravel) in the Lakeview Area shall not extend more than 10 feet above the bottom of the unperforated casing.**

**(D) Alternatives to the special area standards shall be approved only if it can be demonstrated that the alternative techniques proposed to be used are as effective as the techniques required in subsection (1)(B) and (1)(C) above. Such alternatives require prior written approval by the Department and follow-up testing as may be required by the Department.**

**(E) Except as they may conflict with subsection (1) (B) and (1)(C), all other provisions of Oregon Administrative Rules for Well Construction and Maintenance Standards apply.**

**(F) This rule is applicable to wells for which construction, alteration, deepening or conversion began on or after (effective date of this rule).**

**(G) This special area standard may be revised at a future date when additional information and analysis is provided from other agencies including the Oregon Department of Environmental Quality.**

**Bold** text is proposed new language that was proposed in the hearing draft rules. No changes are proposed to the hearing draft rules.