

FINAL PROPOSED RULES
Special Area Well Construction Standards-
Petes Mountain Area & Eola Hills Ground
Water Limited Area
OAR Chapter 690, Division 210
May 30, 2008

1 **690-210-0280**

2 **Access Ports, Dedicated Measuring Tubes and Airlines**

3 All water supply wells shall be equipped with a usable access port with a minimum
4 diameter of 1/2 inch **for the purpose of determining the water level in the well at**
5 **anytime. Dedicated** measuring tubes are recommended to be installed on all wells at
6 **the time of pump installation. Where required, dedicated measuring tubes shall be a**
7 **minimum of 3/4 inch schedule 40 PVC extending to the top of the pump (See**
8 **Dedicated Measuring Tube Diagram and Specifications in Figure 200-5). An airline**
9 **is not a substitute for a required dedicated measuring tube and, if installed, must**
10 enter the well in a location other than the access port. Access ports, **dedicated measuring**
11 **tubes** or airlines shall be capped and be a minimum of twelve inches above finished
12 ground surface or pumphouse floor (See Figure 210-12) **(See Figure 200-5). The access**
13 **port, airline and dedicated measuring tube on all water supply wells required by**
14 **OAR 690-210-0280 shall be maintained in a condition that will prevent**
15 **contamination of the ground water, and shall remain unobstructed and be**
16 **maintained by the landowner so that the water level can be determined at any time.**
17 [ED. NOTE: Figures referenced are available from the agency.]

18

19 Stat. Auth.: ORS 536.090 & ORS 537.505 - ORS 537.795

20 Stats. Implemented:

21 Hist.: WRD 13-1986, f. 10-7-86, ef. 11-1-86; WRD 8-1993, f. 12-14-93, cert. ef. 1-1-94; WRD 7-2001, f.
22 & cert. ef. 11-15-01

23