

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

SALEM, OREGON

RECEIVED

JUN 8 1981

State Well No. 95/40E-2009

State Permit No.

(1) OWNER:

Name Gary Schmitt
Address 135 So Foothill Drive
Baker Ore 97814

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 124 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used Torch

Size of perforations 1/8 in. by 6 in.
50 perforations from 70 ft. to 124 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

Bailer test 12 gal./min. with 6 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Pressure grout
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 14 sacks
How was cement grout placed? Pumped in with
centrifugal pump Thru pipe from
bottom to top

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Baker Driller's well number
NE 1/4 SW 1/4 Section 20 T. 95 R. 40 E W.M.
Bearing and distance from section or subdivision corner 100.5
Then 100' W from NE corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 86 ft.
Static level 76 ft. below land surface. Date 4/12/80
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing

Depth drilled 124 ft. Depth of completed well 124 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	3	
White Clay	3	9	
Light Brown Clay & Small Rock	9	16	
Sandstone	16	19	
Brown Clay & Small Rock	19	86	
Small Gravel	86	88	70
Dark Brown Clay & Small Rock	88	124	"

RECEIVED

MAY 6 1981

WATER RESOURCES DEPT

SALEM, OREGON

Work started 1-5-1980 Completed 4-18-1980

Date well drilling machine moved off of well 4-18-1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Melvin L Copley Date 4-19-1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 671

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Melvin L Copley
(Person, firm or corporation) (Type or print)

Address Box 27 Sumpter Stage Baker

[Signed] Melvin L Copley
(Water Well Contractor)

Contractor's License No. 536 Date 4-19-1980