

(1) OWNER:

Name TOWN OF HAINES ENGINEER
Address HAINES OREGON

(2) LOCATION OF WELL:

County BAKER Owner's number, if any—

R. F. D. or Street No.

Bearing and distance from section or subdivision corner

CORNER OF OLSON & 1st ST.

(3) TYPE OF WORK (check):

New well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

abandonment, describe material and procedure in Item 11.

PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☒
Irrigation ☐ Test Well ☐ Other ☐

(5) EQUIPMENT:

Rotary ☐
Cable ☒
Dug Well ☐

(4) CASING INSTALLED:

Threaded ☐ Welded ☒

FROM	ft. to	ft.	Diam.	Gage or Wall
" 0 "	81 "	12 "	" 12 "	330
" +1 "	162 "	8 "	" 8 "	264
" "	" "	" "	" "	"
" "	" "	" "	" "	"

If gravel packed

Diameter of Bore	from ft.	to ft.
" "	" "	" "
" "	" "	" "
" "	" "	" "
" "	" "	" "

Type and size of shoe or well ring 8"

Size of gravel:

Describe joint 22 JOINT SHOP FABRICATED SHOE

(7) PERFORATIONS:

Type of perforator used Mihls

FROM	ft. to	ft.	No. of perforations	in., length, by	in.
" 5 "	83 "	" "	" 4 "	" 5 "	" 5 "
" 1 "	101 "	" "	" 5 "	" 5 "	" 5 "
" 146 "	150 "	" "	" 5 "	" 5 "	" 5 "
" 153 "	160 "	" "	" 5 "	" 5 "	" 5 "

SCREENS:

Give Manufacturer's Name, Model No. and Size

(8) CONSTRUCTION:

Was a surface sanitary seal provided? ☒ Yes ☐ No To what depth 21 ft.

Were any strata sealed against pollution? ☒ Yes ☐ No

If yes, note depth of strata

FROM 0 ft. to 21 ft.

" 21 " DOWN "

METHOD OF SEALING 21' OF 12" - BENTONITE

(9) WATER LEVELS:

Depth at which water was first found 91 ft.

Standing level before perforating 6 ft.

Standing level after perforating 6 ft.

Log Accepted by:

[Signed] John Haines Dated Oct 19, 1962

owner
Wm F. Puller

(10) WELL TESTS:

Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER

Yield: 167 gal./min. with 37 ft. draw down after 9 hrs.

" " " "

Artesian flow g.p.m.

Shut-in pressure lbs. per square inch.

Bailer test g.p.m. with ft. drawdown

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

Was electric log made of well? ☐ Yes ☒ No

(11) WELL LOG:

Diameter of well, 8 inches.

Total depth 162 ft. Depth of completed well 162 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

ft. to	ft.	
0 "	4 "	SOIL
4 "	9 "	SAND
9 "	14 "	CHAK-SAND
14 "	16 "	CEMENTED SAND
16 "	28 "	SAND-CHAK
28 "	33 "	CEMENTED SAND
33 "	45 "	SAND-CHAK
45 "	53 "	SAND-GRAVEL
53 "	74-6 "	SAND
74-6 "	91-6 "	CEMENTED GRAVEL
91-6 "	97-6 "	SAND-GRAVEL
97-6 "	101 "	GRAVEL
101 "	106 "	CHAK-GRAVEL
106 "	110 "	SAND-GRAVEL
110 "	116 "	CEMENTED GRAVEL
116 "	125 "	CHAK-SAND-MUD
125 "	146 "	SAND-CHAK
146 "	148 "	GRANITE SAND
148 "	150 "	" " "
150 "	153 "	CEMENTED SAND
153 "	156 "	GRAVEL-ROCKS
156 "	162 "	LARGE ROCKS
" "	" "	" "
" "	" "	" "
" "	" "	" "
" "	" "	" "

Ground elevation at well site 390.7 feet above mean sea level. X

Work started AUG. 1 19 62 Completed SEPT. 29 19 62

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME CHAS. JUNGMAUN DRILLING CO.

(Person, firm, or corporation) O. B. Box 128 printed)

Address WALLA WALLA, WASHINGTON

Driller's well number

[Signed] Charles Jungmann

(Well Driller)

License No. 236 Dated OCT. 8, 1962