

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 10/38-19 J

State Permit No.

STATE ENGINEER

SALEM OREGON

(1) OWNER:

Name Willard Bunch
Address 3210 Plum Baker, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

8" Diam. from 0 ft. to 85 ft. Gage .250
6" Diam. from 85 ft. to 150 ft. Gage .250
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch & Mills Knife

Size of perforations 1/4 in. by 4 in.
240 perforations from 40 ft. to 150 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 25 ft. below land surface Date 7-11-68
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.
" " " " "

Bailer test 75 gal./min. with 20 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water 53° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Grout
Depth of seal 20' ft.
Diameter of well bore to bottom of seal 12 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Baker Driller's well number 139
NE 1/4 SE 1/4 Section 19 T. 10S R. 38E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing

Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top soil	0	2	-
Brown clay & boulders	2	24	-
Light brown gritty clay	24	46	-
Brown clay w/fine gravel	46	58	30'
Red gritty clay	58	67	30'
Brown clay w/fine grav	67	83	30'
Gray Basalt (Hard)	83	90	30'
Brn clay w/fine gravel	90	121	25'
Blue clay fine gravel & coarse sand	121	150	25'

Work started 6-28-68 19 Completed 7-11-1968

Date well drilling machine moved off of well 7-11-68 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] James W. Brown Date 10/11/68
(Drilling Machine Operator)

Drilling Machine Operator's License No. 472

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Stoffel Brown Drilling Co.
(Person, firm or corporation) (Type or print)

Address Rt. 2 Box 78 La Grande, Oreg

[Signed] Robert N. Stoffel
(Water Well Contractor)

Contractor's License No. 415 Date 10-11-68 1968

(USE ADDITIONAL SHEETS IF NECESSARY)