

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

SEP 26 1994

Bake
2078

(START CARD) # 57843

(1) OWNER:

Name C. W. Jones Well Number _____
Address 2448 N. Dr.
City BALISE CITY State ORE Zip 97814

(2) TYPE OF WORK:

☐ New Well ☒ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 280 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
12	0 110	SEAL IN 1/4" C			
10	0 280				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 0 ft. to 110 ft. Size of gravel 3/4"

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:					☐	☐	☐	☐
Liner:	10	+1	274	1250	☒	☐	☒	☐

Final location of shoe(s) 274

(7) PERFORATIONS/SCREENS:

☒ Perforations Method DOWN HOLE PERFORATOR
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
40	274	1"	4032	1/4	10	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
700	267	280	1 hr.

Temperature of Water 52 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☒ No ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County BALISE Latitude _____ Longitude _____
Township 5 N or S Range 39 E or W. WM.
Section 15 54 NE 1/4
Tax Lot 400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) SCHOOL HOUSE RD.

(10) STATIC WATER LEVEL:

13 ft. below land surface. Date 9-31-94
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 13

From	To	Estimated Flow Rate	SWL
13	110	250	13
140	175	150	13
200	255	200	13
272	280	100	13

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
WORKS STARTED - SAND - 1/4" D	110	130	13
CLAY + SAND -	130	140	
SAND - 1/4" D	140	175	13
SAND + CLAY 1/4" D	175	200	13
SAND - 1/4" D	200	255	13
1" + CLAY - 1/4" D	255	272	13
SAND 1/4" D	272	280	13

Date started 9-6-94 Completed 9-30-94

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Material used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number 596
Date 9-30-94

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Thelma Danner WWC Number 596
Date 9-30-94