

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

 WELL I.D. # L 64292
 START CARD # 168866

 (1) LAND OWNER _____ Well Number _____
 Name Mark Servid
 Address 14138 Hunt Mt Lane
 City Baker City State OR Zip 97814

 (2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

 (3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

 (4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

 (5) BORE HOLE CONSTRUCTION:
 Special Construction approval ☐ Yes ☒ No Depth of Completed Well 140 ft.
 Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	18	Bentonite	0	18	12
6"	18	140				

 How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Dry Bentonite 3/8" Poured
 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

 (6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	12	140	.250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

 Drive Shoe used ☒ Inside ☐ Outside ☐ None
 Final location of shoe(s) 140

 (7) PERFORATIONS/SCREENS:
☒ Perforations Method Hot Perforator
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
80	140	1"	900	48"	6"	☒	☐

 (8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
22	120	140	1 hr.

 Temperature of water 52° Depth Artesian Flow Found _____
 Was a water analysis done? ☐ Yes By whom _____
 Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
 Depth of strata: _____

 (9) LOCATION OF WELL by legal description:
 County Baker Latitude _____ Longitude _____
 Township 8 N or S Range 39 E or W. WM.
 Section 19 NW 1/4 SW 1/4
 Tax Lot 600 Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) 14138 Hunt Mt Lane
Baker City

 (10) STATIC WATER LEVEL:
20 ft. below land surface. Date 9/3/04
 Artesian pressure _____ lb. per square inch Date _____

 (11) WATER BEARING ZONES:
 Depth at which water was first found 22

From	To	Estimated Flow Rate	SWL
22	140	22	20

 (12) WELL LOG:
 Ground Elevation _____

Material	From	To	SWL
Top Soil	0	1	
Boulders	1	22	
Sand, gravel, some clay w/ls	22	140	20

RECEIVED
OCT 01 2004
 WATER RESOURCES DEPT
 SALEM, OREGON

 Date started 8/26/04 Completed 9/3/04

 (unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

 Signed John Phurcell WWC Number _____ Date 9/25/04

 (bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

 Signed Thelma J. Dennis WWC Number 591 Date 9/25/04