

**NOTICE TO WATER WELL CONTRACTOR**

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 4 1968  
 within 30 days from the date of well completion.

**BAKE 576 RECEIVED**

**RECEIVED WATER WELL REPORT**

DATE OF OREGON STATE ENGINEER  
 (Please type or print) STATE ENGINEER  
 (Do not write above this line) STATE ENGINEER  
 SALEM, OREGON State Well No. B/40-15 C  
 State Permit No. G-4274

**(1) OWNER:**

Name Jim Junell Stage  
 Address Baker Ore Medical Springs

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon

If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary  Driven   
 Cable  Jetted   
 Bored

**(4) PROPOSED USE (check):**

Domestic  Industrial  Municipal   
 Irrigation  Test Well  Other

**CASING INSTALLED:**

Threaded  Welded

12" Diam. from 0 ft. to 40 ft. Gage 50  
 " Diam. from ..... ft. to ..... ft. Gage .....  
 " Diam. from ..... ft. to ..... ft. Gage .....

**PERFORATIONS:**

Perforated?  Yes  No.

Type of perforator used touch  
 Size of perforations 1/4 in. by 12 in.  
 18 perforations from 18 ft. to 40 ft.  
 ..... perforations from ..... ft. to ..... ft.  
 ..... perforations from ..... ft. to ..... ft.  
 ..... perforations from ..... ft. to ..... ft.  
 ..... perforations from ..... ft. to ..... ft.

**(7) SCREENS:**

Well screen installed?  Yes  No

Manufacturer's Name ..... Model No. ....  
 Type ..... Diam. ..... Slot size ..... Set from ..... ft. to ..... ft.  
 Diam. ..... Slot size ..... Set from ..... ft. to ..... ft.

**(8) WATER LEVEL: Completed well.**

Level 8 ft. below land surface Date 2/26  
 Artesian pressure ..... lbs. per square inch Date .....

**(9) WELL TESTS:**

Drawdown is amount water level is lowered below static level

Was a pump test made?  Yes  No If yes, by whom? driller  
1:390 gal./min. with 8 ft. drawdown after 4 hrs.  
"this all" the pump would  
"pump all the water wanted"  
 Baller test 10 gal./min. with ..... ft. drawdown after ..... hrs.  
 Artesian flow ..... g.p.m. Date .....  
 Temperature of water ..... Was a chemical analysis made?  Yes  No

**(10) CONSTRUCTION:**

Well seal—Material used Bentonite  
 Depth of seal 18 ft.  
 Diameter of well bore to bottom of seal 21 in.  
 Were any loose strata cemented off?  Yes  No Depth .....  
 Was a drive shoe used?  Yes  No  
 Did any strata contain unusable water?  Yes  No  
 Type of water? ..... depth of strata .....  
 Method of sealing strata off .....  
 Was well gravel packed?  Yes  No Size of gravel: .....  
 Gravel placed from ..... ft. to ..... ft.

**(11) LOCATION OF WELL:**

County Baker Driller's well number 1  
NE 1/4 T. 11 N. 1/4 Section 15 T. 8 S R. 40 W.M.  
 Bearing and distance from section or subdivision corner .....

**(12) WELL LOG:**

Diameter of well below casing 12

Depth drilled 45 ft. Depth of completed well 45 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

| MATERIAL                             | From | To | SWL |
|--------------------------------------|------|----|-----|
| top soil                             | 0    | 10 |     |
| clay and concretion                  | 6    | 15 |     |
| clay yellow                          | 15   | 26 |     |
| gold sand gravel<br>lots of matter   | 26   | 36 |     |
| clay                                 | 36   | 40 |     |
| coarse sand gravel<br>lots of matter | 40   | 45 |     |

Work started 12/31 1967 Completed 13/26 1967  
 Date well drilling machine moved off of well 13/27 1967

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] A. W. Robinson Date 2/27, 1968  
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 41

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME A. W. Robinson (Type or print)  
 Address 280 9 1/2 St Baker Ore

[Signed] A. W. Robinson  
 (Water Well Contractor)

Contractor's License No. 128 Date 2/27, 1968