

RECEIVED
JUN 15 1959

WATER WELL REPORT

File Original and
First Copy with the
STATE ENGINEER,
SALEM, OREGON

STATE ENGINEER

STATE OF OREGON

G-1527

State Well No.

9/39-4E

State Permit No.

G-1403

(1) OWNER:

Name

Address

(2) LOCATION OF WELL:

County Baker Owner's number, if any—

S.W. 1/4 NW. 1/4 Section 4 T. 9 R. 39E W.M.

Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

In abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐

Irrigation ☐ Test Well ☒ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 0 ft. to 44 ft. Gage 280

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used

SIZE of perforations 3/16 in. by 6 in.

34 perforations from 34 ft. to 44 ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Slot size Set from ft. to ft.

Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

Was a surface seal provided? ☒ Yes ☐ No To what depth? 16 ft.

Material used in seal—

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? Depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 20 ft. below land surface Date 5/29

Artesian pressure lbs. per square inch Date

Log Accepted by:

[Signed] Bert Brink Date June 1, 1959

(Owner)

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom? —

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 19 gal./min. with 20 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water 52 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 6 inches.

Depth drilled 58 ft. Depth of completed well 58 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
gravel clay packed	0	20
sand and gravel clay	20	28
filled		
coarse sand small	28	42
gravel mostly filled		
with clay		
coarse sand loose	42	44
gravel some clay	44	48
clay specimen	48	58

Work started 5/26 19 Completed 5/29 59

(13) PUMP:

Manufacturer's Name

Type: H.P.

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME

(Person, firm, or corporation)

(Type or print)

Address

Driller's well number

[Signed]

(Well Driller)

License No.

Date 5/29 58

RECEIVED

JUN 15 1953

STATE ENGINEER
SALEM, OREGON

Description of Bert Brink Property
address - 2205 - 3rd St
Baker, Oregon

Beginning at a point which is North (Mag. Var. 20 degrees 30' 25920.0 feet and S 89 degrees 26' 12" E, 435.6 feet from the section corner common to Sections 4, 5, 8, and 9, Township 9 South, Range 39 E. W. M.; thence from said point S 89 degrees 26' 12" E, 217.8 feet; thence N 1 degree 24' 12" W, 1218.0 feet, to a point along the southerly right-of-way line 217.8 feet; thence S 1 degree 24' 12" E, 1218.0 feet to the aforesaid point of beginning, said tract containing 6.09 acres, more or less,

Well is located about the center of the south end of lot and about 45' north from line.