

WATER WELL REPORT
STATE OF OREGON

RECEIVED

DEC 4 1981

State Well No.

115/4W-6cd

WATER RESOURCES DEPT
SALEM, OREGON

State Permit No.

(1) OWNER:

Name Charley Fischer
Address 6455 NE Pettibone Dr.
City Corvallis 97330 State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
Cased ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

6" Diam. from +1 ft. to 85 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

NONE

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Mills Knife
Size of perforations 3/8 in. by 1 in.
52 perforations from 72 ft. to 84 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
gal./min. with ft. drawdown after hrs.
Air test 8 gal./min. with drill stem at 95 ft. 1 1/2 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 40 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 19 sacks
How was cement grout placed? Pressure Pumped
from Bottom of Seal

Was pump installed? NO Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Benton Driller's well number
SE 1/4 SW 1/4 Section 6 T. 11S R. 4W W.M.
Tax Lot # Lot Blk Subdivision

Address at well location: 6455 NE Pettibone Dr.
Corvallis Oregon 97330

(11) WATER LEVEL: Completed well.

Depth at which water was first found 61 ft.
Static level 12 ft. below land surface. Date 11-4-81
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing S.I.X.

Depth drilled 95 ft. Depth of completed well 95 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	1	
Clay Brown	1	4	
Clay yellow	4	34	
Clay Gray	34	40	
Clay Brown soft	40	46	
Clay yellow	46	55	
Clay stone Gray	55	61	12'
Clay Dark Brown	61	63	
Clay Brown soft	63	66	
Clay yellow	66	71	
Clay RED	71	80	12'
Brown sand rock BKN	80	86	
Blue sand rock Hard	86	95	
water stratum	72	84	ft

Work started 11-2 1981 Completed 11-4 1981
Date well drilling machine moved off of well 11-4 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Orval Hildbrand Date 11-29-81
(Drilling Machine Operator)

Drilling Machine Operator's License No. 701

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name M & H Well Drilling Inc
(Person, firm or corporation) (Type or print)

Address 7235 NW Appaloosa Corvallis

[Signed] (Water Well Contractor)

Contractor's License No. 237 Date 11-29 1981