

DEC 07 1989

Bent
3456

11s/5w/12ab
2 15098

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON

(START CARD) # 2 15098

(1) OWNER: Well Number: 2
Name LAKE PARK ROLLER RINK
Address 6400 NW HWY 99W
City CORVALLIS State OR Zip 97330

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 77 ft.
Explosives used Yes No Type Amount

Table with columns: HOLE (Diameter, From, To), SEAL (Material, From, To), Amount (sacks or pounds).
Row 1: 10, 0, 33, CEMENT, 0, 23, 12
Row 2: 6, 33, 77

How was seal placed: Method A B C D E
Backfill placed from ft. to ft. Material
Gravel placed from 0 ft. to 33 ft. Size of gravel PEA

(6) CASING/LINER:
Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded.
Casing: 6, +2, 34, 250, , , ,
Liner: NA

Final location of shoe(s) NA

(7) PERFORATIONS/SCREENS:
 Perforations Method TORCH
 Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner.
Row 1: 29, 32, 1/2, 6, , , ,

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min 3 1/2 Drawdown 40 Drill stem at Time 1 hr.

Temperature of water Depth Artesian Flow Found
Was a water analysis done? Yes By whom
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other
Depth of strata:

(9) LOCATION OF WELL by legal description:

County BENTON Latitude Longitude
Township 11s N or S, Range 5w E or W, WM.
Section 12 B 1/4 A 1/4
Tax Lot 400 Lot Block Subdivision
Street Address of Well (or nearest address) 6400 NW HWY 99W
CORVALLIS OR

(10) STATIC WATER LEVEL:

4 ft. below land surface. Date 11-22-89
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Table with columns: From, To, Estimated Flow Rate, SWL.
Row 1: 30, 33, 2, 4
Row 2: 55, 56, 2, 4

(12) WELL LOG:

Table with columns: Material, From, To, SWL.
SOIL 0 3
CLAY GREY 3 7
CLAY BROWN 7 19
BROWN CLAYSTONE 19 24
GREY CLAYSTONE 24 30
GREY CLAYSTONE W/WATER 30 34
GREY CLAYSTONE 34 55
GREY CLAYSTONE W/WATER 55 56 4
GREY CLAYSTONE 56 77

Date started 11-17-89 Completed 11-21-89

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number
Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1238
Signed Date 11-21-89