

STATE OF OREGON WATER SUPPLY WELL REPORT

NOV 06 2000

WELL I.D. # L 34791 START CARD # 127766

Instructions for completing this report are on the last page of this form.

WATER RESOURCES DEPT SALEM, OREGON

(1) OWNER: Name KYLE DUNNING Address 4635 NE ELLIOTT CIRCLE City CORVALLIS State OR Zip 97330 Well Number

(2) TYPE OF WORK [X] New Well [ ] Deepening [ ] Alteration (repair/recondition) [ ] Abandonment

(3) DRILL METHOD: [X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Auger [ ] Other

(4) PROPOSED USE: [ ] Domestic [X] Community [ ] Industrial [ ] Irrigation [ ] Thermal [ ] Injection [ ] Livestock [ ] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [ ] Yes [X] No Depth of Completed Well 63 ft. Explosives used [ ] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Sacks or pounds. Row 1: 12, 0, 18, BENT, 0, 18, 11 SACKS. Row 2: 8, 18, 63.

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E [ ] Other POURED Backfill placed from NA ft. to ft. Material Gravel placed from NA ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 8, +2, 41, 250 [X]. Liner: NA.

Final location of shoe(s) 41

(7) PERFORATIONS/SCREENS: [X] Perforations Method HOLTE PERFORATOR [ ] Screens Type Material. From 31 To 40 Slot size 1/4 Number 98 Diameter Casing [X] Liner [ ]

(8) WELL TESTS: Minimum testing time is 1 hour. [X] Pump [ ] Bailer [ ] Air [ ] Flowing Artesian. Yield gal/min 56.1 Drawdown 20 Drill stem at 4 Time 1/4 hr.

Temperature of water 56 Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County BENTON Latitude 44°37'02 Longitude 123°13'41 Township 11S N or S Range 4W E or W. WM. Section 18 1/4 1/4 Tax Lot 200 Lot Block Subdivision Street Address of Well (or nearest address) 4635 NE ELLIOTT CIRCLE CORVALLIS

(10) STATIC WATER LEVEL: 22 ft. below land surface. Date 10-10-00 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 28

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 28, 39, 45, 22. Row 2: 39, 42, 25, 22.

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. SOIL LT BROWN CLAY 3 24 SAND AND SILT 24 28 FINE GRAVEL AND SAND 28 39 22 SANDSTONE BROKEN 39 42 GREY SANDSTONE 42 63

Date started 10-4-00 Completed 10-10-00

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief. WWC Number Signed Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief. WWC Number 1238 Signed Date 10-10-00