

2.61529

For Official Use Only:

Received Date:

9-25-02

County Well Log ID #

"Bent 52175"

Well Identification Tag #

2-61529

WELL IDENTIFICATION APPLICATION FORM

(please see attached instructions)

RECEIVED

SEP 25 2002

WATER RESOURCES DEPT. SALEM, OREGON

BUYER/CURRENT LANDOWNER (FOR PROPERTY WELL IS LOCATED ON):

Name: Hewlett Packard Company

Mailing Address: 1000 N.E. Circle Blvd.

City: Corvallis State: OR Zip: 97330 Phone: (541) 715-2684

NOTE: Well Identification Tag will be sent to the above address unless otherwise specified above. DO NOT COMPLETE THIS FORM IF YOU ARE SHARING THE WELL ON ANOTHER'S PROPERTY.

WELL LOCATION:

County: Benton Well # (designation owner has given to well if multiple wells exist on same property): C

Township: 11 So. North or South, Range: 5 West East or West, Section: NE Qtr. 25 1/4 1/4

Tax Lot #: 1202 (not the "tax acct.#") Type of Well: water supply X monitoring

Address of Well: Same (Number) (Street) (City)

Does this well have a formal water right associated with it? Yes: X No: (If unknown you may contact the Water Rights Information Group at 503-378-3739 extension 201 for research)

If Yes: Application #: G-8470 Permit #: G-7791 Certificate #: 58859

(Optional): Latitude Longitude (May sometimes be obtained from Well Log Report)

WELL INFORMATION: (If available, attach copy of driller's well report. If report is not available please complete the following, at a minimum the prior landowner names going back until around the time the well would have been drilled. Prior landowners can be obtained from the County Assessor.)

Start Card #: Approx. Well Construction Date: 3-12-73

Well Constructor:

Name of Land Owner at Time of Construction (or list of prior landowners) Hewlett Packard Company

Well Depth (in feet): Static Water Level (in feet):

Diameter of Exposed Well Casing (in inches): 11 3/4"

Please Return Completed Form to: Well ID Program @ Oregon Water Resources Department 158 12th Street NE - Salem, OR 97301-4172, or fax to 503-378-8130

SUBJECT HEAVY METALS

LOG OF DEWATERING WELLS



RECEIVED

SEP 27 1977

WATER RESOURCES DEPT
SALEM, OREGON

WELL "C"

MATERIAL

	<u>FROM</u>	<u>TO</u>
SOFT BROWN CLAYEY SILT	0'	23'
WET BROWN SANDY SILT	23'	28'
FINE BLACK-GREY SAND	28'	33'
BROWN SANDY GRAVEL w/CORRALS	33'	52'
BLUE-GREY CLAYEY SILT	52'	55'

WELL CASING & SCREEN

1 1/4" INSIDE DIAMETER PVC PIPE

1/4" WALL THICKNESS

10' LENGTH OF SLOTTED SECTION (FROM 40' TO 50' DEPTH)

3/16" SLOT WIDTH

2 1/4" SLOT LENGTH

34 SLOTS/ROW/LIN. FT. OF PIPE

8 ROWS OF SLOTS AROUND PIPE

Application No. G-8470
Permit No.

RECEIVED

SEP 25 2002

WATER RESOURCES DEPT.
SALEM, OREGON

CONSTRUCTION

WELL DRILLED WITH 30" BUCKET AUGER

3/8" MINUS 'GRIT' PLACED AS GRAVEL PACK AROUND LOWER PORTION OF PIPE.

WELL SEALED WITH CEMENT FROM LAND SURFACE TO 18' DEPTH.

WELL DRILLED 12 MARCH 1973