

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

RECEIVED
SEP 1 1965

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date of well completion.

STATE ENGINEER
OREGON

(Please type or print)

Bent
5257

State Well No. 12/5w-220

State Permit No. G3277

(1) OWNER:

Name City of Corvallis
Address 5th Madison

(2) LOCATION OF WELL:

County Benton Driller's well number
1/4 1/4 Section 22 T. 12S R. 5W W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☒ Municipal ☒
Irrigation ☐ Test Well ☐ Other ☐ Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 44 ft. Gage 1/4" MAIL
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used GAS TORCH
Size of perforations 4 in. by 16 in.
5 Rows perforations from 33 ft. to 43 ft.
6 PER PER ROW perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 19 ft. Was a packer used?
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 27 ft. below land surface Date AUG. 25-65
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? Philomath Haver.
Yield: 110 gal./min. with 18 ft. drawdown after 4 hrs.
" " " "
" " " "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing 8
Depth drilled 50 ft. Depth of completed well 50 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Brown CLAY	0	19
Blue CLAY MUD	19	24
Blue SAND & CLAY	24	32
FINE BROWN GRAVEL & SAND	32	39
COURSE GRAVEL	39	42
Fine GRAVEL & SAND	42	44
Blue CLAY	44	50

Work started AUG 1965 Completed AUG 1965
Date well drilling machine moved off of well AUG 27 1965

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Bill Howell
(Person, firm or corporation) (Type or print)

Address R# 2 CORVALLIS

Drilling Machine Operator's License No. 79

[Signed] Bill Howell
(Water Well Contractor)

Contractor's License No. 50 Date AUG 1965