

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

WELL I.D. LABEL# L 122203- 122203
START CARD # 1030470
ORIGINAL LOG #

7/4/2016

(1) LAND OWNER
Owner Well I.D.
First Name
Last Name
Company RFP FAMILY STORE
Address 27678 OR-99W
City CORVALLIS State OR Zip 97333

(2) TYPE OF WORK
[X] New Well [ ] Deepening [ ] Conversion
[ ] Alteration (complete 2a & 10) [ ] Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing:
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD
[X] Rotary Air [ ] Rotary Mud [ ] Cable [ ] Auger [ ] Cable Mud
[ ] Reverse Rotary [ ] Other

(4) PROPOSED USE
[X] Domestic [ ] Irrigation [ ] Community
[ ] Industrial/ Commercial [ ] Livestock [ ] Dewatering
[ ] Thermal [ ] Injection [ ] Other

(5) BORE HOLE CONSTRUCTION
Special Standard (Attach copy)
Depth of Completed Well 36.00 ft

Table with columns: Dia, From, To, Material, SEAL, Amt, lbs. Row 1: 6, 0, 36, Bentonite Chips, 0, 18, 12, S. Calculated 8.22

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E
[X] Other POURED
Backfill placed from 0 ft to 18 ft. Material
Filter pack from ft to ft. Material Size
Explosives used: [ ] Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Actual Amount

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
Shoe [ ] Inside [ ] Outside [ ] Other Location of shoe(s)
Temp casing [X] Yes Dia 10 From 0 To 18

(7) PERFORATIONS/SCREENS
Perf/ Casing/ Screen Screen/slot Slot # of Tele/
Screen Liner Dia From To width length slots pipe size
Perf Casing 6 29 34 .125 6 12

(8) WELL TESTS: Minimum testing time is 1 hour
[ ] Pump [ ] Bailer [X] Air [ ] Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
35 36 1
Temperature 52 °F Lab analysis [ ] Yes By
Water quality concerns? [ ] Yes (describe below) TDS amount 146
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County BENTON Twp 13.00 S N/S Range 5.00 W E/W WM
Sec 34 SE 1/4 of the SW 1/4 Tax Lot 400
Tax Map Number Lot
Lat " or DMS or DD
Long " or DMS or DD
[ ] Street address of well [ ] Nearest address
27678 OR-99W CORVALLIS, OR 97333

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration
Completed Well 5/9/2016 8
Flowing Artesian? [ ] Dry Hole? [ ]
WATER BEARING ZONES Depth water was first found 21
SWL Date From To Est Flow SWL(psi) + SWL(ft)
5/9/2016 21 36 35 8

(11) WELL LOG
Ground Elevation
Material From To
Top Soil 0 1
Sand 1 12
Gravelly Clay 12 22
Sand/gravel 22 36
RECEIVED BY OWRD
AUG 23 2016
SALEM, OR

Date Started 5/4/2016 Completed 5/9/2016

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number Date
Signed

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1960 Date 7/4/2016
Signed JACOB HOWELL (E-filed)
Contact Info (optional) Jacob L Howell 541-913-7896