

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED
MAY 31 1985
WATER RESOURCES DEPT
SALEM, OREGON

PLEASE TYPE OR PRINT IN INK

Bent
7443

145/7W-6

(for official use only)

(1) OWNER:

Name Alsea County Service
Address 310 S.W. Avery
City Corvallis State Or.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Thermal: ☐
Irrigation ☐ Withdrawal ☐ Reinjection ☐
Other: ☐
Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from +1 ft. to 19 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

Steel ☐ Plastic ☒
Threaded ☐ Welded ☐
4" Diam. from 0 ft. to 154 ft. Gauge 175

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Size of perforations 1/8 in. by 6 in.
240 perforations from 40 ft. to 152 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.
Air test 20 gal./min. with drill stem at 149 ft. 2 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 52 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used cement
Well sealed from land surface to 19 ft.
Diameter of well bore to bottom of seal 18 in.
Diameter of well bore below seal 6 in.
Amount of sealing material 15 sacks ☒ pounds ☐
How was cement grout placed? pressure

Was pump installed? Type HP Depth ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL by legal description:

County Benton 1/4 1/4 of Section 6 of
Township 14S Range 7W WM.
(Township is North or South) (Range is East or West)
Tax Lot Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address) same

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 84 ft.
Static level 10 ft. below land surface. Date 5/15/85
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 154 ft. Depth of completed well 154 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	1	
brown clay & grit	1	10	
brown clay	12	13	
sand & gravel	13	14	
cemented gravel	14	35	
broken gray claystone	35	75	
hd. gray sandstone 20 gpm	75	125	
gray claystone	125	154	

Date work started 5-13-85 completed 5-14-85
Date well drilling machine moved off of well 5-14-1985

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Donald S. Witham Date 5-29-1985

(bonded) Water Well Constructor Certification:

Bond 503 Issued by: Lystra Ins. Co.
(number) (Surety Company Name)
On behalf of Raymond G. Glatky & R.S. Witham
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

(Signed) Donald S. Witham
(Water Well Constructor)
(Dated) 5/29/85

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690