

WATER WELL REPORT
STATE OF OREGON

RECEIVED
JAN 13 1981
WATER RESOURCES DEPT
SALEM, OREGON

010181 State Well No. 55-22-146C
CLAC State Permit No.

(1) OWNER:

Name Harry K Asner
Address RFD 2 Box 242 D
City Medalla State Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
Cable ☒ Bored ☐ Thermal ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

" Diam. from 0 ft. 240 ft. Gauge 250
" Diam. from 0 ft. to 0 ft. Gauge 0

LINER INSTALLED:

" Diam. from 0 ft. to 0 ft. Gauge 0

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from 0 ft. to 0 ft.
perforations from 0 ft. to 0 ft.
perforations from 0 ft. to 0 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from 0 ft. to 0 ft.
Diam. Slot Size Set from 0 ft. to 0 ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
Air test gal./min. with drill stem at ft. hrs.
er test 30 gal./min. with 60 ft. drawdown after 1 1/2 hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered 0 ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 24 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 9 sacks
How was cement grout placed? Tremie 171 ft.

Was pump installed? Type HP Depth ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☐ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from 0 ft. to 0 ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
BW 1/4 NW 1/4 Section 14 T. 55 R. 2E W.M.
Tax Lot # Lot Blk Subdivision
Address at well location: Same.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 240 ft.
Static level 140 ft. below land surface. Date
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 268 ft. Depth of completed well 268 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	2	
Brown Clay	2	6	
Cement Gravel	6	26	
Dark Brown Clay	26	34	
Cement Gravel	34	44	
Blue Clay & Gravel	44	65	
Blue Clay (light)	65	104	
Cement Gravel	104	111	
Red Shale (Hard)	111	134	
Brown Clay Stone	134	158	
Blue clay stone	158	190	
Cement Gravel	190	210	
Brown Clay Stone	210	224	
Cement Gravel	224	230	
Dark Brown Shale	230	238	
Green Sand Stone	238	268	140

Work started 12-29 19 80 Completed 1-9 19 81
Date well drilling machine moved off of well 1-10 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John W. Beck Date 1-10, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1137

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name J.W. Beck Well Drilling
(Person, firm or corporation) (Type or print)

Address 24437 S. Sky Lane Dr. Canby Ore

[Signed] John W. Beck
(Water Well Contractor)

Contractor's License No. 449 Date Jan. 10, 19 81

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690