

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
FEB 18 1966
STATE ENGINEER
SALEM OREGON
STATE OF OREGON
(Please type or print)

MAR 1 1966

State Well No.

State Permit No.

G 3487

010845
5/3-19 QP

(1) OWNER:

Name Everett F SmithAddress RT 2 Box 22P
Molalla Ore

(2) LOCATION OF WELL:

County Clatsop Driller's well number 148
SE 1/4 SW 1/4 Section 19 T. 55 R. 3E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☒ Other ☐

(5) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6" Diam. from 0+4 ft. to 195 ft. Gage 250
" Diam. from ft. to 22 ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
..... perforations from ft. to ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Model No.

..... Slot size Set from ft. to ft.
..... Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Cemented with cuttings
Depth of seal 19 ft. Was a packer used? yes
Diameter of well bore to bottom of seal 16 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 70 ft. below land surface Date 2-7-66
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Packer test 10 gal./min. with 240 ft. drawdown after 2 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6Depth drilled 312 ft. Depth of completed well 312 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Orange Soil	0	2
Brown clay	2	5
Red clay	5	10
lavender clay	10	19
Partly decomposed Rock	19	75
Partly decomposed graduating to hard Fresh Rock Rock	75	100
Hard Rock	100	273
Orange clay	273	275
Blue & Green clay	275	290
Gravel with clay	290	293
Tan clay Same Rocks	293	312

Well Sub-Contracted to
Miller, Robinson & West, Salem

Work started Feb 2 19 66 Completed Feb 6 19 66
Date well drilling machine moved off of well 11 11 19 11

(13) PUMP:

Manufacturer's Name

Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Tollman Drilling Co

(Person, firm or corporation)

(Type or print)

Address RT 1 Box 268 Molalla OreDrilling Machine Operator's License No. 174[Signed] Frank R. Collins

(Water Well Contractor)

Contractor's License No. 264 Date Feb 16, 19 66

(USE ADDITIONAL SHEETS IF NECESSARY)