

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

CLAC

State Well No.

State Permit No.

011881

45/4E-30 b.d.

(1) OWNER:

Name Sam Oroke
Address 28601 Cox Rd
Edison Ore. 97017

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
☒ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

5" Diam. from 0 ft. to 23 ft. Gage 250
5" Diam. from 12 ft. to 143 ft. Gage 16082
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used SDW
Size of perforations 3/32 in. by 6 in.
120 perforations from 80 ft. to 143 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "
Packer test 8 gal./min. with 32 ft. drawdown after 1 1/2 hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 23 ft.
Diameter of well bore to bottom of seal 9+ in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 9 sacks
How was cement grout placed? Pumped

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☐ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number
SE 1/4 NW 1/4 Section 30 T.4S R. 4E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 104 ft.
Static level 95 ft. below land surface. Date
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 170 ft. Depth of completed well 143 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top	0	1	
Broken Rock	1	9	
Solid Rock	9	74	
Layer Rock	74	82	
Gray Rock	82	104	
Layer	104	111	
Red Shale	111	124	
Gray Shale	124	137	
Light Brown Shale	137	145	
Gray Rock	145	150	

RECEIVED

SEP 05 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 8-25 1980 Completed 8-29 1980
Date well drilling machine moved off of well 8-30 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] John W Beck Date 8-30, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1137

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name J.W. Beck Well Drilling
(Person, firm or corporation) (Type or print)

Address 24137 S Skyline Dr Canby Ore

[Signed] John W Beck
(Water Well Contractor)

Contractor's License No. 4149 Date 8-30, 1980