



JUN 30 1986

Manfred Schosnig (C & S Farms)  
10483 S. Township Road  
Canby, OR 97013

Clackamas COUNTY WATER RESOURCES DEPT  
3S, 1E, Sec. 33 SALEM, OREGON

## Well Log

0	4	Top soil, brown
4	19	Clay, brown
19	33	Clay, brown, sandy, soft
33	55	Gravel, cobbles & sand
55	69	Gravel & clay, brown
69	74	Gravel & cobbles w/clay, brown
74	77	Gravel & sand, brown
77	83	Gravel & clay, brown, sandy
83	90	Gravel, w/some clay
90	100	Gravel, 6" minus
100	102	Gravel, 6" minus cem w/some clay, brown
102	110	Clay, brown
110	113	Gravel, 2" minus, cem
113	114	Clay, brown
114	117	Clay, blue
117	122	Sand, cem & clay, blue-green
122	124	Gravel, 1" minus & sand w/clay, green
124	127	Clay, blue-green
127	129	Clay, blue-green, fine, sandy
129	130	Clay, blue-grey
130	132	Sand, coarse w/some gravel, cem
132	133	Clay, dark green
133	135	Clay, blue
135	142	Sand, coarse, clay, blue-green
142	150	Sand, black, med-coarse, cem w/some pea gravel
150	152	Sand, black, med-coarse & gravel, 1/2" minus
152	158	Clay, blue-green, fine, sandy
158	160	Sand, black, med-coarse
160	162	Gravel, 1/2" minus
162	170	Clay, blue-green
170	175	Clay, grey, fine, sandy
175	179	Clay, dark grey, fine, sandy
179	182	Clay, grey, fine, sandy, soft
182	191	Clay, grey, med, sandy
191	195	Clay, blue-grey w/gravel
195	200	Clay, grey
200	201	Sand, cemented, med-coarse
201	208	Sand, black, med-coarse, w/small gravel
208	216	Sand, black, med, cem
216	220	Clay, dark grey
220	223	Clay, dark brown, w/wood
223	230	Clay, dark grey, firm
230	235	Clay, grey
235	242	Clay, blue
242	244	Clay, grey, fine sandy
244	249	Sand, grey, med, cem w/ some small gravel
249	261	Clay, brown, fine, sandy
261	263	Sand, rust brown, cem

# CLAC 12120

Manfred Schosnig (C & S Farms)  
Clackamas County  
3S, 1E, Sec. 35

Page 2

263	265	Sand, black, fine-med, cem
265	268	Clay, blue
268	271	Clay, blue, fine, sandy
271	276	Clay, med, sandy, gritty
276	283	Sand, black, med-coarse, cem
283	292	Sand, coarse w/wood
292	309	Clay, grey
309	313	Clay, blue-green
313	316	Sand, cem, black, fine
316	345	Clay, grey

Note: "Cem" means some cementation present.