

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

CLAC
C12167

RECEIVED

AUG - 4 1989

(START CARD) # 5685

35/1/E/366c

(1) OWNER:

Name Susan W Clark & Will Newman II
Address PO Box 1106
City Carby State Or Zip 97013

Well Number: 37612

(9) LOCATION OF WELL by legal description:

County Clack Latitude _____ Longitude _____
Township 3 N or S, Range 1E E or W, WM.
Section 36 SW 1/4 NW 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 11124 S Bremer Rd
Carby, Or 97013

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 275 ft.
Explosives used Yes ☐ No ☒ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12"	0	19'	cement	0	19'	26 sacks
8"	19	275'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	18'	165'	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	6" PVC	135	275		☐	☒	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) 165

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Saw
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
241	243	1/8	2			☐	☒
		X				☐	☐
		8"				☐	☐
257	275		16			☐	☒
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
100		274	1 hr.

Temperature of water 54 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(10) STATIC WATER LEVEL:

107 ft. below land surface. Date 7/31/89
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 241

From	To	Estimated Flow Rate	SWL
241	243	5 GPM	107
257	275	95 GPM	107

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
Top soil	0	2	
Clay, brown	2	52	
Clay, sand, blue, black, fine	52	71	
Clay, brown	71	76	
Clay, blue	76	116	
Clay, sand, blue, black, fine	116	152	
Clay, blue	152	241	
Sandstone, black, fractured	241	243	107
Claystone, blue, fractured	243	257	
Sandstone, black, fractured	257	275	107

Date started 7/18/89 Completed 7/31/89

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 637
Signed George J. Wamwright Date 8/1/89