

CLAC 12210

CLAC
012210

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

RECEIVED

JAN 27 1967 WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.STATE OF OREGON
(Please type or print)
SALEM, OREGON

State Well No. 3/1-36 K

State Permit No. G-3903

(1) OWNER:

Name Homer D. Meyers
Address 5212 N. Yale St.
Portland Or 97203

(2) LOCATION OF WELL:

County Clackamas Driller's well number 1967-2
1/4 Section 36 T. 35 R. 1 E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
 abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

(5) TYPE OF WELL:

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☒ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

6" Diam. from 0 ft. to 108 ft. Gage 025
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ NoManufacturer's Name
Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 85 ft. Was a packer used? NO
Diameter of well bore to bottom of seal 9 in.
Were any loose strata cemented off? ☐ Yes ☐ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☒ Yes ☐ No Size of gravel: 1/2" X 1/4"
Gravel placed from 138 ft. to 108 ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 43' ft. below land surface Date 1-25
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom? Driller 271
Yield: 25 gal./min. with 37 ft. drawdown after 1 hrs." 60 " 63 " 2 "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 60 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 6"Depth drilled 138 ft. Depth of completed well 108 ft.Formation: Describe by color, character, size of material and structure, and
show thickness of aquifers and the kind and nature of the material in each
stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top soil	0	3
Brown sandy loam	3	50
Brown sandy	50	85
Blue clay	85	105
Blue shale	105	110
Black sand (Medium)	110	136
Grey shale	136	138

Work started 1-10 1966 Completed 1-23 1967
Date well drilling machine moved off of well 1-23 1967

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.NAME Skyles Drilling & Supply
(Person, firm or corporation) (Type or print)Address Cladstone OregonDrilling Machine Operator's License No. 271[Signed] George H. Skyles
(Water Well Contractor)Contractor's License No. 58 Date Jan 25, 1967

(USE ADDITIONAL SHEETS IF NECESSARY)

WELL IDENTIFICATION APPLICATION FORM **RECEIVED**

NOV 26 1996

BUYER/CURRENT WELL OWNER:WATER RESOURCES DEPT.
SALEM, OREGONName: HOMER D. MEYERSMailing Address: 5212 N YALE STCity: PORTLAND State: OR Zip: 97203-4342 Phone: (503) 285-8917**WELL LOCATION:**County: CLACKAMAS Township: 3S N or S, Range: 1E E or WSection: 36 1/4 1/4 Owner's Well Number: _____Tax Lot Number: 02700 Street Address of Well (if different from above): _____**WELL INFORMATION: (do not complete remainder of application if well log is available)**Start Card Number: _____ Approx. Construction Date: 5-1-1968
1968Well Constructor: SKYLES DRILLINGName of Owner at Time of Construction: HOMER & AUDREY MEYERSWell Depth (in feet): 104 Static Water Level (in feet): _____Diameter of Exposed Well Casing (in inches): 6"Does this well have a formal water right associated with it? Yes: X No: _____If Yes: Application #: _____ Permit #: _____ Certificate #: G 3466**Please Return Completed Form to:**Lisa Juul
Well Identification Program
Oregon Water Resources Department
158 12th Street NE
Salem, OR 97310**For Official Use Only:**Well Tag No. 12279