

AUG 26 1991

Clac 12259

3S/1E/2/CA

STATE OF OREGON WATER RESOURCES DEPT. WATER WELL REPORT SALEM, OREGON (as required by ORS 537.765)

(START CARD) # W 25165

(1) OWNER: Well Number: Name Fred Courney Address 3930 N. Holly St. City Canby State Ore Zip 97013

(2) TYPE OF WORK: [X] New Well [ ] Deepen [ ] Recondition [ ] Abandon

(3) DRILL METHOD [ ] Rotary Air [ ] Rotary Mud [X] Cable [ ] Other

(4) PROPOSED USE: [X] Domestic [ ] Community [ ] Industrial [X] Irrigation [ ] Thermal [ ] Injection [ ] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval Yes No Depth of Completed Well 122 ft. Explosives used [ ] [X] Type Amount

Table with columns: HOLE Diameter, SEAL Material, Amount sacks or pounds. Row 1: 11+0 to 20, Cement, 20 to 0, 7.

How was seal placed: Method [ ] A [ ] B [ ] C [ ] D [ ] E [ ] Other Tremmie Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6, +1, 122, 250, [X], [ ], [X], [ ]

Final location of shoe(s)

(7) PERFORATIONS/SCREENS: [X] Perforations Method Star Drive Down [ ] Screens Type Material

Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 90, 112, 1/2 X 3/8, 220, 6, [X], [ ]

(8) WELL TESTS: Minimum testing time is 1 hour [X] Pump [ ] Bailer [ ] Air [ ] Flowing Artesian Yield gal/min 80 Drawdown 3 FT Drill stem at Time 2 hr.

Temperature of water 52.75 Depth Artesian Flow Found Was a water analysis done? [ ] Yes By whom Did any strata contain water not suitable for intended use? [ ] Too little [ ] Salty [ ] Muddy [ ] Odor [ ] Colored [ ] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Clackamas Latitude Longitude Township 3S Nor S. Range 1E E or W, WM. Section 21 NE 1/4 SW 1/4 Tax Lot Lot Block Subdivision Street Address of Well (or nearest address) 3930 N Holly St Canby Ore.

(10) STATIC WATER LEVEL: 69 ft. below land surface. Date 8-21-91 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 85, 112, 140, 69

(12) WELL LOG: Table with columns: Material, From, To, SWL. Row 1: Top 4 Brown Silty Clay, 0, 8. Row 2: Sandy clay (Brown), 8, 84. Row 3: Sand & small gravel (Brown), 84, 112. Row 4: Dark Blue Clay (stickey), 112, 122

Date started 8-9-91 Completed 8-21-91

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief. Signed WWC Number Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. Signed John W Beck WWC Number 449 Date 8-21-91