

WATER WELL REPORT
STATE OF OREGON

CLAC

012432

RECEIVED

OCT 22 1981

WATER RESOURCES DEPT
SALEM, OREGON

State Well No.

45/1E-23aa

State Permit No.

(1) OWNER:

Name Roger Skoe
Address 3395 6th Ave. So.
City Salem State Or.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
Cable ☐ Bored ☐ Thermal ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED: Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

" Diam. from 0 ft. to 200 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

7 OD 190 ft. to 230 ft. Gauge 188
" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Torch
Size of perforations 1/4 in. by 8 in.
40 perforations from 212 ft. to 222 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller
Yield: 130 gal./min. with 49 ft. drawdown after 2 hrs.
" " " " " "
" test gal./min. with drill stem at ft. hrs.
" test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 19 ft.
Diameter of well bore to bottom of seal 12 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 18 sacks
How was cement grout placed? Pressure grouted from
19 ft. to land surface.

Was pump installed? NO Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Clackamas Driller's well number 199
NE 1/4 NE 1/4 Section 23 T. 4S R. 1E W.M.
Tax Lot # 1700 Lot Blk Subdivision
Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 103 ft.
Static level 72 ft. below land surface. Date 9-25-81
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 230 ft. Depth of completed well 230 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	2	
Clay, brown	2	27	
Clay, blue	27	31	
Clay, gravel, blue, med.	31	36	
Gravel, compacted	36	64	
Clay, brown	64	67	
Gravel, compacted	67	97	
Clay, brown	97	101	
Clay, blue	101	103	
*Sand, brown	103	108	
Clay, brown	108	111	
Clay, blue	111	157	
*Sandstone, soft, black	157	169	
Clay, blue	169	192	
*Sandstone, soft, black	192	195	
Clay, blue	195	212	
*Sandstone, black	212	227	
Clay, blue	227	230	

Work started 9-14 1981 Completed 9-25 1981

Date well drilling machine moved off of well 9-25 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Bob Kern Date 9-29, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 994

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name B. & G. Drilling
(Person, firm or corporation) (Type or print)

Address 10030 S. Macksburg Rd. Canby, Or.

[Signed] George J. Wainwright
(Water Well Contractor)

Contractor's License No. 637 Date 9-29, 1981

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,

SALEM, OREGON 97310

within 30 days from the date of well completion

SP*12658-690